

Book 3.

No				
390.	Known as the Building Code.	✓	✓	1
442	Second hand dealers and junk shops	✓		107
443	Pawn Brokers	✓		110
444	Fixing Tax levy.	✓		113
445	Relating to dead animals	✓		114
446	Market masters Salary	✓		115
447	Authorizing sale of horses	✓		116
448	Operating Automobiles	✓		117
449	Contract with american Telephone and Telegraph co	✓		120
450	Contract with Wayne Auto appliance co	✓		124
451	Fixing Salary of Policeman	✓		125
452	Garbage slops and waste in covered wagons	✓		128
453	Regulating moving travel and traffic	✓		129
454	Authorizing the sale of second hand boilers + scrap iron	✓		136
455	Fixing Salaries of officers of the Health Department	✓		137
456	Fixing Salaries of Employes of the Fire Department	✓		138
457	Fixing Salary of Lieutenant of Police	✓		140
458	Fixing Salaries of employes of Fire Department	✓		141
459- 1911	Fixing Salaries of employes of Board of Public works	✓		142
460	Contract with S. F. Bowser + co	✓		143
461	Contract with Kaough coal co	✓		147
462	Changing name of Hartnett street	✓	✓	151
463	Contract with New york Chicago + St. Louis Rail Road co	✓	✓	152
464	Contract with Gust Lindeman	✓		155
465	Contract with Fort Wayne Electric works	✓		159
466	Contract with Fort Wayne Electric works	✓		163
467	Contract with Fort Wayne Electric works	✓		166
468	Contract with Thrashers and Heaviness	✓		169
469	Contract with Olds coal co	✓		173
470	Contract with J. F. Zurbuch coal co	✓		176
471	Contract with David M. Winburn	✓		182
472	Regulating the use of automobiles	✓		185
473	Fixing salaries of certain empoyees of the Fire Department	✓		187
474	Contract with Tripper + Son - Broadway	✓		188
475	Contract with Tripper + Son - Fairfield ave	✓		197
476	Authorizing the sale of certain ~~offices~~ horses	✓		198
477	Bond of Treasure of City	✓		199
478	To employ an additional Officer	✓		200
479	Contract with W.S. cast iron pipe and Foundry co	✓		201
480	Fire limits	✓		202
481	Storage of Gasoline	✓		204
482	Prohibiting Sale of Fire works	✓		205
483	Taxing of Dogs	✓		206

A B C D E F G H I J K L M Mc N O P Q R S T U V W Y Z

no				Page
484	Revising city ordinances		/	207
485	To employ clerk for Chief of Police		/	209
486	Sealer of weights and measures		/	210
487	Prohibiting Sale of Fire works		/	218
488	Unlawful for dogs to run at large		/	220
489	approving track elevation Resolution no 3		/	222
490	Contract with Fort Wayne Electric works		/	223
491	Employment of Five additional Policemen		/	224
492	Contract with Henry R. Worthington		/	225
493	Track Elevation Resolution no 4		/	226
494	Authorizing the erection and Maintenance of pumps. automatic Valves		/	227
495	Regulating Automobiles and motor Vehicles		/	230
496	An ordinance defining certain Offences		/	232
497	Changing the name of Force St to Weisser Park Ave	X	/	233
498	Ornamental Lamp Posts		/	234
499	Contract with Metcalf and Eddy		/	235
500	Contract with Lake Shore and Michigan Rail Road		/	238
501	Distruction of weeds and noxious plants		/	239
502	Contract with Northern Indiana Traction company		/	241
503	Location of Slaughter houses		/	244
504	Contract with Bernard Berkenstein		/	245
505	annexing Certain Territory		/	249
506	Fixing tax levy		/	250
507	Inspection of scales weights and measures		/	252
508	Regulating Barr Street Market		/	254
509	Safety gates at Walton avenue		/	255
510	Contract with Ft Wayne Northern Ind Traction co		/	256
511	Contract with Wabash Rail Road co		/	257
512	Contract with wabash Rail Road co		/	258
513	Barr Street Market		/	259
514	To furnish water for Parocial Schools		/	261
515	To license itinerate Vendors	/		262
516	Unlawful to parade for gain on Decoration day	/		264
517	authorizing sale of Patrol wagons		/	265
518	Contract with Fort Wayne and northern Traction co		/	266
519	authorizing the employment of one detective and five Policemen		/	267
520	authorizing the employment of Five Firemen		/	268
521	To employ assistant engineer		/	269
522	Contract with Wm H Dunn		/	270
523	Contract with Kavanagh coal co		/	271
524	Contract with Ft Wayne electric works		/	272
525	Contract with Ft Wayne electric works		/	273
526	Authorizing the sale of horses		/	274

				Page
527	Four Park Lerstricts		✓	275
528	Fixing salary of water works employees		✓	278
529	Contract with Fort Wayne printing company		✓	279
530	Fixing salary of clerk of Health Department		✓	280
531	Contract with David M. Winburn		✓	281
532	Contract with Traction company		✓	285
533	Contract with wire and cable company of New Jersey		✓	286
534	Trimming Trees		✓	287
535	Prescribing fire limits		✓	290
536	Barr Street Market		✓	292
537	Disorderly + Offensive conduct		✓	294
538	Signs		✓	296
539	Paving Superior Street		✓	300
540	Contract with Kelly Springfield Road Roller Company		✓	302
541	Traveling crane for Olds Coal Company		✓	304
542	Contract with James B. Clow + Sons		✓	305
543	Contract with Chicago + St Louis Rail Road co		✓	307
544	Contract with Heathering + Berner (asphalt Repair Rank)		✓	313
545	Liquor Licinse		✓	314
546	To sell certain property		✓	316
547	Changing the name of Walton ave to Anthony Boulevard	✓	✗	317
548	Annexing "Foster Park" to the City		✓	319
549	Track Elevations Resolution no 5 + 6		✓	321
550	Contract with John Jacob Auth		✓	322
551	Annexing certain territory		✓	325
552	Circus + Shows give Bonds for parading		✓	326
553	Authorizing Sale of certain property		✓	327
554	Barr Street market		✓	328
555	Regulating the use of Streets and alleys		✓	330
556	Peddlers + Hawkers to take out a licence		✓	331
557	Annexing Certain Territory		✓	332
558	Changing the name of Riddicill avenue to Rudisill Boulevard		✓	333
559	Contract with Olds coal Company		✓	334
560	Contract with Bass Foundry and Machine co		✓	340
561	Contract with Fort Wayne electric works		✓	344
562	Rail road track elevation Resolutions no 7 + 8		✓	345
563	Contract with Pennsylvania Rail Road Company		✓	346
564	Annexing certain Territory		✓	358
565	Contract with Brooks Construction Company		✓	360
566	Contract with Mollering construction Company		✓	366
567	Fire limits		✓	367
568	Annexing certain territory		✓	370
569	Theink Drive		✓	371

A B C D E F G H I J K L M Mc N O P Q R S T U V W Y Z

B

570	Salary of Dairy and Meat inspector	✓	373
571	certain part of Broadway placed in control of Park Commissioners	✓	375
572	To improve E. Wayne + E. Washington boulevard	✓	376
573	Pfeiffer Boulevard	✓	377
574	Contract with John Seelger	✓	379
575	Contract with Wm H. Dunn	✓	380
576	Tax Levy	✓	381
577	Beaver avenue to be plasure driveway	✓	382
578	Rudisill boulevard west of Hanna St.	✓	383
579	Contract with White company of Cleveland O.	✓	384
580	appointment of Weighers of Hay + Grain	✓	385
581	Annexing certain Territory	✓	387
582	Salary of Fire department to inspect buildings	✓	388
583	Salaries of Police Department	✓	391
584	Salaries of Fire Department	✓	393
585	Protecting Public health	✓	395
586	Regulate Moving travel and traffic	✓	398
587	amendment to Sign ordinance	✓	399
588	Changing name of Pfeifer avenue	✓	402
589	Authorizing Sale of certain property	✓	403
590	Contract with Fort Wayne electric works	✓	404
591	approving Track Elevation Resolution No 9	✓	405
592	Contract with Martin Howe coal co	✓	406
593	Contract with Robinson Fire apparatus Manufacturing co	✓	407
594	Tennessee Boulevard	✓	408
595	To issue Fifteen Thousand dollars Bonds	✓	409
596	Contract with Perfection Biscuit co	✓	411
597	Contract with Fort Wayne Electric co	✓	415
598	Contract with Fort Wayne Electric co	✓	416
599	Annexing certain territory	✓	417
600	Making certain Territory a part of the 5th – 6th – 7th + 10th ward	✓	419
601	Authorizing Park Board to improve streets in Lake Side	✓	423
602	Contract with U. S. Cast iron pipe and Foundry company	✓	425
603	Contract with Pioneer Coal Company	✓	428
604	Contract with Moellering Construction Company	✓	430
605	Contract with Brooks Construction Company	✓	431
606	Contract with Brooks Construction Company	✓	432
607	Contract with Moellering Construction Company	✓	433
608	Fixing time for employees to receive Salary	✓	434
609	Annexing certain Territory	✓	435
610	Authorizing the sale of certain Property	✓	437
611	Board of works to Control state Boulevard	✓	438
612	To improve Webster Street	✓	439

613	Regulating the use of Bicycles and Tricycles	✓		441
614	Additional duty Sergeant	✓		443
615	Tax Levy	✓		444
616	Authorizing $140.000.00 Bond issue	✓		446
617	To improve East Wayne Street	✓		448
618	Contract with Berghoff Brewing association	✓		449
619	Contract with Wm H. Lemm	✓		455
620	Contract with Joe H. Berrine	✓		456
621	Providing for placing certain wires underground	✓		457
622	Authorizing the sale of certain personal property	✓		460
623	Anthony Boulevard from State Boulevard	✓	✓	461
624	Fixing Salary of Police court Matron	✓		462
625	Ratifying issue + sale of refunding Bonds	✓		463
626	Installation of service lines and Meters for electric current	✓		464
627	Authorizing five additional firemen	✓		467
628	Shade Trees	✓		468
629	Salary of Electrician and asst Fire chief	✓		472
630	Salary of Sealer of weights and Measures	✓		473
631	Safety gates at Lake Erie R.R. Crossing	✓		474
632	approving Track elevation Resolution No 12.	✓		475
633	Contract with Perfection Biscuit company	✓		476
634	Disannexing certain territory	✓		479
635	Contract with Pioneer Coal Company	✓		480
636	Sale of Certain property	✓	✓	481
637	Requiring Ft Wayne + Wabash Valley Traction Co to extend local service on Lavina St line			482
638	Contract with Indiana Engineering and Construction Co	✓		483
639	annexing certain territory to eighth Ward	✓		487
640	Contract with American Cast Iron Pipe Co.	✓		488
641	Fixing Salary of clerk to building inspector	✓		491
642	Naming Molitor Street	✓	✓	492
643	Naming Schorr Street	✓	✓	493
644	Contract with Alberger Condensing Co.	✓		494
645	Contract with Ft Wayne Electric Works of General Electric Co	✓		502
646	Contract with Ft Wayne Electric Works of General Electric Co Meters	✓		511
647	Contract with Ft Wayne Electric Works of General Electric Co Transformers	✓		514
648	Contract with Ft Wayne Electric Works of General Electric Co Sidetrack	✓		517,
649	Regulating the sale of ice		✓	521
650	Contract United States Cast Iron Pipe and Foundry Co.		✓	522.
651	Contract with W. J. Stevenson, Sewer cleaning machine		✓	525
652	Ordinance regulating the tapping into Sewers		✓	528
653	Ordinance amending sign ordinance 538	✓		530
654	changing name of Court St. Packard Ave	✓	✓	531
655	Contract with Nap Emmeher	✓		532

C

656	Contract with Herman Depp Construction Co. Retaining Wall on Jefferson Ave	✓	544
657	Annexing Certain Territory to 10th Ward.	✓	546
658	Contract with E. D. Etnyre Co., for Street Motor Flusher and Oiler.	✓	547
659	An Order giving Controller power to loan money to Park Board, from General Fund	✓	549
660	An Ordinance Regulating the Hauling & Storage of Manure	✓	550
661	An Ordinance Authorizing Alienation of Certain Personal Property	✓	552
662	An Ordinance authorizing Bd of P. W. to employ 1 additional Sanitary Police & fixing salaries of all Sanitary Police	✓	553
663	An Ordinance prohibiting use of Traction Engines on streets and alleys	✓	554
664	An Ordinance amending certain sections and repealing a Section of Gen Ord No 626 Electric Wiring Installation	✓	555
665	An Ordinance Requiring the use of Peddlers, Hawkers or Vendors to have Scales on their Wagons	✓	557.
666	An Ordinance Empowering Bd of P. W. to pay Henry W Becker for Clerk Hire back pay $900.00 for Services rendered Elect'l Works		558
668	Contract with Olds Coal Company	✓	561
667	An Ordinance fixing the Tax Levy for Year 1915		560
669	An Ordinance Authorizing the alienation of and Appraisement of Certain Property	✓	563
670	An Ordinance concerning the Removal of habitation of families and other persons	✓	564
671	An Ordinance fixing the Salary of Superintendent of Streets.	✓	565
672	An Ordinance fixing the Salary of Clerk of Health Department.	✓	568
673	An Ordinance authorizing the Sale of House and Other building on East 20 ft. of Lot 11 Range 1 S.D.	✓	569
674	An Ordinance approving a contract with the Walter Bledsoe and Company	✓	570
675	An Ordinance approving a contract with the Lindley Schmidt Company	✓	574
676	An Ordinance regulating the operation of motor vehicles	✓	578
677	An Ordinance amending section one (1) of General Ordinance No. 443	✓	579
678	An Ordinance approving a contract with the General Electric Company.	✓	581
679.	An Ordinance approving a contract with the Wm Kaough Coal Company.	✓	584
680.	An Ordinance amending the ordinance regulating the sale of Fish and meat		587
681	An Ordinance approving R.R. Track Resolutions #s 15-16-17-18-19-	✓	590
682	An Ordinance changing Thomas Street & Bowsea Avenue	✓	592
683	An Ordinance approving a Contract with the Gen. Electric Co.,	✓	593
684	An Ordinance approving a Contract with the Gen. Electric Co.	✓	596

C D E F G H I J K L M N O P Q R S T U V W Y Z

General Ordinance No. 3,

An ordinance providing for all matters concerning affecting or relating to the construction, equipment alteration repair or removal of buildings, structures and appurtenances thereof, Erected or to be erected in the City of Fort Wayne, Indiana, as amended May 25th 1909 the same to be known and cited as the Building Code.

The City Council of the City of Fort Wayne, Indiana do ordain as follows

Chapter 1.

Section 1

Appointment of Building Inspector

That the Board of Public Works of the City of Fort Wayne, shall appoint subject to the confirmation of the City Council a Building Inspector who shall be a resident and elector of the City of Fort Wayne, and who shall have had five (5) years experience as an architect, civil engineer or builder, or shall have served in such simular occupation which shall have qualified him for the duties of said office

Such Building Inspector shall hold said office for the term of two (2) years next succeeding the date of his appointment and until his successor is duly appointed and qualified. Such Building Inspector shall receive an annual salary of Eighteen hundred Dollars ($1800.00), payable monthly. Prior to entering upon his duties he shall take the oath required by law, and shall execute a bond to the City of Fort Wayne in the sum of $2,000 to be approved by the Controller, conditioned for the faithful performance of his duties

The Building Inspector herein provided may be removed at any time by the Board of Public Works for incompetency or neglect of duty, and he shall be at all times under direct control of the Board of Public Works

Section 2,

Building Inspectors Clerk

The Building Inspector when necessary shall be allowed the sum of Forty Dollars ($40) per month for clerk hire, the same to be drawn upon proper vouchers from the General Fund

Section 3.

Applications for Permits, Blanks etc.

Whrn any person, persons, or corporation shall be desirous of erecting, repairing, changing, or altering or removing any building or part of any building, any structurn or part of any structurn or wall, platform, staging or flooring within thr limits of thr City of Fort Wayne (except in cases of repairs for maintenance not affecting thr construction or sanitation or other vital features of thr building or structurn thr cost of which shall not exceed ($100), hr or his agent shall make application at thr office of thr Building Inspector for a permit so to do, and if it shall appear to thr Building Inspector that thr laws and ordinances of thr City are complied with, hr shall give thr permit applied for upon payment of thr fee hereinafter prescribed: provided that in case of buildings of thr first and second class, thr applicant for a permit shall furnish thr Building Inspector with a written statement on blank forms for thr purpose, such blanks to be furnished by thr Building Inspector; such statement to show thr location, thr intended use and thr approximate cost of thr proposed building or structurn; such statement shall also contain an agreement to thr effect that thr proposed building or structurn will be built in accordance with thr plans and specifications, copies of which, together with such statement and agreement, shall be filed with thr Building Inspector

Thr said person, or persons, or corporation or Contractor or Employee having in charge thr construction of any building or structurn, a permit for such work, having been issued shall place conspicuously upon said building or structurn a sign to be furnished by thr Building Inspector bearing thr words, "Building Permit Issued".

Section 4.

Thr fees for building permits shall be as follows:

First and second class of 40,000 cubic feet or less	$ 2.00
First and second class of more than 40,000 cubic feet	.05 per M.
Third Class	1.00
Fourth Class	.50
Removal Permits	5.00

Section 5

Inspection of Work under Construction

It shall be the duty of every Building Inspector appointed under the provisions of this Chapter to inspect all buildings of first and second class which may be in the course of erection construction or alteration within the limits of the City to see that said building or buildings and being erected constructed or altered according to the provisions of the various Chapters of the Building Code, and all acts and ordinances in force in said City and to observe the manner adopted for the security thereof against fire, and the safety of occupants: to see that the materials used are suitable for the purpose and that it is of sufficient strength and solidity for the purpose for which it was designed

Before the foundations are laid he shall examine the trenches dug for the same and be fully satisfied that the soil or substratum is sufficient for the ~~strong~~ structure, or at least the best that can be obtained; and should the nature of the soil [illegible] and the work of sufficient magnitude as to require piling such piling should be ordered done. Provided, that if it be deemed necessary by the Building Inspector, his visits and inspections shall be repeated from time to time during the construction, erection or alteration of such building or buildings. He shall on application for that purpose, furnish the owner or owners, contractor or contractors, his certificate that the said house or building is in all respects conformable to law and properly constructed

It shall be unlawful for any person persons or corporation to erect, construct or build, or cause to be erected, constructed or built, any brick, iron, granite, cement, concrete, marble, or stone house or building, or any house or building composed partly of brick, iron, granite, cement, concrete or stone or to alter any such building so as to make it substantially a new building unless the same shall have been inspected from time to time by the Building Inspector and a certificate furnished by him that the said house or building is properly constructed and in all respects safe and secure.

Section 6

Information Furnished by the Building Inspector

The Building Inspector shall when requested furnish preliminary information relative to the application or interpretation of any of the provision of the various Chapters of this

ordinance when the same is needed in the preparation of Plans.

The Building Inspector shall be notified by the owner or his authorized agent or by the builder, whenever any building is ready for inspection and such inspection shall be made within twenty-four (24) hours. And no building partition or structure of the first or second class shall be covered in by lathing, plaster sheathing, or otherwise until such inspection is made and the Building Inspector has issued a certificate to the effect that the said building, partition or structure has been constructed in compliance with the provisions of the various Chapters of this Code

Section 7.

Unsafe and Unsanitary Buildings

It shall be the duty of the Building Inspector to inspect any building or structure reported or believed to be unsafe or in any unsanitary condition, and if so found, to require the same to be put in safe and sanitary condition without unnecessary delay.

In any case where the public safety requires immediate action the Building Inspector may enter upon the premises with such assistance as may be necessary and cause any building or structure to be made secure without delay so that the occupant or occupants and passers by may be protected, and the expense so incurred shall be borne by the owner of the property.

Section 8.

Report of Work Done

The said Building Inspector shall keep an office in the City Hall where it shall be the duty of said Building Inspector to keep a record of all permits issued, the same to be regularly numbered in the order of their issue, and also a record of the statements upon which permits are issued and such statements and records shall be left in the permanent files of his office

He shall also file a report with the Board of Public Works on or before the tenth day of each month for the calendar month preceding, showing the number of permits issued within such month. He shall also on the thirty-first day of December of each year make a full and complete report to the City Council, keeping a record of the same, such report to show the number of buildings erected within the city limits during the preceding calendar year, the kind character and

classification of such. buildings of what material construct-
ed. purpose for which each is to be used. the location and
cost.

Chapter II

Classification of Buildings According to Occupancy

First Class

Section 1.

Public Buildings

All buildings devoted in whole or in part to the use of the
general public. either for the purposes of state or places of.
assemblage

Section 2.

Detention Buildings

Includes all. public or private hospitals reformatories. prisons
police stations and buildings for housing persons of feeble minds
or persons held under restraint or against their [illegible]

Section 3.

School. Buildings

Includes. all schools. colleges or other buildings containing
class drawing. lecture rooms or rooms for the purpose of edu-
cation or instruction. If any such. building has an assembly.
room of greater capacity than four. of the class rooms therein
such assembly. rooms shall be deemed. Assembly. Halls.

Section 4.

Assembly. Hall.

Includes all churches, convention halls auditoriums expos
ition buildings. music halls railroad. depots, or that part
of any. building containing an assembly room. for a concourse
of more than 100 people.

Section 5

Theaters.

Includes all theaters, opera houses. play houses. pavilions
or any. assembly. hall. designed or used for the entertainment
of spectators having a permanent stage upon which stage
scenery and theatrical apparatus is employed

Section 6

Public Utility Buildings

All other buildings used or owned. by the general public but
not classified by. the foregoing divisions or sections

Section 7

Club. Houses.

A building used or intended for use by an organization or society for mutual entertainment or recreation having a common kitchen, dining room or other rooms of utility and recreation and containing lodging apartments for the use of the members of the organization only will be classed as an apartment house.

Section 8.

Hotels

Includes all hotels, public inns or part thereof designed to be used for supplying food or shelter to residents or guests and having a public dining room, cafe or office or either A public lodging house or building used for the shelter of residents or guests whether with or without a public dining room or cafe, shall be classified as a hotel.

Section 9.

Office Buildings

Any building designed or used for office purposes in the conduct of general business, but which may have a store or sales room on the ground floor, and no part of which building shall be used for living purposes, except for the janitor and his family.

Section 10.

Store Buildings

Any building designed or used for the sale of merchandise or objects of utility or general supplies

Second Class

Section 11.

Factory

Any building designed or used for the manufacture of goods wares merchandise or articles of general or special utility

Section 12.

Apartment House

Any building or portion thereof designed or used as a residence for more than two (2) families or households living independently of each other and in which every family or household shall have provided for it a kitchen, set bath tub and water closet separate and apart from each other but with or without a common right in the halls and stairways.

Section 13.

Tenement House

A Tenement house is any house or building or any portion

thereof which is designed to be used or is used or occupied as the home or residence of more than two (2) families living independently of each other, and doing their cooking upon the premises, but having a common right in the yards, water closet set bath tubs fixtures or some of them

Any building having a store on the first or ground floor and sleeping or living apartments on the second story for more than one family will be classed as a tenement

Third Class.

Section 14

Dwelling House

A dwelling shall be taken to mean and include any building which shall be intended or designed for, or used as the home or residence of not more than two (2) separate and distinct families and in which not more than sixteen (16) rooms shall be used for the accommodation of boarders and no part of which structure is used as a store or for any business purpose

Fourth Class

Section 15.

Stables

Includes all buildings designed or used for public livery boarding or transfer stables private barns, carriage houses, sheds, pens, coops stock-yards or any building for the feeding or sheltering of animals or fowl

Chapter III

Classification of Buildings According to Construction

Section 1.

Fire-Proof Buildings

As used in the various chapters of this code shall apply only to buildings in which all parts that carry weights or resist strains are constructed wholly of stone burnt clay, iron, steel, or concrete and in which all stairs elevators partitions and other permanent fixtures are made entirely of incombustible materials and in which metallic structural members are protected against the effects of fire by coverings of a material entirely incombustible and slow heat conducting

Section 2

Semi-Fire-Proof Buildings

when enclosing walls and roof coverings are made of incombustible materials with doors, windows and frames of

wood. but with interior walls of brick, or with columns or girders made of fire-proof iron or steel and with the floor construction of wooden beams, joists, and ceilings furred and fire-proof material and all concealed spaces fire-stopped, and all sub-divisions made with incombustible partitions; or if the interior is of mill construction, wood columns containing 100 square inches or more need not be fireproofed. In buildings of this class, a single thickness of metal lath or furring and hard incombustible plaster will be deemed sufficient protection

Section 3.

Mill Construction

When the enclosing walls and roof covering are made of incombustible materials, with doors, windows and frames of wood but with interior walls of brick or columns and girders and the floor and roof systems composed of heavy timbers and planks with no concealed air space between

Section 4.

Ordinary Construction

As used in the various chapters of this code means the ordinary system of construction in which timbers and other structural parts are not protected with fire-resisting coverings.

Section 5

Frame Construction

When the enclosing and interior partition walls are constructed entirely of wood. Wooden frames covered with veneer will be classed as frame buildings.

Chapter IV

Fire Limits and Kinds of Buildings Therein

Section 1

Limits

The Fire Limits are and shall be that territory in the city of Fort Wayne contained within the boundary limits described as follows: Beginning at the intersection of East Superior St. and Lafayette St (extended) thence south along Lafayette St to East Wayne St. thence along East Wayne St. to Barr St. thence south along Barr St. to East Jefferson St. thence west along Jefferson St. to South Clinton St. thence south along Clinton St to main tracks of the Pittsburg, Fort Wayne & Chicago Railroad. thence west along said main tracks to Harrison St. thence north along Harrison St. to West Wayne St. thence west along Wayne St. to Webster St. thence north along Webster St. Wayne St (extended)

to West Superior St. thence in an easterly direction to Wells St thence northerly on Wells St. to Fairmount Place. thence westerly on Fairmount Place to the first alley west of Wells St. thence in a southerly direction along said alley and the west line of said Alley produced in a southeasterly direction and paralleled with Wells St. until said west line intersects Superior St. thence east along Superior St to the point of beginning

Section 2.

Kind of Building Thereon

Every building of whatever class hereafter erected or altered within the Fire Limits described in Section 1. of this Chapter shall be of brick. stone. steel iron or other substantial and incombustible material except as otherwise herein provided

No building of frame construction shall be moved to a location within the Fire Limits

No building of frame construction shall be erected. altered or moved from one location to another within the Fire Limits

All roofs within the above described territory must be of incombustible material approved by the Building Inspector

Grain elevators located along the railroad if isolated may be erected within the above described territory provided that crib-construction is used not less than six inches ~~less~~ thick and that the walls are covered on the outside with sheet-iron sheathing and the roofs with incombustible material

Section 3

Building of Frame Construction Damaged.

Whenever any building of frame construction within the Fire Limits shall have become damaged or impaired to the extent of fifty per cent of the value of such building the Building Inspector shall order such building to be taken down. If the owner of such building objects to such conclusion. arrived at by said Building Inspector the Building Inspector shall notify the Chief of the Fire Department and the City Engineer and they shall make an examination of the building and make a report to the Building Inspector as to the amount of damage. Whenever such building shall be adjudged by such arbitrators to have been damaged or impaired to the extent of fifty per cent of its value such building shall be condemned by the Building Inspector and it shall be unlawfull. as aforesaid to repair the same, but it must be taken down.

If such building be adjudged unsafe, the Building Inspector may order its immediate removal at the expense of the owner

Section 4

The term "Fire Limits" wherever used in this Building Code shall refer to the territory within the boundary lines described in Section 1 of this Chapter or as described in any amendment of said section and Chapter which may be hereafter adopted by the City Council of Fort Wayne Indiana

Chapter V

Definitions

Section 1

Alterations

Alteration means any change or addition (excepting any necessary repairs) in to or upon any building affecting an external party or partition wall chimney flue stairway or the plan arrangement or structural part of any building, or such as conflicts with any of the requirements of this ordinance.

Section 2

Areas

Sub-surface excavations adjacent to the building line for lighting or ventilation of cellars or basements

Section 3

Attic Story

A Story situated either in whole or in part of the roof

Section 4.

Basement Story

A Story whose floor is three feet or more below the sidewalk and whose height does not exceed eleven (11) feet in the clear and is suitable for habitation.

Section 5

Bay-Window

A floor projection for a window other than a tower-projection or a show window.

Section 6

Bearing Walls

Those upon which beams, trusses or girders rest

Section 7

Brick

The word "Brick" wherever used in this ordinance referring to thickness of wall shall mean "eight inches" and likewise "one and one-half brick" shall mean twelve inches

Section 8.

Brick Building

a building, the walls of which are built of brick, stone, iron or other substantial and uncombustible materials

Section 9.

Building Line

The line of demarkation between public and private property

Section 10

Business Buildings.

These embrace all buildings used for business purposes thus including among others hotels, theaters, and office buildings

Section 11

Cellar.

A cellar is that portion of a building below the first floor of joists if partially or entire below the level of the passing street or ground, and not suitable for habitation.

Section 12.

Cement Mortar

a proper portion of cement and sand without the admixture of lime

Section 13.

Concrete

Concrete is a species of artificial compound of (1) of the matrix composed of cement and sand, and the (2) aggregate which may be either gravel or broken stone

Section 14.

Division Wall

One that separates part of any building from another part of the same building

Section 15

External Wall

An external wall means every outer wall or vertical enclosure of a building other than a party wall

Section 16

First Story)

The story the floor of which is at or above the level of the sidewalk or adjoining ground, the other stories to be numbered in regular succession, counting upward.

Section 17

Foundation

That portion of the wall below level of street curb and where the wall is not on a street, that portion of wall below the level of the highest ground next to the wall

Section 18.

Frame Building

A building or structure the exterior walls of which are constructed of wood or veneered with brick stone or concrete

Section

Inflammable Materials

Inflammable material consists of dry goods, clothing millinery and the like in stores flyings or goods in factories or other substances readily ignited by droppings or flaming from electric lights

Section 20.

Mansard. Roof

A. mansard. roof is one formed with an upper and under set of rafters and upper set more inclined to the horizon than the lower set

Section 21

Parking

Parking is the space between the sidewalk and the building line

Section 22

Partition

An interior division constructed of iron. glass, wood. lath and plaster or other materials.

Section 23

Stand

A. skeleton structure for storage or shelter

Section 24

Show. Window

A store window in which goods are displayed for sale. or advertisement

Section 25

Standard. Fire Doors

Wood. doors, triple thickness of wood, cross or diagonal constructed covered. on both sides and all edges with sheet iron tin, Joints securely clinched and nailed

Chapter VI

Materials. Fire Walls, etc

Section 1

Quality of Materials

All materials are to be of good quality for the purpose for which they are intended to be used, and conform to trade and manufacturers standards. All materials must be free from

imperfections whereby its strength and durability may be impaired and no material will be classed as good when its strength falls below ten (10) per cent. below the best of its kind.

No salmon brick shall be used in any building where exposed to the weather or in piers, nor in any part of any wall where there is unusual weight, or where there is more than thirty-five (35) feet of wall above them; and in no case shall more than fifteen (15) per cent of salmon brick be used

The sand used for mortar in all buildings shall be clean sharp, and coarse sand and well washed and free from loam or other vegetable matter

Section 2.

Fire Walls

Any brick building of three (3) or less stories and a basement and not more than forty-eight (48) feet in height and having a flat roof shall have all the walls except rear walls extend eighteen (18) inches above the roof. Such walls shall not be less than twelve inches thick and shall have proper copings of incombustible material. Any such buildings having a double pitched roof shall have its division and side walls extended up forming fire walls in like manner Walls at the eaves of all roofs other than flat roofs shall be carried up their full thickness of not less than twelve (12) inches flush with upper edge of the rafters of the roof and the sheathing boards shall be bedded in mortar on such walls

Any brick building of more than three (3) stories and a basement or more than forty-eight (48) in height having a roof as prescribed in the preceding paragraph of this section shall have applied to it the same provisions except that the parapets shall extend not less than thirty six (36) inches above the roof and properly coped in like manner

Section 3.

Openings

No opening or doorway shall be cut through the party wall of a brick building without a permit from the Inspector and every such opening or doorway shall have the top, bottom and sides of stone, brick, or iron and shall be protected on both sides of the wall by standard fire doors separated by the thickness of the wall and hung to the rabbetted iron frames or to iron hinges in brick or stone Rabbets which doors shall not exceed ten (10) feet in height by eight (8) feet in width

Section 4

Temporary Structures.

Any temporary support placed under any structure wall, girder or beam during the erection, finishing, alteration, or repairing of any building or structure, or any part thereof, shall be of sufficient strength to safely carry the load to be placed thereon.

Temporary frame structures for the use of builders while engaged in building operations, may be erected adjoining the work in any part of the city; said temporary frame to be removed as soon as the permanent building is in place

Temporary staging for observation grandstands, platforms and similar structures, shall not be erected upon the roof of any building or in any locality within the city, without a written permit from the Building Inspector, which permit shall only be issued after complete plans and specifications for the proposed structure shall have been filed in the office of the Building Inspector,

Section 5

Open Light Wells

Open light wells or courts shall not be permitted to extend through from floor to floor above the second floor, in any store building warehouse, factory, workshop, or in any fireproof building over two stories high, except that the floor openings shall be covered over with heavy glass of strength equal to that of the floor or that the opening be enclosed the entire height with wire glass of suitable thickness

Section 6

Heights and Proportions

No building or other structure hereafter erected, except a church spire, shot-tower, water-tower or smoke stack shall be of a height exceeding two and one-half (2½) times the width of the widest street upon which the building faces, but no building shall be over two hundred (200) feet high.

Chapter VII

Chimneys Flues, Stacks and Heating

Section 1

Height above Roofs

No chimney shall be built with less than four (4) inch walls and no chimney top shall be less than five (5) feet above the roof (for flat roofs) and two (2) feet above the ridge of any pitched roof. Ordinary flues in business buildings shall have walls and eight (8) inch arms; flues larger than two hundred

and fifty (250) square inches and less than five hundred. (500) square inches shall be surrounded with walls not less than eight (8) inches thick, the walls of such flues above the inlet funnel shall be twelve (12) inches thick for the first fifteen (15) feet around and above such inlet: tops of such chimneys to be at least eight (8) feet above the roof. or five (5) feet above the highest part of the roof within fifty (50) feet of such chimney.

Flues with more than five hundred (500) and less than eight hundred (800) inches area shall not have less than twelve (12) inch walls for the first thirty-six (36) feet and sixteen (16) inch walls opposite the inlet. and ten (10) feet above the same: top of chimney ten (10) feet above the roof or seven (7) feet above the highest part of the roof within fifty (50) feet of such. chimney provided that all chimneys having walls less than eight (8) inches thick, shall be plastered on the brick or covered with metallic lath or wire cloth before plastering

The provisions as to the thickness of walls pertaining to chimneys. shall be applicable only to such chimneys as are part of or are situated in any building. Flues in party walls shall not extend beyond the center of the wall, joint flues in party walls shall be separated by. a four (4) inch width of fire brick their entire height.

Section 2

Each dwelling tenement, or apartment in which cooking is done shall have at least one chimney built as hereinafter prescribed.

Section 3.

Construction of Chimneys and Flues

Chimneys shall be built of brick, stone, or other similar fireproof material and in no case shall a chimney rest upon a flooring of wood. or timber construction. Every chimney not forming a part of the wall. shall rest upon the ground. of other sufficient fireproof foundation. Brick work of all flues, without reference to the purpose for which they may be intended, must be laid with solid joints, thoroughly. filled with mortar or grouted and the joints struck flush. on the outside and plastered on the inside where they pass through the floors and partitions and between the ceiling joists and rafters, and no opening shall be made or left between the joists for any purpose.

Wooden floor beams. studs, and other wood work must be framed around the flues at each and every story and be not less than one (1) inch. except trimmers which shall be two (2)

inches distant therefrom if flue is lined or two and three inches respectfully when the flue lining is omitted

Section 4.

Walling of Flues

No flue of any area of sixty-four. (64) square inches or greater shall be without flue-linings.

Chimneys and flues less than two hundred and sixty (260) square inches in all buildings shall have walls at least one brick thick if of brick, unless terra cotta or fire clay flue linings are used for their full height or if used only for vent flues in either of which cases one-half (½) brick of brick work may be omitted. If built of material other than brick they shall have walls at least Eight (8) inches thick and shall have an additional lining of brick work or terra cotta or fire clay flue lining. Standard fire clay flue linings may be used for flues of from sixty-four (64) to five hundred and seventy six (576) square inches in clear area

The walls back of flues in party walls, and walls between flues in adjoining buildings shall in no case be less than one brick, and between each flue in a group of flues one-half brick in thickness

The top of all smoke flues, chimneys or stacks within one hundred feet of any viaduct or bridge, shall be at least twenty-five (25) feet above the roadway of the same

Section 5,

Hollow Chimney Walls

All brick smoke flues, chimneys or stacks having a greater area than five hundred and seventy six (576) square inches, shall have hollow walls in which the combined thickness of the enclosing walls shall be at least one and one half brick and the air space between the inner and outer walls shall not be less than four (4) inches if straight, and not less than two (2) inches at its narrowest neck if the outer shell is pitched

Section 6.

Topping Out

All smoke flues, chimneys or stack shall be topped out with brick stone, terra cotta or cast iron, properly anchored, and if such chimney flue is liable to emit sparks or if shavings or saw-dust is used for fuel or is used as a cupola, it shall be covered over the top with a heavy wire netting.

Nothing in this section shall be so construed as to permit the use of any flue lining or crock pipe as a smoke flue without be walled in with brick or other fire proof material.

Section 7.

Heating

The subjects under this Chapter include all pipe and heating apparatus and their enclosures in a building.

Section 8.

Flue Connections

All boilers, furnaces, fireplaces, ovens and other heating apparatus mentioned under this Chapter shall be properly connected with a flue chimney, or stack, as directed and within the shortest distance possible.

This shall include all permanent or temporary heat generators which are used in the erection of a building and no such heat generators shall be hereafter placed upon the floor or in close proximity to the building which allows the product of combustion to escape directly into the air within twenty (20) feet of any building without being connected with some flue as herein prescribed.

Section 9.

Boilers - Brick Set

No brick-set or vertical or horizontal boiler for the generation of hot water or steam for heating or power, or any portable power boiler or engine over ten (10) H. P. shall be placed on any wood floors or beams. And when such boilers of 10 H. P. or less are so placed on wood floors or beams they must be protected by at least 3 inches of concrete or ½ brick of thickness laid with joints flushed with cement, the cement or brick base to extend 12 inches beyond the sides and rear, and 3 feet in front of such boiler

Section 10

Cold Air Boxes

The cold air boxes of all hot air furnaces shall be made of metal brick or other incombustible material.

Section 11.

Ranges

Where a kitchen range is placed less than six (6) inches from a wood stud partition, the said partition shall be shielded with metal from the floor to a height of not less than three (3) feet higher than the range. All ranges on combustible floors or beams that are not supported on legs, and have ash pan three (3) inches or more above their base, shall be set on suitable brick foundations, consisting of two courses of brick well laid,

in mortar on sheet iron, except small ranges that have as to pass three (3) inches or more above their base. which shall be placed on at least one course of brick work, on sheet iron or cement, No range shall be placed against a furred wall. All lath and plaster or wood ceiling over large ranges, and ranges in hotels and restaurants shall be guarded by metal goods, placed at least nine (9) inches below the ceiling.

Section 12,

Gas Stoves and Ranges

All low gas stoves shall be placed on metal guard plates placed four (4) inches below the burners and all woodwork under them shall be covered with metal Gas ranges if properly air insulated within themselves shall be placed at least one foot distant from all unprotected woodwork or plastered stud partitions, and in no case shall rubber hose or rubber tubing be used to make any gas connections except for drop lights.

Section 13.

Bake Ovens

Bake ovens are to rest on solid foundations or metal beams and columns, the sides and ends shall be at least two (2) feet from any woodwork, and the crown of arch at least four (4) feet from ceilings that have wood joists. The hearth in front of bake ovens shall extend at least three and one-half (3½) feet beyond the face of said oven.

Section 14.

Smoke Pipes

Where smoke pipes pass through a wood or plastered stud partition or furred wall or floor, they shall be surrounded by either a body of hard, incombustible materials measuring at least four (4) inches all around said smoke ~~stack~~ pipe or they shall be surrounded by a double safety thimble of sheet metal, made of two concentric rings of sheet metal at least one inch apart and the entire thimble so constructed that there will be a circulation of air between the rings forming same. No smoke pipe shall project through any external wall unless connected with a chimney or metal stack carried above the roof

No stove or smoke pipe or any pipe conducting the products of combustion from any range, oven or heater shall be concealed in any wood partition or be placed nearer than nine (9) inches to any unprotected lath and plaster or board partition ceiling

or woodwork.

Smoke pipes of less diameter than twelve (12) inches shall be kept at least twelve (12) inches distant from any woodwork unless the same is properly protected by a metal shield in which case, the distance shall not be less than three (3) inches

Smoke pipes of a greater diameter than twelve (12) inches and less area than six (6) square feet must be kept at least twenty (20) inches from any woodwork, unless the same is properly protected by a shield in which case the distance shall not be less than eight (8) inches.

Smoke pipes of larger area than six (6) square feet shall be kept at least three (3) feet distant from any woodwork unless the same is protected by a shield, in which case the distance shall not be less than sixteen (16) inches

Section 15.

Smoke Pipe Shield

The metal shield prescribed in the previous Section shall be at least one and one-half (1½) the diameter in width and shall have a ventilated air space of at least one (1) inch between shield and woodwork.

Section 16.

Hot Air Pipes

Hot air conductors built in between timbers or other combustible material must be made of double thickness known as safety pipe metal.

All pipes leading from furnace to stack and register boxes shall be made of bright tin and insulated with asbestos sheathing

Such pipes are to be made with airtight joints and to be securely fastened in place.

When the air conveyed through pipes is heated in an ordinary hot air furnace or in any other ~~place~~ apparatus by direct contact of the air with the fire-box, the material used for these ducts, pipes and register boxes, shall be bright tin and insolated with asbestos

Section 17

Wood Casings

All wood boxes or casing enclosing steam or hot water pipes and all wood covers to recesses in walls, in which steam or hot water heating pipes are placed, shall be lined with asbestos, or said pipe shall be covered with incombustible sectional pipe covering at least one-half of an inch thick

Section 18

Incombustible Pipe Covering

No concealed pipe shall be covered with a covering whose non-conductivity depends upon cork, felt, or any other organic matter.

All coverings of heated surface or surfaces requiring protection from heat, and all concealed or inaccessible steam or hot water pipes, and all coal and ice water pipes and other pipes in buildings having iron frames, shall be made of standard fire resisting covering, either of magnesium carbonate, calcium carbonate with binders of asbestos fiber, or asbestos fiber and sheet coverings.

Section 19.

Boilers

Boiler and fuel rooms and smoke houses, which may hereafter be constructed, shall be built throughout of incombustible material

All the openings in such boiler and fuel rooms and smoke houses, if same is located within thirty (30) feet of any other building shall have shutters, and doors of metal or wood covered with metal on both sides and edges.

Boiler and fuel rooms, when constructed in buildings shall be separately enclosed, in brick walls so arranged that all openings between them and other parts of the building will be securely closed with fire doors at the end of each day's work.

Section 20.

Drying Rooms

All floors, walls, ceilings and partitions enclosing drying rooms when not made of fireproof material, shall be with lathed and plastered or covered with metal, tile or other hard incombustible material

Section 21,

Heating Apparatus in Basement.

All portable hot air furnaces shall be kept at least two (2) feet from any wooden or combustible partition and at least eighteen inches from any wooden or combustible ceiling unless protected by one-third inch incombustible material for a distance of at least six (6) inches from the furnace.

When heating boilers are used that portion of the ceiling over the boiler and within a radius of four (4) feet thereof shall be plastered on metal lath or be protected by metal shields.

Section 22

Protection Against Molten Metal. Hot Liquids Gases and Dust.

In every factory and work shop all machinery and appliances connected therewith. also every. vat. pan or other structures with molten or hot liquids, shall be placed upon an incombustible foundation or hearth and shall be constructed in such manner and so guarded and further protected by. such ventilating ducts or pipes as to protect those employed in their operation or use or about them.

Section 23

Dangerous Chimneys and Flues

It shall be unlawfull to maintain any chimney flue fireplace. or heating apparatus on any premises when in the opinion of the Building Inspector, they shall be dangerous or unsafe by. reason of endangering the buildings on said or enjoining premises by. fire or otherwise. In all cases the Inspector shall at once notify in writing the owner. agent, or other party having an interest in said premises and shall require him to make the same safe: and upon the neglect of said persons so notified to comply with the provisions of said notices for a period of fifteen (15) days after the services of said notice upon him he shall be subject to a fine of not less than one dollar and not more than fifty dollars and each days continuance of such violation shall constitute a separate offense.

Chapter VIII

Stairs Halls and Entrances

Section 1

Stairs and Ladders to Scuttles

All buildings over two stories in height shall have scuttles in roof covered with uncombustible material and iron stairs or ladders leading thereto from the floor below and no scuttle shall be less in size than twenty (20) by thirty (30) inches nor shall any scuttle be placed in any place but a hallway if the interior is subdivided into rooms

The lid to any scuttle shall not be locked in any way except with an ordinary bolt or hooks which can be withdrawn without the use of a key. The ladder to the roof of any building requiring fire-escapes shall be of iron

Section 2.

Stairs in School Buildings

School buildings, if more than one story in height, and having more than three rooms above the first floor, shall have at least two separate and distinct stairways as far remote from each other as practicable. School buildings, or all buildings of the first and second grade, containing a general assembly room shall have stairs and fire escapes proportioned as prescribed for assembly halls.

Section 3.

Stairs Support

All stairs to be constructed to support a live load of not less than one hundred and fifty (150) pounds to the square foot, and the supports at the foot of same to safely carry at least two-thirds of the total of this load.

Section 4.

Exit of Hotel, etc

In all buildings used as hotels, tenements, lodging or rooming houses, the halls, stairways, passageways, and exits shall be arranged to facilitate egress in case of fire or accident, and all such buildings having more than twenty-five (25) rooms above the first floor, shall have at least two independent stairways connected with the ground floor, each stairway not less than four (4) feet wide, and at opposite ends or sides of the building.

All doors at the foot of such stairways shall open outwards and never be fastened but with a movable bar or bolt, readily drawn from the inner side without the use of any key or combination whatever. At the top and foot of all such stairs there shall be kept burning a red light from 9 P. M. to 6 A. M. of each day

Section 5.

Stairways in Workshops

In all buildings of class one (1) which are used as workshops or which are used as sales rooms, where there is an occupancy of the same at any one time of one hundred (100) or more persons employed or engaged therein, there shall be at least two staircases each not less than three feet in width. If the number of persons so employed exceeds three hundred (300) then the width of the stairs shall not be less than five (5) feet. If the number of persons or occupying such premises exceeds eight hundred (800) there shall not be less than three stairways not less than five (5) feet in width.

In all cases the stairways shall be located at as great a distance from each other as practicable and the number of persons above any floor shall be counted as being on that floor as well as being counted on the floors above: provided that in fireproof buildings, one less flight of stairs than above called for may be used. All stairs over five (5) feet shall have railings on both sides

Section 6.

Width of Doors

The aggregate width of doors opening at the street level in buildings of Class 1 and 2 shall be equal to the aggregate width of stairs: and in no case shall the doors leading to any means of egress be locked, or the egress in any ~~manner~~ way be obstructed during the occupancy of any such building

Chapter IX

Roofs

Section 1

Shingle Roof

The use of shingle roofs or other forms of combustible roof coverings upon buildings erected or altered within the fire limits is prohibited

Section 2

Gravel Roof

A roof whose slope is not more than three (3) inches per foot horizontal and the coverings of which is made with a composition of felt and gravel, shall be considered incombustible under the provisions of the various Chapters on buildings of all classes

Section 3.

Snow Brakes

Snow brakes or guards made of incombustible materials shall be attached to all roofs of buildings over two stories or twenty-five (25) feet high hereafter constructed or altered along any courtway or street lines, or within ten (10) feet of the same having a pitch of more than twenty-five (25) degrees, unless projecting cornices or gutters are so arranged as to form adequate snow guards

Section 4.

Down Spouts and Gutters

All buildings shall be provided with proper metallic spouts and eave or cornice gutters for conducting water from the roof to the ground, sewer or street, in such manner as shall protect

the walls and foundations from damage and in no case shall water from roofs be allowed to flow upon sidewalks, but shall be conducted by drain pipe or pipes to sewer or under sidewalks to the gutter where no sewer exists.

Chapter X

Skylights and Floorlights

Section 1.

Skylights

In all buildings hereafter erected, the roof immediately over the enclosed elevator openings stairways, hoistways chutes or well-holes shall be provided with skylights or side lights above the roof having a glazed area of at least three-quarters of the shaft. The skylights shall be made of glass set in metal frames, set on curbs not less than three (3) feet above the roof. Said curbs shall conform to the construction of the building, but in all cases shall be covered on the outside with metal or other incombustible material.

All skylights shall have immediately underneath or above the glass or wire netting made of wire not smaller than No 12 and to be netted to not more than one inch mesh, securely fastened therein, unless the glass contains a wire netting within itself.

In unenclosed elevator shafts, where the machinery can be placed between the attic floor and the roof, such machine loft shall be enclosed on all sides in the attic by incombustible partitions and fire doors, and if such loft is not provided with equivalent window space in the outside walls then each such enclosure shall be provided with a ventilated skylight with a glass area of no less than one-third (1-3) of the area enclosed

Section 2.

Floor lights used for transmission of light to floors below shall be constructed either of metal frames and bars or plates; and if any glass in the same measure more than sixteen (16) square inches, the said glass shall be provided with a mesh of wire, either in the glass or under the same, and the floor lights shall be of the same proportioned strength as the floors or sidewalks in which they are placed or else a railing four (4) feet high shall be built around the same

Chapter XI

Fences and Railings

Section 1.

Temporary Fences

Temporary wooden fences to shield lots during building operations may be erected upon public property after a permit for the same has been obtained. but they shall not be less than five (5) feet nor more than eight (8) feet in height. and all such fences shall be removed within ten (10) days after the external walls of the building are erected. and the roof enclosure is covered in

Section 2

Guard Rails

Metal guard rails not less than forty two (42) inches in height with not less than two intermediate rails equally spaced. shall be placed along all open areas or passageways or stairs crossings areas from the street to the entrance to the building, or along any area which adjoins habitable rooms in a basement, Said rails shall be of sufficient strength to resist the pressure of a crowd.

Section 3

Gratings

Buildings hereafter to be erected shall have no open gratings covering the areas adjoining any habitable rooms in any basement except for cellars in private property where there is no thoroughfare

Section 4

Balcony Railings

All railing for exterior or interior balconies along court well holes and light shafts shall not be less than Thirty six (36) inches high. and on buildings over three stories high all exterior railings shall be metal

Section 5

Stair Railings

The banisters and well-hole railings of public stairs shall not be less than thirty-four (34) inches high measured on the plumb. in the center of the treads or platform landings

Chapter XII

Dangerous Buildings - Repair and Removal.

Section 1.

Character of.

All buildings in which the following conditions obtain shall be deemed dangerous

(a) Those which list. lean or buckle to such an extent

that when a plumb line drawn through the center of gravity falls outside the middle third of the base of the structural parts supporting loads

(b) Those which exclusion of the foundation show (33) per cent of damage or the deterioration of the supporting member or members or fifty (50) per cent of damage or deterioration of the non-supporting enclosing walls or covering.

(c) Those which have improperly distributed loads upon the floors or in which the floors are overloaded.

Section 2

Repairs

All defective or dangerous buildings shall be repaired and put in a safe condition at once or if the deterioration is of greater per cent. than given under Section 1 of this chapter and are beyond the possibility of repair they shall be entirely removed

Section 3

Distribution of Load.

The weight placed on any of the floors of any building during its erection of after completion shall be safely distributed thereon. The Inspector shall require the owner or occupant of any building or any portion thereof to redistribute the load on any floor, or to lighten such loads where he deems it necessary.

Section 4.

Moving of Buildings

No building of any class shall be moved from one lot to another within the Fire Limits unless it be of a class and meets with the requirements of a new building of a class permissible to be erected in such district

Section 5

Location of Moved Buildings

The situation plan of the building to be moved to a new location as prescribed in the previous Section shall be first approved by the Inspector before the building is moved

Section 6

Building Moved Through Streets

No building of any class which has deteriorated or has been damaged more than fifty (50) per cent of its original strength shall be moved through the streets of the city of Fort Wayne And before any building shall be moved in or along any

street, Alley, or public highway, within the limits of the city of Fort Wayne, a permit therefor shall first be issued by the Inspector of Buildings upon the payment of a fee of Five Dollars ($5)

Section 7

House Movers to be Licensed Must give Bond

No person except a licensed house mover shall remove any building upon any street or upon any public ground within the limits of the city and every such person shall annually, before engaging in said occupation obtain a license therefor from the Board of Public Works, for which he shall pay the sum of Ten dollars ($10) per year: and no such license shall be granted until the party applying therefor shall have given a bond in the sum of Five hundred Dollars ($500.00) with good and sufficient sureties to be approved by the Mayor or Comptroller conditioned among other things that said party will pay any and all damages which may happen to any tree, pavement, street or sidewalk or to any public building or structure, and all damages resulting to any person whomsoever, which may be caused by the carelessness or negligence of the person so licensed, or by his agent employees or workmen while engaged in the removal of any building in the streets alleys or public highways of said city; and conditioned also that said party so licensed will save and indemnify and keep harmless the City of Fort Wayne, against all liabilities judgments, costs and expenses which may in anywise accrue against said city in consequence of the granting of such permit or license and will in all things strictly comply with the conditions of the permit.

Section 8.

Permit Stating Route Conditions etc

Upon the execution of said bond to the Mayor or Comptroller of said City a license shall be issued and the said licensed person or the owner of the building shall in each and every instance before removing any building obtain a permit to do so from the Building Inspector of said City, stating specifically all the conditions prescribing the route to be taken, the building proposed to be moved, and the site to which the same is to be removed, and limited the time for the removal of any such building.

Section 9.

To be Guarded at night with Red Lights

Any person having such permission and license shall

while engaged in the removal of any building in the public streets. alleys or highways of said City. and while occupying and using the streets. alleys and public ways for said purpose cause a red light to be placed in a conspicuous place in the front and rear of such building or obstruction and upon the caption used in moving the same from dark to sunrise each night during the time such building and obstruction remains in said streets. alleys and highways of said city

Section 10

Penalty for Violating Conditions of Permit

The owner of any building or the contractor for its removal either or both who shall suffer the same to be or remain in any of the streets. alleys, highways or upon any of the public grounds of the City for a time longer than may be specified in the permit issued by the Building Inspector and license issued by the Board of Public Works shall be punished as hereafter provided and forfeit his license and such building shall be deemed a nuisance.

Section 11.

Penalties for Violations of Sections 7, 8 and 9.

Any person or persons violating any of the provisions of section 7, 8 and 9 of this Chapter and who shall remove or attempt to remove any building in or along any of the said streets. alleys public ways or public grounds of said City without first having executed and given a bond to the approval of the Mayor or Comptroller as herein provided and obtain from the Building Inspector a permit for the removal thereof, shall be punished as hereafter provided.

Sections 12.

Must comply with section 7 and 8

It shall be unlawful for any person to move any building upon any street. alley or avenue or public grounds within the limits of the City unless such house mover has first complied with all the requirements specified in sections 7 and 8 of this chapter.

Section 13.

Interfering with Telegraph Lines etc.

It shall be unlawful for any licensed house mover or any other person co-partnership or corporation to move any house building or other structure on or along any street alley, lane or public grounds within the City Limits where the

moving of such house, building or other structure would be liable to interfere with break or tear down any leads lines or wires of any telegraph company, telephone company electric light company police patrol or fire alarm wires or the lines of any strait railway company operated by electricity the location of which has heretofore been authorized by said City except upon the conditions and terms specified in the next section

Section 14.

Must give written notice to Manager

The mover of such house, building or other structure desiring to move the same across through or under any of the lines or wires aforesaid shall give the local manager or agent thereof twenty four hours previous written notice of his intention and purpose to do so. and such written notice shall specify the streets and routes along which he proposes and desires to move the same. It shall then be the duty of such manager or agent in charge of such lines or wires to raise or remove the same at a reasonable expense, not to exceed the actual cost of cutting and repairing said wires or leads, to be paid by the person or corporation giving such notice so that such house, building, or other structure, can be moved through or past the same without injury to said lines or wires

Section 15

Strait Railroads Amenable only at Certain Hours

No Strait railway company shall be amenable to the provisions of the preceding Section except between the hours of 12 o'clock a.m. and 6 o'clock a.m.

Section 16

Penalty for Violating Sections 12, 13, and 14

Whoever violates any of the provisions of sections 12, 13 and 14 of this Chapter shall be fined not less than five dollars ($5.00) nor more than twenty-five dollars ($25.00)

Section 17.

Demolished Buildings

When plans and detailed statements are filed in the office of the Building Inspector for the erection of a new building if an existing building is to be demolished, such fact shall be stated in the statement so filed.

In demolishing any building, story after story shall be removed and no material shall be placed upon the floor of any such building in the course of demolition but the brick, timbers, and

other structural parts of each story shall be lowered to the ground immediately upon displacement and all rubbish shall be dropped through a closed chute if such building is over two stories in height or is located within thirty (30) feet of the street line. The owner of any building or the architect builder or contractor in charge of any building structure, wall platform, staging or flooring to be demolished shall give not less than twenty-four hours' notice to the Building Inspector of such intended demolition.

Section 18.

Removal; etc of Unsafe Buildings

The owner of any building structure or staging or anything attached to or connected with a building or any other structure which shall be unsafe so as to endanger life, shall immediately upon written notice received from the Building Inspector, cause the same to be made safe and secure, or taken down, and where the public Safety requires immediate action, the Building Inspector may enter upon the premises with such assistance as may be necessary and cause the said structure to be secured, or taken down without delay and the passageway to be protected at the expense of the owner

Chapter XIII

Tenements and Dwellings

Section 1.

New and Old Tenements

All tenements hereafter erected shall comply to the following regulations and if any existing building, whose occupancy complies with the provisions of buildings of the second grade be so damaged by fire or other causes (including ordinary wear so that at any time its value be one-half or less than one-half of its original value (exclusive of the value of the foundation) such building shall not be repaired or rebuilt except in conformity with the provisions of this Chapter applicable to new tenements.

Section 2.

Plans and Specifications

When the plans and specifications for the erection or alteration of a tenement or building of the second class are presented with the application for a permit to build the Inspector shall insist that the following provisions are complied with in conformity with all structural fire protection and sanitary requirements prescribed under all previous and following Chapter on Buildings

Section 3

Limits of Heights

The height of a tenement exclusive of any roof appendages shall not exceed one and one half (1½) times the width of the widest adjoining street, courtways and open spaces upon which it fronts and no existing tenement shall be increased beyond such height provided that no such tenement shall exceed eight (8) stories and a basement, or nine (9) stories without a basement or one hundred and twenty (120) feet in height. The basement if occupied by apartments shall have not less than four (4) feet and six (6) inches of its height above ground or grade and if such building has a cellar only, the first or ground floor level shall not exceed three (3) feet in height above the grade.

Section 4.

Framing Construction

All frame tenements hereafter constructed shall not exceed three stories above basement or forty (40) feet in height and no tenement so constructed shall contain more than one family on a floor unless each compartment is separated by party or fire walls of brick at least one brick thick. All such tenements shall be separated by party or fire walls not less than one (1) brick thick. Frame tenements two stories high shall not have more than two families or apartments above the first ground floor without brick division walls between each two (2) or less suites of rooms, provided that no frame tenement shall contain any living rooms in the third floor or attic or in the basement if the first floor is used for any other purpose, as modified under the various Chapters on Buildings.

Nor shall such frame tenements exceed twenty (20) feet in width if single or forty (40) feet in width if two tenements are on a floor; nor shall they be longer than sixty (60) feet or have an area of over twelve hundred (1200) square feet for each apartment without being separated by dead brick division or party walls.

Section 5

Frame Tenements

No existing wooden frame tenements within the territory described in the fire limits shall be enlarged either by adding to its height or to its superficial area

Section 6.

Fire Escapes

Every non-fireproof or pame tenement three or more stories in height shall be provided with fire escapes. In every case each separate apartment shall have direct access either through a room or private hall opening directly upon it to at least one such fire escape unless such apartment has access (without passing through any other apartment) to at least two flights of stairs leading to the building, one of which is out side of the building

Section 7

Stairs and Stair Halls

(a) The stairs and stair halls in all tenements more than three stories and a basement or four stories high shall be constructed of fireproof material throughout. All windows in stair halls opening on inner courts or shafts shall be of good quality fireproof or wire glass

(b) In every new non-fireproof tenement all stair halls shall be enclosed on all sides with walls of solid masonary all glass in such stair halls shall be of good quality fireproof or wired glass except where same opens into a street alley, outer court or yard. There shall be no movable transums or sash openings from any such stair halls to any other part of the building. This section does not apply to tenements which are not more than three stories and a basement high with only one apartment on each floor.

Section 8

Main Entrance Hall

In every non fireproof tenement except where there is only one suite of apartments on each floor the entrance hall shall be enclosed with solid masonry walls and with ceilings of incombustible materials and shall comply with all of the conditions of the various Chapters on buildings as to the construction of stair halls

Section 9

Dimensions of Tenements

In addition to the general requirements of occupancy of lots and proportion of courts and rooms and stairs given under their respective Chapters, the following three Sections shall be applicable alike to dwellings tenements, or all other living apartments

Section 10,

Minimum Widths

No single dwelling or tenements shall be less than fourteen 14 feet

wide if detached or sixty in a block with a separate entrance or less than twelve and one-eighth (12⅛) feet if attached, and there is a common entrance for each suite of two apartments or for any double house

Section 11

Number of Rooms

Every living apartment in which cooking is done exclusive of the water closet and bath room, shall have not less than two rooms one of which shall have not less than eighty (80) square feet of floor area and the other not less than one hundred and twenty (120) square feet of area and every suite of apartments in a tenement containing a greater number of rooms shall have at least one room of one hundred and twenty (120) square feet area

Section 12

Division Walls

In non-fireproof tenements or terraces the maximum number of rooms, exclusive of the water closet and bath rooms in any suite of apartments shall not exceed eight (8) unless there be a brick division fire wall between such room or some of them

Section 13.

Old Buildings Converted Into

No room in any tenement or building now in existence shall hereafter be constructed, altered or converted or occupied for living purposes unless it contains a window having a superficial area not less than one-twelfth of the floor area of the room which window opens upon a street or alley, or upon a yard having a sectional area of not less than twenty five (25) square feet: or unless such room adjoins another room in the same apartments which other rooms have each a window opening upon such street, alley, yard or court and between which two adjoining rooms, there is a sash window having at least fifteen (15) square feet of glazed surface, the upper half of which is made to open easily. Furthermore, no room in any now existing tenement which has no window as aforesaid opening upon a street, alley, or upon a yard or court, having a horizontal area of not less than twenty-five (25) square feet shall hereafter be constructed, altered converted or occupied for living room unless it contains a floor area of at least sixty (60) square feet and also at least six hundred (600) cubic feet: nor unless every part of the finished ceiling of such room

be at least eight (8) feet distant from every part of the finished floor thereof: provided that an attic room need be eight (8) feet high in but one-half of its area

Section 14.

Additions to.

Any additional room or hall that may be hereafter constructed or created in any existing tenement shall comply in all respects with all the provisions of the various Chapters on buildings as to size arrangement light and ventilation of halls but no addition or alteration shall be made which encroaches upon the minimum yard or porch space as prescribed

Section 15

Living Rooms in Basement

In no now existing or new tenement shall any room in the cellar be constructed altered converted or occupied as living rooms, unless all the following conditions of this Chapter are complied with and that at least one-third of the height of the basement shall be above grade at building: provided that in such case it shall be at least four (4) feet six (6) inches above the street grade.

(a) Such room shall be at least eight (8) feet six (6) inches high in all now existing or new tenements in every part from the floor to the ceiling except as provided for janitor's use only which may be eight (8) feet

(b) In any tenement of No. 2 Class construction in which the basement is fitted up for offices work rooms or living rooms other than the janitor's use, such basement shall be regarded as the first story of such tenements and their height shall be measured from the basement floor level upwards

Section 16.

Lighting by Skylight

When a water closet compartment is located on the top floor and is lighted and ventilated by a skylight over it, or is located at the bottom of a shaft or court of lawful size and is lighted and ventilated by a skylight over it at the bottom of such shaft or court, no windows shall be necessary provided that the roof of such skylight contains at least three (3) square feet of glazed surface and is so arranged as to readily open

Section 17

Building not to be used as

No building of which any part of which is used for the storage or

sale of hay. straw. hemp. flax shavings. burning fluid turpentine camphine or any inflammable oil or other highly combustible substance. shall be occupied in any part as a dwelling. Tenement or lodging house except that rooms for coachman or rooms must be allowed in stables upon receiving special permit therefor from the Building Inspector when the means of exits are deemed safe by. him in case of fire

Section 18.

Hotels

Every building hereafter erected or enlarged as a hotel for the accommodation of transit guests and containing more than fifty (50) sleeping rooms above the first floor shall be first class construction. Buildings containing less than fifty (50) sleeping rooms above the first floor. shall be governed by. the regulations prescribed for the construction of tenements but no hotel hereafter constructed shall exceed twelve stories or one hundred. and fifty feet in height

Chapter XIV

Dry. Cleaning Works

Section 1

For the purpose of this ordinance. a dry cleaning business is defined to be the business of cleaning cloth. clothing. feathers or any sort of fabrics by. the use of gasoline. naphtha. benzine. benzol or similar light petroleum, or coal tar products, or cleaning by process known as dry. cleaning.

No such business shall be carried on except in a fireproof building not more than one story high. with no basement beneath. which building must be of brick laid in cement mortar. iron. stone or concrete construction with cement floor.

The doors of said building must be made of the most improved pattern of automatic fire doors on sliding rails. and the frames and sashes of all windows shall be of metal and glazed with wire glass. or protected by. fireproof automatic shutters.

The walls of said building shall have vent holes at the floor line not less than twenty (20) square inches in area. and not more than six (6) feet apart from center to center properly protected by. iron bars or other improved means of ventilation.

In order to further ventilate said building an exhaust fan shall be. set in the wall close to the floor, which is of a size sufficient to change the air of the building every. three minutes

and said fan shall be in operation at all times during the use of said building.

There shall be no connection from the said dry cleaning building to public or private sewer, drain catch basin or pit.

It shall be unlawful to heat this building by any other than hot water or steam heat

The lighting must be done by electricity in the most improved manner, the wires must be run in conduits; all lamps must be approved vapor proof lamps with keyless sockets, and all switches must be 4½ feet above floor of building and located near door so as not to allow opportunity for vapor to collect near it

It shall be unlawful to locate, have use, or maintain a steam generating boiler dynamo or motor within the walls of any dry cleaning building except in a room entirely separated from the balance of the building

Section 2.

No storage or dry cleaning building shall be placed, installed constructed or maintained, until an application for permission to do so, with plans and specifications showing full details of locations construction and connections have been filed with and approved by the Building Inspector

Section 3.

All of the volatile liquids named herein shall be stored in underground tanks of the specifications as required herein. All storage tanks shall be constructed of steel and coated on the outside with tar or other rust resisting material

Tanks must not exceed two hundred and eighty (280) gallons capacity each, shall be made of at least twelve (12) gauge galvanized steel or at least one-quarter (1/4) inch black open-hearth tank steel

Not more than six (6) tanks of two hundred and eighty gallons shall be allowed.

All tanks to be installed under-ground not less than two (2) feet below the surface entirely surrounded by earth or earth and concrete

Should there be more than one (1) tank, they shall be separated by at least twelve (12) inches of earth; all well tamped in place the top of all tanks must be below the level of the lowest pipe line in the building used in connection with the equipment

There must be no opening or pipe connections except on the top of said tanks. They shall be properly vented, and shall not

be connected either directly or indirectly with any public or private sewer drain, catch basin or pit

Section 4.

All storage tanks shall be provided with a one (1) inch diameter or larger galvanized iron vent pipe, same to be constructed to the top of the tank (connections at the tank to be fitted with a brass wire screen of at least thirty (30) mesh.)

This vent pipe must be carried up at least four (4) feet above the roof of said building and terminate in a double gooseneck spark protector, openings of which must be covered with a brass wire screen of at least thirty (30) mesh.

Section 5.

No volatile substance in excess of one (1) quart shall be used for cleaning purposes except in closed machines, and must be conveyed from the tanks to the machine only in pipes by means of an approved pump or pumps properly controlled by approved valves.

It shall be unlawful to store or sell any of said volatile substances in open vessels or tanks.

Section 6.

Filler pipes must be made of galvanized iron pipe two (2) inches or more in diameter entering at the top of tank and extending to bottom of same upper end of said filler must terminate in a screw cap securely locked

Where filler pipe runs to sidewalk, or to an alley or other public highway, it must terminate in a screw-cap securely locked and be protected by a cast iron filler box, same to be flush with the sidewalk or alley, the cover of the said filler box to be securely locked.

Section 7.

Dry rooms may be located outside of said dry cleaning building and shall have an eight (8) inch vent opening into the atmosphere for each two hundred and fifty six (256) feet of cubic space or fraction thereof; said vent pipe shall be carried up to a height of two (2) feet above the roof of building and terminate in an approved ventilator hood.

Section 8.

Any person firm or corporation that now have shall establish or carry on a dry cleaning business in violation of this ordinance shall on conviction be punished by a fine of not less than ($5.00) or more than ($25.00) for each days continuance in said business and the cost of prosecution.

Chapter XV

Gasoline

Section 1.

Gasoline and Kerosene Oil Engines for Power.

Gasoline and Kerosene oil engines for power shall rest on solid brick or stone foundations built on the ground. No such engine shall be located above the ground floor of any building

Section 2

Gasolene Tanks

(a) All tanks to be installed outside of building underground not less than two (2) feet below the surface, entirely surrounded by earth well tamped in place, and the top of the tank must be below the level of the lowest pipe line in the building used in connection with the equipments

(b) If impracticable to locate storage tanks outside of building they may be buried three (3) feet below the level of the basement floor imbedded in the earth and covered by at least three (3) feet of earth or earth and concrete

(c) All tanks of five hundred and sixty (560) gallons or under shall be made of at least twelve (12) gauge galvanized steel or at least one quarter (1/4) inch black open hearth tank steel, all tanks exceeding five hundred and sixty (560) gallons capacity shall be made of three sixteenth 3-16 inch galvanized steel or one quarter (1/4) inch black open hearth tank steel, all tanks made of galvanized steel must be carefully riveted and soldered and coated on the outside with tar or other rust resisting materials. All tanks made of black tank steel must be carefully riveted and calked and coated on the outside with tar or other rust resisting materials. All tanks must have no openings or pipe connections except on the top thereof shall be properly vented, and shall not be connected either directly or indirectly with any public or private sewer, drain, catch basin or pit in the City of Fort Wayne.

(d) Filler pipes must be made of galvanized iron pipe two (2) inches or more in diameter entered at the top of tank and extending to bottom of same, upper end of said filler pipe must terminate in a screw cap securely locked. Where tanks are located under the building filler pipe must be run to the outside of the building and terminate in a screw cap same to be securely locked. Where filler pipe runs to sidewalk or to an alley or other public highway. It must terminate

in a screw cap securely locked and be protected by a cast iron filler box the same to be flush with the side walk or alley the cover to the said filler box to be securely locked.

(e) Tanks located within ten (10) feet of any building shall be provided with a one (1) inch diameter or larger galvanized iron vent pipe same to be connected to the top of such tank (connection at the tank to be provided with a brass wire screen of at least thirty (30) mesh) this vent must be carried up to at least four (4) feet above the roof of said building and terminate in a double goose-neck spark protector both openings of which must be covered with a brass wire screen of at least thirty (30) mesh

(f) Pipe connecting the tank with pumps must be of galvanized iron and must enter top of tank. Said pipe must be buried at least eighteen (18) inches below the surface and any exposed portion thereof must be thoroughly and properly protected This connection pipe must not be lower at any point than where same leaves the tank.

Section 3.

Pumps

All gasolene must be drawn from the tank by means of an approved suction or pressure pump or pumps which shall have a shut-off valve with ground key on the nozzle and automatic check valve between the pump and the nozzle. In no case shall there be a return or waste pipe to the tank where suction pump or pumps are used

Section 4.

Pressure Systems.

Pressure systems for delivering volatile inflammable liquid from storage tanks shall -

1. Be so arranged that the gasoline will return through pipes by gravity to the storage tank when system is drained
2. Be connected in a manner that will prevent the spilling of the volatile inflammable liquid to a draining off cock or cocks situate -

(a) At a permanent filling station or -

(b) In a pump house.

Section 5.

Where gasoline is pumped inside the building lighting shall be by incandescent electric lights with all electric switches and cut-offs permanently located at least four feet above the floor.

Section 6.

Handling or Storing of Gasolene inside of Building

(a) No gasolene or other volatile inflammable liquids shall be kept in any building, except when stored or handled in self-closing safety containers, or in portable filling tanks

(b) When self-closing safety containers are used for the storing or handling of gasolene or other volatile inflammable liquids not more than five (5) gallons of gasolene or other volatile inflammable liquids shall be kept in any building and the self-closing containers must be made of metal and must be of approved construction and must be of a capacity not to exceed five (5) gallons

(c) When portable filling tanks are used for the storing of or handling of gasolene or other volatile inflammable liquids the tanks must be of a capacity not to exceed fifty (50) gallons and must be made of at least three-sixteenth (3-16) inch tank steel and must be of approved construction. The said portable tanks shall be supported on all-steel wheels not less than thirty (30) inches in diameter, the same being equipped with rubber tires, and the tank must be provided with an approved all metal suction pump. This pump to be provided with hose attachments, and hose must not exceed eight (8) feet in length. The pump must be equipped with approved ground key shut-off cock where hose is attached to pump also with approved ground key shut-off cock at end of hose Pump must be equipped with a convenient lock and the same must be locked when not in use.

Section 7

There shall constantly be kept and maintained convenient receptacles filled with sand, to be used in absorbing waste oils on the floor. In addition to this sand shall be kept in box or boxes of approved construction provided with hand scoop to be used for fire extinguishing purposes only.

Section 8.

No smoking shall be allowed in any room in which volatile or inflammable liquids are kept.

Section 9

Valves

Valves in supply pipes to engines between the engine and tank and near such tank shall be provided: valves in supply pipes shall be closed when filling the tank, and when engine

is shut down for the night

Section 10

Pumps

Gasolene and Kerosene oil shall be supplied to engines by approved pumps provided with cut-off valves, overflow and by-pass so arranged that all gasolene and kerosene oil shall drain back to the storage tank so as to leave the building entirely free from gasolene or kerosene oil when the engine is not in operation.

Section 11.

Permits and Inspection

No change shall be made in the arrangement or construction of engines operated by gasolene or kerosene oil without notice to and approval by the Building Inspector. Notice of intention to introduce gasolene or kerosene oil engines into buildings shall be given to the Building Inspector, who will make an inspection of the proposed location and if in accordance with the foregoing will issue a permit therefor.

The dimensions for storage tanks for gasolene or kerosene oil or rooms in which such articles are worked or stored shall be determined by the Building Inspector in accordance with the provisions of the various Chapters on buildings when not otherwise provided for in the Ordinances of the City relating to explosives

Section 12.

All tanks used for storage of gasolene or other oils now located on sidewalk or above ground shall be removed and installed in accordance with ordinance on or before May 1. 1911.

Section 13.

Any person, firm, or corporation who shall violate any of the provisions of this ordinance shall be held guilty of a misdemeanor and shall be punished by a fine of not less than five ($5.00) dollars and not more than twenty-five ($25.00) dollars for each offence.

Chapter XVI

Lumber.

Section 1.

Lumber Yards

It shall be unlawful to pile lumber in any yard to a greater height than thirty (30) feet above the grade of the adjoining Alley or Street, and when the piles of lumber are situated adjacent

to each other. the space between the piles shall be kept entirely free from refuse, chips or blocks and equipped with standard fire hydrants spaced at regulation distances when deemed necessary by the Chief of the Fire Department. Where lumber Yards face on streets a proper and suitable fence shall be erected and maintained along the street line. Such fences to be provided with gates or other suitable openings at intervals of at least one hundred (100) feet to allow of easy access to lumber yard by the Fire Department should the necessity occur.

Section 2

Lumber Piles

No lumber shall be piled for the purpose of storage, seasoning or drying, within thirty (30) feet of any building or planing mill or woodworking factory unless such building is provided with a solid brick fire wall on the side adjacent to the lumber pile, and when such is the case no lumber pile shall be higher than ten (10) feet below the coping of said fire wall but not exceeding thirty (30) feet in height: nor within fifty (50) feet of any building of the first grade or any hotel dwelling or tenement unless the same has been erected since the establishment of such yard. but nothing in this section shall prevent the erection of a two story frame office building not exceeding twenty-five (25) feet in height in any lumber yard provided the chimney of said office building is at thirty (30) feet distant from any lumber pile.

Chapter XVII

Temporary Occupancy

Section 1.

Fencing in Building Sites

During the erection of the external walls of any building within five (5) feet of any street line the owner or his agent in charge thereof shall cause the part of said building fronting on such street to be enclosed by a fence located not less than seven (7) feet from the building line and not more than eight (8) feet and not less than five (5) feet high.

Section 2

Sidewalk around fence.

If the enclosing fence shall prevent passage on the sidewalk the owner through his agent in charge thereof shall cause to be laid and maintained thereof, in good repair and free from rubbish, dirt or snow a temporary plank, side-

walk around the same not less than one-third the width of the sidewalk but never less than three (3) feet wide

Section 3.

Covered Sidewalks

If the building to be erected is more than three stories in height and is set on or near the street line, there shall be built over the temporary sidewalk a roof having a frame work covered by two layers of two-inch planks. Said roof shall not be less than ten (10) feet above the sidewalk and extend to the curb and be maintained as long as material is being used or handled on said street front above the level of such sidewalk. Temporary enclosures of shop fronts during their construction or repair may extend over the street line seven (7) feet for their entire height subject to all regulations herein prescribed for temporary fences

Section 4.

Method of Protection to be used

Before a permit to build is granted the method of protection and enclosures of the building site as prescribed in the previous Sections and the placing and working of building materials upon public property elsewhere described in the various Chapters on buildings shall be determined upon, if any method in whole or in part is necessary during the conduct of building operations such change shall be ordered by the Building Inspector under the direction of the Board of Public Works

Section 5

Excavated Materials

Earth taken from excavations and rubbish taken from buildings being erected altered or demolished shall not be stored upon streets and alleys but must be removed from day to day as rapidly as produced. Where dry rubbish apt to produce dust is being handled it must be kept wetted down so as to prevent its being blown about by the wind

Building rubbish and useless material accumulated upon the upper floors shall be lowered in receptacles by elevators or by closed chutes directly into wagons; chutes over public property shall extend clear to curb line

Section 6

Working Materials

No building material shall be worked such as dressing stone, timber or other materials upon public property or on any street having railway tracks. Provided that this does not prohibit framing joist studding or roofing.

Section 7.

Storage of Material upon Streets and Maximum Area Occupied

The occupancy of sidewalks or streets by articles not intended for immediate use that is from day to day in connection for the operation for which the permit was issued shall not be allowed except that old brick or building material may be stacked in front of the site of said building for a time to be limited by the Building Inspector in the permit, provided the new building wherein these materials are to be used is to be immediately erected upon the said site

The maximum area permitted to be occupied shall not exceed beyond one-third of the width of the roadway immediately in front of the building site

Section 8

Roadways with Railroad Tracks

On streets containing railroad tracks, the space to be occupied by building materials outside of the curb shall be based on the width of the roadway in front of the building under construction or repair, where the roadway between the curb and the nearest rail of the track is twenty (20) feet or more the building materials shall be compactly stacked or arranged at all times to leave at least eight (8) feet clear between materials and nearest rail, and teams, wagons, carts, barrows, hods, vehicles, buckets or other appliances delivering or removing materials to or from the building under construction or repair or to or from allotted space for building materials shall not obstruct any part of the space so reserved.

On streets containing railway tracks where the roadway is less than twenty (20) feet wide between the outer edge of curb to railway track (nearest rail thereto) the building materials may when compactly arranged to the satisfaction of the Building Inspector extend out from the curb to a distance of not less than eight (8) feet of the outer rail of the track nearest the materials, and said space of eight (8) feet is to be kept clear of all obstructions at all times. In all cases the space allowed for building materials is to be

restricted laterally to the width of the front or fronts of the building under construction or repair, or the frontage of the premises upon which it is erected or to be repaired

Section 9.

On Alleys

Building material or earth from excavation may be temporarily deposited in alleys sixteen (16) feet or more in width; not however, to encroach on space more than one-third of the width of the alley, and subject to the immediate removal when so ordered by the Building Inspector. On ends or turn-arounds in alleys the earth or materials shall be deposited in such a manner to permit the free use of the alleys for the passage of teams or cars and to allow unobstructed egress from the property abutting on the alley

Section 10.

Arrangement of Materials

No material fence or shed shall be placed within two (2) feet of any tree, or four (4) feet from any lamp post, fire hydrant, electric conduit, manhole fire alarm boxes or catch basins; and all gutters must be free and clear at all times. When material is piled or worked upon any paved roadway, it shall be placed upon plank platforms with 2-inch sleepers as prescribed in the next section.

Section 11.

Mortar Beds

Lime, cement or other mortar or concrete may be prepared upon any public lawn or roadway within the space designated to be occupied by building materials. If prepared upon the lawn, roadway or sidewalk, it shall be upon a tight bed of tongued and grooved boards and placed upon 2 inch bearers or sleepers leaving an air space below and properly protected so as to prevent any splashing or dripping upon the lawn, roadway or sidewalk. The distance that mortar beds and building materials may extend from the curb into the street shall be noted on permits.

Section 12.

Derricks - Limitation

In all buildings more than two stories in height the use of elevators set or derricks set upon sidewalks is prohibited. In no condition shall derrick posts be allowed to set in the roadway of any street or alley, and in no case shall the guy lines be

less than fifteen (15) feet above the roadbed.

Section 13.

Danger Lights

Red glass globe lanterns shall be displayed and maintained during the whole of every night wherever fences are built or excavations are made along or building materials are piled in any street, alley or courtway, as follows

One red light may be securely and conspicuously posted on or near such excavation building material or obstruction: provided such obstruction does not extend more than ten (10) feet in length and if not over ten (10) feet and less than fifty (50) feet, two red lights, one at each end shall be so placed, and one additional light for each fifty (50) feet or part thereof.

Section 14.

Sidewalk Vaults

The space which may be occupied under a sidewalk by a property owner on the front or side of his building shall be limited to the exterior line of the curb; measurement to be taken from the curb line to the outside base of the retaining wall. Provided the space under the sidewalks to the exterior line of the curb may be occupied by the property owner: the retaining wall to be of such strength and thickness as shall be prescribed by the Building Inspector and in no case shall an area be built under an alley or under an entrance to an alley from the street. The application for a vault shall be accompanied by a written agreement upon an official blank, signed by the owner of the abutting property, contracting to release and relinquish the vault space or permit its use as set forth in Section 15, and to remove without cost to the City of Fort Wayne, all machinery, fixtures or structural parts of the vault when so ordered by the Board of Public Works

Section 15.

Conduits and Piping Reservations

No vaults shall be constructed as to interfere with any sewer or water pipe, fire hydrant, manhole, gas pipe, or any other public work or improvement nor with any of the electrical conduit carrying fire alarm or police wires, and the City of Fort Wayne, in granting its permits to build a vault upon public property reserves the right to at any time construct under, over or through such vault space, water or gas pipe conduits for electrical heat or power, or other pipes or other underground

work needed for the public service that the Board of Public Works may deem necessary to be placed in, below or through the space occupied by the vault without compensation

Section 16.

Sidewalk Vault Retaining Walls

Retaining walls if built of brick shall not be less than two and one half (2½) brick thick at the top, and shall average not less than two and one half (2½) brick in thickness for the first eight (8) feet up to ten (10) feet in clear height above the cellar floor; if the wall is battered, it shall not be less than three (3) brick thick at the bottom and for every additional three (3) feet or part thereof over ten (10) feet in height one-half (½) brick shall be added to the thickness at the bottom

Section 17.

Laying up Sidewalk Vault Retaining Walls

All retaining walls shall be laid up with first class cement mortar and shall be well grouted in against the earth bank and pointed on the outside for at least four (4) feet down from the top of the wall.

Section 18.

Covering Over of Sidewalk Vaults

The roofs of all vaults shall be iron flagging, concrete terra cotta, or hard brick and the crown of the arch, or top of the covering shall be at least six (6) inches below the established surface of the sidewalk. The sidewalk paving shall be either of stone or of concrete jointed parallel to and four and one-half (4½) feet from the curb line, and laid in sections not exceeding six (6) feet in length along said curb and under the rules of the Board of Public Works

Section 19.

Sidewalk Vault Floor Lights

Hereafter no open area shall be left in any sidewalk and no sidewalk vault shall be covered with open gratings, when areas are covered with glass floor lights such floor lights shall be confined to one-third (1-3) of the width of the sidewalk next to the building line, and shall not exceed five (5) feet in width without a special permit

Section 20

Openings in Sidewalks

Hereafter all openings made in sidewalks for coal holes elevators or skids shall be located with the outer edge within

two (2) feet of the outer curb line provided that if the space between the curb line and the retaining wall is occupied as provided in Section 16 of this Chapter, such openings shall be made just inside the retaining wall.

Section 21.

Coal Hole Covers and Gratings in Sidewalks

There shall not be more than one (1) coal hole for every twenty (20) feet or part thereof of frontage. The aperture in the sidewalk over any coal hole or vault shall not exceed eighteen (18) inches in diameter, and shall be covered with a substantial cast iron plate and frame, with a second top surface flush with the sidewalk. Provided that such covers for the purpose of ventilation may be perforated with openings not exceeding one (1) inch in width. Cast iron open gratings not exceeding sixty (60) square inches in area and twenty-four (24) square inches in perforations shall be permissible if placed next to the curb line and used for fresh air inlets for [illegible]

Section 22.

Sidewalk Lifts

The location of any elevator, skid or lift is prohibited in sidewalks fronting any building accessible by teams from the side or rear, nor shall there be more than one such lift in any sidewalk for every twenty (20) feet building frontage or over, up to eighty (80) feet

Section 23

Drainage of Vaults

Vaults in areas shall be properly drained and floors of vaults and areas shall be paved as required for cellars.

Section 24

Boiler Gas Engines etc, not allowed in Vaults

Boilers, Gasolene, gas and steam engines, pumps and plumbing fixtures urinal or water closets gasolene petroleum or gas storage tanks, or any pipe or fixtures generating or emitting gas, steam or offensive odors, shall not be located in any sidewalk vault outside the building line. No fans or pipes ejecting vitiated or superheated air from the adjoining buildings or exhaust pipes causing disagreeable noises shall be located in or open into such vaults. The application for a vault, must state fully the purposes of the vault and the uses of all machinery

or. fixtures intended to be placed. therein and no fixtures which is not mentioned in the application or which is prohibited by. this section. shall at any time be placed. therein

Section 25

Board of. Public Works

Wherever. the subject of any occupancy. is not fully. set forth in any. section of this Chapter the tenancy. of the occupancy. shall be subject to the approval. of the Board of Public Works under the statutes and ordinances governing its custody of public property

Section 26.

Building Permits

Building permits subject to the approval. prescribed in the proceeding Sections shall carry. the right to occupy. public property for the conduct of building operations as prescribed in this Chapter, and such. occupancy must terminate with the completion of the operations for which a permit was issued by. the Building Inspector. and no owner shall. place any. building apparatus or material or any. building shed. or other structure, or any. part thereof. on any. public street alley. courtway. or lawn, park, or other public property in violation of any of the provisions prescribed in this Chapter

Chapter XVIII

Poles and Signs

Section 1

Poles on. Public Streets

Before any telegraph, telephone or electric light or street railway poles shall be placed. on any street, alley or public highway within the limits of the city of Fort Wayne. a permit shall first be issued therefor by. the Board of Public Works and said poles shall be placed. so as to cause least inconvenience to public travel. and all telegraph. telephone or electric light and street railway poles upon the streets, alleys or public highways which now or hereafter hinder or obstruct public travel. shall be removed upon a notice being served by. the Board of Public Works in writing so to do within twenty-four. hours after such notice has been. served.

Section 2

Signs

No sign or advertisement other than an electric one. shall project

more than three (3) feet beyond the building line and no such electric sign or advertisement shall project more than ten (10) feet beyond supporting structures. no portion of any sign projecting beyond the building line shall be less than ten (10) feet above the surface of the sidewalk nor less than fourteen (14) feet if projecting from an alley wall. No such or other sign or advertisement shall be placed, built erected or hung upon or from the roof or on or from the wall of any building without a permit therefore from the Building Inspector, and all signs now erected not in compliance with the provisions of this ordinance shall be removed on the order of the Building Inspector. Any sign or advertisement now or hereafter erected on the top or outer wall of any building or attached to a projection therefrom shall be removed. when rotten or unsafe

Chapter XIX

Walls Piers and Partitions

Section 1

Material of Walls

The walls of all buildings. other than veneered. frame or wooden buildings shall be constructed on stone. brick Portland cement. concrete. iron steel. or other hard incombustible material. and the several component parts of such buildings shall be as herein provided all buildings shall be enclosed. on all sides with independent or party

Section 2

Walls and Piers

In all walls the thickness specified in this ordinance. the same kind or quality of materials may be used in piers or buttresses. Bearing walls shall be taken to mean those walls on which the beams trusses or girders rest.

The walls and piers of all buildings shall be properly and solidly bonded together with close joints filled with mortar. They shall be carried up plumb and straight. The walls of each story shall be built to a line. and shall be built up the full thickness to the top of the beams above

All brick laid in non-freezing weather shall be well wetted before being laid except non-absorbent brick

All isolated piers shall be built of stone Portland cement concrete. or good hard well-burnt brick laid in lime or cement mortar

In case piers are faced with pressed brick, they must be laid so as to have proper bearings of mortar under each pressed brick, so that the strength of the pier may be fully maintained on all sides.

Section 3
Brick Piers

Brick piers shall be built of good, hard well-burnt brick of uniform size laid in cement or lime mortar with uniform joints throughout facing and backing and of sufficient size to carry safely, the load, which they are intended to carry. The joints shall not exceed three-eighth of one inch in thickness. One course of brick shall be laid over the whole surface of the pier and each brick be thoroughly surrounded by mortar and all to be properly bonded, and the joints shall be full of mortar before the next course shall be laid. The top of the pier when finished shall be level for the cap-stone, plate or other covering

Proper bearings proportioned to weight to be sustained and full size of pier shall set under all columns or girders bearing on said piers. Oolitic or stratified stone shall not be used in any basement pier. Isolated piers shall not exceed in height at least ten (10) times their least dimension

When walls or piers are built of coursed stone with dressed level beds and vertical joints said walls or piers shall be proportioned to the duties they have to perform

In case of an external brick pier, the plate may be reduced sufficiently in size to allow four (4) inches of brick work to intervene between the edge of the plate and the face of the pier exposed providing that the part of the pier over which the plate extends, shall be equal to the duty imposed thereon.

Section 4

The expression "Walls for Business Buildings" shall be taken to mean and include in this class walls for the following as defined in Chapter 2. Classes 1 and 2. Hotels, Lodgings Houses office buildings, warehouses factory buildings and public buildings. Said walls if of brick shall be of the following thickness

Outside Party and Division Walls	Rubble Basement	Brick Basement	1st Story	2nd Story	3rd Story	4th Story	5th Story	6th Story	7th Story	8th Story	9th Story	10th Story	11th Story	12th Story
1 Story	16	12	12											
2 Story	20	16	12	12										
3 Story	20	16	16	12	12									
4 Story	20	20	16	16	12	12								
5 Story	24	24	20	20	16	12	12							
6 Story	28	24	20	20	16	16	16	12						
7 Story	30	24	20	20	20	16	16	12	12					
8 Story	35	28	24	24	20	20	16	16	16	12				
9 Story	35	28	24	24	20	20	20	16	16	16	12			
10 Story	35	28	24	24	24	20	20	20	16	16	16	12		
11 Story	40	32	28	24	24	24	20	20	20	16	16	16	12	
12 Story	40	32	28	28	24	24	24	20	20	20	16	16	16	12

Section 5.

Buildings having the first story, the basement or both designed for business purposes, and the upper stories for dwellings shall have walls if of brick of the following thickness

Brick Walls in Business and Dwellings	Rubble Basement	Brick Basement	1st Story	2nd Story	3rd Story	4th Story	5th Story	6th Story	7th Story	8th Story	9th Story	10th Story	11th Story	12th Story
1 Story	18	12	12											
2 Story	18	16	12	8										
3 Story	24	16	12	12	8									
4 Story	24	20	16	12	12	12								
5 Story	24	20	16	16	12	12	12							
6 Story	24	20	20	16	16	12	12	12						
7 Story	30	24	20	20	16	16	12	12	12					
8 Story	30	24	24	24	20	16	16	12	12	12				
9 Story	30	24	24	20	20	20	16	12	12	12	12			
10 Story	36	28	24	24	20	20	20	16	16	12	12	12		
11 Story	36	28	24	24	24	20	20	16	16	16	12	12	12	
12 Story	40	32	28	24	24	24	20	20	16	16	16	12	12	12

The above tables shall apply to all walls of sixty (60) feet and under in length; walls exceeding sixty (60) feet in length shall not have more than two upper stories twelve (12) inches thick, unless strengthened by brick cross walls or pilasters.

Section 6.

Walls for Dwellings and Apartments and Flat Buildings

Dwellings and apartment and flat buildings shall have walls if of brick of the following thickness

Brick Walls for Dwellings and Apartment and Flat Buildings	Rubble Basement	Brick Basement	1st Story	2nd Story	3rd Story	4th Story	5th Story	6th Story	
1 Story	18	12	12						
2 Story	18	16	12	8					
3 Story	18	16	12	12	8				
4 Story	20	16	16	12	12	12			
5 Story	25	20	16	16	12	12	12		
6 Story	25	20	20	16	16	12	12	12	

The above walls apply to all walls sixty (60) feet and under in length; when over sixty (60) feet in length such wall shall not have more than two upper stories twelve (12) inches thick unless strengthened by brick cross walls or pilasters.

Section 7.

Division Walls - Thickness of

The thickness for each story and basement of all brick division walls in dwellings, apartment and flat buildings shall be shown in the following table

	Basement	1st Story	2nd Story	3rd Story	4th Story	5th Story	6th Story		
1 Story	12	12							
2 Story	16	12	8						
3 Story	16	12	12	8					
4 Story	20	16	12	12	12				
5 Story	20	16	16	12	12	12			
6 Story	20	16	16	16	12	12	12		

Section 8.

Partitions in Two-story Dwellings or Apartments

Partitions of brick or portland cement concrete not less than nine (9) inches in thickness may be used above first floor where stud partitions in buildings are allowable in this ordinance Where such partitions exceed one story in height thirteen (13) inch foundation walls must be provided

Hollow tile partitions may be used under simular conditions if constructed and proportioned as elsewhere indicated in this ordinance. No hollow tile partition less than eight (8) inches in thickness shall be used as a bearing wall. Such partitions if more than one story high shall be provided with twelve (12) inch foundation. Hollow tile partitions less than nine (9) inches in thickness may be provided with nine (9) inch foundation walls in basement provided said basement is not more than ten (10) feet in the clear.

In case of dwellings or apartments more than two stories in height eight (8) inch walls of concrete or brick may be used in lieu of stud partitions specified in this Ordinance. In no case however shall eight (8) inch walls be more than two (2) stories in height without sub-walls proportioned as elsewhere indicated in this Ordinance

This section of this Ordinance in no way effects the provisions relating to division walls between apartments.

Section 9.

Foundations for Frame Dwellings

Frame dwellings not over two (2) stories high may have outside foundations walls of brick or Portland cement concrete eight inches in thickness where floor level of basement or cellar is not more than five and one-half (5½) feet below the established grade. if provided with proper lateral supports. In case of veneered frame houses, the foundation of Portland cement concrete or brick shall be four (4) inches thicker than the above. In event of basement floor being more than five and one half (5½) feet below the established grade, or in event of basement or cellar being more than ten (10) feet in depth. outside foundation walls shall be four (4) inches thicker than the above, and shall be provided with proper lateral supports. Rubble foundations not less than sixteen (16) inches in thickness may be used for any part of frame house foundation. Inside walls of brick or Portland cement

concrete may be nine (9) inches in thickness. if not over ten (10) feet in height. No wall under any part of a frame dwelling shall be less in thickness than the above. This applies to porches, bay-windows and other appurtenances to a dwelling.

Proper ventilators shall be provided in foundations one under each outside wall of each room. By lateral supports for walls is meant cross walls, buttresses or other supports made of Portland cement, concrete brick or stone.

All foundation walls as above shall be provided with footings properly proportioned to carry the superimposed load on the soil where they are used.

Section 10.

Frame Veneered. Flat Buildings. Height of.

No person or persons shall hereafter construct any wooden frame or brick or stone veneered apartment or flat building more than two stories in height.

Section 11.

Wooden or veneered. Apartment or Flat Buildings Division Fire Walls - Where

If the ground area of any two-story frame or veneered apartment or flat building constructed exceeds 4,500 superficial feet in area then there shall be constructed division walls of brick, stone or other incombustible material extending from front to rear and built from basement through the roof of such building as a fire wall. Provided that in all buildings covered by this Section the street frontage shall not exceed fifty-five (55) feet without a division wall, constructed from front to rear of such building and constructed of such materials as above provided for division walls.

All apartments or flat buildings hereafter constructed or erected ~~without~~ in the City of Fort Wayne that are over two stories in height shall have the outside walls constructed of brick stone or other incombustible material, and if more than one flat or apartment in width shall have division walls of brick stone or other incombustible material, extending from front to rear and from basements through roof of said building as aforesaid.

It shall be unlawful to construct any brick or stone veneered building for any purpose over two and one-half (2½) stories in height

Section 12.

Basement Walls for Brick or Stone Buildings Thickness Thereof.

All basement walls built of brick shall be laid in lime or cement mortar. If solid buttresses, or if iron or steel pillars not over eighteen feet between centers with sufficient strength to carry trusses ~~and~~ or girders are used, then the thickness of the walls may be reduced four (4) inches: provided however that no brick wall shall be less than twelve (12) inches in thickness

The thickness of walls herein specified and set forth in the table for the various buildings are intended to apply to all exterior enclosing walls and all such interior walls as may be required for the support of floors and roofs

Section 13.

Curtain Walls - Thickness of.

No curtain wall shall be over one (1) story in height without underbearing and not less than twelve (12) inches in thickness, except in case of tenement or apartment buildings when they may be eight (8) inches in thickness

Section 14.

Additional Thickness of Walls - when

When it should appear that extra or additional strain shall come upon any wall or pier extra provision shall be made for carrying the same by additional thickness of walls or additional size of pier or the addition of proper pilasters

Section 15.

Party Wall Three Feet Above Roof - When

When an adjoining roof comes in contact with a party wall the said party wall shall be at least three feet above the adjoining roof at all points of contact, and there shall be no openings in such walls above contact of roof. No such Wall shall be of less thickness than the wall next below

Section 16.

Recesses in Walls - When

Recesses may be made in external walls provided the thicknesses of the backs of such recesses be not less than eight (8) inches

Section 17

Fireproof Doors - When

Whenever it becomes desirable to cut an opening through or leave an opening in any party or division wall, notice shall be filed with the Building Inspector, who shall when satisfied that such opening is protected by a fireproof door or doors on each side of wall, said doors shall be sliding doors whenever practicable, issue a permit therefor

Section 18

Hollow Walls

Hollow walls not being bearing walls, may be used in all cases but all hollow walls should be bonded or tied together with incombustible anchors placed not more than three (3) feet apart If used as bearing walls, the thickness shall be reckoned by their solid parts, unless either part is at least eight (8) inches thick and solid connections are made in upright directions not less than twelve (12) inches wide nor more than eight (8) inches apart from centers

Section 19

Hollow Brick

Hard burned hollow brick may be used for the inside course of walls for building, when well bonded into the solid brick walls Provided, however, that the strength of walls so built shall be sufficient to properly support the dead and live loads they may have to sustain

Section 20,

Exterior Walls

Exterior walls faced with stone shall have a backing of not less than eight (8) inches of hard brick work laid in mortar, but in no case shall the thickness of stone and backing taken together be less than the thickness required for a brick wall of the height as given in the tables.

The stone facing of such walls shall be securely tied to the brick backing by means of bond stones or metal clamps.

Section 21,

Stone Cornice - How Laid

In all cases where a wall is finished with a stone cornice the greater weight of material of such cornice shall be on the inside of the face of the wall, so that the cornice shall firmly balance upon the face of the wall

Section 22

Brick Walls - How Bonded

In every brick wall, every sixth course of brick shall be a

heading course except where walls are faced with face brick in which case every sixth course shall be bonded with Flemish headers or by cutting the course of face brick and by putting in diagonal headers behind the same or by metal anchors All backing courses shall be of good hard perfect brick

Section 23,

Backing of Walls Faced with Ashler - How Thick

In all walls which are faced with thin ashler anchored to the backing or in which the ashler has not alternate headers and stretchers in each course, or alternately heading and stretching courses the backing of brick shall not be less than twelve (12) inches thick. Each stone of said ashler work shall be properly anchored.

The backing of all walls of whatever material it may be composed shall be of such thickness as to make all walls the facing of which is less than four (4) inches thick, conform as to thickness independent of the facing with the requirements of this ordinance

Section 24.

Wooden Girders or Lintels not allowed - When

It shall be unlawful to erect construct or build any rear front party, division, or partition wall upon wooden girders rafters or lintels or to support any such wall by any wooden support whatever. But all such supports shall be of iron brick or stone and shall rest on sufficient stone or incombustible templates

Section 25

No Timber allowed in Brick Walls

No timber shall be used in any wall of any building as a means of support where stone brick or iron is used as a common construction except arch forms for interior arch openings: arch forms not to rest on wall exceeding two (2) inches

Section 26

Anchors - When

The end and side of party walls shall be anchored at each tier of beams or joists at intervals of not more than ten (10) feet with good strong wrought iron anchors at least three-eighths (3/8) by one and one-half (1½) inches well built into the walls and fastened to the beams, and where the beams are supported by girders, the end of the beams resting on the girders shall be bolted together end to end and properly tied together at the same distance apart and in the same beams as the

wall anchors and shall be well fastened
All wall anchors shall run within four (4) inches of the opposite side of the wall where they do not run through the wall.

Section 27

Height of Wall above another Wall not more than two Stories

In the construction of any building, no wall shall be carried to a greater height than two stories above any other wall of the same building. All walls shall be securely braced during the process of construction

Section 28

Floor Beams or Joists

Floor beams or joists shall have a bearing of at least four (4) inches at each end.
The butts or ends of all floor beams and rafters entering a brick wall shall be cut on a splay of three (3) inches in their width

Section 29.

Trimmers and Headers hung in Stirrups

Every trimmer or header more than four (4) feet long, or tail Joists used in floors of any buildings, except dwellings shall be hung in stirrup irons of suitable strength for the weight to be supported.

Section 30.

Roof and Floor Timbers not to go through Walls

Roof or floor timbers entering the same wall from opposite sides shall have at least four (4) inches solid brick work between the ends of said timbers, except foundation walls in dwelling houses.

Section 31

Floor Timbers not to enter Chimney Walls

All floor beams, joists and headers shall be kept at least two (2) inches clear of any wall enclosing a fire flue or chimney breast

Section 32

Furred Walls or Chimneys

In all walls or chimneys furred with wood, two courses of the brick work between the ends and opposite the wood beams or joists shall project the thickness of the furring beyond the inner face of the wall.

Section 33.

Scantling Partitions not to support Floors - When scantling partitions shall not be employed to support any floor or roof except in dwellings and two (2) story store buildings

Section 34.

Non-Combustible Supports—

No building hereafter to be used as an apartment house, hotel lodging house, office building, hospital, school building, assembly hall of any kind, or public buildings located in any part of the city or any structure within the fire limits of the city given in Chapter 4. Section 1. shall be constructed with floor beams or joists of wood exceeding twenty-six (26) feet clear span. Each joist shall have proper bearings at each end on non-combustible or properly insulated material.

These supports may be of brick, stone, or other forms of burnt clay, concrete or structural metal. In case of structural metal it shall be properly insulated against the destructive action of heat in the following manner.

Such insulation shall be made of burnt clay, metal lath covered with cement or plaster or other approved method of fire-proofing; all to be done according to the recognized standard methods

Girders, beams or joists of metal for supporting joists may be in excess of twenty-six (26) feet in length but no joist shall be supported by a stud or other combustible partition or a partition that is destructible by heat, except as provided in Section 32.

Within the above district or for structures of the class above named, furrings of wood or other combustible material or partitions shall have at the bottom thereof in each story, cut-offs eight (8) inches in height of brick, cement, plaster, concrete or other incombustible material

Each span of joists for the above structures shall be provided with cut-offs of block bridging two (2) inches thick by the width of the joists or other material which shall prevent the passage of heat and smoke from one end of the joist to the other

Each ramp of stairway of above structures shall be provided with two (2) sections of blocking as above. This blocking is in addition to the bridging elsewhere described

Section 35

Iron and Steel Girders to rest on Stone Templates - Where under the ends of iron or steel girders resting on walls, stone templates may be used of sufficient carrying capacity to sustain the superimposed load, Standard metal plates may be used under all metal beams or girders.

Section 36,

Brick and Hollow Tile Partitions.

Eight (8) inch brick and six (6) inch and four (4) inch hollow tile partitions of hard burnt clay, or porous terra cotta may be built not exceeding in their vertical portions a measurment of twenty-five feet, sixteen (16) and twelve (12) feet respectively and in their horizontal measurments a length not exceeding seventy-five (75) feet, unless strengthened by proper cross walls, piers, or buttresses, or built in iron or steel framework. All such partitions shall be carried upon proper foundations or under supports or on iron or steel girders and columns or piers of masonry

Chapter XX

Section 1

Bonding of Walls

All rubble masonry work shall be thoroughly bonded with three-quarter or full load

Ledges will be permitted to support joist or beams, but shall be of sufficient strength to carry the load imposed thereon

Section 2,

Ground Dampness

In all cases where the nature of the soil is damp or contains water, suitable provisions shall be made to carry off such dampness or moisture by means of drainage tiles laid inside or outside of the wall or both. Such drain tiles shall be connected with a catch basin or other suitable device, and thence discharged into a dry well or sewer

Section 3.

Party Walls

The Thickness of a party wall of brick shall be one-half brick thicker than external walls, given in the tables but never less than one and one-half (1½) brick except in building of the third and fourth class and shall be so constructed that the thickness of the wall shall not be less than one brick between the ends of the joists after allowing for a full bearing of

Joists and timbers entering from opposite sides

Section 4,

Existing Party Walls.

Walls heretofore built or used as party walls whose thickness at the time of erection was in accordance with the then existing laws, but which are not in accordance with the requirements of the various Chapters on Buildings may be used if in good condition for the ordinary use of party walls provided the height of same is not increased and provided further that the conditions of stability required by the various Chapters on Buildings are complied with

Section 5,

Lining Existing Walls

In case it is desired to increase the height of existing party or any other walls which are less in thickness than required under the various Chapters on Buildings the same shall be done by a lining of brickwork to form a combined thickness with the old wall not less than one-half brick more than the thickness required for a new wall corresponding with the total height of the wall when so increased in height. The said lining shall be supported on proper foundations. No lining shall be less than one (1) brick in thickness and all linings shall be laid upon cement mortar and thoroughly anchored to the old brick walls with suitable wrought-iron anchors placed two (2) feet apart and properly fastened or driven into the walls in rows alternating vertically and horizontally with each other, the old walls being first cleaned of plaster or other coatings where any line is to be built against the same.

No Wall shall be lined less than one and one-half (1½) brick in basement.

All lining in basement must project one-half the brick beyond the lining in the first floor, or skeleton steel or iron construction may be used with posts and girders supporting each story and carrying up to the full height of the proposed building, resting on such foundation as provided

Section 6

Portland Building Blocks.

Portland building blocks with hollow spaces not exceeding one-third the area of the block and having an annulus of iron of uniform thickness and not exceeding nine (9) inches

high nor less than eight (8) inches, on the beds may be substituted for brick in all buildings up to two stories, and eight (8) inches by (8) eight (8) inches and eight (8) inches by ten (10) inches hollow tile blocks may be used in the interior walls not exceeding in their height a measure of twelve (12) feet

Section 7.

Arches and Lintels

Openings for doors and windows in all buildings shall have good and sufficient arches of stone, brick or terra cotta well built and keyed, with good and sufficient abutments, or lintels of stone, iron or steel of sufficient strength, which will have a bearing of each end of not less than six (6) inches on the wall. On the inside of all openings in which the outer lintels are less than the thickness of the wall to be supported, there shall be timber lintels, which shall rest at each end and shall have a suitable arch turned over the timber lintel. Or the inside lintel may be of cast-iron, or wrought-iron or steel in which stone blocks or cast-iron plates shall not be required at the ends when the lintel rests on the wall, provided the opening is not more than six (6) feet in width

Section 8.

Hollow Brick and Tile Lining of Walls

The inner facing of one-half (½) brick of walls, except under concentrated loads of girders may be built of hard burned hollow brick if of the same dimensions of ordinary brick and properly bonded into walls, course by course

Where hollow tile or porous terra cotta blocks are used as lining or furring for walls they shall not be included in the measurement of the thickness of such wall except in certain walls not over one (1) story or fifteen (15) feet high and where the lining course is of the same dimension of ordinary brick or they may be used in any other position; provided that the applied stresses do not exceed the maximum of safety established

Section 9

Foundation Soil and Walls

Proper foundations, walls, piers, posts or columns and their footing of masonry, concrete or other approved materials shall be provided for the support of buildings or structures

Foundation walls built of brick or of stone, with smooth level beds and square ends shall be at least four (4) inches

thicker than the base of the wall of the story next above, and for each additional twelve (12) feet or fraction thereof in depth below the first twelve (12) feet of every foundation wall shall be increased four (4) inches in thickness and foundation and area walls shall in all cases be sufficiently heavy or rigid to resist the thrust of the surrounding ground. Foundation walls built of stone not having smooth level beds and squared ends, must be thrown out four (4) inches thicker than above prescribed. The bottom of foundation or footings of external walls or piers shall be at least three (3) feet below the ground surface exposed to frost and all walls and piers shall begin at least six (6) inches below the level of the excavation of the cellar.

Section 10

Drainage and Traps

Before the walls of buildings built on clay or compact soils which hold water are carried up above the foundation walls the cellars shall be connected through drain tiles and catch basins with the street sewers. Should there be no sewer in the streets or if the cellars are below the sewer or ground water level, there provisions shall be made to prevent water accumulating in the cellars to the injury of the foundations or the occupancy of the basement or cellar. All foundation walls are to be protected against the effect of frost

Chapter XXI

Reinforced Concrete

Section 1

Materials

All of the manufactured building materials employed in the construction of buildings shall be in accordance to the rules and standards adopted by the American Society of Civil Engineers in so far as they apply

Section 2.

Concrete Foundation.

No reinforced or manufactured concrete building materials shall be employed in the construction of buildings except in the construction of buildings except in accordance with the restrictions of this chapter

Section 3

Plans to be Submitted

Every system of concrete construction involving the application of reinforced members structural calculation to determine

strain bending moment and tensile strength must first be submitted to a committee composed of the Building Inspector. the Chief of the Fire Department and the City Engineer for their approval. A complete digest and exhibit of the principle and details of such system shall be submitted for the investigation of said committee who shall except or reject such system in their discretion.

Section 4

Supervision

All reinforced concrete construction shall be erected subject to the supervision of the Building Inspector. acting for and with the Building Committee and shall be according to the system or method of construction in use.

Section 5

Curtain or Apron Walls

The curtain walls for steel or iron skeleton, or reinforced concrete buildings supported in every story on independent iron. steel or reinforced concrete beams which have no brick or other bearing support intermediate between the piers, and spacing of piers is not over sixteen (16) feet shall be of a thickness not less than one-half brick (½) less than indicated by Table

Section 6.

Thickness of Walls

Buildings higher than seventy five (75) feet. but less than one hundred, (100) feet may have the upper story one (1) brick thick and all below, one and one half (1½) brick thick: provided further that the intermediate supporting beams or girders are not more than two (2) stories apart

Chapter XXI.

Fire Escapes and Stand Pipes - Fire Protection

Section 1

Permits and supervision

The granting of permits and the construction of fire escapes, fire doors and stand pipes, shall be under the supervision of the Building Inspector with the concurrence of the Chief of the Fire Department as to their location and proper use as hereinafter prescribed

Section 2.

Notice to Owners

The Building Inspector shall serve upon the owner or agent in charge of any building which does not conform to the

requirements of the various Chapters on Buildings regarding fire escapes, fire doors, stand pipes or other appliances required to be placed in or upon buildings a written notice requiring that such building be made to conform to the provisions thereof, within thirty (30) days after the service thereof

Section 3.

Any owner or agent failing to comply with such notice shall be guilty of a misdemeanor and for every period of thirty (30) days such failure shall continue shall be guilty of a separate offense and be subject to the penalty imposed by this Building Code for each offense

Chapter XXIII

Fire Escapes

Section 1

Buildings Exempt

Buildings which have the necessary number of fire-proof stairways as provided by the various Chapters on Buildings and all fire-proof hotels, school, hospitals, detention buildings and office buildings and tenement, apartments and club buildings having more than one interior stairway one of which, if there are two stairways, or two-thirds of which, if there are three or more stairways, lead in a direct line to an entrance on the ground floor, and which are accessible from all inter communicating hallways and provided with self-closing fire-proof doors to cut off smoke, and all other fire-proof buildings with two or more stairways, the occupancy of which contains nothing of a hazardous risk or inflammable nature under the rules of the Fire Department and dwellings not over three stories high, shall be exempt from the placing of fire escapes under the provisions of this chapter

Section 2

Buildings Requiring Fire Escapes

Every building now occupied or built to be occupied by one or more families above the second floor and every building already erected more than two stories in height to be used and occupied and used as a hotel and lodging house and having more than five (5) sleeping rooms above the second story, and every factory, mill manufactory, workshop, or other building three stories or more in height or where provision is made to employ ten or more persons above the second floor of such building: and any public or private hospital, asylum or school house, place of instruction or assembly

more than two(2) stories high which are not fire-proof buildings and every office building or any other building of any class occupied as described above, having but one stairway and being three stories or more in height shall be provided with one or more metal fire escapes extending from the first floor to the upper stories of such buildings and above the roof, and of such material and construction as here-in prescribed in this Chapter.

Section 3.

Number of Occupants - Number of Fire Escapes

All buildings described in Section 3 shall be provided with standard fire escapes (See Section 6) easily accessible by all the occupants of the building, without passing through sleeping or living apartments or rooms which have doors fastened by locks or bolts, as remote from the stairway as possible. When the number of people accommodated in or occupying any such building does not exceed fifty (50) above the second floor, it shall be provided with at least one (1) standard fire escape; if the number exceeds fifty (50) but does not exceed one hundred (100) the stairs of such fire escape shall be increased to twenty-four (24) inches and the balconies to forty-eight (48) inches in the clear; and when the number exceeds one hundred (100) ~~feet~~ but not more than five hundred (500), there shall be at least two such enlarged fire escapes; where there are over five hundred (500) the number shall be one additional for every five hundred (500) or part thereof or the two as specified above may have their proportions increased as provided for assembly halls and theaters.

Section 4

Floor Area

Every building requiring fire escapes or outside emergency stairs as prescribed in the various Chapters on Buildings and for which no special provision is made as to the number of escapes required, or in which there is doubt as to the number of occupants to be provided for, shall have the number of fire escapes or emergency stairs in addition to main stairs or other means of egress, determined according to area of floor area served, as set forth in the following schedule; except that in case of fire-proof office buildings not more than one escape shall be required, if not in conflict with any other provisions of the various Chapters on buildings. Standard fire escapes placed on buildings under the provision of this

Section shall have stairs not less than twenty-four (24) inches wide.

Class 1 – 2

Building height in Stories	Maximum No. of Sq. Ft per floor for one Escape	Provide one more Escape for each Additional
3 and 4	25.000	15.000 sq. ft
5 and 6	20,000	12.500 sq. ft
7 and 8	15,000	10,000 sq. ft-
9 and 10	10,000	7.500 sq. ft-
11 and 12	[illegible]	5.000 sq. ft-

Nothing in this Section shall be so construed as to admit of the use of a small number of fire escapes in buildings subdivided provided that when one fire escape of proper proportions serves two adjoining or two separate divisions of the same building the division fire or party walls in or between such buildings shall be 'dead' from foundation to coping.

Section 5.

Proportioning of Fire Escapes.

Fire escapes shall be proportioned to carry the live loads with the factors of safety bolted to the wall or otherwise securely attached to the exterior frame provided, however that in proportioning the treads of stairs and rungs of ladders a "live load" of not less than two hundred (200) pounds per foot of length is assumed, and where a stand pipe is used in connection with a fire escape, the weight of the water column is allowed for. the "dead" load with a "live load" of two hundred (200) pounds per square foot on each balcony.

Section 6.

Standard Fire Escapes

Unless otherwise provided in Sections 11 and 12 all fire escapes herein required shall be standard fire escapes

The standard fire escape shall be that as approved by the State Factory Inspection Department, which provides open metal return Fire Escapes with balconies forty-five (45) inches wide at each floor above the ground balconies to take in two (2) or more windows; the stairs connecting the balconies shall not be less than twenty-one (21) inches in the clear between hand-rails; hand-rails shall be three (3) feet high measured on balconies, and in center of treads; treads and risers shall be eight (8) by eight (8) inches the lowermost

balcony may be two (2) feet long by two and one-half (2½) feet wide placed eight (8) or ten (10) feet above the sidewalk grade with a straight wall run leading to the first landing next above. In lieu of the above exterior fire escapes if placed upon buildings of the second grade occupied by warehouses mills workshops and factories may have the stair risers not exceeding ten (10) inches high with treads not less than six (6) inches wide; from the topmost balcony to the roof an extension ladder shall be run not less than twenty-one (21) inches distant from the wall and extending above the roof twenty-one (21) inches in goose-neck form down to the roof and bolted thereon

Where the first balcony is more than ten (10) feet above the ground there shall be attached thereto a counter-balanced stairway extending to the ground. Said stairway shall be of the same construction, pitch and width and be provided with two hand-rails as the portion of the fire escape next above

Section

Straight Run. Escapes

Straight run fire escapes with balconies under different windows at the different stories may be placed on buildings the interiors of which are so divided that they are ~~promptly~~ properly accessible, provided that each balcony is not less than thirty (30) inches wide, and extends at least six (6) inches in length beyond each window jam. The stairway shall be run on solid walls and shall be at least twenty-one (21) inches in the clear with hand-rails on both sides; the outer edge of the nearest hand-rail shall be at least four (4) inches distant from the wall and be run from balcony to balcony without crossing a window or any other opening

Section 8.

Distance of Stairs from Windows

The balcony floors of all fire escapes shall not be lower than ten (10) inches below the top level of the sills of openings and no fire escape stairs shall cross a window or other walled openings at a less distance than twenty one (21) inches from the same, and fire escapes requiring intermediate stairs and landings and such portions of the stairs nearest the walls shall be placed on blank surfaces of walls and piers

Nothing in this section shall be so construed as to prohibit

the use of return fire escapes or emergency stairs in front of windows with balconies as described herein when placed at right angles to the face of the wall provided that no such portion of such escapes shall be within four (4) feet of any other window and that the stairs are not less than two (2) feet apart.

Section 9

Fire Escapes in Courts

No court less than eight (8) feet in width above the first floor shall contain a fire escape.

Every court in which there shall be a fire escape shall have direct and unobstructed access along the surface of the ground to a street alley or yard opening into the alley or street without entering or passing through or over a building unless by four (4) feet wide passage on the court or ground floor.

Section 10.

Fire Escapes on Streets.

All fire escapes overhanging streets alleys areas or passageways shall be subject to the limitation of head room. No fire escape wider than four (4) feet shall overhand any public property. All detention buildings, school buildings, assembly halls and theaters of First Grade hereafter erected, shall have their fire escapes or emergency stairs extend to the ground and along the street lines, the buildings shall be set back for that purpose, but in no case shall ladder escapes or drop ladders on fire escapes be used for such buildings.

Section 11.

Ladder Escapes

Ladder escapes may be employed on the street fronts of existing non-fire-proof building of any grade if upon examination by the Building Inspector and the Chief of the Fire Department it be found that the structural features of such fronts prevent the erection of a standard escape.

Ladder escapes may also be employed on street fronts of all fire-proof buildings occupied as public or private offices, hotels, warehouses or club houses.

When ladder escapes are used they shall extend from the grade to the roof as prescribed for stair escapes: the balcony shall take in not less than two (2) windows and shall never be less than thirty (30) inches wide and six (6) feet

long if the ladder is parallel with the wall and forty five (45) inches wide if the ladder stands perpendicular. If the ladder is perpendicular the scuttle holes (21 by 21 inches in the clear) shall be staggered in each alternate story. Provided that where ladder escapes are used they shall be at least eighteen (18) inches in the clear width between the uprights and rungs not less than three-fourths (3/4) inch square spaced not over fourteen (14) inches on centers. All ladders and scuttles of such fire escapes shall be opposite solid piers or portions of walls and the edge of scuttle holes shall be at least six (6) inches distant from the nearest window jamb: no ladder purporting to be placed as a fire escape shall be without balconies provided with hand-rails three (3) feet high.

All stand pipes placed on the outside of buildings shall be provided with ladder escapes.

Section 12
Other Designs

Nothing embodied under this chapter shall prohibit any person whose duty it is under the various Chapters on Buildings to erect fire escapes on buildings not over four (4) stories high from selecting and erecting a different stair pattern or any other and different device, design or instrument which upon test made under the rules and regulations of the State Factory Inspector, prove equally as efficient permanent and safe, external means of escape from fire and smoke as the devices prescribed in this Chapter.

Section 13
Stationary Ladders

All buildings requiring fire escapes shall have stationary iron ladders leading to the scuttle opening in the roof thereof and scuttles and ladders shall be kept so as to be ready for use at all times.

If the bulk-head is used in place of a scuttle, it shall have stairs with sufficient guard on hand-rail leading to the roof. In case the building should be a tenement house the door in the bulk-head or any scuttle shall at no time be locked, but may be fastened on the inside by movable bolts or hooks.

Section 14.
Painting and Repairing of Fire Escapes

Every new fire escape shall be painted with two coats of durable paint one put on in the shop and the other

at once upon the erection of such fire escapes and all fire escapes shall be kept painted and in good repair

Section 15.

Lighting and Gongs

The location of fire escapes in all buildings shall be conspicuously placarded during the day time and all hotels factories workshops, schools, detention buildings assembly halls and theatres and all other buildings requiring fire escapes which are occupied at night shall have all public halls, stairways, and passageways properly lighted and at the head and foot of such flight of stairs and at the intersection of egress to each fire escape shall be kept during the night a red light; and one or more proper alarms capable of being heard throughout the building shall always remain easy of access and ready for use in each of said buildings to give notice to the inmates in case of fire and there shall be kept posted in a conspicuous place in every sleeping room a notice descriptive of such means of escape

Section 16

Incumbrances on Escapes

All fire escapes shall be kept free from incumbrances or obstructions at all times and it shall be unlawful to place incumbrances or other obstructions or permit or cause such incumbrances or obstructions to be placed before or upon any fire escape at any time

Chapter XXIV

Fire Doors and Appliances

Section 1.

Other Suitable Protection

All windows and openings above the first story of any building may be provided with other suitable protection if approved by the Building Inspector and the Chief of the Fire Department and not in conflict with the various Chapters on Buildings

Section 2

Shutters to be Opened from Outside

All shutters opening on fire escapes and at least one row vertically in every three rows on any front with protected window openings above the first story in any building shall be so arranged that they can be readily opened from the outside by firemen. This Section also applies to all grated windows

Section 3

Inside Fire Doors

Where openings in interior brick walls are fitted with fire doors to prevent the spread of fire between buildings or parts of any building, the said fire doors shall be made of wood covered with tin described for standard fire doors and shutters. All buildings specified in this Chapter hereafter erected or altered, having openings on interior walls shall be provided with fire-proof doors, as hereinbefore provided.

Section 4.

Doors and Shutters to be closed at Night

Occupants of all buildings provided with fire doors and shutters shall close said fire doors and shutters at the close of business of each day.

Section 5

Painting and Repairing

All sheet metal coverings of shutters shall be painted on the under side at least one coat, and all exterior surfaces shall be painted and kept in good repair as prescribed for fire escapes.

Chapter XXV

Stand Pipes and Pumps

Section 1

Stand Pipes and Hose

Every building hereafter erected of greater height than sixty (60) feet but not exceeding one hundred and fifty (150) feet shall be provided with a suitable stand pipe running from the cellar to the roof not less than two (2) inches nor more than four (4) inches in size, the same to be provided with two (2) outlets with one and one-half (1½) inch hose, attached thereto on each floor including the basement cellar and placed as near the stairs as practicable but no outlet shall be placed more than five (5) feet above the floor level.

All buildings of the first grade over three stories and not less than seventy-five (75) feet high, and all buildings of the second Grade having two or more families or suites of apartments above the third floor, but less than seventy-five (75) feet high shall be provided with a three (3) inch stand pipe leading direct to the street water main. Said stand pipe shall be provided with valves and outlets on each floor as herein described.

Section 2

Siamese

Each interior or exterior stand pipe shall be provided with one two-way 2½-inch automatic Siamese at the bottom of each stand pipe placed on street above the curb level. Said Siamese shall be within four (4) feet distance from the sidewalk, and be securely anchored to the wall of the building.

Section 3

Exterior Stand Pipe

Exterior stand pipes may be placed on the outside of buildings not exceeding one hundred (100) feet in height

Each such stand pipe shall have connected with it a ladder fire escape. The pipe shall not be less than that of three (3) inch standard wrought iron pipe with a two and one half (2½) inch valve attached to every outlet on each floor, and goose-necked over and above the roof. Said stand pipe shall be secured to the ladder at every four (4) feet and bolted to each balcony.

Section 4

Number of Stand Pipes

If any of said buildings extend from street to street or form an L shape, they shall be provided with stand pipes for each frontage

Section 5

Standards

All valves, fittings and couplings used in connections with with stand pipes shall be of the standard size and thread in use by the Fire Department in the City of Fort Wayne.

Section 6.

Inspection

All valves, hose, tools and other appliances provided for in this section shall be kept in perfect working order, and once a month the person in charge of said building shall make a thorough investigation of the same to see that all valves, hose and other appliances are in perfect working order and ready for immediate use by the Fire Department

Section 7

Boiler Pit

The boilers which supply power to the passenger elevators and pumps, if located in the lower story shall be so surrounded by a dwarf brick wall laid in cement mortar or other suitable permanent water-proof construction as to exclude water to

a depth of two (2) feet above the floor level from flowing into the ash pits of said boilers.

Section 8

Cess Pool

Where the level of the floor in the lowest story is above the level of the sewer in the street, a large cess pool shall be placed in said floor and connected by a four (4) inch cast-iron pipe with the street sewer.

Section 9

Sewer Connections

In all buildings already or hereafter to be built in the City of Fort Wayne, used or intended to be used for mercantile or manufacturing purposes and located where a sewer connection can be made there shall be in the cellar or basement a sewer connection which can be ~~operated~~ immediately for the purpose of drainage in case the building or any of the floors or basement or cellar thereof should be flooded from any cause and the location of said sewer connection shall be as near the main stairs as possible, and shall be indicated by a permanent and conspicuous sign near the cellar or the wall near the same and such sign shall never be hidden or obstructed, but shall always be in plain view.

Section 10.

Sprinkling System.

In building three stories or more in height within the fire limits, used or occupied for store, warehouse, workshop or factory purposes, there shall be provided in connection with said stand pipe or pipes two and one-half (2½) inch perforated iron pipes placed on and along the ceiling line of each floor exclusive of all those below the first floor and extending to the full depth of the building. Such perforated pipes shall be provided with a valve placed on or near the stand pipe so that the water can be let in to the same when deemed necessary by the Chief of the Fire Department, or in lieu of such perforated pipes a separate and distinct system of automatic sprinklers with fusible plugs shall be installed under the supervision of the Building Inspector and the Chief of the Fire Department in accordance with the rules and regulations of the Water Works Department

Store buildings, warehouses, factory buildings and workshops in which automatic sprinklers are installed shall have

their floors built water-tight and scuppered to a depth of at least one and one half (1½) inches provided with proper iron holes in the side walls of floor drain connected with drop pipes leading to the cellar floor drains.

Section 11.

Number of Lines.

When the building is twenty-five (25) feet or less in width, two lines of perforated pipes shall be provided and one line additional for each twelve (12) and one-half (½) feet or part thereof, that the building is wider than twenty-five (25) feet

Section 12

Placard.

A suitable plate shall be fastened to the wall near said stand pipe to read: This stand pipe connects to perforated pipes in the cellar.

Section 13

Tests and Repairs.

All stand pipes, tanks fire alarms, hose and other appliances provided for in this Chapter shall be maintained in good repair and working order at all times, and shall be subject to inspection and test at least twice a year by the Fire Department to ascertain their condition.

Chapter XXVI

Elevators - Explanatory

Section 1

Subjects Included

The subjects under Chapters 27, 28 and 29 shall include all elevators, hoists, lifts, derricks, dumb-waiters or any mechanical devices which employ cables, pulleys, platforms and swinging ladders or scaffolding, whether permanently or temporarily fixed in position for the purpose of conveying people animals or lifting merchandise building materials or any other load to any point on or in a structure above or below the grade line

Section 2

Lifting Tackle of Derrick Hoist or Swinging Scaffold

For the purpose of various Chapters on Buildings all lifting tackle of any derrick, hoist or swinging scaffold shall be subject to the rules and regulations governing freight elevators and all the other supporting parts of such derricks, hoists and swinging scaffolds shall be proportioned to meet the conditions of stability of frame structures

Chapter XXVII

Permits Inspections and Fees

Section 1

Permits for Erection of Elevators

It shall be unlawful for any person or persons company or corporation to construct, erect or place or cause to be placed in any building or structure, erected or in course of erection any elevator to be used for carrying passengers or freight from one floor to another without first having obtained from the Building Inspector a permit therefor.

Before said Building Inspector shall issue such permit for the erection, construction or use of such elevators, there shall be filed in his office as a matter of record, plans and specifications showing the type and make of the machine the motive power to be used the size of all ropes sheaves, drums and supporting beams; also speed, travel and capacity of car, type of safties dimensions of pressure tank the pressure carried thereon the number of volts and amperes of electric current or motor used

The Building Inspector shall not issue a permit for the erection construction or use of any elevator as defined in Chapter 29. that may have less than two (2) ropes of approved diameter carrying the weight of the car and its load, or each counter-balance weight thereof

Sections 2

Existing Elevators to be Equipped

Any person or persons company or corporation having charge of any building in which is or may be in use, shall equip such elevator with the devices or appliances required in Chapter 29 on Buildings; and keep the same in good working order and repair; and it shall be unlawful for any person or persons, company or corporation to erect use or operate or cause or permit to be erected used or operated in any building within the city of Fort Wayne, freight or passenger elevator, unless the same be equipped, with the devices and appliances as provided in the aforesaid Chapter

Section 3

Inspection and Notice of Repairs

When an elevator is placed in a building the owner or his agent shall so immediately notify the Building Inspector

in writing, and such elevator shall not be used until it shall have been duly inspected. A like notice of any repairs or alterations intended to be made shall be given by the person employed to make such repairs or alterations

Nothing in this Section shall prevent an owner from making the ordinary repairs for maintenance or prevent him from making repairs at once when needed, pending the serving of the above notice when a certificate of inspection is needed

Section 4

Examination and Certificate

Every owner shall require the person in charge of the running of his elevator to carefully examine the same and its appliances once in twenty four (24) hours and upon the discovery of any defects or impairments tending to endanger life the elevator shall be shut down at once and the Building Inspector notified, The use of such defective elevator shall be prohibited until the necessary repairs to make it safe have been made inspected by the Building Inspector and a certificate in writing is issued by him that said elevator has been put in safe working order and is fit for use

The said certificate shall be placed under glass and framed and hung in a conspicuous place in the car of the elevator for which the certificate was issued

Section 5

Metal Plate Showing Carrying Capacity

The owner, lessee manager or other person having charge or control of any elevator in the City of Fort Wayne shall cause to be fastened in a conspicious place in said elevator metal plate having suitable letters on same, which shall prescribe the number of pound weight which said elevator after proper test have capacity to carry

All elevators, before being put into use shall be tested with a load equivalent to twenty five (25) per cent. more than the lifting capacity stamped on the plate, This test shall show no weakness when the elevator is working either upward or downward as in ordinary use

Section 6

Prohibiting use of Unsafe

Should any defect be found in any parts or part of any

elevator which would intend to impair its safety or endanger life by the continued use of such elevator the Building Inspector shall immediately inform the person in charge of the danger of continuing the use thereof: and the Building Inspector shall immediately cause a notice in writing to be served upon the owner or owners, lessee, or manager or any other person or persons having use, control or management of said elevator, which notice may contain a statement of the necessary repairs: and said elevator shall not again be used, until a certificate in writing shall be issued by the Building Inspector that it has been put in a safe running order and is fit for use. The notice herein provided for may be served upon any person having charge of the running of said elevator

Chapter XXVIII

Construction

Section 1

Passage under adjoining Elevators

There shall be no kind of a passage in any story of a building below the platform of an elevator and wherever such passage is in existence it shall forthwith after the passage of this Ordinance be abolished. Public Halls or passageways in front of elevators hereafter erected shall be at least one (1) foot wider than the width established for elevator doors

Section 2

Ropes, Cables and Platforms

Ropes and cables whose diameter shall be approved for use in any elevator shall have a factor of safety of at least five (5) for all diameters over five-eighths (5/8) inch: six (6) for under five-eighths (5/8) inch. but more than one-half (1/2) inch. and eight (8) for all diameters below one-half (1/2) inch All elevator platforms shall have a factor of at least four (4). If elevators are exposed to the action of the elements the factor shall be increased twenty-five (25) per cent of the above and where any rope or cable show twenty-five (25) per. cent. of deterioration it shall be considered unsafe

Section 3.

Number of Cables

All freight elevators shall have not less than two (2) hoisting cables with suitable adjustments or equalizers the bearings No passenger elevator shall have less than four (4) hoisting

cables provided that those passenger elevators the cables of which wind around a drum may have two (2) hoisting cables if the car is counterweighted separate from the drum the counterweight to have two (2) cables and cables to be provided with suitable equalizers to equalize bearings. All ropes and cables shall be independently fastened at their terminal

Section 4.

Elevator Sheaves

All elevator sheaves or drums for rope transmission shall not be less in diameter than twelve (12) times the circumference of the cable used on such elevator.

Section 5

Elevator Governor

All freight and passenger elevators (except hand power) shall be provided with an automatic down speed governor or regulator except worm gear elevators the speed of which is less than sixty (60) feet per minute

Section 6

Shut-off

Every power elevator shall be provided with an automatic shut-off which shall stop it at its foot and at its highest landing. Such elevator shall also have slack cable devices

Section 7

Cable Stops

All freight and passenger elevators (except hand power) in any building the cables of which wind around a drum must be provided and equipped with an automatic trip or slack cable stop and automatic brake of sufficient strength to hold the car at any point

Section 8

Safety Floor Stops

All freight elevators shall be provided with a safety device by which persons using the elevator at one floor can lock the operating cable to prevent the moving of the elevator by persons on another floor during loading and unloading

Section 9

Automatic Trap Doors

All freight elevators whose speed is less than fifty (50) feet per minute not inclosed in shafts as provided in Section 14 shall have automatic trap doors, tin lined on the under

side at each floor so constructed as to form a substantial floor surface when closed and so arranged as to open and close by the action of the elevator ascending and descending

Section 10
Supports and Guides

In all buildings hereafter to be erected over three stories high the beams for supporting overhead work shall be of iron or steel and such beams shall be supported on brick walls or continuous iron columns resting on concrete or masonery foundations, and all guide posts or run-rails for elevator car and counter weights shall be of iron or steel in all buildings over five stories high when operating in open or grill enclosed hatchways and in all buildings over nine (9) stories in all hatchways.

The counterweight guide shall be provided with limit stops so constructed as to prevent the running of the weights above the guide strips into the elevator shaft under any circumstances either by accident or to loss of control of the elevator. All weights shall be securely bolted together with rods passing through all the weights.

Section 11.
Automatic Oilers for Guides

All passenger elevators shall be provided with suitable oiling device for lubricating the guides automatically, to obviate the necessity of a person riding on top of the cage for that purpose

Section 12.
Screens under Sheaves and Beams

Every power elevator shall be provided with a proper screen under its sheaves and beams to prevent tools and other things dropping on the hoistway.

Section 13.
Elevator Pits

All freight or passenger elevators shall have a pit extending at least thirty-six (36) inches below the lowermost floor level and elevators not extending down to the basement shall have fireproof pits at the lowermost floor level above which they serve. Such pits shall have no openings except holes for cables

Section 14
Brick Enclosure

Whenever an elevator shaft extends down to a basement that portion thereof inclusive of the space occupied by the machinery

shall be constructed of brick and be filled with an automatic fire door as provided in Section 15.
All freight elevators in every building shall be enclosed with brick walls or fireproof partitions which do not depend upon wooden beams for support. And where they are not placed on an outside wall with window openings therein and serve more than one floor their enclosures shall be carried six (6) feet or more above the roof of the building and be covered with a skylight of double thick glass and is protected by a screen made of No 12 wire with one (1) inch or closer meshes. All elevator skylights shall have an opening device controllable from each and every floor.

Section 15

Elevator Fire Doors and Safety Gates

All elevators enclosed with brick walls or in fire proof shafts shall be provided with fire proof frames and doors. Said doors shall be provided with an approved device or system which will automatically close the openings in the event of fire. And in addition to said automatic fire doors the elevators shall be provided with automatic opening and closing hatch gates to protect the approach to the elevator when the doors are open

Section 16.

Freight Elevator wall hole Railings

All freight elevator shafts and hoistways in any building not enclosed as provided in Section 14. shall be protected and enclosed on each and all floors of any such building with suitable frame work or railing not less than three (3) feet high and all approaches and entrances to any such elevator shafts and hoistways shall be provided with Automatic self-closing gates; and no person shall use permit or cause to be used any such freight elevator shaft or hoistway in any building unless the same is protected or enclosed as above required

Section 17.

Hoists and Elevators - Well Holes to be Guarded

In all buildings in the City of Fort Wayne in course of construction and in all buildings having elevators for freight lifts only and not constructed, protected and operated as required for passenger elevators it shall be unlawful to use hoists and elevators for hoisting materials etc., in any such building buildings unless the well holes or openings for such elevators

or hoistō on each and every floor of thē building shall be closed with guard rails composed of boards placed six (6) inches apart to a height of three (3) feet. with a gatē or door swinging outwards from thē elevatōs and other such safety or equivalent appliances as shall be necessary for thē protection of life and limb.

Section 18

Dumb-Waiters

Dumb-waiters extending to a basement and serving three or more floors in a building shall be deemed freight elevatōs and shall be enclosed. accordingly except that they need not extend to thē roof. provided that they are thoroughly fire-stopped at thē bottom and thē uppermost story served. In non-fireproof buildings. where dumb-waiters are enclosed in shafts thē walls of such shafts shall be plastered on metal lath or lined with tin.

Section 19

Passenger Elevatōs - Shafts

Elevatōs used exclusively for passenger service in all wholesale stōres. factories or warehouses. or passenger elevatōs with a freight attachment underneath located in any buildings shall be treated and provided as above prescribed for freight elevatōs with thē distinction that thē enclosing partitions may be of plastering on metal lath or any other fireproofing having wooden doors with wire glass if any glass at all.

Section 20

No Elevatōr in Well Hole

No elevatōr shall hereafter be constructed in thē well hole of any stairway. unless there be a fireproof wall between such elevatōr and said stairway. extending from thē basement to a point three (3) feet above thē level of thē roof. elevatōr shafts in fireproof building alone. excepted

Section 21,

Stairs Adjoining Elevatōr

In either of thē cases cited under Sections 19 and 20 thē stairs accompanying such elevatōr shall be enclosed with partitions equal to those employed for enclosing thē respective elevatōr and there shall also be such partition between thē elevatōr and thē adjoining stairway

Section 22

Elevatōrs in Staircases

Open grill work enclosures for passenger elevatōrs not extending below thē level of thē first floor. may be erected in

staircase enclosures in buildings where the entire space is occupied by the stairs and the elevator is enclosed in brick or stone walls and the stairs are of fireproof construction.
All elevators if used exclusively for private purposes in all dwellings or within a suite of offices of business apartments for not more than three (3) stories and a basement in height, if entirely detached from the public hall or stair halls or passage ways leading thereto need not have their shafts extended to the roof, provided such shafts are properly enclosed in conformity with the various Chapters on Buildings

Section 23
Passenger Elevator Enclosures

All passenger elevator shafts except as prescribed in Section 19 shall be enclosed from the floor to the ceiling on all entrance sides and to a height not less than seven (7) feet six (6) inches on all other sides and when iron work or grill work is used no greater spaces than two (2) inches square or one and three-fourths (1 3/4) inches clear way if vertical rod work is used, shall be permitted, and no obstruction of any kind shall extend into any elevator shaft or be placed on the enclosure thereof in front of the entrance door

Section 24
Doors

The doors approaching elevator shafts shall have safety locks of approved make so that said doors will be closed when the elevator car is not at the floor where said doors are located

Section 25
Door Ways to Cars

It shall be unlawful to maintain or operate any passenger elevator in the City of Fort Wayne which has more than one entrance or doorway to the car unless each of said entrances or doorways is provided with a door on the inside of said car, said door to be closed by the operator before said car is put in motion: all doors to cars shall not be less than seven (7) feet high.

Section 26.
Cage of a Car

The cage of all passenger elevator cars shall be constructed of metal or other incombustible material except floor covering but there shall be no glass or porcelain used in the structural or ornamental parts or canopy of any cage The use of glass or porcelain in all elevator cars for general public use shall be

confined to covering of certificates of inspection annunciators and the lighting lamps. In every passenger elevator there shall be placed a metal hand rail one (1) inch in diameter and forty two (42) inches above the floor, on all sides not having door openings. The canopy of any of any passenger elevator shall be so constructed that the whole or semi-circular part sixteen (16) inches in depth by the width of the door in width above the entrance door can be easily removed from the top

Section 27

Sidewalk Elevator Doors

All doors covering sidewalk elevator holes when opened shall open only sufficiently for proper service and also form a guard to the aperture while open, and when the covering doors attached to the frame of the lift open automatically the sides of the lift at right angles to the curb shall be safeguarded with metal lattice work

Section 28.

Protection of Well Holes. Elevator Shafts and Open Courts in Existing Buildings

Owners of all buildings erected prior to the passage of the various Chapters on Buildings containing elevator hatches or Well holes, Elevator shafts or open ports shall upon written notice from the Building Inspector so to do properly and sufficiently guard and protect such elevator hatches well holes or elevators with gates or guides so as to avoid danger to human life, and said gates or guides shall be closed on all floors except where cars are in actual use.

Section 29

Elevator in Existing Hotels

In every non-fireproof building used or occupied as a hotel after the passage of the various Chapters on Buildings in which there is an elevator not enclosed in a fireproof shaft such elevator shall be enclosed in partitions of uncombustible materials constructed and arranged as described in Section 19 for passenger elevator shafts

Chapter XXIX

Opera Houses and Theaters

Section 1

Aisles not to be Blocked

In all buildings of a public character such as hotels, theaters restaurants railroad depots public halls and other buildings

except churches used or intended to be used for purposes of public assembly amusement or instruction and including apartment stores and other business and manufacturing buildings where large numbers of people are congregated the halls, door stairways, seats, passageways aisles and all lighting and heating apparatus and appliances shall be arranged to facilitate egress in case of fire or accident and to afford the requisite and proper accommodation for the public protection in such cases All aisles and passageways in said buildings shall be kept free from camp stools chairs, sofas, drop seats, and other obstruction, and no person shall be allowed to stand in or occupy any of the said aisles during any performance exhibition lecture, concert, ball, or any other public assembly. The Building Inspector having jurisdiction may serve a written or printed notice upon the owner or lessee or manager of said buildings directing any act or thing to be done or provided in or about said buildings and the several appliances therewith connected, such as halls doors, stairs windows, seats, aisles, fire-walls fire apparatus and fire escapes to comply with the provisions of this chapter.

Section 2

Construction and Character

Every theater or opera house or other building intended to be used for theatrical purposes or for public entertainment of any kind hereafter erected for the accommodation of more than three hundred (300) persons shall be built to comply with the requirements of this Chapter. No building which after the passage of this ordinance is not in actual use for theatrical or operatic purposes, and no building hereafter erected not in conformity with the requirements of this Chapter, shall be used for theatrical or operatic purposes or for public entertainments of any kind until the same shall have been made to conform to the requirements of this Chapter. And no building hereinbefore described shall be open to the public for theatrical or operatic purposes or for public entertainments of any kind until the Building Inspector shall have approved the same in writing as conforming to the requirements of this Chapter. Every such building shall have at least one front on the street, and in such front there shall be suitable means of exit and entrance for the audience

In addition to the aforesaid entrance and exits on the street there shall be reserved for service in case of emergency

an open court or space on the side not bordering on the street where said building is located on a corner lot; and on both sides of said building where there is but one frontage on the street The width of such open court or courts shall not be less than ten (10) feet in width when the seating capacity is eighteen hundred (1800) or above that number, and when less than eighteen (1800) hundred. eight (8) feet in width. said open court or courts shall begin on a line with the proscenium wall and extend the length of the auditorium proper, to or near the wall. separate the same from the entrance lobby or the vestibule. A separate and distinct corridor shall continue to the street from each open court through such superstructure as may be built on the street side of the auditorium with continuance walls of fire proof materials on each side of the entire length of said corridor or corridors and the ceiling and floor shall be fireproof. Said corridor or corridors shall not be reduced in width to more than three (3) feet less than the open court or courts and there shall be no projections in the same; the outer openings to be provided with doors or gates opening toward the street.

During the performance the doors or gates in the corridors shall be kept open by proper fasteners at other times they may be closed and fastened by movable bolts or locks. The said open courts and corridors shall not be used for storage purposes or for any other purpose whatsoever. except for exit from and to the auditorium stage and must be kept free and clear during performance. The level of said corridors at the entrance to the building shall not be greater than one step above the level of the sidewalk where they shall begin at the street entrance The entrance to the main front to the building shall not be on a higher level from the sidewalk than four (4) steps thirty two (32) inches unless approved by the Building Inspector.

Section 3,

Number and Character of Exits

To overcome any difference of level in and between court corridors lobbies passages and aisles on the ground grade inlets shall be employed of not over one (1) foot in twelve with no perpendicular risers. From the auditorium opening into said court or into side street there shall be not less than two exits on each side in each tier from and including the parquet and each and every gallery. Each exit shall be at least five (5) feet in width in the clear, and provided with doors

of iron or wood. if of wood. the door shall be battened. and covered. within. all of said doors shall open outwardly and shall be fastened with movable. bolts. the bolts to be kept drawn during performance

Section 4

Balconies. Staircases. Rooms. Offices. Doors, Walls, and Curtains

There shall be. balconies not less than four (4) feet in width in the said open court or courts at each level or tier above the parquet on each side of the auditorium of sufficient length to embrace the two exits and from said balconies there shall be staircases extending to the ground level. with a rise of not over nine (9) inches to a step and not less than nine (9) inch tread exclusive of the nosing. The staircase from the upper balcony to the next below shall not be less than thirty six (36) inches in width in the clear. and from the first balcony to the ground. the width shall be the same All the before-mentioned balconies and staircases shall be constructed throughout of iron. including the floors and of ample strength to sustain the load. to be carried by. there where one side of the building borders on the street. there shall be balconies and staircases of like capacity and kind as before mentioned carried to the ground. where located on a corner lot that portion of the premises bordering on side street and not required for the use of the theater. may if such portion be not more than twenty-five (25) feet in width be used for offices. stores or apartments. provided the walls separating this portion from the theater proper are carried up solidly to and through the roof and that a fire-proof exit is provided for the theater on each tier equal to the combined width of exits opening on opposite sides of each tier. communicating with balconies and staircases leading to the street in manner provided elsewhere in this section: said exit passages shall be entirely cut off. by. brick walls from said offices stores or apartments and the floors and ceilings in each tier shall be fireproof No workshop storage or general property room shall be allowed above the auditorium or stage or under the same or in any of the fly galleries. all of said rooms or shops may be located in the rear or at the side of the stage but in such cases they shall be separated from the stage by. a brick wall and the openings leading into said portions

shall have fire-proof doors hung on each side of the openings hung to iron eyes built into the wall. No portion of any building hereafter erected or altered used or intended to be used for theatrical or other purposes as herein specified shall be occupied or used as a hotel, boarding or lodging house workshop or manufacturing or for storage purposes except as may hereafter be specifically provided for.

Said restrictions relate not only to that portion of the building which contains the auditorium or stage but applies to the entire structure in conjunction therewith. No store or room contained in the building, or the offices, stores or apartments adjoining as aforesaid, shall be let or used for carrying on any business dealing in articles designed as specially hazardous in the classification of the underwriters association or for manufacturing purposes. No lodging accommodation shall be allowed in any part of the building communicating with the Auditorium. Interior walls built of fire-proof materials shall separate the auditorium from the entrance vestibule and from any room or rooms over the same also from any lobbies corridors, repastment or any other rooms. All staircases for the use of the audience shall be enclosed with walls of brick or fireproof material, in the stories through which they pass and the openings to said staircases from each tier shall be the full width of said staircase.

No door shall open immediately upon a flight of stairs but a landing at least the width of the door shall be provided between such stairs and such door. A firewall built of brick shall separate the auditorium from the stage and the same shall extend at least four (4) feet above the stage roof or the auditorium roof if the latter be the higher and shall be coped. Above the proscenium opening there shall be an iron girder of sufficient strength to safely support the load above and the shall be covered with fire-proof material to protect it from the heat. The moulded frame around the proscenium opening shall be formed entirely of fire-proof materials; if metal is used, the metal shall be filled in solid with non-combustible material and securely anchored to the wall with iron. The proscenium opening shall be provided with a fire-proof metal curtain of asbestos or other fireproof material sliding at each end within iron grooves securely fastened to the brick wall and extending into such

grooves a depth of not less than six (6) inches on each side of the opening. Said fire proof curtain shall be operated by approved machinery for that purpose. The proscenium curtain shall be placed at least three (3) feet distant from the foot-lights at the nearest point. No doorway or opening through the proscenium wall from the audetorium shall be allowed above the level of the first floor and such first floor openings shall have fireproof doors which shall be hung so as to be opened from either side at all times

Section 5,

Skylights, Fire-Proof. Requirments Aisles and Seats

There shall be provided over the stage metal skylights of an area or combined area of at least one-eighth the area of said stage filled with sliding sash and glazed with double strut thick glass not exceeding one-eighth of an inch thick and each pane therefrom measuring not less than three hundred (300) square inches, and the whole of which skylight shall be so constructed as to open instantly on the cutting or burning of a hemp cord which shall be arranged to hold said skylight closed or some other equally approved device for opening them may be provided. Immediately underneath the glass of said skylight there shall be wire netting, but wire glass may be used in lieu of this requirment. All that portion of the stage not comprising in the working of machinery traps and other mechanical apparatus for the presentation of a scene usually equal to the width of the proscenium opening shall be built of iron or steel beams, filled in between with fireproof material and all girders for the support of said beams shall be of wrought iron or rolled steel

The fly galleries entire including pairails shall be constructed of iron or steel and the floors of said galleries shall be composed of iron or steel beams and no wood boards or sleepers shall be used as a covering over beams but the said floor shall be entirely fire-proof The rigging loft must also be fireproof. all stage scenery curtains and decorations made of combustible material and all woodwork on or about the stage shall be painted or saturated with some non-combustible material or otherwise rendered safe against fire and the fireproofing

coat applied to all wood work throughout the building shall be of such kind as will resist fire. The roof over the audetorium and the entire main floor of the audetorium and vestibule also the entire floor of the second story of the front superstructure over the entrance lobby and corridors and all galleries and supports for the same in the audetorium shall be constructed of iron or steel and fire proof materials, not including the use of wood floor boards and necessary sleepers to fasten the same to but such sleepers shall not mean timbers for support and the space between the sleepers, except the portion under the slipping in the galleries which shall be properly fire stopped shall be solidly filled in with uncombustible material up to the underside of the floor boards, The fronts of each gallery shall be formed of fire proof materials except the capping which may be of wood. The ceiling under the gallery shall be entirely formed of fire-proof materials, All lathing wherever used, shall be of iron or other metal. The partitions in that portion of the building which contains the audetorium the entrance and vestibule, and every room and passage devoted to the use of the audience shall be constructed of fire-proof materials, including the furring of out side or other walls None of the walls or ceilings shall be covered with wood sheathing, canvas or other combustible material. But this shall not exclude the use of wood wainscoting to a height of not to exceed six (6) feet which shall be filled in solid between the wainscoting and the walls with fireproof materials.

The wall separating the actors dressing rooms from the stage and the partitions dividing the dressing rooms together with the partitions of every passage way from the same to the stage and all other partitions on or about the stage shall be constructed of fireproof materials. All doors in any of the said partitions shall be fireproof. All shelving and cupboards in each and every dressing room property room or other storage room shall be constructed of metal slate or some other fire-proof material.

Dressing rooms may be placed in the fly galleries provided that proper exits are secured therefrom to fire escapes in the open courts and that partitions and other matter pertaining to dressing rooms shall conform to the requirements herein contained, but the stairs leading to the

same shall be fire proof. All dressing rooms shall have an independent exit leading directly to the court or street and shall be ventilated by windows in the external wall and no dressing room shall be more than one story below the street level All windows shall be arranged to open, and none of the windows in the inside walls shall have fixed sashes iron grills or bars All seats in the auditorium except those contained in box seats shall not be less than thirty two (32) inches from back to back measured in a horizontal direction and firmly secured to the floor. No seat in the auditorium shall have more than twelve (12) seats intervening between it and an aisle on either side. No stool seat or drop seat shall be placed in any aisle. All platforms in galleries, formed to receive the seats, shall be not more than twenty one (21) inches in height of riser nor less than thirty two (32) inches in width of platform.

All aisles on respective floors in auditorium having seats on both sides of the same shall not be less than three (3) feet wide where they begin and shall be increased in width toward the exist in the ratio of one and one-half (1½) inch to five (5) running feet. All aisles having seats on one side shall not be less than two (2) feet wide at their beginning and increase in width, the same as the aisles having seats on both sides. The aggregate capacity of the foyers, lobbies, corridors and passages and rooms for the use of the audience not including aisle space between seats shall on each floor or gallery be sufficient to contain the entire number to be accommodated on said floor or gallery, in the ratio of one hundred and fifty (150) superficial feet of floor room for every one hundred (100) persons Gradients or inclined planes shall be employed instead of steps where possible to overcome slight differences of level in or between aisles corridors and passages. Every theater accommodating three hundred (300) persons shall have at least two exits: when accommodating five hundred (500) persons, at least three exits shall be provided; these exits not referring to or including the exits to the open court at the side of the theater

Section 6

Doors, Stairs and Galleries

All doors of exits and entrances shall open outwardly

and shall be hung to swing in such manner as not to become an obstruction in a passage or corridor and no such door shall be closed and locked during any representation or when the building is open to the public. Distinct and separate places of exit and entrance shall be provided for each gallery above the first. A common place of exit and entrance may serve for the main floor of the auditorium and the first gallery provided its capacity be equal to the aggregate capacity of the outlets from the main floor and the said gallery. No passage leading to any stairway communicating with any exit or entrance shall be less than four (4) feet in width in any part thereof. All stairs within the building shall be constructed of fire-proof materials throughout. Stairs from balconies and galleries shall not communicate with the basement or cellar. All stairs shall have treads of uniform width and risers of uniform height throughout in each flight. Stairways serving for exit of fifty (50) people shall be at least four (4) feet wide between railings and for every additional seventy-five (75) people to be accommodated six (6) inches must be added to this width. The width of all stairs shall be measured in the clear between hand rails. In no case shall risers exceed seven and one-half (7½) inches in height nor shall the treads exclusive of the nosings be less than ten and one-half (10½) inches wide in straight stairs. No circular or winding stairs for the use of the public shall be permitted. When the seating capacity is for more than one thousand (1,000) people there shall be at least two independent staircases with direct exterior outlets provided for each gallery, in the auditorium where there are not more than two galleries, and the same shall be located on opposite sides of said galleries. Where there are more than two galleries one or more additional staircases shall be provided the outlets of which shall communicate directly with the principal exit or other exterior exits all said staircases shall be of brick proportionate to the seating capacity as elsewhere herein described when the seating capacity is for one thousand (1,000) people or less two direct lines or staircases only, shall be required located at opposite sides of the galleries, and in both cases shall extend from sidewalk level to the upper gallery with outlets from each gallery to each of said staircases, At least two independent staircases with direct exterior outlets shall also be provided for the service of the stage and shall

be located on opposite sides of the same.
All inside stairways leading to the upper galleries of the auditorium shall be inclosed on both sides of fire-proof materials. Stairs leading to the first or lower gallery may be left open on one side in which case they shall be constructed as herein provided for similar stairs leading from the entrance hall to the main floor of the auditorium but in no case shall stairs leading to any gallery be left open on both sides. When straight stairs return directly on themselves, a landing of the full width of both flights without any steps, shall be provided

Section 7.

Landings, Hand-Rails, Heating, Stand Pipes,
Sprinklers and Hose

The outer line of landings, shall be curved to a radius of not less than two (2) feet to avoid square angles. Stairs to an angle shall have a proper landing without winders introduced at each turn. In stairs where the two side flights connect with one main flight no winders shall be introduced and the width of the main flight shall be at least equal to the aggregate width of the side flights. All stairs shall have proper landings introduced at convenient distances. All enclosed staircases, shall have on both sides strong hand-rails firmly secured to the wall about three (3) feet above the stairs but said handrails shall not run on level platforms and landings where the same is more in length than the width of the stairs. All staircases eight (8) feet and over in width shall be provided with a center hand-rail of metal not less than two (2) inches in diameter placed at a height of about three (3) feet above the center of the treads and supported on wrought metal or brass standards of sufficient strength, placed not nearer than four (4) feet nor more than six (6) feet apart and securely bolted to treads or risers or stairs or both, and at the head of each flight of stairs on each landing the post or standard shall be at least six (6) feet in height to which the rail shall be secured. Every steam boiler which may be required for heating or other purpose shall be located where possible outside of the building and the space allotted to the same shall be enclosed with walls of

masonery on all sides and the ceiling of such space shall be constructed of fireproof materials except where the above is impossible a low pressure circulating system may be installed in building. All doorways in said walls shall have fire-proof doors. No floor registers for heating shall be permitted No coil or radiators shall be placed in any aisle or passage-way used as an exit but all said coils and radiators shall be placed in recesses formed in the walls or partitions for that purpose. All supply, return, or exhaust pipes shall be properly encased and protected where passing through floors or near woodwork. Stand pipes four inches in diameter shall be provided with hose attachment on every floor and gallery as follows: One on each side of the auditorium on each tier, also on each side of the stage on each tier and at least one in the property room, and one in the carpenter shop if the same be contingent to the building. All such stand pipes shall be kept clear of obstructions; Stand pipes shall be separated and distinct receiving their supply of water from the power-pumps or pumps and shall be filled with regulation couplings of the Fire Department and shall be constantly filled with water by means of an automatic power pump or pumps of sufficient capacity to supply all lines of hose when operated simultaneously; and said pump or pumps shall be supplied from the street main and be ready for immediate use at all times during a performance in said building. A separate and distinct system of automatic sprinklers with fusible plugs supplied with water from a tank located on the roof or above the stage, and not connected in any manner with the stand pipes shall be placed each side of the proscenium opening and on the ceiling or roof over the stage at such intervals as will protect every square foot of stage surface where said sprinklers are in operation.

Automatic sprinklers shall also be placed wherever practicable in the dressing rooms under the stage and in the carpenter shops, paint shops, store rooms and property rooms A proper and sufficient quantity of one and one half (1½) inch hose, not less than one hundred (100) feet in length filled with the regulation couplings of the Fire Department, and with nozzles attached thereto, and with hose spanners at each outlet shall always be kept attached to each hose attachment.

Section 8

Waters. Axes. Hooks. Lights. etc

There shall also be kept in readiness for immediate use on the stage at least six (6) approved chemicals fire extinguishers of three (3) gallons capacity each; same shall be located in stage fly. galleries and in basement. There shall also be provided at least four (4) axes and two (2) twenty-five (25) foot hooks and two (2) ten (10) foot hooks on each tier or floor of the stage. Every portion of the building devoted to the uses and accommodations of the public also all outlets leading to the streets and including open courts and corridors shall be well and properly lighted every performance and the same shall remain lighted until the audience has left the premises. All gas or electric lights in the halls corridors. lobbies. or any other part of the building used by the audience except the Auditorium must be controlled by a separate shutoff located in the lobby and controlled only in that particular place. Gas main supplying the building shall have independent connection for the auditorium and the stage and the provision shall be made for shutting off the gas from the outside of the building When interior gas lights are not lighted by electricity other suitable approval appliances shall be provided. All suspended or bracket lights surrounded by glass in the auditorium or in any part of the building devoted to the public shall be provided with proper wire netting underneath. No gas or electric lights shall be inserted in the walls woodwork ceiling or in any part of the building unless protected by fireproof materials. All lights in passages and corridors in said building wherever necessary shall be protected by proper wire net work. The foot lights in addition to the wire net-work shall be protected with a strong wire guard and chain placed not less than two (2) feet distant from said footlights and the trough containing said footlights shall be formed of and be surrounded by fire-proof materials; all border lights shall be constructed according to the best known method. And shall be suspended for ten (10) feet with wire ropes. All ducts or shafts used for conducting heated air from the main chandelier or from any other lights or light shall be constructed of metal and made double with an air space between

All stage lights shall have strong wire metal guard or screens. not less than ten (10) inches in diameter so constructed that any material in contact therewith shall be out of reach of the flames of said stage lights and must be soldered to the fixtures in all cases

Section 9.

Fire Apparatus. Diagram or Program

The stand pipes gas pipes, electric wires, hose. foot lights and all apparatus for the extinguishing of fire or guarding against the same as herein specified shall be subject to the inspection by. the Chief of the Fire Department. and the Building Inspector, is hereby. directed to see that the provisions of this ordinance in respect thereto are carried out and. enforced. A diagram or plan of each tier. gallery or. floor. showing distinctly the exits therefrom each occupying a space of not less than fifteen (15) square inches shall be printed in black lines in a legible manner or the program of the performance. Every. exit shall have over. the same on the inside the word. "Exit" painted in legible letters not less than five (5) inches in height

Chapter XXXI.

Plumbing

Section 1.

The. Board of. Health of the city of Fort Wayne. is hereby authorized and empowered. to and shall appoint a Board of Examiners for the examination and registration of Plumbers. Said Board shall consist of two practical plumbers. in the city of Fort Wayne one of whom shall be a recognized plumbing contractor and one a competent journeyman. plumber. not in the employ of said contractor and the regular appointed Building Inspector of said city. Said Board of Examiners shall serve during the incumbency of the Board. of Health who made the appointment or until their successors are appointed and qualified. And said Board of Examination and Registration exclusive of the Building Inspector. whose salary is otherwise provided for. shall receive the sum of twenty-five dollars ($25.00) each per year in full. for all services rendered the city by. them as members of said Board

Section 2.

Examination and License of Plumbers

Said. Board of Examiners shall as soon as may be

after their appointment meet at such time and place as the Board of Health may designate, and at such other times as may be necessary, and proceed to carry out the provisions of this ordinance. Said Board shall examine applicants as to their practical knowledge of plumbing house drainage and plumbing ventilation, and if satisfied as to the competency of any such applicant the City Comptroller shall upon the presentation of any such certificate issue a license to such person to engage in the business of plumbing in the City of Fort Wayne. Said examination shall be in writing and record of questions and answers shall be kept. The decision shall be submitted to the Board of Health in writing and shall be final and conclusive.

A fee for such examination and license shall be five Dollars ($). All fees shall be paid into the office of the City Controller. In case of a firm combinations or corporations engaging in the business of plumbing desiring to take out license, one member of such firm combination or corporation may elect to take out license in the manner indicated and which license shall entitle such firm, combination or corporation to do business in the City of Fort Wayne. Such license shall be for the term of one year and shall be renewed annually for a like fee of $5.00

Section 3.

Bond of Plumbers

Before any plumber shall receive a permit under the conditions of this Ordinance he or his firm or corporation shall execute a surety company or fraternal bond to the City of Fort Wayne, with sureties to be approved by the proper official in the penal sum of one thousand dollars ($1.000) conditioned for the faithful performance of his or their duties according to the terms of this ordinance, and this bond shall be for the term of one year and shall be renewed annually

Section 4

Duties of Inspector

The Building Inspector is empowered to examine and inspect all plumbing hereafter installed within the City of Fort Wayne: and whenever such plumbing shall be found defective, it shall be the duty of the owner, agent or lessee

of such building to place the same in a proper sanitary condition after reasonable notice from the Board of Health.
The Building Inspector shall be notified when work is ready for inspection, and test and must examine and approve or reject all work not less than sixteen hours from the time of such notification. All work shall be left uncovered for examination until the test is made and the work approved by the Inspector.
It shall be the duty of the Building Inspector and he is hereby empowered to enforce this Ordinance. He shall keep a recorded list of all licensed plumbers doing business in the City of Fort Wayne.
When additional fixtures are required or alterations are to be made and not practicable to be constructed in accordance with the provisions of this Ordinance, a special permit may be issued by the Building Inspector. It shall be unlawfull for any person, firm or corporation to erect, construct or alter or perform any labor at plumbing or house drainage within the city of Fort Wayne without first having secured the proper permit provided for in the following section.

Section 5.

Permits

All permits for plumbing or house drainage shall be issued by the City Comptroller after approval by the Building Inspector. The fee for issuing permits shall be according to the estimated cost or value of the improvement or house drainage at the following rates
A nominal fee of Fifty (50) cents shall be charged for a permit where the cost shall exceed twenty dollars ($20) but not exceeding two hundred ($200). and fifty (50) cents for each additional one hundred Dollars ($100) or fractional part thereof. Said fees to be paid to the City Comptroller when the permit is issued
Each permit shall state specifically the name of the applicant the address number of application and the date of issue.
When additional fixtures are required after the permit is issued and do not require an extra inspection no fee shall be charged except when the additional fixture or fixtures brings the contract above the limit for which the permit was issued in which case the extra amount must be paid according to specifications herein provided for; and when such additional fixture or fixtures require an additional inspection an additional fee of fifty (50) cents shall be charged for each subsequent inspection.

Section 6
Repairs

Repairs shall be taken to mean repairing or replacing of an old fixture by a new one to be used for the same purpose: forcing out waste and repairing leaks in waste pipes; but such repairs or alterations shall not be construed to include cases where new vertical or horizontal lines of soil, waste, vent or leader pipes are proposed to be used: Provided that in a building condemned by the Board of Health, because of unsanitary conditions no plumbing shall be considered as coming under the head of repairs but all such plumbing shall be done as in the case of new buildings.

Section 7.
Details of Plumbing

Every dwelling house, hotel, apartment house, tenement or business house, factory, store or other building, in which plumbing arrangements are to be placed, shall be connected with the city sewer where such sewer is accessible, and where such sewer is not accessible with a cesspool in the location to be approved by the Building Inspector. The plumbing and ventilation of every building shall be separated and independent from the roof to the outside of the foundation walls provided that private stables may be connected with the house drain. That portion of the house drain which is inside the walls and underneath the building and three (3) feet outside the area or foundation walls shall be constructed with what is known to commerce as cast iron soil pipe, and standard fittings

Fittings and pipe shall be coated outside and inside with coal tar varnish or other coating equally as good; they shall be securely ironed to the walls, laid in trenches of uniform grade or suspended to the floor timbers by strong iron hangers in all cases a brass clean-out connection shall be clean-outs at all angles near the exit of drain from building placed in an accessible location.

The end of all drains or branch drains shall be provided with a brass clean-out connection of a size not less than two (2) inches, and placed in an accessible location. Drain and soil pipes shall have a uniform fall of not less than one-quarter (1/4) of an inch per foot towards the sewer or cesspool; when such grade cannot be obtained, a special permit may be obtained from the Building Inspector for a less fall per foot,

A running trap, provided with a fresh air inlet and an accessible brass cleanout connection shall be inserted into the house drain, inside or outside of the foundation wall, and as near the said wall as practicable. The fresh air inlet shall be not less than four (4) inches internal diameter connected to the drain on the house side of the trap and not more than eight (8) feet or less than four (4) feet from the running trap, and extending to the external air. All drains shall be run as direct as practicable. Changes in direction shall be made with regular fittings; and connection shall be made with Y's sanitary tees and one-eighth (1/8) bends

Soil pipes receiving the discharge from one or more water closets shall be of standard cast iron soil pipe, the same as specified for drains, and not less than four (4) inches in internal diameter, and continuing of undiminished size to the highest roof of the building, above and away from any opening or window and left open at the top and shall extend at least twelve (12) inches above the roof. flashing of sheet lead, not less than four (4) pounds to the square foot, or of copper, shall be provided and properly attached where the pipe passes through the roof.

Section 8.

Waste Pipes- Size of.

No waste pipe shall be less than one and one-quarter (1¼) inches for one fixture and not to exceed two fixtures; and not less than one and one-half (1½) inches for three fixtures and not to exceed four fixtures

Lead waste and vent pipes shall not be of less weight than the grade known as "light".

In no case shall the waste pipe from another fixture connect to the house side or in the seal of a water closet trap such connections shall be made independently (and) of such trap

No refrigerator or other receptable in which provisions are stored shall be connected with a drain, soil or vent pipe or discharge upon the ground beneath the building, but in every case there shall be an open drip tray beneath the refrigerator. The waste must discharge into a sink or other fixture and be provided with a flap valve or discharge end. No steam exhaust or blow-off pipes shall be connected with a sewer, or with any building but must discharge into an open tank or condenser from which a perfect connection to the sewer or house drain may be

provided. All joints in cast iron pipe shall be packed with picked oakum and run with molten lead well calked Connections of lead pipe with those of iron shall be made with brass or combination ferrules or brass soldering nipples of a size not less than the lead pipe with properly soldered joints and calked or screwed to the iron pipe.

All private water service pipes in the ground which are supplied by water from a public water system shall be placed in accordance with the rules and regulations of the City Water Works

Section 9.

Traps

Every sink, bath tub basin, water closet, washing or set of wash trays and every fixture having a waste pipe shall be separately and independently trapped with an approved anti-siphon water sealing trap placed as near the fixtures as practicable. Traps must be placed above floors or in accessible locations No trap shall be placed at the foot of a vertical soil or waste pipe. Rain water leaders within the building shall be of wrought iron or standard cast iron pipes when connected with drain waste or soil pipes and shall be suitable trapped

Section 10

Vent Pipes

And when it shall be deemed necessary to provide a system of back venting with spicial air or vent pipes they shall be of a size not less than the waste pipe up to and including two (2) inches and not exceeding four (4) inches not less than two (2) inch vents shall be used

Each vent shall be provided with a brass union when it connects to the trap. Such connections shall be made on the crown of the trap when practical and shall extend at least two (2) feet above the fixture it serves before connecting with the other vent or soil pipe.

Section 11

Vent Pipe - Size of.

When two (2) fixtures connect into one vent such connection shall be made with not less than one and one-half (1½) inch pipe and for three (3) fixtures not less than two (2) inch pipe. And for water closets not less than two (2) inch pipe for forty (40) feet or less and two and one-half (2½) inch pipe to be used for an additional twenty

(20) feet. Provided that vent pipes for three (3) or more fixtures with waste three (3) or four inches in diameter shall not be less than three (3) inch for twenty (20) feet or less: over twenty (20) feet. four (4) inch

Section 12.

Must be run Straight

Vent pipes shall be run straight and as direct as practicable and with a grade to avoid trap fouling of condensation, but in all cases where vent pipes connect to soil pipes such connection shall not be less than two feet above the highest fixture. Vent pipes may be run out separately through the roof and shall be encased the same as soil pipe going through the roof. or when run up, in or out of a sealed flue. the casing may be omitted. No pipe going through the roof to be less than two (2) inches in diameter.

Section 13.

Chimney Flues not to be used for Ventilation

Sewer, soil pipe, waste pipe or ventilation pipe shall not be constructed of brick, earthenware or short mortar, and chimney flues shall not be used for such ventilators

Section 14.

Other Pipes

Safe pipes, drips or overflow pipes from tanks or cisterns shall be run to some place in open sight and provided with a flap valve or louver end, and in no case shall any pipe connect with drains, soil, waste, vent pipe or rain water leader.

Water closets shall be supplied with water from a tank or cistern and the flush pipe shall not be less than one and one-quarter (1¼) inches in diameter. No person shall place in any building a pan water closet; and when such kind of closet is removed for repairs or other causes it shall not be replaced. The use of wooden wash trays or sinks in residences, hotels or restaurants is strictly prohibited. They shall be of non-absorbent material. Provided that wooden sinks may be lined with sheet lead or sheet copper.

A grease trap shall be constructed under the sink of every hotel restaurant, eating house or boarding house or other public cooking establishment

The use of mercury, vents or so-called "anti-siphon" traps

shall not be allowed

Nothing herein contained shall prevent the use of wrought iron soil or waste pipe with the proper fittings Coated outside and inside as provided for cast iron pipe.

Section 15

Test

The whole system of drainage. waste. soil and ventilation pipes shall be made tight and tested with an air or water pressure of not less than ten (10) pounds per square inch and to stand not less than fifteen (15) minutes without a drop. This test to be made by the plumber in the presence of the Inspector and in all cases where only a part of the system has been tested at one time. the Inspector shall require an additional test of the whole system, and it shall be absolutely tight. When the work shall be found to be tight and in accordance with this Ordinance. the Inspector shall so certify on the back of the permit previously issued for such plumbing work and no plumbing shall be used. until such certificate is made by the Building Inspector.

Chapter XXXII

Electrical Work

Section 1

No electrical wiring insulation electrical apparatus or appliances furnishing light heat or power shall be introduced or placed in any building in the city of Fort Wayne except in compliance with the regulations of the National Board of Fire Underwriters and its authorized branches known as the National Electrical Code.

Said rules and regulations are hereby made a part of the requirements of this Ordinance.

The Inspection of all electrical work shall be subject to the approval of the Electrical and Building Inspector

Chapter XXXIII

Penalties

Section 1

Revocation of Permits

Every permit shall be considered canceled if action work is not commenced within the period of six (6) months from the date of the issue of same

If work upon any building shall be conducted in vio-

tation of any of the provisions of the various Chapters on buildings, either as to occupancy of sidewalk or street or the use or application of material or workmanship, it shall be the duty of the Building Inspector to revoke the permit for the building operations in connection with which such violations shall have taken place. And it shall be unlawful after the revocation of such permit to proceed with such building operations unless such permit shall first have been re-instated or re-issued by the Building Inspector. Before a permit revoked for the cause or causes before mentioned can lawfully be reissued or re-instated the entire building and building site must be first put in position corresponding with the terms of the various Chapters on Buildings and any work or material applied to the same in violation of the terms of the various Chapters on Buildings shall be first removed from said building

Revocation of a permit shall be in writing, and shall be served on the owner or his agent or on the tenants or any one doing any of the work

Section 2

Penalty for Violation

The owner, or owners of any building, structure, wall, platform, staging or flooring, or part thereof, where anything in violation of the various Chapters on Buildings shall be placed, or shall exist or any architect, builder, plumber, carpenter, or mason, who may be employed or assist in the commission of any such violation, and all persons who shall violate any of the provisions of the various Chapter on Buildings, or fail to comply therewith or any requirement thereof or who shall build in violation of any detailed statement of specifications or plans submitted and approved thereunder, or any certificate or permit issued thereunder shall for each and every violation or non-compliance, be guilty of a misdemeanor and upon conviction thereof shall be fined not less than five Dollars ($5) nor more than three hundred Dollars ($300) or imprisoned not more than thirty (30) days, or both

Section 3.

Right to Trespass

The Building Inspector and his deputies, assistants or employees assigned by him or persons assigned to co-operate with him by other departments of the City so far as

may be necessary for the performance of their duties shall have the right to enter upon any building site or premises or any new or unoccupied building or any building under construction repair alteration. removal. or any building alleged to be unsafe. or a menace to life or limb or damaged or menaced by fire. upon showing their badge of office: and any person or persons interfering with them in the performance of such duties shall be liable to a fine of not less than five Dollars ($5) nor more than three hundred dollars ($300) or by imprisonment not more than thirty (30) days or both;

Chapter XXXIV

Building Code. Defined

Section 1.

Chapter 1 of this Chapter. inclusive shall be denominated and known as the Building Code. for the City of Fort Wayne. Indiana

Section 2.

All laws and parts of laws. in conflict with any of the provisions of this Ordinance are hereby repealed

Section 3

This Ordinance to be in full force and effect on and after its passage. and. approval. by. the Mayor and legal Publication

J M. Heiny

Done at in the Council Chamber of the City of Fort Wayne. Indiana on the 25th day of May 1909.

We hereby. certify that the Common Council of the City of Fort Wayne. Indiana. at a regular meeting held on the 25th day of May 1909 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No. 390.

W C. Schwier.
President

J Frank Mungovan
City Clerk

Presented to the Mayor for approval on the 4th day of June 1909

J Frank Mungovan
City Clerk

Approved this 14th day of June 1909

Wm J Hosey
Mayor

General Ordinance No 442

Introduced by Chas E. Welch

An ordinance providing for the regulation and duties of second hand dealers and owners of junk shops or anyone who buys and sells second hand merchandise. providing a bond and a penalty for the violation thereof. and repealing all ordinances in conflict therewith:

Section 1: Be it ordained by the common council of the City of Fort Wayne Indiana. that is shall be unlawful for any. person firm or corporation to conduct. Maintain or engage in the business of a second-hand dealer or junk shop or any other place where they buy and sell second-hand Merchandise in said city. unless such person firm or corporation shall have first paid the license fee to the City Comptroller of such city and procured a license therefor. as hereinafter prescribed in this ordinance.

Section 2: Every person, firm or corporation desiring to conduct. Maintain or engage in the business of a second-hand dealer. or junk shop or any other place where they buy and sell second-hand merchandise shall make application in writing to the City Comptroller of said City of Fort Wayne for a license so to do Specifying the Street and house number of the building in which said person firm or corporation intends to carry on said business. Said applicant shall also file with City Comptroller his bond for ($500.) Five hundred dollars payable to the city of Fort. Wayne Indiana and signed by at least (3) three resident free holders of said city. conditioned that said applicant will conform with the requirements of this ordinance. Said bond subject to the approval of the Mayor.

Section 3: after such application shall have been granted and before a license shall be issued thereon. Such person. firm or corporation shall pay to the city Comptroller an annual license fee of five ($5.00) dollars and upon presentation of the Citys Comptrollers receipt therefor. the said city Comptroller shall issue to said person firm or corporation the license applied for. Said license shall bear date of January first of the year in which the same be issued and no reduction shall be made for any part of the year elapsed at the time of making such application for such license

Section 4: No person. firm or corporation. shall by virtue of one license. conduct. Maintain or engage in the business of keeping or operating more than one second-hand store or junk shop or any other place where the buy. and sell second-hand Merchandise provided however that any person. firm or corporation may procure from the city comptroller any number of the licenses herein provided for upon payment of the stipulated fee and compliance with the other requirments of this ordinance. and provided also that such person. firm or corporation may remove from one place of business to another in said city by giving an immediate written notice to the City Comptroller of said city. Specifying the street and house number of the building to which said removal is made.

Section 5: Every person. firm or coporation licensed to conduct. Maintain or engage in the business of a second-hand store or junk shop or any other place where they buy and sell second-hand merchandise shall keep a book in which shall be legibly written in ink. at the time of the purchase. taking or receiving any goods. articles or things. and preserve an accurate account and discription in the English language. of the goods. articles. or things received or taken: the amount of money paid therefor. the time of purchasing. taking or receiving same. the name, residence color. Style of dress of the person or persons selling or delivering said goods articles or things to said licensed place.

Section 6: Every person, firm or corporation licensed as aforesaid. shall make out and deliver to the chief of Police of said City. every day before the hour of twelve. noon. a legible and correct copy from the book required in the above section giving an accurate account and discription of the goods. articles or things taken or received during the preceding day; the precise time of purchasing. taking or receiving of same. the name. residence. color. style of dress of person or persons from whom such goods. articles or things were purchased. taken or received; said copy to be made on blank white paper ten by twenty inches in size on one side thereof only.

Section 7: The book provided for in the above section of this ordinance shall be at all times during business hours open to the inspection of the chief of Police of said City

or any member of the Police force authorized by the chief of Police to examine the same

Section 8: It shall be unlawful for any person firm or coporation licensed as aforesaid, to purchase take or receive any article. goods or things from any person while such person is in an intoxicated condition

Section 9: It shall be unlawful for any person firm or coporation licensed as aforesaid to take purchase or receive goods articles or things from any person who is under the age of twenty one (21) years. unless the paunt or guardian of such person shall be present and authorize said minor to sell and deliver such goods. articles or things to such person firm or coporation

Section 10: All goods or articles purchased or received by any proprietor. Manager or employe of said licensed second-hand store or junk shop and place where they buy and sell second-hand Merchandise shall be retained at said licensed second-hand store or junk shop or any place where they buy and sell second-hand merchandise. by said proprietor. Manager or employe for a period of not less than forty-eight (48) hours before disposing of the same

Section 11: Any person, firm or corporation violating any of the sections of this ordinance. shall. upon conviction. be fined in any sum of not less than one ($1.00) dollar and not moore than one hundred ($100.00) dollars for each offense

Sec 12: This ordinance to repeal any and all ordinances in conflict herewith

Section 13: This ordinance shall be in full force and effect from and after its passage and approval by the Mayor

Charles E. Welch

Done at the council chamber in the City of Fort Wayne Indiana This the 26th day of July 1910

We hereby certify that the common council of the City of Fort Wayne Ind at a Regular meeting held on the 26th day of July 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 442

Gust. F. Rogge
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 30th day of July. 1910

Wm. J. Jeffries City Clerk

Approved this 4th day of august 1910

Jesse Grice Mayor

General Ordinance no 443

Introduced by Lucas E. Welch

An ordinance to regulate and License Pawn Brokers and providing a Bond and fixing a penalty for the Violation of Same

Section 1: Be it ordained by the Common Council of the City of Fort Wayne Indiana. that no person or persons shall carry on or conduct the business or calling of a Pawn Broker within the city of Fort Wayne Indiana. without having first obtained a license so to do from the City Controller

Section 2: Any person who loans money on deposit or pledge of personal property. or other Valuable thing. or who deals in the purchasing of personal property or other Valuble thing. on the condition of selling the same back at a Stipulated time or price or any person who loans money and takes a note for same. taking as security for said note any Watches. Diamonds. Jewelry or like Valuables or anyone who becomes Surety on a note for a third party taking for his protection any Watches. Diamonds. Jewelry. or other Valuable. except Stocks. Bonds Mortgages. Notes or other negotable instruments. is hereby defined and declared a Pawn Broker.

Section 3: The City Controller is hereby authorized to issue a Pawn Broker's license to any person of good Character. who may apply therefor under the following conditions:

The person making such application shall first pay into the City Controller the sum of one hundred ($100.) Dollars for each and every license issued by the year in addition to which he shall charge a fee of two ($2.00) for every license thus issued. For every Quarterly license issued covering a period of three successive months he shall charge the sum of Fifty ($50.00) dollars. to which shall be added a fee of two ($2.00) dollars for every license thus issued. Every applicant shall execute a bond to the City of Fort Wayne Indiana. in the sum of five hundred ($500.) dollars. conditioned that the said applicant will conform in every particular to the requirements of this ordinance and to the requirements or provisions of any other ordinance concerning Pawn Brokers that may hereafter be passed by the Common Council. which Bond shall be approved by the Mayor. and thereupon the City Controller shall issue a license in due form under the corporate seal of the City

Section 4: The City Controller shall keep a correct register of all license granted under this ordinance. which register shall record the name of the person licensed. the time of issuing such license. and the place of business of the person thus licensed
Section 5: Every person so licensed as aforesaid shall keep at his place of business a substantial and well bound book. in which he shall enter in writing a minute description of all personal property. bonds. or notes. or other securities received on deposit as aforesaid the time when they are received. Mentioning in particular any. prominent or descriptive Marks that may be on such personal property. bonds. notes or other securities for which such Pawn ticket or check was given together with the name and residence and a general description of the person or persons by whom they are left. which said book shall be clean and legible. and no entry therein or any part thereof. shall be erased. obliterated or defaced. and all such entries shall be numbered consecutively and all tickets issued shall bear a duplicate number of same. All entries shall be made in ink. Such person so licensed shall make out and deliver to the Chief of Police on each day before 10 O'clock A.M. a legible and correct statement giving a minute description of all personal property received on deposit during the proceding day. together with the correct time when received.
Section 6: Every person or persons so licensed as aforesaid. shall at any time during the hours of business. when requested so to do by the Mayor. Superintendent of Police or any authorized Police officer of said City. submit and exhibit such book and Pawn ticket Stubs as provided for in section five (5) to the inspection of said Mayor or Officer of the Police Department. and he shall also exhibit any goods. personal property. bonds. Notes or other securities that may be left with such licensed person. or which may be in his possession or on his said premises, to the inspection of said Mayor or Officer of the police department.
Section 7: No person licensed as aforesaid shall take or receive in pawn or pledge for money loaned. any property article. or thing from any Minor or the ownership of which is in or which is claimed by any Minor or which may be in the possession or under control of any Minor
Section 8: Any person who shall violate of fail to comply with any of the provisions of this ordinance shall be fined in any sum not less than Twenty five ($25.) dollars Nor more

than one hundred ($100.) dollars for each and every Violation thereof. and the Mayor may revoke such license granted under this ordinance to any person for any violation of failure to comply with the provisions of this ordinance

Section 9: This ordinance shall be in full force and effect from and after its passage and approval by the Mayor

Charles E. Welch

Done at the Council Chamber in the City of Fort Wayne Indiana this the 26th day of July 1910

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 26th day of July 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 443

Gust. F. Rogge
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 30th day July 1910

Wm. J. Jefferis
City Clerk

approved this 4th day of august 1910

Josse Grice
Mayor

General Ordinance No 444

an ordinance fixing the tax levy for city purposes for the year 1910

Section 1: Be it ordained by the common council of the City of Fort Wayne Indiana that a levy of one dollar and eight cents ($1.08 ct) upon each one hundred dollars ($100.00) of assessed valuation of all property within the corporate limits of the City of Fort Wayne Indiana be made for the year 1910. That the above levy be as follows:

General purposes	$ .84
Sinking Fund	.05
Anthony Wayne Monument fund	.00¼
Firemans Pension Fund	.01
Police Pension Fund	.01
Municipal Electric light fund	.07½
Track Elevation Fund	.05
River Bank Improvement	.04¼
Total	$1.08

Also that there shall be collected from each male inhabitant liable according to law. a poll tax of two dollars ($2.00)

Section 2: That all taxes shall be collected in Semi-annual installments

Section 3: This ordinance shall be in full force and effect from and after its passage and approval by the Mayor.

Harry G Pinniger

Done at the council chamber in the City of Fort Wayne Ind this 27th day of Sept 1910

We hereby certify that the common council of the City of Fort Wayne Ind at a Regular meeting held on the 27th day of Sept 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 444

Gust. F. Rogge
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 30th day of Sept 1910

Wm. J. Jeffries
City Clerk

Approved this 30th day of September 1910

Jesse Grice
Mayor

General Ordinance No 445

An ordinance relating to dead animals

Section 1: Be it ordained by the common council of the City of Fort Wayne. That it shall be unlawful for any Scavenger or other person to haul or convey through upon or across or over any Street or alley of the city any dead horse. cow dog or other animal unless the same be carried in a wagon with wooden or iron top. sides. ends. and bottom so as to completely hide the same from view.
Section 2: Any person violating this ordinance or any provision thereof shall upon conviction. forfeit and pay a fine to said City of Fort Wayne of not more than one hundred dollars (100^{00}).
Section 3: That the ordinance adopted October 11-1887 and designated in the revised ordinance of 1901 as Section 770 and 770.A. is hereby in all things repealed
Section 4: This ordinance to be in full force and effect on and after its passage. approval by the Mayor and legal publication

P. M. Braun.

Read at the council chamber in the City of Fort Wayne Indiana this 27th day of Sept 1910

We hereby Certify that the common council of the City of Fort Wayne Ind at a Regular meeting held on the 27th day of Sept 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 445

Gust. F. Rogge
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 30th day of Sept 1910

Wm. J. Jeffries
City Clerk

Approved this 30th day of Sept 1910

Jesse Grice
Mayor.

General Ordinance No 446

An ordinance fixing the Salary of the City Marketmaster

Section 1: Be it ordained by the common council of the city of Fort Wayne Ind that the city Marketmaster of said city shall receive from and after the 1st day of august 1910 a Salary of Four hundred eighty ($480.00) dollars per annum

Section 2: That this ordinance shall be in full force and effect on and after its passage approval of the mayor and legal publication

Charles W. Zeitler

Done at the council chamber in the city of Fort Wayne Ind this 27th day of Sept 1910

We hereby Certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 27th day of Sept 1910 by a Majority vote of all members elect did pass the ordinance hereunto attached and known as

General Ordinance No 446

Gust. F. Rogge
President

Wm. J. Jefferis
City Clerk

Presented to the mayor for approval on the 30th day of Sept 1910

Wm. J. Jefferis
City Clerk

Approved this 30th day of September 1910

Jesse Grice
Mayor

General Ordinance No 447

An ordinance authorizing the alienation of certain personal property and ordering an appraisement of the same

Section 1: Be it ordained by the common council of the City of Fort Wayne Ind that the Mayor be and he is hereby authorized to sell one Brown Horse. named "Fred" 16 years old used on no 2 Engine. Engine House no 2. and one bay horse named "Frank" 16 years old used on no 2 Hose wagon Engine house no 2 and one coal wagon at no 3 Engine House and to sign any and all instruments to consumate such sale provided that such sale shall not be made until said property has been appraised by appraisers appointed by the Judge of the allen circuit court.

Section 2: That the city attorney be and he is hereby authorized to petition the Judge of the allen circuit court for the appointment of three appraisers to appraise the property referred to in section 1 of this ordinance.

Section 3: That this ordinance shall be in full force and effect from and after its passage and approval by the Mayor.

Charles W. Slittoe

Done at the council chamber in the city of Fort Wayne Ind this the 27th day of sept 1910

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 27th day of sept 1910 by a Majority vote of all members elect did pass the ordinance hereunto attached and known as General Ordinance No 447

Geust F. Rogge
President

Wm S. Jeffries
City Clerk

Presented to the Mayor for approval on the 30th day of Sept 1910

Wm S. Jeffries
City Clerk

Approved this 30th day of Sept 1910

Jesse Grice
Mayor.

General Ordinance No 448

An Ordinance requiring persons driving or operating automobiles or motorcycles upon the Streets alleys and public highways of the Leity of Fort Wayne to obtain a license: providing penalties for the violation thereof and fiping a time when the same shall take effect.

Section 1: Be it ordained by the Common Council of the Leity of Fort Wayne Indiana That is shall be unlawful for any person to drive or operate upon or along any street alley or public place in the Leity of Fort Wayne any Automobile Motorcycle or similar Vehicle unless the person in charge or control thereof shall have first procured a license so to do from the City Controller of said Leity for which the sum of one dollar ($1.00) shall be paid. The Leity Controller is hereby authorized to issue such license only upon the presentation of a permit properly signed by the Board of Public Safety

Section 2: For the purpose of this ordinance the term or names "Automobiles" "Motorcycles" and other Similar Vehicles" wherever and whenever used in this ordinance shall be held to embrace and mean and are hereby dfined to mean any Vehicle or propelled upon or along the Streets alleys or other public ways of the city of Fort Wayne. The motive power of which is electricity. Compressed air, Naptha. gasoline. Kerosene. or Steam: Provided. however that nothing herein shall apply to the operation of any locomotive. Trolley car or other Vehicle used by any Steam or Street railway upon or along any track or tracks owned or lawfully used by any Steam or street railway Company.

Repealed Feb 14-1911,

Section 3: The Board of Safety is authorized to adopt rules setting out the requisites necessary to qualify a person to secure a license as an operator. Any person desiring a license as an operator of such Vehicle shall file a written application therefor with the Board of Public Safety Stating his name and address and shall present the number of his State License together with Satisfactory evidence of his ability and capacity as such operator. If the Board be Satisfied that he is a proper and safe person to act as such operator a permit for such License shall be issued: Provided that no such permit shall be issued to any person under the age of Sixteen (16) years.

any such operator shall within five (5) days notify the Board of Public Safety of any change of address of such operator shall whenever requested by the Police authorities disclose and furnish his name and address and the number of his license

Sec 4: Any person violating any of the provisions of this ordinance shall upon conviction thereof be fined not less than five dollars ($5.00) nor more than One hundred dollars to which may be added imprisonment not to exceed 90 days in the allen county jail: and the court finding any person guilty of violating any Statue of the State or ordinance of this City relating to Automobiles or Motor Vehicles as herein defined. May revoke said persons license:

Provided that when any person shall be found guilty for a third time of violating any Statue of this state or ordinance of this city relating to automobiles or motor vehicles. as herein described. said third conviction shall operate to revoke the license taken out by such person under provisions hereof and if such person shall thereafter be found guilty of Violating any of the provisions of this ordinance he shall be fined not less than Twenty five dollars ($25.) nor more than Two Hundred dollars ($200.) and shall also be imprisoned in the allen County jail not more than 90 days.

Section 5: That this ordinance shall Take effect and be in full force from and after its passage and approval by the Mayor and legal publication

Charles E Welch
Henry W. Folger
Gottlieb Haller.

Done at the Council Chamber in the City of Fort Wayne Indiana this 11th day of Oct 1910

Wm. S. Jeffries
City Clerk

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 11th day of Oct 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as

General Ordinance no 448

Gust. F Rogge President

Wm. S. Jeffries City Clerk

Presented to the mayor for approval on the 15th day of Oct 1910

Wm. J. Jeffries
City Clerk

Approved this 18th day of Oct 1910

Jesse Grice
Mayor.

General Ordinance No 449

An ordinance ratifying and approving a contract entered into the 31st day of August 1910 by and between the City of Fort Wayne and the American Telephone and Telegraph Company of Indiana

Whereas. heretofore on the 31st day of aug 1910 The City of Fort Wayne by and through its Board of Public works entered into a contract with the American Telephone and Telegraph Company of Fort Wayne Indiana giving said Company the right to construct. Maintain and operate its lines of Telephone and Telegraph including necessary poles wires and fixtures upon and over Clinton Street in the said City which contract is in the following words:

This agreement. made and entered into this 31st day of August 1910 by and between the City of Fort Wayne Indiana by and through its Board of Public works party of the first part. and the American Telephone and Telegraph Company of Indiana a Corporation organized under and by virtue of the laws of the state of Indiana party of the second part.
Witnesseth. That the City of Fort Wayne Indiana by and through its Board of Public works does hereby authorize and empower the said party of the second part. its successors and assigns and by the terms of this contract. consent. permission and authority are granted unto and vested in the said party of the second part. subject to any laws and ordinances now in force or hereafter enacted or put in force as Police Regulations. the right to construct. Maintain and operate its lines of telephone and telegraph. including the necessary poles and wires and fixtures. upon and over North Clinton Street between Seventh street and the northern boundery of the City of Fort Wayne as more fully shown by a blue print dated as of even date herewith and on file in the office of the Board of Public works and Styled "Map showing location of Fort Wayne loop" and to string Maintain and operate its wires of telephone and telegraph on Clinton Street south from Seventh Street to the exchange of the Central union telephone Company on existing poles and underground of said Central Union Telephone Company. upon the following terms and conditions Viz:

First: All poles erected under this contract shall be located and erected under the supervision of the Board of Public works and shall not be placed so as to interfere with the Public travel or free use of such street or of Public or private property. Such poles shall be Symmetrical in shape and neatly dressed and painted. Said Company shall restore and repair to the Satisfaction of the Board of Public works of said City any damage or injury caused to said street by the location or Maintenance of said poles. and on its failure so to do. upon ten (10) days notice in writing by the Board of Public works the City may repair or restore the same and said company shall be liable to it for the cost thereof. If at any time public necessity requires the change of location of any of said poles it shall be the duty of said Company. upon ten (10) days notice in writing by the Board of Public works. to change the location thereof and on its failure so to do the City shall have the right to change the same and the Company shall be liable for the cost thereof. Not more than eighty (80) wires shall be carried on said poles. and all wires in excess of that number shall be placed in cable. nor shall any wires or cables be less than twenty five (25) feet from ground. it being further provided. however. that said party of the second part shall begin the construction of its lines within six (6) months from the date of the ratification hereof by the Common Council of said City of Fort Wayne.

Second: Nothing herein contained shall be construed as a grant to the said Company of the exclusive right to occupy such street or to prevent the grant of like or other privileges to other persons or companies for like or other purposes. and the grant herein made shall continue for a period of Ten years. from date of this contract and for no longer

Third: In consideration of the rights and privileges herein granted. Said Company its successors and assigns. shall furnish free of cost to said City the two (2) top gains or Spaces for cross arms upon all such poles erected. for its electric light wires. fire alarm and Police wires: provided that in the event any electric light wires are placed on said poles the voltage shall not exceed Five thousand (5000) Volts and all such electric light wires shall be placed on cross arm in the top gain or Space of said poles. It being understood that sufficient space is to be left on the top

of said poles for the aforesaid two (2) top gains or Spaces for the cross arms to be used by the Leity for its wires. so that the wires of said Leity will not in any. way interfere with the wires of said second party on the cross arms below.

Fourth: Said Company shall protect. indemnify and save harmless said Leity against all damages and liability that it shall incur on account of any injury to persons or property caused by the neglect of said Company in the performance of any of the duties required of it by this contract: Also against any damages or liability said Leity shall incur by the reason of the failure of said Company. to perform any of the conditions or agreements herein contained.

Fifth: Nothing in this agreement shall be so construed as to grant to said party of the second part the right to established and Maintain a local telephone exchange service in said Leity: Such local telephone exchange service being defined to be telephone service furnished to customers or Subscribers between points located within the city of Fort Wayne Indiana

Sixth: In event that any of the terms and conditions of this contract are violated then the party of the first part may declare all priviledges and rights granted herein as forfeited after first giving to said second party ten (10) days in which to comply with any of the terms or conditions violated. That on the failure of the second party to so comply after receiving notice said first party may proceed to remove said poles and wires and charge the cost thereof to said second party provided however that the failure of the party of the first part to insist upon a forfeiture for any violation of this contract shall not in any sense be considered as a waiver of its right to insist upon a forfeiture for any subsequent failure

In witness whereof: The undersigned members of the Board of Public works of the Leity of Fort Wayne Ind on behalf of said Leity have hereunto set their hands and seals and the American Telephone and Telegraph Company of Indiana has caused this instrument to be signed under its corporate name by C. R Bangs as president and to be attested by its Secretary under its corporate seal: all done on the day and year first above Written

Frank. J. Benoy.
Henry Hilgemann
E. J. Lennon
Board of Public works

American Telephone and Telegraph Company of Indiana
C. R. Bangs
President

(seal) Alfred. E. Holcomb
Secretary

Whereas said contract and agreement has been submitted by said Board of Public Works of the City of Fort Wayne Ind to the Common Council of said City for its consideration and action thereon therefore.

Section 1: Be it ordained by the Common Council of the City of Fort Wayne that the contract heretofore entered into by and between the City of Fort Wayne by and through its Board of Public works and the American Telephone and Telegraph Company of Indiana as fully set forth in the preamble hereto be and the same is hereby in all things confirmed and approved.

Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Harry G. Pinniger

Done at the Council Chamber in the city of Fort Wayne Indiana this 11th day of Oct 1910

Wm. S. Jefferis
City Clerk

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 11th day of Oct 1910 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 449

Gust. F Rogge
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval on the 15th day of Oct 1910

Wm. S. Jefferis
City Clerk

Approved this 18th day of Oct 1910

Jesse Grice
Mayor

General Ordinance No 450

An ordinance approving the contract entered into between the City of Fort Wayne by and through its Board of Public works and the Wayne Auto Axle Company.

Whereas on the 22d day of September 1910 the Board of Public works of the City of Fort Wayne entered into the following agreement and contract with the Wayne Auto Axle Company.

This agreement Made and entered into this 22d day of September 1910 by and between the City of Fort Wayne. by and through its Board of Public Works party of the First part and the Wayne Auto Axle Company. party of the second part. Witnesseth.

That the party of the first part does hereby grant the party of the second part its successors and assigns subject to law and ordinance now in force authority and permission to allow a single track diagonally over and across the intersection of McCulloch Street with the alley immediately South of Hayden Street connecting the track of the Wabash Railroad Company with the ground owned by the Wayne Auto Axle Company. The permission and authority hereby given are upon the following terms and Conditions: That the track herein authorized to be laid shall be so placed that it will not interfere with the public use of said Street. That if the said Street is hereafter graded or paved or otherwise improved. that the said party of the second part shall make the grade of its said track conform with the grade established by the Board of Public works.

That if said Street is hereafter paved that said second party shall pay for so much of the pavement as lies between the tracks and the space of two (2) feet on either side thereof. That the grade of said tracks shall be at all times so maintained so as not to interfere with public travel. That said tracks shall be used for no other purpose than for that of switching cars into the grounds of the said Wayne Auto Axle Company its successors and assigns. and in doing so. no cars shall remain standing in any part of said intersection.

That the permission herein granted to the said party of the second part shall continue for the period of Twenty five years from the approval of said contract by the

Common Council
Witness our hand and seals this 22d day of September 1910
City of Fort Wayne By.
Frank J. Benoy. (seal)
Henry Helgeman (seal)
E. J. Lennon (seal)
its Board of Public works
Wayne auto Aplc Company. By.
Henry C. Pequignot
its Secretary

attest N. W. Becker
Clerk

Done at the Council Chamber in the City of Fort Wayne Indiana this 11th day of Oct 1910
Wm J. Jefferies
City Clerk

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 11th day of Oct 1910 by a Majority vote of all the Members elect did pass the Ordinance hereunto attached and known as
General Ordinance 450
Gust. F. Rogge
President
Wm J. Jefferies
City Clerk

Presented to the Mayor for approval on the 15th day of Oct 1910
Wm J. Jefferies
City Clerk

Approved this 18th day of Oct 1910
Jesse Grice
Mayor

General Ordinance No 451

An Ordinance Authorizing the employment of Certain Officers and employees of the Police Department of the City of Fort Wayne and Fixing their compensation

Section 1: Be it ordained by the Common Council of the City of Fort Wayne that the Officers and employees of the Police Department of the City of Fort Wayne shall respectfully receive the compensation and Salaries as hereinafter in this Ordinance provided. The employment of such officers and employes as hereinafter named are hereby authorized and the compensation and Salaries of such officers and employes are hereby fixed at the sums and amounts respectfully named for such officers and employes.

The Chief of Police shall receive a Salary at the rate of Fifteen hundred dollars ($1500.00) per annum

The Captain of Police shall receive a Salary at the rate of Twelve hundred sixty dollars ($1260.00) per annum

This section Repealed Dec 13-1915

The Lieutenant of Police shall receive a Salary at the rate of Ten hundred and twenty dollars ($1020.00) per annum

Two Sergeants of Police Shall each receive a Salary at the rate of Ten hundred twenty dollars ($1020.00) per annum

Two Detective Sergeants of Police shall each receive a Salary at the rate of Ten hundred twenty dollars ($1020.00) per annum.

Each patrolman. court Bailiff of the city court. Police Station Master. Patrol Driver and Police Station Clerk. during the first year of his service in the City of Fort Wayne under the Board of Public Safety in any of the capacities above mentioned. Shall receive a Salary at the rate of seven hundred and eighty dollars ($780.00) per annum

Each patrolman. court Bailiff of the city court. Police Station Master. Patrol Driver and Police Station Clerk. during the second year of his service in the City of Fort Wayne under the Board of Public Safety in any of the capacities above mentioned. Shall receive a Salary at the rate of eight hundred forty dollars ($840.00) per annum

Each patrolman. court Bailiff of the city court. Police Station Master. Patrol Driver. and Police Station Clerk during the Third and Subsequent consecutive years of his service in the City of Fort Wayne under the Board of Public Safety in any of the capacities above mentioned. Shall receive a Salary at the rate of nine hundred dollars $900.00 per annum

The electrician shall receive a salary at the rate of Five hundred forty dollars ($540.00) per annum

The Humane officer shall receive a salary at the rate of Six hundred Sixty dollars ($660.00) per annum.

Section 2: That all ordinances or parts of ordinances in conflict herewith be and they are hereby repealed.

Section 3: That this ordinance be in full force and take effect on and after the 1st day of January 1911

John J. Bauer.

Done at the Council Chamber in the City of Fort Wayne Indiana this 25th day of Oct 1910

Wm. S. Jefferis
City Clerk

We hereby certify that the common council of the City of Fort Wayne Indiana at a Regular meeting held on the 25th day of Oct 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 451

Gust. F. Rogge
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval on the 29th day of Oct 1910

Wm. S. Jefferis
City Clerk

Approved this 31st day of Oct 1910

Jesse Grice
Mayor.

General Ordinance No 452

An ordinance regulating the transportation and carrying of Garbage. Slops. and waste Matter over the Streets and alleys of Fort Wayne

Section 1: Be it ordained by the Common Council of the City of Fort Wayne that is shall be unlawful for any person. persons. company, or corporations to carry. convey. haul or transport along or upon any street or alley of said city any slops. garbage or refuse Matter in an open. leaky or uncovered wagon or Vehicle. but all slops. garbage or refuse matter shall be carried in tight covered boxes or wagon beds.

Section 2: That this ordinance shall include any and every person firm or corporation carrying and transporting garbage under contract with said City.

Section 3: Any person violating this ordinance shall be deemed guilty of a misdemeanor and on conviction shall be fined in any sum not exceeding fifty dollars ($50.00)

Section 4: That this ordinance shall be in full force and take effect from and after its passage and approval by the mayor and legal publication

Charles E. Welch

Done at the Council Chamber in the City of Fort Wayne Indiana this 25th day of Oct 1910

Wm J. Jeffries
City Clerk

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 25th day of Oct 1910 by a majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 452

Gust. F. Rogge
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 29th day of Oct 1910

Wm J. Jeffries City Clerk

Approved this 31st day of Oct 1910

Jesse Grice
Mayor

General Ordinance No 453

An ordinance to regulate moving travel and traffic upon the streets. alleys and public places of the leity of Fort Wayne and providing punishment for violation thereof

Term "Vehicle" Shall include

Section 1: Be it ordained by the Common Council of the leity of Fort Wayne Indiana that the owner. operator. driver or person in charge of any vehicle. driven or propelled upon the streets. alleys or public places of the leity of Fort Wayne. shall conform to and observe the following. "Rules of the Road" and the term. "Vehicle" shall include wagons. carriages. omnibuses. Sleighs. push carts. Automobiles. Motorcycles. bicycles. tricycles. of whatever kind or by whatever force or power driven. ridden or propelled. excepting trains. Street cars and baby carriages. It shall also include equestrians and led horses.

Keep to the right curb except when passing another Vehicle ahead.

Section 2: a Vehicle except when passing another vehicle ahead shall keep as near the right hand curb as safely and prudence will permet.

Keep to right when passing

Section 3: a Vehicle meeting another Vehicle shall pass on the right

Overtaking another pass to the left.

Section 4: a Vehicle overtaking another Vehicle shall pass on the left side of the overtaken Vehicle and shall not pull to the right until entirely clear of the overtaken Vehicle

Heavily Loaded keep close to right curb

Section 5: Slow moving and heavily laden vehicles shall keep close to the right curb.

Keep to right on Street divided by parkway

Section 6: On all avenues or streets divided by park way walks.. Sunken. way. Viaduct. Vehicles shall keep to the right of such division

Keep to right-hand curb turning into another street to the right

Section 7: A Vehicle turning into another street to the right shall turn the corner squarely as near the right hand curb as practicable.

Turning to the left will pass Beyond intersection

Section 8: A Vehicle turning into another street to the left Shall pass to the right of and beyond the center of the street intersection before turning.

Shall make a complete turn and not cross Street

Section 9: Vehicles proceeding correctly along the right side of the street which are to discharge or take on Merchandise or passenger on the left side of the street. shall cross over Making a complete turn.

Not stop with left side to curb

Section 10: No Vehicle shall stop with side to the curb

Not stop in Street. except near the right-hand curb

Section 11: No Vehicle. unless in an emergency. or upon order of a Policeman. or to allow another Vehicle or pedestrian to cross its path shall stop in any public Street or highway except near the right hand curb thereof and so as not to obstruct the crossing

Not back to make a turn

Section 12: No Vehicle shall back to make a turn in any Street if by so doing it interferes with other Vehicles. but in such case shall go around the block or to a Street sufficiently wide to turn without backing

Not to proceed in procession

Section 13: The drivers of Vehicles owned or controlled by any firm. person or coporation. shall not proceed in procession and a distance of at least fifty (50) feet must intervene between such Vehicles. This provision shall not apply to funeral processions or parades.

Drivers signal Vehicles in rear when stopping

Section 14: The driver or person in control of a Vehicle in Slowing or Stopping. shall signal Those in the rear by raising a hand or whip Vertically.

Drivers to give signal before Making a turn

Section 15: No Vehicle shall be turned while in motion or in starting to turn from a Standstill. unless a Signal is previously given by raising the whip or hand. Indicating by it the direction in which the turn is to be Made.

Drivers to give signal before backing a Vehicle

Section 16: No Vehicle shall be backed without ample warning having been given. and while backing unceasing Vigilance must be epercised.

Pull to the right when Vehicles behind desires to pass

Section 17: Every Vehicle shall pull to the right side of the Street or rodd when signaled from a vehicle behind desires to pass

Vehicles that have right of way.

Section 18: Vehicles of the Police department. Fire department and ambulances shall have the right of way at all times in any Street or through any procession.

Vehicles going north or South have right of way.

Section 19: All Vehicles going in a northerly or Southerly direction shall have the right of way over Vehicles going in an northerly easterly or westerly direction Southerly.

Street or alleys not to be obstructed by Vehicles

Section 20: No Vehicle or Street car shall occupy any street or alley So as to interfere with or interrupt the passage of other cars or Vehicles

Vehicles taking on or letting Of Passengers

Section 21: Any Vehicle waiting at the curb shall promptly give place to a Vehicle about to take on or let Of Passengers.

Street cars not to be delayed by Vehicles

Section 22: No Street car shall be delayed longer than five minutes (5) by persons loading or unloading a vehicle.

Stops until Street cars has passed

Section 23: Any Vehicle about to pass a Street car which is taking or or discharging passengers. Shall either stop until the Street car has passed on and cleared the view of the Street for both pedestrians and driver of the Vehicle or keep at Moderate Speed at a distance of not less than ten (10) feet from each car.

Horses not to be left unattended

Section 24: No horse shall be left unattended in any Street or highway unless securely fastened or unless the wheels of the vehicle to which he is harnessed and securely tied fastened or chained. and the vehicle is of sufficient weight to prevent it being dragged at a dangerous speed with the wheels so secured.

Horses no be unbitted in Street

Section 25th No horse shall be unbitted in any Street or highway unless secured by a halter.

Horses to be unhitched

Section 26: No person in any street or highway shall remove a wheel. pole. shaft whiffle tree. or any part of a Vehicle. or any part of the harness of the horse likely to cause an accident if the horse should start. without first unhitching the horse or horses attached to said Vehicle.

Not to cause Blockades

Section 27: No one shall drive. conduct or load a Vehicle in such a manner so as to be likely to cause a blockade accident breakdown or injury to Man or beast or property

Not to be loaded so as to make noise

Section 28: No person shall so load a vehicle with iron or other Material that in hauling may strike together and produce a great noise without properly "deadening" it so that it shall cause no unnecessary noise.

Speed at alleys and crossings

Section 29: No Vehicle Should cross any Street or alley or Make any turn at a rate of Speed exceeding one half its legal Speed.

Speed from Stable. Garage ETC.

Section 30: No Vehicle shall emerge from an alley. Stable or Garage at a pace faster than a walk

Signals to Drivers

Section 31: One blast of a police Signal indicates that east and west traffic must stop and that North and South traffic may proceed. Two blasts that North and South traffic shall stop and that east and west traffic may proceed Three or more blasts is a signal of alarm and indicates the approach of danger.

Not to ride upon without permission

Section 32: No one shall ride or jump upon the rear of any Vehicle without permission

To have red lights at night when unhitched

Section 33. no Vehicles shall be left in the Street of public ways at night without a light displayed in front and rear of same

Loading and unloading

Section 34: A. Vehicle shall back up to the curb only long enough to be loaded or to be unloaded.

Backed up to the curb turned to the right

Section 35. Horses attached to vehicles backed up to the curb shall be turned to the right. The shafts of unhitched Vehicles backed up to the curb shall be turned to the right.

Whips not to crack

Section 36: No one shall crack or use a whip as to annoy interfere with or endanger any person or excite any horse other than the one he is using.

Pedestrians to use Sidewalks

Section 37: Except in case of emergency. pedestrians should use only the sidewalks and crosswalks. and should never cross streets except at regular crossings and at right-angles. The road-beds of highways and streets are primarily intended for Vehicles. but pedestrians have the right to cross them in safety. and all drivers of vehicles shall exercise all proper care not to injure pedestrians and pedestrians. before stepping from the sidewalk to the roadbed should look to see what is approaching. and should not needlessly interfere with the passage of Vehicles.

Signals on Motor Vehicles

Section 38: All automobiles. automobiles trucks and Motor-cycles shall be equipped with a suitable bell. horn or gong but only with such bell or horn or gong as makes a reasonable noise.

Drivers shall obey instructions of Policemen

Sec 39: Traffic upon the streets shall be under control of the Board of Public Safety. and all operators and drivers of Vehicles shall obey the instructions and directions of Policemen

Section 40: It shall be the duty of any person driving or in charge of any vehicle driven or propelled upon the streets. alleys or public places of the city at once to stop such Vehicle or turn to the right or left whenever signalled so to do by any Policeman of the city.

Vehicles may be seized and held

Section 41: any Policeman shall have the right to seize and hold any Vehicle which has been driven or operated contrary to any of the provisions of this ordinance until such a time as the penalty provided for such violation shall have been fully paid or replevied

Board of Safety May declare "Zone of Quiet"

Section 42: The Board of Safety May declare any Street or alley within two hundred feet of a hospital. School, church or sick chamber. "A Zone of Quiet" and upon this Zone when so declard there shall be no ringing of bells. Sounding of gongs or whistles or itinerate music

Children not to be carried on Bicycles

43: No bicyclist shall carry thereon any child under the age of five (5) years

Vehicles used for advertising purposes.

44: A Vehicle or Vehicles while being used exclusively for advertising purposes shall not be driven on any congested Street.

Signals to be used only when necessary.

Section 45: No bell or gong. or other signal shall be Sounded excepting such as are reasonably necessary to give warning of danger to persons on or about to enter the Street or other public place

Penalties for Violation

Section 46: Any person firm or corporation who shall violate any provision of this ordinance shall be fined not less than five nor more than twenty five dollars for each offense.

Section 47: All ordinance or parts of ordinance in conflict herewith are hereby repealed

Section 48: This ordinance shall take effect from and after its passage. approval by the Mayor and legal publication

Paul. P. Kinder

Done at the Council Chamber in the City of Fort Wayne Indiana this 25th day of Oct 1910

Wm. J. Jeffries
City Clerk

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 25th day of Oct 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known

as General Ordinance no 453.

Gust. F. Rogge
President

Wm. J. Jefferis
City Clerk

Presented to the mayor for approval on the 29th day of Oct 1910

Wm. J. Jefferis
City Clerk

Approved this 31st day of Oct 1910

Jesse Price
Mayor.

General Ordinance no 454

An ordinance authorizing the alienation of certain personal property and ordering an appraisement of the same

Section 1: Be it ordained by the Common Council of the City of Fort Wayne Ind. That the mayor be and he is hereby authorized to sell all the second hand Machinery, boilers and scrap iron located at no 1 and 2 pumping Stations. The City yards and on the Crematory premises. and to sign any and all necessary instruments to consumate such sale. provided that such sale shall not be made until said property shall be appraised by appraisers appointed by the Judge of the Allen County Circuit Court.
Section 2: That the City attorney be and he is hereby authorized to petition the Judge of the Allen County Circuit court for the appointment of three appraisers the property referred to in section one of this ordinance.
Section 3: That this ordinance shall be in full force and take effect on and after its passage and approval by the Mayor and legal publication

Peter M. Braun.

Done at the Council Chamber in the City of Fort Wayne Ind this 10th day of November 1910

We hereby Certify That the Common Council of the City of Fort Wayne Ind at a regular session held on the 10th day of November 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 454

Gust. F. Rogge
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of November 1910

Wm J. Jeffries
City Clerk

Approved this 15th day of November 1910

Jesse Grice
Mayor.

General Ordinance no 455

An Ordinance authorizing the employment of certain officers and employees of the Health Department of the City of Fort Wayne and fixing their compensation

Section 1: Be it ordained by the common council of the City of Fort Wayne. That the officers and employees of the health Department of the City of Fort Wayne shall respectively receive the compensation and salaries hereinafter in this ordinance provided.

The employment of such officers and employees as hereinafter named and hereby authorized and the compensation and salaries of such officers and employees are hereby fixed at the sums and amounts respectfully named for such officers and employees

The Chief of the Sanitary Police shall receive a Salary at the rate of eight hundred and forty dollars ($840.00) per annum.

Each Sanitary Policeman shall receive a Salary at the rate of eight hundred and ten dollars ($810.00) per annum.

The assistant food and meat inspector shall receive a Salary at the rate of eight hundred and forty dollars ($840.00) per annum

Section 2: That all ordinances or parts of ordinances in conflict herewith be and they are hereby repealed.

Section 3: That this ordinance be in full force and take effect on and after its passage and approval by the mayor and legal publication and on and after the 1st day of January 1911

Harry S. Pinnegar

Done at the Council Chamber in the City of Fort Wayne and this 22d day of nov 1910

We hereby Certify that the Common Council of the City of Fort Wayne at a regular meeting held on the 22d day of nov 1910 by a majority vote of all the members elect. did pass the ordinance hereunto attached and known as ~~General~~ Ordinance No 455

Gust. F. Rogge
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval on the 26th day of November 1910

Wm. S. Jeffries City Clerk

approved this 28th day of nov 1910

Jesse Grice
Mayor

General Ordinance No 456

An Ordinance authorizing the employment of certain officers and employees of the Fire Department of the City of Fort Wayne and fixing their Salaries

Section 1: Be it ordained by the Common Council of the City of Fort Wayne. That the Officers and employees of the Fire Department of the City of Fort Wayne shall receive the salaries as hereinafter in this ordinance provided for. The employment of such officers and employees as hereinafter named are hereby authorized and the salaries of such officers and employees are hereby fixed at the sum and amounts respectively named for such officers and employees.

Each Captain of the Fire Department shall receive a Salary at the rate of Ten hundred and fifty dollars ($1050.00) per annum

Each Engineer of the Fire Department shall receive a Salary. at the rate of Tenhundred and fifty dollars ($1050.00) per annum.

Each Fireman during the first six (6) months of Service in the City of Fort Wayne under the Board of Public Safety shall receive a Salary at the rate of Seven hundred and eighty dollars ($780.00) per annum.

Each Fireman during the second six (6) Months of Service in the City of Fort Wayne. under the Board of Public Safety shall receive a Salary at the rate of eight hundred and Forty dollars ($840.00) per annum

Each Fireman during the second and succeeding years of Service in the City of Fort Wayne under the Board of Public Safety shall receive a Salary at the rate of Nine hundred dollars ($900.00) per annum.

Section 2: That all parts of ordinances in conflict herewith be and they are hereby repealed

Section 3: That the ordinance be in full force and take effect on and after its passage and approval by the Mayor and legal publication.

Gust. F. Rogge

Done at the Council Chamber in the City of Fort Wayne this 22d day of November 1910

Wm J. Jeffries
City Clerk

We hereby Certify that the Common Council of the

City of Fort Wayne Ind. at a regular meeting held on the 22nd day of November 1910 by a majority vote of all members elect did pass the ordinance hereunto attached and known as General Ordinance No 456

Gust. F. Rogge
President

Wm. S. Jefferies
City Clerk

Presented to the Mayor for approval on the 26th day of Nov 1910

Wm. S. Jefferies
City Clerk

Approved this 28th day of November 1910

Jesse Grice
Mayor.

General Ordinance no 457

An ordinance fixing the Salary of the Lieutenant of the Police Department

Section 1: Be it ordained by the common council of the City of Fort Wayne Ind that the Lieutenant of Police shall receive a Salary at the rate of Ten hundred and eighty dollars per annum

Section 2: That part of General Ordinance no 457 providing for the Salary of the Lieutenant of Police be and is hereby repealed

Section 3: That this ordinance be in full force and effect from and after January 1st 1911 its passage by the council approval by the Mayor and legal publication

P. M. Braun

Done at the council chamber in the city of Fort Wayne Ind this 13th day of December 1910

Wm J. Jefferis
City Clerk

We hereby certify that the common council of the City of Fort Wayne Ind at a Regular Meeting held on the 13th day of December 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 457

Gotlieb Haller
Vice President

Wm J. Jefferis
City Clerk

Presented to the Mayor for approval on the 16th day of Dec 1910

William J. Jefferis
City Clerk

approved this 17th day of December 1910

Jesse Grice
Mayor

General Ordinance no 458

An Ordinance authorizing the employment of certain Officers and employes of the Fire Department of the City of Fort Wayne and fixing their salaries.

Section 1: Be it ordained by the common council of the city of Fort Wayne that the officers and employes of the Fire department of the City of Fort Wayne shall receive the salaries as hereinafter in this ordinance provided for. The employment of such Officers and employes as hereinafter named are hereby authorized and the salaries of such Officers and employes are hereby fixed at the sums and amounts respectively named for such Officers and employes.

Each Captain of the Fire Department shall receive a Salary at the rate of ten hundred and eighty dollars ($1080.00 per annum.

Each Engineer of the Fire Department shall receive a Salary at the rate of Ten hundred and eighty dollars ($1080.00) per annum

Section 2: That all parts of ordinances in conflict herewith be and they are hereby repealed.

Section 3: That this ordinance be in full force and take effect on and after its passage and approval by the Mayor and legal publication

Allen Hamilton

Done at the council chamber in the City of Fort Wayne this 27th day of Dec 1910

Wm J. Jeffries City Clerk

We hereby Certify that the Common Council of the City of Fort Wdyne Indiana at a Regular meeting held on the 27th day of Dec 1910 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known a General Ordinance no 458

Gust. F Rogge
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 31st day December 1910

Wm J. Jeffries
City Clerk

Approved this 3d day of January 1911

General Ordinance No 459.

An ordinance authorizing the employment of certain employees by the Board of Public works of the City of Fort Wayne fixing their salaries repealing conflicting ordinances or parts thereof and fixing the time the same shall take effect.

Section 1: Be it ordained by the Common Council of the City of Fort Wayne Indiana. That the Board of Public works be and are hereby authorized and empowered to employ a Superintendant of Streets and a foreman of Street repairs to receive Salaries hereinafter provided.
Section 2: That Superintendant of Streets shall receive a Salary of twelve hundred dollars ($1200.00) per annum.
Section 3: That the foreman of Stret repairs shall receive a Salary of Nine hundred dollars ($900.00) per annum.
Section 4: That all ordinances and parts of ordinances in conflict herewith are hereby repealed.
Section 5: That this ordinance be in full force and effect on and after its passage. approval by the Mayor legal publication and on and after January 1st 1911

Harry P Fleger

Done at the Council Chamber in the City of Fort Wayne This 27th day of December 1910

Wm. J. Jefferies
City Clerk

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 27th day of December 1910 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 459

Gust. F. Rogge.
President

William. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 3rd day of December 1910

William. J. Jefferies
City Clerk

Approved this 3d day of January 1911

Jesse Grice
Mayor

General Ordinance No 460

an Ordinance confirming and approving a contract entered into the 22d day of September 1910 by and between the City of Fort Wayne by and through its Board of Public Works and S. F. Bowser & co Inc.

Whereas Heretofore on the 22d day of September 1910 the City of Fort Wayne by and through its Board of Public works intered into a contract with S. F Bowser & co Inc which contract is in the following words:

The agreement made and entered into the 22d day of Sept 1910 by and between the City of Fort Wayne by and through its Board of Public works party of the first part and S. F. Bowser & co Inc party of the second part. Witnesseth:

Whereas The party of the second part desires to secure a Monorail carrier from the finishing department of their factory on the west side of Holton avenue to their warehouse on the east side of Holton avenue: Now.

Therefore. In consideration of the covenants and agreements to be performed and complied with by the party of the second part as hereinafter provided. Consent permission and authority are hereby given by the party of the first part to the party of the second part to construct. Maintain and operate or cause to be operated an elevated Monorail track or carrier together with columns and supports for the same running across the side walk on the west side of Holton avenue from their finishing department of their factory at a point three hundred and ten (310) feet South of the south line of Creighton avenue: thence South from said point along the west side of Holton avenue to a point one hundred and seventy nine (179) feet north of the north line of Fisher Street: thence diagonally across Holton avenue to the warehouse of the said party of the second part on the east side of Holton avenue: all in accordance with the plan attached hereto and made a part hereof: on which plan the line and the route of said Monorail are marked and indicated together with the columns and supports of said line or Monorail.

It is understood and agreed that the consent permission and authority herein given and granted are upon the following terms and conditions.

Section 1: The party of the second part if it desires to avail itself of the benefits of the consent permission and authority herein granted shall cause the complete construction of said Monorail or carrier within two (2) months from the date hereof and in the event that is so avails itself of such grant permission consent and authority then is shall cause the complete construction of said track within thirty (30) days from the time it commences work thereon and within the period of two (2) Months as above stated, and shall at no time in the construction of said track occupy for such purpose any of the streets above mentioned for any length of time in excess of five (5) days: but in the event that the party of the second part is prevented from complying with any of the above conditions by reason of any judgment of any court then said Board of Public works may grant a reasonable extension of time as to any one of the above provisions

Section 2: Said monorail where it crosses Holton avenue at the point one hundred and seventy nine (179) feet North of the north line of fisher Street shall 21 feet above the surface of said street. Said Monorail or carrier shall be so operated and maintained so as not in any event to be an annoyance or inconvenience to pedestrians or people in the immediate neighborhood. Said Monorail columns and supports shall be kept properly painted at all times whenever so ordered by the Board of Public works.

Section 3: The party of the second part shall so construct and maintain its said Monorail or carrier in such a manner as to not in any way interfere with the drainage of the surface waters on said street and shall when constructing said track over and across said Street do the same under the direction of the said Board of Public works and in the manner required by said Board.

Section 4: The party of the second part agrees and binds itself to keep and hold said city free and harmless from any and all liability from any and all damages that may accrue to any person or persons or property on account of any injury to their persons or propety growing out of the construction. Maintenance and operation of said Monorail or any of the carries thereon by any person or corporation and in case suit shall be filed against said City on account

thereof said second party upon notice to do it by said City shall defend such action at its own expense and in the event that Judgment be rendered in said action against said city the party of the second part shall pay such Judgment with all costs and hold the city harmless therefrom and said second party shall execute to the party of the first part a bond with sufficient surety to be approved by said Board of Public works payable to said city in the sum of five thousand dollars ($5.000.00) conditioned for the faithful performance by said second party of all of the conditions and provisions contained in this constract to be performed on its part and will from time to time whenever desired by said Board of Public works renew said bond

Section 5: It is further agreed that if the second party fails to comply with and perform any of the provisions of sections one (1) two (2) three (3) and four (4) of this constract the consent permission and authority herein granted shall at once terminate and the second party shall forfeit all rights hereunder and shall cause the removal at its expense of said Monorail. including supports and columns and place said Street in the same condition as the remainder of said street.

Section 6:

It is further understood that this contract and the provisions thereof shall be binding on the Successors and assigns of the party of the second part.

Section 7: The consent. permission and authority hereby granted shall continue for the period of twenty five (25) years from the date hereof.

Witness our hands and seals

City of Fort Wayne

By Frank. J. Benoy.

Henry Hilgeman

E. J. Lennon

Its Board of Public works

S. F. Bowser & co Inc

By S. F. Bowser Prest.

attest

H. W. Becker clerk

(over)

Section 1: Be it ordained by the common council of the City of Fort Wayne Indiana that the contract heretofore entered into on the 22d day of Sept 1910 by and between the City of Fort Wayne by and through its Board of Public works party of the first part and D. F. Bowser & co Inc party of the second part as fully set out in the preamble hereto be and is in all things hereby approved

Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Harry G. Pinniger

Done at the council chamber in the city of Fort Wayne Indiana this the 10th day of Jan 1911

We hereby certify that the common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 10th day of January 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 460

Louis J. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 14 day of January 1911

Wm. J. Jeffries
City Clerk

Approved this 23d day of January 1911

Jesse Grice
Mayor

General Ordinance no 461

an ordinance ratifying and approving a contract entered into the 27th day of December 1910 by and between the city of Fort Wayne and the Kaough Coal Company.

Whereas heretofore on the 27th day of December 1910 the city of Fort Wayne by and through its Board of Public works entered into a contract with the Kaough Coal company. providing for the purchase of its years supply of coal to be used at its no 2 pumping Station which contract is in the following words:

This agreement Mad this 27th day of December 1910 by and between the City of Fort Wayne by and through its Board of Public works party of the first part and the William Kaough Coal Company party of the second part. witnesseth

That in consideration of the purchase by said city from the party of the second part of its years supply of Coal to be used at its no 2 pumping Station from the 1st day of January 1911 to the 31st day of December 1911 in the manner herein after provided. the party of the second part agrees to furnish to said city during said period of time such quantity as said city may desire of Elk Ridge Gas no 2 Mine Run Coal at ninety-seven and one half (.97½) cents per ton F. O. B. Mines.

Said City to buy from said company all of the coal used by it at its said no 2 pumping station during said period of time so long as the kind. quality is satisfactory to said Board of Public works and the same to be shipped and billed on flat bottom cars direct from the mines to said City at its said pumping Station on the New York. Chicago & St. Louis railroad. Said City to pay all freight on all coal so purchased by it.

It is mutually agreed between the parties hereto that payments by the first party shall be made to second party on or before the 15th day of every month. based upon invoice weights on all coal delivered as aforesaid during the month previous thereto. The Strict performance of the contract by the party of the second part and the prompt deliveries of coal herein on cars at said Mines as aforesaid shall be subject to delays

occasioned by strikes. accidents and other unavoidable temporary casualties in the operation of said mines and want of car supply and failure of railroad company's to deliver and place cars at the mines for loading or other causes beyond control of the said party of the second part.

It is further agreed between the parties hereto that after the delivery of said coal on Board of said cars by said party of the second part. Said party at the request of the first party and as the agent of the party of the first part. will use its best endeavors with the carriers to have said cars of coal delivered as aforesaid. billed and sent forward promptly to destination

The prices made in this contract are based upon the present mining rate and shall advance or decline as said rate of mining may advance or decline during the period of this contract.

This contract shall not be binding or take effect until the second party shall execute to the party of the first part a bond in the sum of one thousand dollars ($1000.00) with sufficient surety thereon. to be approved by the Mayor and city Controller of party of the first part and conditioned for the faithful performance by party of the second part of all terms conditions and agreements herein to be performed by it and until the contract has been ratified and approved by the Common Council and said city

Witness our hands and Seals this 27th day of December 1910

City of Fort Wayne by

Henry Helgemann
E. J. Lennon
Its Board of Public works

William Kaough coal Company by.
Wm Kaough
its President

attest Martin Leitzer
Secr

Know all men by these presents the William Kaough Coal Company as principal and William Kaough. P. J. McDonald as surety are held and firmly bound unto the city of Fort Wayne Indiana in the full and just sum of one thousand dollars ($1,000.00) lawful money of the United States for the payment of which well and truly to be made. the said principal binds themselves. their heirs. executors and administrators. and the said surety binds itself. its successors and assigns. Jointly and Severally by these presents.

Witness our hands and seal this 27th day of December 1910. Whereas on the 27th day of December 1910 the above bound William Kaough Coal Company executed and entered into a certain contract with the city of Fort Wayne by and through its Board of Public works to sell and deliver to the said city during said period of time such quantities as said city may desire of Elk Ridge Gas no 2 Mine Run Coal as may be required for use at the no 2 pumping station from the 1st day of January 1911 to the 31st day of December 1911 as said city may from time to time direct.

And whereas in said contract it was provided that said William Kaough Coal Company should execute and deliver to said city a bond conditioned for the faithful performance by them of said contract and for the payment or forfeiture of other sums of Money required to be paid by them for any violation of said Contract.

Now therefore the condition of this obligation is such that if the said William Kaough coal Company shall well and truly perform and fulfill all and every covenant condition Stipulation and agreement in said contract Mentioned to be performed and fulfilled by them and shall pay said City all sums of Money due to it under the provisions of said contract and shall pay to said city any damages or other sums of money that may accrue to said City by reason of any failure on their part to perform the covenants. conditions. Stipulations and agreements contained in said contract or to comply with all of its provisions then this obligations shall be void: otherwise the same shall remain in full force and effect.

It is however mutually understood between the parties that in no event shall said surety be liable for a greater sum then the penalty of the bond

William Kaough Coal Company by
Wm Kaough Pres
Wm Kaough
P. J. McDonald

approved this 27 day of December 1910
Henry Hilgeman
E. J. Lennon
Bds Board of Public Works

Section 1: Be it ordained by the common council of the City of Fort Wayne Indiana that the contract heretofore entered into on the 27th day of December 1910 by and between the city of Fort Wayne and the Kaough Coal Company. as fully set forth in the preamble hereto be and the same is hereby in all things ratified and approved

Section 2: That this ordinance be in full force and take effect on and after its passage and approval by the Mayor and legal publication

Charles W. Dittoe

Done at the Council chamber in the city of Fort Wayne Indiana this 10th day January 1911

We hereby certify that the common council of the the city of Fort Wayne Indiana at a Regular meeting held on the 10th January 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 461

Louis. S. C. Schroeder
President

Wm S. Jeffries
City Clerk

Presented to the Mayor for approval on the 14th day January 1911

Wm S. Jeffries
City Clerk

Approved this 23d day of January 1911
Jesse Grice
Mayor

General Ordinance no 462

An Ordinance changing the names of certain streets and alleys in the city of Fort Wayne

Section 1: Be it ordained by the common council of the city of Fort Wayne that the following described street shall hereafter be known and called by the following name:
Hartnett Street from Broadway west to the river shall be known and called Packard avenue. Making it a continuation of the present throughfare known as packard avenue
Section 2: This ordinance shall be in full force and effect from and after its passage and appiroval by the Mayor.

E. A. Wagner

Done at the council chamber in the Cety of Fort Wayne Indiana this 24th day of January 1911

We hereby certify that the Common Council of the Cety of Fort Wayne Indiana at a Regular session held on the 24th day of January 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 462

Louis S. E. Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for appiroval on the 27th day of January 1911

Wm. S. Jeffries
City Clerk

approved this 30th day of January 1911

Jesse Grice
Mayor.

General Ordinance No 463

An ordinance approving a contract entered into by and between the City of Fort Wayne Ind by and through its Board of Public works and the New York. Chicago and St Louis Railroad Company.

Whereas. On the 9th day of January 1911 the Board of Public works of the city of Fort Wayne Indiana on behalf of the city entered into a contract with the New york. Chicago and St Louis Railroad Company for the construction of additional tracks on Barr street which contract is as follows.

This agreement made and entered into the 9th day of January 1911 by and between the city of Fort Wayne by and through its Board of Public works party of the first part and the New york Chicago and St Louis Railroad Company a corporation party of the second part. Witnesseth:

That the party of the first part hereby grants to the party of the second part its successors and assigns subject to the laws and ordinances now in force. or hereafter enacted. authority and permission to lay a single track of railroad over and across Barr Street in the city of Fort Wayne at the following point Viz The center line of said track to be twelve and five tenths (12.5) feet North of the center of the main track on the east line of Barr Street and fifteen (15) feet North of the center line of the main track on the west line. of said Street and to connect with the side track of said Company on the east of said Street. The permission and authority hereby given are upon the following terms and conditions.

That the track herein authorized to be laid shall be so placed that is will not interfere with the public use of said Street. That if the said Street is hereafter graded or paved or otherwise improved that the said party of the second part shall make the grade of its said track conform with the grade established by the board of public works

That if said Street is hereafter paved that said second party shall pay for so much of the pavement as lies between its tracks and the space of two (2) feet on either side thereof. That the grade of said tracks shall be at all times so maintained so as not to interfere with public travel

That the party of the second part if it desires to avail itself of the benefits of the consent. permission. and authority herein granted shall cause the complete construction of said track within

one (1) year from the date thereof.
The party of the second part further agrees and binds itself to keep and hold said city free and harmless from any and all liability from any and all damages that may accrue to any person or persons or property, on account of any injury to their person or property growing out of the Construction Maintenance or operation of said track or the Operation of any cars thereon by any person or corporation.
This contract shall not in any manner enter into or effect the question of the elevation of the tracks of the second party. and all or any laws that may now or hereafter prescribe the manner of or effect the elevation of the now existing tracks of the party of the second part shall apply to and affect the track to be constructed under this contract.
That the permission herein granted to the said party of the second part shall continue for the period of (25) Twenty five years from the approval of said contract by the Common Council
It is further understood and agreed that this contract and the provisions thereof shall be binding upon the successors and assigns of the party of the second part.
Executed in duplicate by the parties hereto on the day and year first above written

City of Fort Wayne by
Frank T. Bixby
Henry Hilgeman
E. J. Lennon
Its Board of Public works

attest H. W. Becker
Clerk

The New York Chicago & St Louis Railroad Company
A. W. Johnson
General Manager

Section 1: Be it ordained by the Common Council of the city of Fort Wayne Ind that the contract heretofore entered into on the 9th day of January 1911 by and between the city of Fort Wayne by and through its Board of Public works and the New York Chicago and St Louis Railroad Company as fully set forth in the preamble hereto be and the same is in all things ratified and approved.
Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Charles E. Welch

(over)

Done at the Council Chamber in the city of Fort Wayne Indiana this 24th day of January 1911

Wm S. Jeffries
City Clerk

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 24th day of January 1911 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 463

Louis S. C. Schroeder
President

Wm S. Jeffries
City Clerk

Presented to the Mayor for approval on the 27th day of January 1911

Wm S. Jeffries
City Clerk

Approved this 30th day of January 1911

Jesse Grice
Mayor.

General Ordinance No 464

an ordinance ratifying and approving the contract between the city of Fort Wayne Indiana and Gust Lindeman relative to the building and constructing of a storage house on the city property on North Clinton Street.

Whereas heretofore on the 27th day of December 1910 the city of Fort Wayne by and through its Board of Public works entered into a contract with Gust Lindeman relative to the construction of a storage house on the city property on north Clinton Street which contract is as follows:

This agreement. made and entered into this 27th day of December 1910 by and between the city of Fort Wayne Indiana by and through its Board of Public works. party of the first part and for convenience hereinafter referred to as the Board. and Gust Lindeman party of the second part. and for convenience hereinafter referred to as contractor. Witnesseth: That for and in consideration of the payment by the Board to the contractor of the sum of money hereinafter referred to the contractor hereby agrees to erect and construct a storage house on the city property on North Clinton Street. Said Storage house to be built and constructed as set forth in the plans and Specifications for the same. Subject to certain changes made in such Specifications set out in the minutes of the Board of Public works sitting as Water work Trustees all of which are made part and parcel of this Contract and binding upon the parties hereto thim same as if fully copied herein. Said plans and Specifications for the purpose of indentification and for the purpose of more fully Making the same a part thereof. have been signed by the parties hereto as of even date herewith.

The contractor agrees that he will within ten days after the execution of this contract and its approval by the Common Council of said City. execute a bond to said City for the faithful performance of the contract and indemnify the city against all damages arising out of said contract. said bond or bonds to be Satisfactory to the Board.

The Board shall have the right to make any alterations additions to. or omissions of work or material in such contract as herein specified that may be deemed advisable and the same shall be acceeded to by the Contractor and carried into effect by him without

in any way violating or vitiating the contract or any bond given by the contractor: That no alterations additions to or omissions of work or material shall be made unless the same shall first be ordered by the Board. in writing and the written agreement entered into between the Board and the contractor as to the amount of money to be allowed or deducted for such alterations or additions

The contractor further agrees that in the prosecution of said work all proper skill and care will be exercised: That said Contractor will properly and fully guard and protect all excavations and dangerous places. and will use all due and proper precautions to prevent injury to the property. person or persons. what or whomsoever thereon and during the time of making such improvement the city of Fort Wayne shall be saved harmless from any and all liability whatsoever growing out of any injury or damage to property or persons because of any neglect or fault of the contractor. his agent or employees in the execution of this contract or any matters connected thereto or relative thereto. and to pay any judgment with costs which may be obtained against said city growing out of any such injury or damages

Said Contractor further contracts and agrees to pay any and all moneys due any contractor. personor persons furnishing and material for said work and pay any laborers employed by him for any work done in the prosecution of said improvement and that in the event any liens are filed with said Board for any such material. men or laborers this Board is authorized to hold out of the amount of moneys due said Contractor an amount equal to the amount of the liens or claims filed. That before said Contractor shall receive his money for the performance of the work he agrees to fully satisfy the Board that all liens and claims have been paid

The Board to determine for itself whether the evidence of said payment is or is not satisfactory

It is hereby expressly understood that no assignment of this contract shall be made to any party without the consent of said Board in writing and that said work shall be completed in sixty days after the execution and approval of this contract.
The contractor agrees to pay the city as liquidated damages the sum of Five Dollars ($5.00) for each and every day that said contract is unfinished after aforesaid time. The City reserving the right after five days notice to contractor after expiration of aforesaid time, to take possession of the premises and all Materials thereon and provide work and material to complete said work and deduct the cost and charges thereof from any sum that may be due said Contractor.
It is agreed by the Board that for and in consideration of the furnishing of said Material and the performance of said work it will pay to the contractor that the sum of twelve hundred and sixty dollars ($1260.00) on the completion and final acceptance of the work by the Board.
In witness whereof the parties have hereunto set their hands and seals the 27th day of December 1910

City of Fort Wayne. by.

Henry Hilgeman
E. J. Lennon
Its Board of Public works
Gustave Lindeman
Contractor

attest Martin Metzger
Secretary

Know all men by these presents that we Gust Lindeman and H. Franke are jointly and severally held and bound unto the city of Fort Wayne state of Indiana in the sum of One Thousand dollars ($1000.00)
Whereas the above bound Gust Lindeman entered into a contract with the city of Fort Wayne on the 27th day of December 1910. relative to the building and constructing of a storage house on the city property on North Clinton St. and in which contract the said Gust Lindeman obligated himself to execute to said city a bond for faithful performance by him of said contract as therein provided Now therefor. If the above bound Gust Lindeman shall well and truly faithfully and honestly perform all the conditions of said contract agreed to and shall

furnish all the material, and perform all the work mentioned in said contract in accordance with in the manner, with the time, and of the Material provided in said contract. Specifications, proposals and bids and shall said city harmless from the payment of any and all damages that may accrue to any person or property then this bond shall be void otherwise to be and remain in full force and effect.

Gustave Lindeman
H. Franke

approved this 27th day of Dec 1910

Henry Hilgeman
E. J. Lennon
Its Board of Public works

Section 1: Be it ordained by the common council of the City of Fort Wayne Indiana that a contract heretofore entered into by and between the city of Fort Wayne by and through its Board of Public works and Gust Lindeman as fully set forth in the preamble be and the same is in all things ratified and approved

Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

P. M. Braun.

Done at the council chamber in the city of Fort Wayne Indiana this 24th day of January 1911

We hereby certify that the common council of the City of Fort Wayne Ind at a Regular meeting held on the 24th day of Jan 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 464

Louis A. C. Schroeder
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 27th day of ~~December~~ January 1911

Wm. J. Jefferis City Clerk

approved this 30th day of Jan 1911

Jesse Grice
Mayor

General Ordinance No 465

An Ordinance approving a contract entered into by and between the City of Fort Wayne by and through its Board of Public works and the Fort Wayne electric works.

Whereas on the 7th day of December 1910 the Board of Public works of the city of Fort Wayne Indiana on behalf of the city entered into a contract with the Fort Wayne electric works for the purchase of electric lamps for use in the municipal Electric light and power works which contract is in the following words:

Consumers Contract

This agreement made this 7th day of December 1910 between the Fort Wayne electric works. a New York corporation (hereinafter called the Company) and Board of Public works of Fort Wayne State of Indiana (hereinafter called the purchaser)

Witnesseth: Whereas the company controls or is licensed under certain United States letters patent relating to incandescent electric lamps and processes and apparatus used in the manufacture thereof which said letters patent are enumerated herein:

And Whereas the purchaser desires to purchase and the company is willing to sell to the purchaser incandescent electric lamps embodying or made in accordance with said inventions:

Now Therefore:

1. The Company agrees to sell and the purchaser agrees to take within one year from date hereof and to pay for a quantity of Eddison and G. E. Incandescent electric lamps which at the list prices stated in the attached Schedules thereto (les hereinafter mentioned discounts) shall aggregate One Thousand Six hundred dollars estimated to cover the purchasers entire requirements of Incandescent lamps during the period of one year from date and purchaser further agrees that his purchases shall not be less than One Thousand six hundred dollars The above lamps will be shipped from time to time as the purchaser may request and will be billed only as shipped. The purchaser agrees that payments for such shipments shall be made at list prices subject to the discounts to which the purchaser may be entitled as hereinafter stated within thirty (30) days from the date of invoice.

The purchaser is entitled during the period covered by this agreement but only so long as all the conditions of this agreement are fully lived up to by the purchaser to the following discounts from the list prices given in the schedules hereto attached

Schedule	Kind of Lamp	Discount	Schedule	Kind of Lamp	Discount Standard Package	Discount Broken Package
C-1	Regular Large Carbon	20 %	G-1	Reg Large Gem 100 watts and over Meridan Gem	20 %	10 %
C-2	Regular Large Carbon	20 %	J-1	Large Mazda	20 and 10 %	10 %
C-4	Cand & Elec. Min Car	20 %	J-5	Min Mazda	20 and 10 %	10 %
C-5	Battery & Telep Min car	20 %	J-6	Street series Mazda	20 and 10 %	10 %
G-1	Reg Large Com. 80 watts & under	20 %	Ta-1	Large Tantalum	20 and 10 %	10 %

3 The Company agrees that Lamps purchased und this agreement may be furnished either as free renewals or at any price the purchaser may establish to consumers of current on lighting circuits to which the purchaser supplies current exclusively or on circuits which are owned or controlled by him

The purchaser however understanding that each lamp purchased under the agreement is a patented article on which the price to all classes of customers is established agrees that all lamps purchased under this agreement shall be used or sold for use only on circuits to which he supplies current exclusively or on circuits owned or controlled by him except that to consumers having what is termed a break down connection and purchasing a part only of their yearly supply of current from the purchaser. Lamps may be furnished only at the prices established by the Company which established prices can be obtained from time to time upon application to the Company. But the purchaser agrees that lamp purchased under this agreement will not be delivered or sold at any price to or for the use of jobbers. dealers or Contractors purchasing lamps for resale.

4: The purchaser agrees that the transportation (not including cartage) allowed on lamps shall be in accordance with the companys published rules regarding deliveries as shown in delivery schedule hereto attached.

5: The Company agrees that at any time after thirty (30) days from its acceptance of this agreement or at any time after thirty (30) days from its acceptance of any additional future delivery orders under this agreement provided that the purchaser at the date of such acceptance shall have specified fully the types of lamps required under this agreement or any additions thereto it will make prompt shipments and if at any time thereafter prompt shipments cannot be made should the necessities of the purchaser require express shipments express charges will be prepaid or allowed in accordance

with the companys published rules regarding deliveries as shown in delivery schedule herewith. The purchaser agrees that broken package quantities of lamps are to be supplied by the company with no allowance for transportation F. O. B. only the companys factory or established storerooms.

6: The company further agrees that the net prices allowed the purchaser under this agreement are the lowest given similar purchasers purchasing in like amounts who may have signed future deliverys orders with the company and that during the period covered by this agreement should the company make any reduction in price affecting similar customers purchasing in like amounts the purchaser shall be immediately notified and will thereafter receive the benefits of such reduction in price on lamps shipped after the day on which such lower prices take effect.

7. Breach of any of these provisions of this contract or any failure to maintain and observe prices rules and regulations in accordance herewith shall give the Company the option immediately to cancel this contract and the purchaser is hereby expressly put on notice that in case of any such failure he can thereafter obtain lamps manufactured under the letters patent hereon enumerated only at standard package prices without any discount whatever or in case he fails to take and pay for during the ensuing year all the lamps contracted for hereunder he can thereafter obtain lamps manufactured under the letters patent hereon enumerated only at a price based on the net value of lamps actually purchased hereunder.

8: It is understood that subject to cancellation at any time at the companys option. the purchaser may purchase Mazda and Tantalum Lamps from any licensed manufacturer and that the purchaser es excused from taking the full quantity of lamps required hereunder provided it can be shown by the purchaser that during the period of this contract and prior to the date of written notification of said cancellation he has purchased from any licensed Manufacturer or his agents a quantity of Mazda and Tantalum Lamps of all Styles except Miniature (made under provisions of the license agreement) the aggregate net price values of which together with the purchases under this contract make up the required quantity.

9: This agreement does not becomes binding upon the Company until accepted in writing at the foot hereof by the sales

Manager or his duly authorized representative located in the main sales office of the company.

Frank. J. Benoy President

Board of Public works purchaser.

accepted this 22d day of December 1910

Fort Wayne electric works

By A. U. Senna assist Secretary

Section 1: Be it ordained by the Common Council of the city of Fort Wayne Indiana that the contract heretofore entered into on the 7th day of December 1910 by and between the city of Fort Wayne of Fort Wayne by and through its Board of Public works and the Fort Wayne electric works as fully set forth in the preamble hereto be and the same is in all things ratified and approved

Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

E. A. Wagner.

Done at the council chamber in the city of Fort Wayne Indiana this 24th day of January 1911

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 24th day of January 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 463

Louis S. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 27th day of Jan 1911

Wm S. Jefferies
City Clerk

approved this 30th day of Jan 1911

Jesse Grice
Mayor

General Ordinance no 466

An ordinance approving a contract entered into by and between the city of Fort Wayne through its Board of Public works and the Fort Wayne electric works

Whereas on the 28th day of November 1910 the Board of Public works of the city of Fort Wayne Indiana on behalf of the city entered into a contract with the Fort Wayne electric works for the purchase of electric Meters for use in the municipal electric light and Power works which contract is in the following words.

Fort Wayne Electric Works

Executive Offices Fort Wayne Indiana

Future delivery Meter Contract

This contract and agreement executed in duplicate. Made and entered into this 28th day of November 1910 by and between the Fort Wayne electric works of Fort Wayne Indiana party of the first part and Board of Public works of Fort Wayne 2nd party of the second part their successors and assigns!

Witnesseth: That for and in consideration of one dollar and other valuable considerations paid by said party of the first part to said party of the second part, the receipt of which is hereby acknowledged the said party of the second part hereby agrees to purchase of the said party of the first part all electric alternating current watthour meters which the said party of the second part may need during a period of one year from the date of this contract for use by it in the operation of the electric plants controlled by it and to pay for all meters purchased under this contract within thirty (30) days from date of shipment thereof the price hereinafter set forth: and all said meters to be used as above mentioned shall be of Type K-3 alternating current watthour meters as manufactured by the said party of the first part at Fort Wayne Indiana

For and in consideration of the exclusive purchase of alternating current watthour meters as hereinbefore mentioned from the said party of the first part by the said party of the second part the said party of the first part hereby agrees that all meters purchased under this contract shall be free from all inherent electrical and Mechanical defects and to hold said party of the second part harmless and indemnified against all sums which the said party of the second part shall be adjudged to pay in any suit brought against it alleging infringement of patents by the use of the meters hereinbefore Mentioned

provided that the party of the first part be given immediate written notice of suits and permission through their counsel to defend same: and provided further that said party of the second part is not in default in its payments.
The said party of the first part hereby agrees to sell to said party of the second part alternating current watthour meters as hereinbefore mentioned. new and in good condition. delivered F.O.B. Fort Wayne Indiana} consigned to the address of the said party of the second part at a discount of 50 + 10 per cent from Schedule A. 10th Edition. attached

50 + 10 per cent from Schedule E. 1 + 2 attached.

Said Schedule being attached hereto and made a part of this contract.
The party of the second part agrees that he is under no obligations inconsistent with the carrying out of the conditions of this agreement.
This contract is not binding unless approved by an executive Officer of the Fort Wayne electric works

Fort Wayne Electric works
By J. E. Hall
agent.

accepted Board of Public works
Witness H.W. Becker Clerk By. Frank. J. Benoy

The above contract and agreement is hereby fully ratified and approved by us at Fort Wayne Indiana this 22nd day of December 1910

Fort Wayne Electric works
A. A. Serva
assist Secretary

Section 1: Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered into on the 28th day of November 1910 by and between the city of Fort Wayne by and through its Board of Public works and the Fort Wayne electric works as fully set forth in the preamble hereto be and the same is in all things ratified and approved
Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Leone at the council chamber in the city of Fort Wayne Indiana this 24th day of January 1911

We hereby certify that the common council of the city of Fort Wayne Indiana at a regular meeting held on the 24th day of January 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 466

Louis S. C. Schroeder
President

Wm. J. Hoffmeister
City Clerk

Presented to the mayor for approval on the 27th day January 1911

Wm. J. Hoffmeister
City Clerk

Approved this 30th day of January 1911

Jesse Grice
Mayor

General Ordinance No 467

An ordinance approving a contract entered into by and between the City of Fort Wayne. by and through its Board of Public works and the Fort Wayne electric works.

Whereas on the 28th day of November 1910 the Board of Public works of the city of Fort Wayne Indiana on behalf of the city entered into a contract with the Fort Wayne Electric works for the purchase of Transformers for use in the Municipal Electric light and power works. Which contract is in the following words.

Fort. Wayne Electric works

Executive Offices Fort Wayne Ind

Future delivery transformers contract.

This contract and agreement. executed in duplicate. Made and entered into this 28th day of Nov 1910 by and between the Fort Wayne electric works of Fort Wayne Indiana party of the first part and Board of Public works of Fort Wayne. 2nd party of the second part. their successors and assigns

Witnesseth:- That for and in consideration of One dollar and other valuable considerations paid by said party of the first part to said party of the second part. the receipt of which is hereby acknowledged the said party of the second part hereby agrees to purchase of the said ~~city~~ party of the first part all Multiple transformers that the said party of the second part may require during the period of one year from the date of this contract for use by it in the operation of the electric plants controlled by it all Standard Transformers to be rated 1100/2200 Volts primary 110/220 Volts Secondary. The party of the second part agrees to pay to the party of the first part for all transformers purchased under this contract within (30) days from date of shipment thereof the price hereinafter set forth and all transformers to be used as above mentioned shall be the type. A. transformer as manufactured by the said party of the first part at Fort Wayne Indiana

For and in consideration of the exclusive purchase of transformers as hereinbefore mentioned from the said party of the first part by the said party of the second part. the said party of the first part hereby agrees that all transformers purchased under this contract shall be free from all inherent electrical and Mechanical defects and to hold said party of the second part.

harmless and indemnified against all sums which the said party of the second part shall be adjudged to pay in any suit brought against it alleging infringement of patents by the use of the transformers hereinbefore Mentioned provided that the party of the first part be given immediate written notice of suits and permission through their counsel to defend same: and provided further that the said party of the second part is not in default in its payments.

Said party of the first part hereby agrees to sell to the said party of the second part Standard Multiple transformers as hereinbefore mentioned. New and in good condition F.O.B. Fort Wayne Ind. consigned to the address of the said party of the second part at a discount of

50. 10 + 10 per cent from Schedule A. Attached

Said Transformers Schedules being attached hereto and made a part of the contract.

Should transformers other than standard be required they will be furnished at prices comparable with prices on Standard transformers as Specified in the attached Schedules.

The party of the second part agrees that he is under no obligations inconsistent with the carrying out of the conditions of this agreement

This contract is not binding unless approved by an executive officer of the Fort Wayne electric works

Fort Wayne Electric works

By J. E. Hall

agent.

accepted Board of Public works

By Frank. J. Lenoy

Witness

H. W. Baker

The above contract and agreement is hereby ratified and approved by us at Fort Wayne Ind this 8th day of December 1910

Fort Wayne Electric works

A. A. Berna

asst Secretary

Section 1: Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered into on the 20th day of November 1910 by and between the city of Fort Wayne by and through its Board of Public works and the

Fort Wayne Electric works as fully set forth in the preamble hereto be and the same is in all things ratified and approved Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Gust. F. Rogge

Done at the council chamber in the city of Fort Wayne Indiana this 24th day of January 1911

We hereby testify that the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 24th day of January 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 467

Louis S. C. Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval on the 27th day of January 1911

Wm. S. Jeffries
City Clerk

Approved this 30th day of January 1911

Jesse Grice
Mayor

General Ordinance 468

An ordinance Ratifying and approving a contract between the city of Fort Wayne and Thrasher and Herman relative to the drilling of certain wells.

Whereas heretofore on the 10th day of January 1911 the city of Fort Wayne Indiana by and through its Board of public works entered into a Contract with Thrasher and Herman relative to the drilling of certain wells in said city. which Contract is in the following words.

This agreement. Made and entered into this 10th day of January 1911 by and between the city of Fort Wayne by and through its Board of Public works party of the first part. and W. J. Thrasher and Adolph Herman partners doing business under the firm name of Thrasher & Herman parties of the second part Witnesseth:

That in consideration of the mutual covenants hereinafter expressed the parties of the second part agree to drill and caused to be drilled for the said city said number of wells not less than one (1) or more as may be desired by said city acting by and through its said Board of Public works. Such well to be eight inches (8") in diameter from top to bottom. and the best quality of heavy eight inch (8") wrought iron drive pipe to have Nominal weight of not less than twenty eight (28) pounds per foot. and all pipe used in the drilling and constructing of said well to be protected by first-class steel shoe to prevent damage while driving to rock and to enable the pipe to be driven into the rock the proper distance to insure its being tight so as to shut off any seepage of surface water. Each joint shall be firmly screwed together one and one quarter inches (1¼") into the coupling with red lead in each joint. and a Vacuum guage must be used on each Well. to show the number of feet lift it may have and it is further agreed by the parties of the second part that they will use the newest and latest improved machinery in drilling any of the above wells and which will enable them to avoid all delay due to breakage and shall provide new lines for drill in such manner as to do away with risks and customary accidents in finishing of the job. all the castings must be driven into the bed rock so as to shut off all surface water and Sand.

and it is expressly understood and agreed by the parties of the second part that if sand runs into the well it will be worthless and in which case the Board of Public works is given the expressed power to reject ~~any~~ and all wells unless so drilled or constructed as to prevent the seeping in of sand and surface water and in constructing and drilling of such wells the second parties agree to keep employed laborers to be experts in making of wells of this size and must have had practical oil or deep well experience and must keep constantly drilling at any wells to be so constructed until the suffecient depth as hereinafter designated shall be attained

and it is further agreed by the parties of the second part that each well after the construction thereof as herein provided. must be pumped until it is clean and free from drillings and after the well is so cleaned and freed from drillings by the parties of the second part it must be left to stand at least fifteen minutes to show whether or not it leaks. If the same leaks said Board of Public works is hereby expressly given and reserved the power to accept same. and if it cannot be made tight. any loss by reason of expense of material or labor in construction of any such well. shall be the loss of the second parties.

and it is further agreed by the parties of the second part that all wells to be constructed by them under this agreement are to be located at such place as may be designated by the said Board of Public works.

and it is hereby further agreed by the parties of the second part that they will cause to be drilled and constructed any number of wells not less than one (1) in the manner. and of the material and by kind of laborers above specified and described and will begin work drilling and construction of one (1) well not later than five (5) days after the approval of this contract by the common council: and the said wells are to be completed and ready for acceptance and in good working order within sixty (60) days from that time and any and all further wells that said Board of Public works may desire to be constructed and drilled under this contract shall be completed and ready for acceptance and in good working order within thirty (30) days from such time as the said Board of Public works may notify said parties of the second part to cause the same to be

drilled and constructed. And said second parties agree to commence the drilling and construction of such wells within ten (10) days from the time that they may be so requested to do by the said Board of Public works. all wells so constructed by the parties of the second part under this agreement shall be of said depth as may be designated by the said Board of Public works not less than one hundred (100) feet nor more than two hundred and fifty (250) feet and in case said Board of Public works may deem it necessary to suspend operations on the construction of any one or more of said wells for the purpose of making tests as to the capacity thereof. The said second parties agree to cause said test to be made and to furnish all necessary suitable testing apparatus to make any such test as may be so deemed necessary by the Board of Public works and said second parties agree to make such test and to furnish such apparatus at their expense. and it is further agreed by the said second parties that they will furnish all necessary suitable fuel. water material labor. Machinery and other apparatus in the successful drilling of said wells.
and it is further understood and agreed by the parties hereto that said city shall pay to said parties of the second part for each of the wells to be so constructed under this contract, and which has been accepted by the said Board of Public works the sum of one dollar and sixty-eight cents ($1.68) for each foot thereof from the top of the ground to the bottom of said well, and said second parties agree to accept said sum in full payment of all work and labor performed and Material furnished in the construction and drilling of said wells as provided in this contract. Said payment to be made to the parties of the second part within thirty (30) days from the time of the completion of all such wells, and the acceptance thereof by the said Board of Public works.
and it is further agreed by and between the parties hereto that in case it becomes necessary at any time to grant the parties of the second part an extension of time in the completion of any well or wells under this contract said Board of Public Works may in its discretion. grant such extension of time as it may deem proper and this contract shall not be binding upon the party

of the first part until said parties of the second part. has executed and delivered to said Board of Public works a bond payable to the city of Fort Wayne in the sum of One thousand dollars ($1000.00) with sufficient surety to be approved by the said Board of Public works conditioned for a careful and faithful performance of all the terms and conditions of this agreement by said parties of the second part.

It being understood by the parties hereto that the Specifications for which bids were made are made a part and parcel of this contract as fully as if written herein at full length.

Witness our hands and seals this 10th day of January 1911

City of Fort Wayne By

Frank. J. Benoy.

Henry Helgeman

E. J. Lennon

Board of Public works

attest Martin Meltzer

Clerk

Thrasher & Herman

W. J. Thrasher.

Section 1: Be it ordained by the common council of the city of Fort Wayne Ind that the contract heretofore entered into on the 10th day of January 1911 by and between the city of Fort Wayne by and through its Board of Public works and Thrasher and Herman as fully set forth in the preamble hereto be and the same is in all things ratified and approved.

Section 2: That this ordinance be in full force and the effect on and after its passage and approval by the Mayor and legal publication

Allen Hamilton

Done at the council chamber in the city of Fort Wayne Ind this 28th day January 1911

We hereby Certify that the common council of the city of Fort Wayne Ind at a Special Meeting held on the 28th day of Jan 1911 by a Majority vote of all the members elect did pass the ordinance hereto attached and known as General Ordinance 468

Louis X. C. Schroeder

President

Wm. J. Jaffurs

City Clerk

Presented to the Mayor for approval on the 1st day of Feb 1911

Wm. J. Jaffurs

City Clerk

approved this 2d day of Feb 1911

Jesse Grice Mayor

General Ordinance no 469

An ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne and the Olds Coal Company. on the 10th day of January 1911 relative to the purchase by said City of Coal. which contract is in the following words.

This agreement made and entered into this 10th day of January 1911 by and between the City of Fort Wayne. by and through its Board of Public works. party of the first part and Noble G. Olds and Eugene H. Olds doing business under the firm name of the Olds Coal Company party of the second part. Witnesseth:

The party of the second part agrees to deliver to the party of the first part thirty (30) cars of Little Kate Hocking Run of mine to be delivered in approximate even quantities. Monthly. for which the party of the first part agrees to pay to the party of the second part one dollar ($1.00) per ton. F.O.B. Mines.

Said city to buy from said company all of the coal used by it at its City Crematory during said period of time so long as the kind. Quality and quantity is satisfactory to said Board of Public works and the same to be shipped and billed on flat bottom cars direct from the mines to said City at its said City Crematory on the L.S. & M.S. unless otherwise directed by the Board said City to pay all freight on all coal so purchased by it, and it is understood and agreed that the freight rate shall not exceed one dollar and thirty five cents ($1.35) but if lower freight rates can be obtained by the party of the second part. then said city shall pay no more than the actual freight rates so obtained if the rate is increased the city shall pay the same.

It is mutually agreed between the parties hereto that payments by the first party shall be made to second party on or before the 15th day of every month based upon invoice weights on all coal delivered as aforesaid during the month previous thereto. The strict performance of this contract by the party of the second part and the prompt deliveries of coal herein on cars at said mines as aforesaid shall be subject to delays occasioned by strikes. accidents and other unavoidable casualties in the operation of said Mines and want of car supply and failure of railway companies to deliver

and place cars at the mine for loading or other causes beyond the control of the said party of the second part.

It is further agreed between the parties hereto that after the delivery of said coal on Board of said cars by said party of the second part. said party at the request of the first party and as the agent of the party of the first part. will use its best endeavors with the carriers to have said cars of coal delivered as aforesaid. billed and sent forward promptly to destination.

The prices made in this contract are based upon the present mining rate and shall advance or decline during the period of this contract.

All freight rates over the above that mentioned in ~~this~~ contract shall be paid by party of the second part.

This contract shall not be binding or take effect until the second party shall execute to the party of the first part a bond in the sum of One Thousand dollars ($1000.00) with sufficient surety thereon to be approved by the Mayor and City controller of party of the first part and conditioned for the faithful performance by party of the second part of all terms. conditions and agreements herein to be performed by it. and until this contract has been ratified and approved by the common Council and said City.

Witness our hands and seals this 10th day of January 1911

City of Fort Wayne by.
Frank J. Benoy.
Henry Hilgeman
E. J. Lennon
Its Board of Public Works
Olds Coal Company.
N. G. Olds.

attest H. W. Becker clerk

Know all men by these presents that we Noble G. Olds and Eugene H. Olds doing business under the firm name of the Olds coal Company. Caroline M. Olds and Charles McCulloch surety. are held and firmly bound unto the City of Fort Wayne in the sum of One Thousand dollars ($1000.00) for the payment of which we Jointly and Severally bind ourselves. our heirs. executors administrators. Successors and assigns.

Witness our hands and seals this 10th day of January 1911

Whereas the above bound Olds Coal Company entered into a contract with the city of Fort Wayne on the 10th day of Jan 1911 to furnish to said city all the coal required by said city from the first day of January 1911 to the 31st day of December 1911 at its city crematory and provided in said contract that it would execute to said city a bond in the above named sum for the faithful performance by it of said contract.

Now therefore if the above bound the Olds Coal Company shall faithfully perform all the terms. conditions and agreements in said contract contained then this bond shall be void else to remain in full force and effect.

Olds Coal Company. by
N. G. Olds
Its Manager.

Approved
City of Fort Wayne by
Frank. J. Bruny.
Henry Hilgeman
E. J. Lennon
Its Board of Public works

Caroline M. Olds
Charles McCulloch.

Section 1. Be it ordained by the common council of the city of Fort Wayne Ind that the contract heretofore entered into on the 10th day of Jan 1911 by and between the city of Fort Wayne by and through its Board of Public works and the Olds Coal Company as fully set forth in the preamble hereto be and the same is hereby in all things ratified and approved

Section 2: That this ordinance be in full force and effect from and after its passage and approval by the Mayor

P. M. Braun

Done at the council chamber in the city of Fort Wayne Ind this 28th day of Jan 1911

We hereby certify that the common council of the city of Fort Wayne Ind at a special meeting held on the 28th day of Jan 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 469

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 1st day of Feb 1911

Wm. J. Jeffries
City Clerk

Approved this 2d day of Feb 1911

Jesse Grice Mayor

General Ordinance no 470

An ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne and J. F. Burbach doing business under the name of J. F. Burbach coal co. on the 12th day of December 1910 relative to the purchase by said city of coal.

Whereas Heretofore on the 12th day of December 1910 the city of Fort Wayne entered into a contract with Joseph F. Burbach doing business under the name of J. F. Burbach Coal co. providing for the purchase of Six Thousand tons of coal by said city which contract is in the following words:

This agreement. Made and entered into this 12th day of December 1910 by and between the city of Fort Wayne by and through its Board of Public works party of the first part. and Joseph F. Burbach. doing business under the name of the J. F. Burbach Coal co. of Fort Wayne Indiana party of the second part. Witnesseth:

That the party of the second part agrees and hereby binds itself. to sell and deliver to the city of Fort Wayne. Nine thousand (9000) or more tons of Hocking Nut Pea & Slack coal. as such quantity of coal thereof as may be required by said city for use at its Electric Light and Power plant. to be delivered in approximately even quantities monthly from the 1st day of Jan 1911 to the 31st day of December 1911 as the party of the first part may from time to time direct and in the manner hereinafter provided. In consideration of which the party of the first part agrees and hereby binds itself to pay to the party of the second part the sum of fifty seven cents (.57) for each ton of coal so sold and delivered to said city F.O.B. mines. In case during said year the quality of said coal or quantity thereof delivered is not in accordance with the terms and conditions of this contract then the city may discontinue the further purchase of any of such coal. All coal is to be shipped and billed direct from the mines to said city at its said Municipal Lighting Plant over the Lake Shore and Michigan Southern Railroad on dump cars. unless some other route is given by the Board of Public works. and it is hereby agreed that if said coal is shipped on flat bottom cars the party of the second part shall pay to the party of the first part damages sustained by said city by reason of the failure to ship such coal on said dump cars and it is agreed as liquidated damages that said party of the

second part shall pay to the said party of the first part the sum of five cents for each ton of coal that may be shipped to said city on such flat bottom cars instead of such dump cars Provided however that no liquidated damages for failure to furnish dump cars shall be paid during the months of may and June which provisions however does not in any way release the party of the second part from furnishing as many dump cars as possible during the aforesaid two months.

Said city to pay the freight on all coal so purchased by it but it is understood and agreed that the freight rate shall not exceed one dollar and thirty-five cents ($1.35) per ton and if lower rates can be obtained by the party of the second part then said city shall pay no more than the actual freight rate so obtained. All freight rates over and above one dollar and thirty five cents ($1.35) per ton shall be paid by the party of the second part unless the rate from the Hocking district is advanced in like manner in which event such advance in rate shall be paid by the party of the first part.

It is mutually agreed between the parties hereto that payments by the first party shall be made to second party on or before the 15th day of each month based upon invoice weights on all coal delivered as aforesaid during the month previous thereto. The strict performance of this contract by the party of the second part and the prompt deliveries of coal herein on cars at said mines as aforesaid shall be subject to delays occasioned by strikes accidents or other unavoidable temporary or permanent casualties in operation of said mines want of car supply. failure of railway companies to deliver and place cars at mines for loading or other causes beyond the control of said party of the second part.

It being understood by the parties hereto if the coal on board the cars has been screened through a screen set smaller than one and one fourth (1¼) inch the Board of Public works will have the right and privilege to refuse to accept such coal and the same will be considered as rejected by the giving of notice by said Board of Public works to said party of its refusal to accept

It is further agreed between the parties hereto that after the delivery of said coal on board cars by said party of

the second part. said party as the agent of the party of the first part shall use its best endeavors with carriers to have said cars billed and sent forward promptly to destination.
The prices made in the contract are based upon the present mining rate and shall advance or decline as said rate of mining may advance or decline during the period of this contract.
It is agreed by the party of the second part that in the event that it becomes desirious on the part of the party of the first part to institute any suit against the party of the second part or the sureties on its bond hereinafter mentioned, or either of them. for damages growing out of any breach of any of the provisions of this contract for said bond or either of them on the part of the party of the second part or said Sureties on its said bond. that such suit shall be brought in the Circuit or Superior Courts of the County of Allen. in the State of Indiana and no question shall be raised by the party of the second part or the sureties on the bond as to the Jurisdiction of either of said courts over the persons of the party of the second part or its sureties on said bond or any of them and said pairty of the second part hereby agrees that either of said courts shall assume Jurisdiction over the persons of the party of the second part and the sureties on this said bond.
This contract shall not be binding until the second party shall execute to the party of the first part. a bond in the sum of Five thousand dollars ($5000.00) with sufficient surety company security thereon to be approved by the Mayor and City Controller for the party of the first part and conditioned for the faithful performance by the party of the second part of all the terms conditions and agreements herein contained to be performed by said party of the second part and providing that the party of the second part and the sureties shall consent to the Jurisdiction over their persons of the circuit or Superior Courts of said county of allen in any suit instituted on such bond. Nor shall this contract be binding upon the party of the first part until it has been ratified and approved by the common council of said city.
Witness our hand and seals this 12th day of December 1910

Frank J. Bunoy
Henry Hilgeman
E. J. Lennon
its Board of Public works
J. F Burbach Coal co by.
Joseph. F. Burbach

attest H. W. Becker
Clerk

Know all men by these presents. That Joseph. F. Burbach doing business under the name of J. F. Burbach Coal co. as principle and United States & Guaranty co as surety are held and firmly bound unto the City of Fort Wayne Ind in the full and just sum of Five thousand dollars ($5000.00) lawful money of the United States. for the payment of which well and truly to be made the said principal binds themselves their heirs. executors and administrators and the said surety binds itself. its successors and assigns jointly and severally by these presents.

Witness our hands and seal the 7th day of January 1911

Whereas on the 12th day of December 1910 the above bound Joseph. F. Burbach doing business under the name of J. F Burbach coal co executed and entered into a certain contract with the City of Fort Wayne by and through its Board of Public works to sell and deliver to the said City Six thousand tons or more of Hocking Nut pea. and Slack coal or such quantity thereof as may be required for the use at the Electric Light & Power Plant to be delivered in approximately even quantities Monthly from the 1st day of January 1911 to the 31st day of December 1911 as said city may from time to time direct.

And Whereas in said contract it was provided that said Burbach should execute and deliver to said City a bond conditioned for the faithful performance by them of said contract and for the payment or forfeiture of other sums of money required to be paid by them for any violation of said contract.

Now therefore the conditions of this obligation is such that if the said Joseph. F. Burbach shall well and truly perform and fullfill all and every Covenant. Condition Stipulation and agreement in said Contract Mentioned to be performed and fullfilled by them and shall pay said city all sums of money that may come due to it under the provisions of said contract and shall pay to

said city any damages or other sums of money that may accrue to said city by reason of any failure on their part to perform the covenants. conditions. stipulations and agreements contained in said contract. or to comply with all of its provisions then this obligations shall be void: otherwise the same shall remain in full force and effect.

It is however mutually understood between the parties that in no event shall said surety be liable for a greater sum then the penalty of this bond

J. F Burbach Coal co by.
Joseph H Burbach

approved the 10th day of Jan 1911

Frank. J. Benoy
Henry Hilgemann
E. J. Lennon
Its Board of Public works

The United States fidelity and guaranty company.
of Baltimore Maryland
Ronald. a. Foster

State of Indiana }
Marion County } SS

Before me a Notary Public in and for said county and state personally appeared Ronald. A. Foster who being by me duly sworn upon his oath did dispose and say he is the attorney-in-fact of the said United States fidelity and Guaranty company of Baltimore Maryland: That he knows the corporate seal thereof and that the seal affixed to the within bond is such seal: That the said Ronald a Foster signed the bond as attorney in fact of said company in accordance with a resolution passed at a meeting called and held by the Board of Directors of the said United States fidelity and guaranty company at its Home Office in Baltimore Maryland under date of February the 29th 1904. Witness my hand and notarial seal the 7th day of June 1911

Mary Gray
Notary Public

my commission expires Jan 1st 1912

Section 1: Be it ordained by the common council of the city of Fort Wayne Ind That the contract heretofore on the 12th day of December 1910 entered into by and between the city of Fort Wayne by and through its Board of

Public works and Joseph F. Burbuck. doing business under the name of J. F. Burbuck Coal Co, as fully set forth in the preamble hereto be and the same is hereby in all things ratified and approved.

Section 2: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor

P. M. Braun

Done at the council chamber in the city of Fort Wayne Ind this 28th day of Jan 1911

We hereby certify. That the common council of the city of Fort Wayne Indiana. at a Special Meeting held on the 28th day of January 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 470

Louis S. C. Schrader
President

Wm J. Jefferies
City Clerk

Presented to the Mayor for approval on the 1st day of February 1911

Wm J. Jefferies
City Clerk

approved this 2d day of Feb 1911

Jesse Grice
Mayor

General Ordinance no 471

An ordinance approving and ratifying a contract Entered into on the 12th day of January 1911 by and between the city of Fort Wayne and David M. Winburn providing for the removal of Garbage

Section 1. Whereas. heretofore on the 12th day of Jan 1911 the city of Fort Wayne by and through its Board of Public works entered into a contract with David M. Winburn for the removal of kitchen garbage and other matter during the year 1911 which contract is as follows.

This agreement made this 12th day of January 1911 by and between the city of Fort Wayne by and through its Board of Public works party of the first part and David M. Winburn of the city of Fort Wayne Indiana party of the second part Witnesseth:

That for and in consideration hereinafter expressed. that the party of the second part shall and hereby agrees to collect and remove all kitchen garbage. tin cans. broken dishes and glassware during the year 1911 from the territory described in districts Nos one. two. three. four. five. six and Seven (1-2-3-4-5-6-7) referred to and mentioned in the official Specifications adopted by said board for the removal of such garbage. which Specifications are on file in the office of said board and are for identification Signed by. the parties hereto: Such Kitchen garbage tin cans. broken dishes and glassware to be collected and removed in accordance with and as provided by such specifications above referred to which are hereby made a part of this contract and all the conditions. terms and provisions of said Specifications shall be complied with and performed by the parties hereto. the same as if such specifications and provisions thereof were set forth in full in the body of this contract.

In consideration of the covenants and agreements herein expressed the party of the first part agrees to pay to the party of the second part the sum of six thousand eight hundred and fifty dollars ($6.850.00) said sum to be paid in equal monthly installments at the end of each month. and for the work performed under the contract during such Month less such deductions as the said Board of Public works may be authorized to make under said Specifications or this contract.

It is further agreed by the parties hereto that this contract

shall not be by party of second part assigned in whole or in part without the written consent of said Board of Public works and the second party shall and hereby agrees to furnish a bond in the sum of thirty five hundred dollars ($3.500.00) to be approved by the Board of Public works conditioned that he will faithfully comply with and carry out the terms and stipulations of his part to be performed contained in this contract and said Specification

It being understood that the party of the second part and his drivers and employees will while in the execution of the within contract obey and conform to all said ordinances and for any violations of the same the second party will be liable on his bond for the payment of any penalties that may be found against him or his employees. It being also understood that the party of the second part will see to it that the tops of the wagons used by him in carrying garbage shall be covered at all times while the same are passing through the streets and shall at no time be so loaded that the cover cannot be closed. It is further understood that he will see to it that his employees and drivers will report to the Board of Health all places where proper receptacles for the holding of garbage and not provided or any other violations of any other city ordinances relating to the manner in which garbage shall be kept by the house holder. for which purpose each employee of said second party shall be supplied by party of second part with a book containing blank slips or notices on which shall be placed the name and address of the offender and the same turned in to the Superintendent of the Crematory and in turn by him delivered to the Board of Health.

It is also understood that said second party will file with the Board of Public works a routing showing the said points. the way and detail in which the route is covered by the driver so that the driver of any garbage wagon can be found practically at any time by consulting the route sheet: Second party agreeing not to make any change in such route until the same is approved by the Board of Public works for any failure to file said routing. or to follow the same or for Making any changes therein without first receiving permission from the Board of Public works or for failing to collect garbage properly as herein provided said second party agrees that he shall pay to the party of the first part as liquidated damages the sum of One dollar

for each and every failure or violation of said provisions

It being also further understood that said second party shall at all times keep working and in operation not less than 7 wagons or as many more as may be necessary.

Witness our hands and seals the day and year first above written

City of Fort Wayne by.
Frank. J. Benoy
Henry Helgeman
E. J. Lennon
Its Board of Public works
David-M. Winburn

attest H. W. Zecker
Clerk

Section 2: Be it ordained by the common council of the city of Fort Wayne Ind. That the contract entered into on the 12th day of January 1911. by and between the city of Fort Wayne by and through its Board of Public works. and David-M. Winburn providing for the removal of all kitchen garbage from said City as fully set forth in the preamble hereto be and the same is hereby approved. ratified and Confirmed.

Section 3: That this ordinance be in full force and take effect from and after its passage and approval by the Mayor.

P. M. Braun

Done at the council chamber in the city of Fort Wayne Ind this 14th day of Feb-1911

We hereby Certify that the Common Council of the City of Fort Wayne Ind at a Regular Meeting held on the 14th day of Feb 1911 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as

General Ordinance no 471

Louis S. C. Schroeder
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval on the 17th day of Feb-1911

Wm. S. Jefferis
City Clerk

approved this 17th day Feb-1911

Jesse Grice
Mayor.

General Ordinance no 472

An ordinance regulating the use of automobiles and motor Vehicles upon the streets. alleys and public highways of the city of Fort Wayne Ind. and providing penalties for the Violations thereof and repealing General Ordinance no 448 and fixing a time when the same shall take effect.

Section 1: Be it ordained by the common council of the city of Fort Wayne Ind. That it shall be unlawful for any person firm or corporation to leave standing in a public street alley or highway within the limits of the city of Fort Wayne from one-half hour after sunset to one-half hour before Sunrise. any automobile. Motor Vehicle or other conveyance. carriage. Wagon. engine or machine. the motor power of which shall be electricity. Steam. Gasoline. or any source of energy other than human or animal power. unless there shall be kept burning on the front of said Vehicle at least one white light visible for a distance of not less than two hundred feet. and on the rear on said Vehicle at least one red light visible for a distance of not less than two hundred feet.

Section 2: No person driver or operator. in charge of any automobile or motor vehicle or carriage described in Section 1 of this ordinance shall permit the Machinery of said Vehicle to run while such vehicle is standing in any Street. alley or public Highway within said city without an attendant for a longer period of time than five minutes at any one time

Section 3: No person. firm or corporation shall use upon the Streets. alleys or public highways of the city of Fort Wayne any automobile. Motor vehicle. or other conveyance. Carriage wagon. engine or Machine. the motor power of which shall be Steam. gas. or gasoline. or any like source of energy unless such vehicle shall be equipped with a Sufficient Modern and improved Muffler to prevent noise from the exhaust of the engine or engines of such Vehicle and said Muffler shall be kept and remain closed by the person operating or in charge of such Vehicle at all times when such Vehicle is in Motion.

Section 4: No person under Seventeen years of age shall operate upon the streets or public Highways of the city of Fort Wayne Ind any automobile. Motor Vehicle carriage

Wagon. engine or machine or other conveyance the motor power of which shall be electricity. Steam gasoline. or any source of energy other than human or animal power.
Section 5: Any person firm or corporation violating any of the provisions of this ordinance shall. upon conviction. be fined not less than one ($1.00) dollar or more than one hundred ($100.00) dollars to which may be added imprisonment not to exceed six months in the Allen county jail. and upon a second conviction for such offense said person firm or corporation shall be fined not less than twenty-five ($25.00) dollars. to which may be added imprisonment not to exceed six months in the allen county jail and upon a third conviction for such offense said person firm or corporation shall be fined not less than fifty ($50.00) dollars to which shall be added imprisonment for a period of not less than thirty days in the allen County jail
Section 6: That general Ordinance no 448 be and the same is hereby repealed.
Section 7: That this ordinance shall be in full force and effect on and after its passage approval by the Mayor and legal publication

H. W. Fellger.

Done at the council chamber in the city of Fort Wayne Ind this 14th day of ~~Jan~~ Feb 1911

We hereby Certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 14th day of Feb 1911 by a Majority vote of all the Members elect did pass ~~the~~ ordinance hereunto attached and known as
General Ordinance no 472

Louis B. & Schroeder
President

Wm. S. Jeffries
City Clerk.

Presented to the Mayor for approval on the 17th day of ~~February~~ 1911

Wm. S. Jeffries
City Clerk

Approved this 17th day of ~~January~~ February 1911

Jesse Grice
Mayor.

General Ordinance no 473

An Ordinance authorizing the employment of certain Officers and employees of the Fire Department of the City of Fort Wayne and fixing their salaries.

Section 1: Be it ordained by the Common Council of the City of Fort Wayne Ind. that the officers and employes of the Fire Department of the City of Fort Wayne Ind shall receive the salaries as hereinafter in this ordinance provided for. The employment of such officers and employes as hereinafter named are hereby authorized and the salaries of such officers and employes are hereby fixed at the sums and amounts respectfully named for such officer and employe.

Each Telephone operator of the Fire Department shall receive a Salary at the rate of seven hundred eighty dollars ($780.00) per annum

Section 2: That all parts of ordinances in conflict herewith be and they are hereby repealed.

Section 3: That this ordinance be in full force and effect on and after its passage and approval by the Mayor and legal publication.

Charles W. Dittoe

Done at the Council Chamber in the city of Fort Wayne Ind this 28th Day of February 1911

We hereby Certify that the Common Council of the city of Fort Wayne Indiana at a Regular meeting held on the 28th day of February 1911 by a Majority vote of all the members elected did pass the ordinance hereunto attached and known as General Ordinance no 473

Louis S. & Schroeder
Prusident

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 3d day of March 1911

Wm. J. Jeffries
City Clerk

Approved this 6th day of March 1911

Jesse Grice
Mayor.

General Ordinance no 474

An ordinance Ratifying and Approving the Contract between the City of Fort Wayne Indiana. And Tripper and Son of Peru Indiana Relative to work to be done for the City at Broadway Street under Track Elevation Resolution no 2.

Whereas. Heretofore on the 12th day of May 1910 the City of Fort Wayne by and through its Board of Public works entered into a Contract with Tripper & Son relative to work to be done under Track Elevation Resolution no 2 which contract is as follows

This agreement. Made and entered into this 12th day of May 1910 by and between the city of Fort Wayne by and through its Board of Public works. party of the first part for convenience hereinafter refered to as the "Board" and Benjamin Tripper and Allen. G. Tripper. partners doing business under the firm name of Tripper & Son of Peru Indiana party of the second part. for convenience hereinafter called the "Contractor. Witnesseth

That for and in consideration of the payment by the said Board to the said contractor of the prices. per item hereinafter set out and refered to the said Contractor agrees and binds itself to furnish all the portion and Share of work to be done by said Board at Broadway Street in the City of Fort Wayne Indiana. as provided for in Track Elevation Resolution number Two (2) and certain resolutions heretofore passed by the said Board for changing the grade at Broadway Street and certain other Streets and as set out in the plans and specifications made in relation thereto which are hereinafter made a part of this contract. all under and by virtue of an act of the General Assembly of the State of Indiana. entitled "an act providing for the changing of the grades of Streets and highways in cities having a population of not less than forty three thousand nor more than forty nine thousand, etc. approved March 12. 1907 and also an act of the General Asembly of the State of Indiana entitled "an act concerning municipal Corporations approved March 6. 1905 and all acts supplementary and amendatory to the aforesaid acts.

The Contractor hereby expressly agrees to perform all work in the prosecution of the above described improvement according to the terms and conditions of this contract and the plans. estimates. profiles specifications and

bids submitted by said Contractor on said work to the entire satisfaction of the said Board. which said plans. estimates profiles. Specifications and bids are hereby made a part of this contract as fully and effectually as if copied herein at full length. all of which for the purpose of identification and making them a part of this contract. are signed by the parties hereto as of even date herewith. and if there be any conflict between the prices set out in the aforesaid bids and as set out in this contract then the latter is to control.

The work to be performed by the said Contractor under this contract consists of brick pavement. excavation. concrete retaining walls. cement sidewalks. resetting of curbing where necessary. laying water mains and services. laying sewers and all necessary connections man holes and catch basins and other work. all of which is more specifically described and set out in the plans and specification which work is to be performed by the contractor for the following prices.

Street excavation per cubic yard fifty cents (.50). Wall excavation per cubic yard fifty cents (.60) Concrete in place per cubic yard five dollars and fifty cents ($5.50) street paving per square yard two dollars and twenty five cents ($2.25). Sidewalk paving per square foot thirteen cents (.13) resetting curbing. per lineal foot ten cents (.10) New curbing (5"x12") per lineal foot fifty cents (.50) Standard W.I. Pipe Railing in place. per lineal foot. one dollar($1.00). New Water pipe size 12". per lineal foot two dollars ($2.00) relaying water pipe. size per lineal foot thirty cents (.30) removing and resetting fire hydrants each five dollars ($5.00) new water service 6" size each one dollar($1.00) per foot V.C.P. Sewer 12" size per lineal foot. one dollar($1.00) per foot. New Manholes. each forty five dollars ($45.00). repairing Manholes each ten dollars ($10.00). New catch basins 4'x 7'. each forty five dollars ($45.00) house connections. each fifty cents per foot (.50). New water service size 4", each ninty cents per foot (.90) New water service size 3/4" each fifty cents per foot (.50)

It is further understood and agreed that the Contractor is to commence said work not later than twenty (20) days after being notified to commence by said Board. said notice to be given only when the elevation of the tracks is

so advanced that the contractor can actually and practically begin work, and he further covenants and agrees to complete said work within three (3) months after the commencement of same and in event said Contractor fails to begin said work within said time or to finish said work within said time or fails at that time or any time thereafter to furnish a sufficient number of skilled workman or adequate equipment to properly push and finish said work, then the Board may, at its option, consider said contract void and relet said work or use the materials, tools and equipment of the Contractor in the use of said work, and finish the work itself and deduct from any money that might be due the Contractor a sufficient sum to cover the expenditures made by said Board in the performance of said work. It being understood that any extension of time for the commencement or completion of the work is not in any way to effect this contract or release the sureties on any bond given by the Contractor to said Board, nor will it be necessary to give notice of any extension to said sureties.

It is hereby agreed that no assignment of this contract shall be made without the written consent of the said Board, and any assignment in violation of this provision will be absolutely void.

The Board reserves the right to alter or change any detail in the materials or method of construction which will not materially increase or decrease the cost of the work without any additional compensation to the Contractor.

More important changes or alterations may be made by the Board should the exigency arise and become apparent during the progress of the work through faulty design as provided by the plans and specifications or by reason of obstructions met with which could not reasonably have been foreseen before the work was begun. Notwithstanding such changes or alterations may materially increase or decrease the cost of the work; but the Contractor shall not proceed with such changes or alterations without a written order from the Board the price agreed upon to be added to or deducted from the contract price being stated in the order. In case the Board and

Contractor cannot agree as to the price is shall be taken as the estimated actual cost plus fifteen per cent (15%) as determined by the engineer. No claim whatever shall be allowed for extra materials or labor furnished unless the same shall have been ordered in writing. It is expressly agreed and understood that any alterations or changes made shall not in any way violate or annul the contract or affect and bond hereafter given by the Contractor or release his sureties therein. Any claim for damages or for any other Matter or cause must be made in writing to the Board at the time the alleged damage occurs or the cause for the claim arises and, unless such claim is so presented it shall be held that the Contractor has waived such claim and it shall not be entitled to receive pay for the same.

It is agreed that, in event the work to be performed under the contract is for any reason not commenced or discontinued after commencement, the contractor will not be entitled to any damage for any loss he might be put thereto by reason thereof and he hereby waives and releases the City from any claim that he might have against it for any such failure to begin or discontinuation of said work, except he will be entitled to payment for the estimated value of work performed.

It is understood that all the materials and workmanship of whatever description shall be subject to the inspection and rejection of the engineer and the contractor shall recognize any assistant or inspector that the Board may appoint, under the direction of the engineer, to inspect the materials furnished or labor performed. Such inspection by the said Board however, is not to be considered in any sense as such an acceptance of the work that the Contractor might demand his money for the same.

It is further agreed by and between the parties that the acceptance of the work provided for in this Contract, or the payment therefor shall not constitute a waiver on the part of the city of any of the provisions of the contract plans and specifications, nor shall is release said contractor or his sureties upon their bond for the faithful performance or guarantee thereof, nor shall the final acceptance of the work

be even prima facie evidence of the performance of any of the provisions of this contract. except to the extent of entitling said Contractor to receive the prices therefor and then only shall such acceptance and payment be considered prima facie evidence:
payment to be made within twenty (20) days after the performance of all conditions of the contract and acceptance and approval of the work by the Board,
The Contractor further contracts and agrees that in the prosecution of said work it will comply in all things with all the requirements of said plans specifications and resolutions. and that all proper skill and care will be exercised to avoid accidents. that is will properly and fully guard all excavations and dangerous places and will use all due and proper precautions to prevent injury to any property. person or persons what or whomsoever.
That for and during the period of the making of such improvement and the period for which the same is to be maintained and kept in repair by the Contractor. The City of Fort Wayne shall be saved harmless from any and all liabilities whatsoever growing out of any injury or damage to property or persons because of any neglect or failure of the Contractor to comply with any of the provisions herein contained including the guarantee provisions. and to pay any and all judgments with costs which may be obtained against said City growing out of any such aforesaid injuries or damages. or from any damage or injury resulting to any person or building by reason of excavation near buildings or by removal of any lateral support.
It is further agreed in addition to all the conditions of said Specifications relative to the guarantee and Maintenance of said work that the work shall be done in a substantial manner as to material and workmanship so that no repairs will be needed or required for a period of five (5) years: but should repairs become necessary during said period then the Contractor shall without any additional compensation make good such repairs and any settlement of pavement. any derangement of the alignment and grades of the curbing or castings

any cracking or crumbling of the concrete or concrete walls or any defective sewer or water connections which may occur or appear during said period. The guarantee of the pavement concrete walls. concrete work. cement work and all other work and the guarantee to repair is to cover all defects growing out of any imperfection or unsuitability of materials or composition of materials used. defects of construction all defects of workmanship. extremes of temperature and all other effects of climate. and shall cover all other deteriorations of the improvements. such as holes cracks crumbling. chipping or settlement of or in the walls pavement sidewalk or any other part of the work and all defects resulting from the decomposition of the wearing surface that may appear in the improvement within the said five (5) years and within the entire guarantee period as here and in the specifications more fully provided

The Contractor agrees that within ten (10) days after being awarded the contract it will execute to the city of Fort Wayne two (2) Bonds to be fixed by the Board of Public works. one conditioned that is will faithfully comply with all the provisions of the contract except the warranty and guarantee of the work and improvement as to the workmanship. Materials and condition for the period of five (5) years and the other conditioned that it will faithfully perform and fulfill all the requirements of the warranty and guarantee contained in said contract and will make all repairs required under such guarantee and in the manner provided for in the contract. each of said bonds to be signed by a recognized surety company authorized to sign instruments and authorized to do business in the state of Indiana.

The contractor further agrees to pay any and all moneys due to any contractor or any person or persons furnishing any Material whatever and to pay all laborers employed for any work done for the contractor or any other person in the prosecution of said improvement and the contractor and his sureties on his liability bond shall be jointly and severally liable on such bond to such contractor. Material Men and laborer for any moneys due or becoming due to them or either of them. The Board reserving the right in event any lien or claim

is filed or that any work or material remains unpaid them to hold from the sum due and owing the contractor a sum sufficient to pay any and all such claims.
The Board to refuse payment to said contractor until is has been Salisfactorily and suffucintly assured that all such liens and claims have been paid. The decision of the Board as to the sufficiency of the proof offered as to the payment of said claim or liens is to be final and binding.

The Contractor further agrees to waive any right to have issued to him monthly estimates of work and certificates of fifty five per cent (65%) of the amount shown by such estimates and shall receive no compensation from said city for the performance of said work until after the completion thereof and the performance of all the conditions hereinbefore and hereafter set out and the acceptance of the work by the Board.
To each of the aforsaid conditions and stipulations of this contract the undersigned bind themselves. their successors and assigns

In witness whereof We the foregoing named parties hereunto set our hands and seals this 12th day of May 1910.

City of Fort Wayne by
Frank-J. Benoy
Henry H Eigeman
E. J. Lennon
Its Board of Public works

attest H. W Becker
Clerk

Trippeer and son by
A. G. Trippeer

Fort Wayne Ind March 16-1910

To the Board of Public works of the City of Fort Wayne Ind

Gentlemen. The undersigned propose to furnish all material. tools. labor and appliances necessary to complete in a first class workmanship manner the city portion of the work as designed including any and all work and material that may be necessary to connect the improvement made with the adjoining roadway and sidewalk improvements and in accordance with the drawings and specipications on file in the Office of the Department of Public works of said City and in conformity with the terms of Rail Road Track elevation Resolution no 2-1909

for Broadway and according to the laws ordinances and regulations of said city and under the direction and to the entire satisfaction of the Board of Public works at and for the following price per each item. The undersigned waives the right to have issued to him monthly estimate of work and certificate of 65 per cent of amount shown by such estimate.

See estimate sheet for Quantities	Price written in words here	Figures here Dollars	cents
Street excavation per cubic yd	Fifty cents		50
Wall " " " "	Sixty cents		60
Concrete in place " " "	Five dollars and Fifty cents	5	50
Street paveing " Sq "	Two dollars and Twenty five cts	2	25
Sidewalk Paving " " ft	Thirteen cents		13
Resetting Curbing " Lineal "	Ten cents		10
New Curbing 5"x22" " Lineal "	Fifty cents		50
Standard W I Pipe " " " Railing in Place	One dollar	1	00
New Water pipe Size 12" " " "	Two dollars	2	00
Relaying water pipe Size " "	Thirty cents		30
Removing and Resetting Fire Hydrants each	Five dollars	5	00
New Water Service 6" Size each	One dollar per ft.	1	00
V.C.P. Sewer 12" Size Per lineal ft.	One dollar per ft.	1	00
New Manholes. each.	Forty five dollars	45	00
Repairing manholes each	Ten dollars	10	00
New catch Basins 4'x7' each	Forty five dollars	45	00
House connections each	Fifty cents		50
New water service Size 4" each	Ninty cents per ft.		90
" " " " 5/8" " "	Fifty cents per ft.		50

Enclosed find certified check to the amount of $1200.00

Tripper and Son
Contractor by A. G. Tripper
Peru Indiana

Errors or diffrences between written prices and figures will be considered intentional and proposal rejected as informal a failure to endorse certified check as provided for in legal advertisement of "Notice to Contractors" will result in the rejection of the bid. Bids will be rejected for a failure to make an affidavit in accordance with section 65 chapter CIV. acts of 1899. The striking out of any of the provisions of this form of making any interlineations or erasures without consent of the Board of Public works being first obtained will result in the rejection of the proposal as informal

All bids must have been delivered to the clerk of the Board of Public works by 2:00 Oclock March 16-1910 as no bids will be accepted after that hour. Fort Wayne Ind Aug 31st 1910

Received the inclosed check of $1200.00

Tripper & son

A. G. Tripper

Section 1: Be it ordained by the common Council of the City of Fort Wayne that the contract heretofore on the 12th day of May 1910 entered into by and between the city of Fort Wayne Ind by and through its Board of Public works and Tripper & son as fully set forth in the preamble be and the same is in all things ratified and approved

Section 2: This ordinance to be in full force and effect from and after its passage and approval by the Mayor

Charles W. Slattery

Done at the Council Chamber in the city of Fort Wayne Ind this 14th day of March 1911

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 14th day of March 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 474

Louis A. W. Schroder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 17th day of March 1911

Wm. J. Jeffries
City Clerk

approved this 17th day of March 1911

Jessie Grice
Mayor

General Ordinance no 475

An ordinance Ratifying and approving the Contract between the City of Fort Wayne Indiana and Tripper and son of Peru Indiana Relative to work to be done for the city at Fairfield avenue under Track elevation Resolution no 1

Whereas Heretofore on the 12th day of may 1910 the City of Fort Wayne by and through its Board of Public works entered into a contract with Tripper and son relative to work to be done under Track Elevation Resolution no 1

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that the contract heretofore on the 12th day of May 1910 entered into by and between the city of Fort Wayne Indiana by and through its Board of Public works and Tripper and son. as fully set forth in the preamble. be and the same is in all things ratified and approved

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor

Charles W. Zollner

Done at the Council chamber in the city of Fort Wayne this 14th day of March 1911.

We hereby certify that the common council of the City of Fort Wayne did at a Regular meeting held on the 14th day of March 1911. by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 475

Luis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 17th day of March 1911

Wm. J. Jeffries
City Clerk

Approved this 17th day of March 1911

Jesse Grice
Mayor

General Ordinance no 476

An ordinance authorizing the alienation of certain personal property and ordering an appraisement of Same.

Section 1: Be it ordained by the Common Council of the City of Fort Wayne Ind. That the Mayor be and he is hereby authorized to sell the cart team of horses named Gip and Luke age 14 years used at no 1 Engine House: Engine team named Jack and Sam. age 8 years. Used at no 1 Engine House: One Gray horse 15 years old. named Bill at no 5 Engine House: and one Gray horse. named Gip age five years and crippled at no 7 engine house. also two horses belonging to the Water Works Department: one black and bay horse. age eight years: and to sign any and all necessary instruments to consumate such Sale: provided that such Sale shall not be made until said property has been appraised by appraisers appointed by the Judge of the Allen circuit court.

Section 2: That the city attorney be and he is hereby authorized to petetion the Judge of the Allen circuit court for the appointment of three appraisers to appraise the property referred to in section 1 of the ordinance.

Section 3: That this ordinance shall be in full force and effect from and after its passage and approval by the Mayor

Charles W. Lettick

Done at the council chamber in the city of Fort Wayne this 28th day of March 1911

We hereby certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 28th day of March 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 476

Louis C. G. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 1st day of April 1911

Wm. J. Jeffries
City Clerk

Approved this 3d day of April 1911

Jesse Grice Mayor.

General Ordinance no 477

An ordinance fixing the amount of the bond to be given by the Treasurer of allen County to the city of Fort Wayne Indiana

Section 1: Whereas. under the Cities and Town act of the Statues of Indiana. the Treasurer of allen county becomes the acting Treasurer of the City of Fort Wayne: and
Whereas. the County Treasurer of the state of Indiana now deposit moneys in banks according to the depository law: and
Whereas when the amount of the bond of the County Treasurer affecting the city was heretofore fixed the said depository law was not in force;
Now therefore. Be it ordained by the common council of the city of Fort Wayne. that the amount of the bond to be given by Herman Benter. to the city of Fort Wayne Indiana. as County Treasure elect of allen County Indiana be fixed at Two Hundred and fifty Thousand dollars. and which amount is more than one-half of the estimated amount of all taxes. including delinquents. to be levied and collected from municipal purposes in the city of Fort Wayne for the current year.
Section 2: All ordinances or parts of ordinances in conflict therewith are hereby repealed

J. J. Lauer

Done at the council chamber in the city of Fort Wayne Indiana this 28th day of March 1911
We hereby certify That the common council of the city of Fort Wayne Ind at a Regular meeting held on the 28th day of march 1911 by a majority vote of all the members elect did pass the Ordinance hereunto attached an known as
General Ordinance no 477
Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 1st day of april 1911

Wm. J. Jeffries
City Clerk

approved this 3d day of april 1911

Jesse Grice
Mayor

General Ordinance No #78

An Ordinance authorizing the Board of Safety to hire additional Police Officer.

Section 1: Be it ordained by the Common Council of the City of Fort Wayne Ind that the Board of Public Safety is hereby authorized to hire an additional Police Officer provided that he is paid out of funds already appropriated to the Police Force Pay Roll account.

Section 2: This ordinance to be in full force and effect from and after its passage and approval by the Mayor.

Harry G. Pennegar

Done at the Council Chamber in the City of Fort Wayne Ind this 28th day of March 1911

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 28th day of March 1911 by a Majority vote of all Members elect did pass the ordinance hereunto attached and known as General Ordinance no #78

Louis A. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 1st day of April 1911.

Wm S. Jefferies
City Clerk

approved this 3d day of April 1911

Jesse Grice
Mayor

General Ordinance no 479

An Ordinance Ratifying and approving a contract by and between the City of Fort Wayne Indiana and the United States Cast iron pipe & Foundry company of Chicago Illinois relative to cast iron pipe for the Water Works Department.

Whereas on the 25th day of March 1911 the City of Fort Wayne by and through its Board of Public works entered into a contract with the United. States cast iron pipe and Foundry company, which contract is in the following words

Section 1: Be it ordained by the Common council of the City of Fort Wayne that a contract heretofor entered the 25th day of March 1911 by and between the city of Fort Wayne by and through its Board of Public works and the United States Cast iron pipe and Foundry company as fully set forth in the preamble be and the same is in all things ratified and approved.

Section 2: That this ordinance be in full force and effect from and after its passage and approval by the mayor.

P. M. Brunn.

Came at the council chamber in the City of Fort Wayne Ind this 28th day of March 1911

We hereby Certify That the common council of the city of Fort Wayne Indiana at a Regular Meeting held on the 28th day of March 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 479

Louis S. G. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 1st day of April 1911

Wm. J. Jeffries
City Clerk

Approved this 3d day of April 1911

Josse Grice
Mayor

General Ordinance no 480

An ordinance amending Section 1 Chapter 4 of an ordinance entitled "an ordinance providing for all Matters concerning. affecting or relating to the construction equipment alteration. repair or removal of buildings Structures and appurtenances thereof. erected or to be erected in the City of Fort Wayne Indiana. as amended May 25th 1909 the same to be known and cited as the "Building code" adopted May 25th 1909 and being General ordinance no 390. as amended april 11-1909.

Section 1: Be it ordained by the Common Council of the City of Fort Wayne. That section 1 of said ordinance be and the same is hereby amended to read as follows: Section 1. The fire limits are and shall be that territory in the City of Fort Wayne. contained within the boundary limits described as follows. Beginning at the intersection of Superior Street and the east line of County addition thence south along the east line of County addition to Columbia Street. thence east on Columbia Street to Clay Street thence South on clay Street to Old Fort place. thence west on old Fort Place to Lafayette Street. thence South on Lafayette Street to Murray Street. thence west on murray Street to Calhoun Street thence north on Calhoun Street to the first alley South of Grand Street. thence west along the first alley South of Grand Street to Webster Street. thence north on Webster Street and Webster Street produced north across the lands of the Wabash Railway Company and the Pittsburg. Fort Wayne and Chicago Railway Company to Webster Street on the north side of said Pittsburg. Fort Wayne and Chicago Railway Company. thence north on Webster Street to the St. Marys River. thence in a straight line crossing the St. Mary river to the first alley west of Wells Street and North along said alley to Fairmount place thence east on Fairmount place to Wells Street. thence North on Wells Street to the South line of Lot no. 57 North side addition. thence east on the South line of Lots numbered 57-58-and 61 North side addition to the alley east of Cass Street. thence north in the alley east of Cass Street to the north line of First Street thence east on the North line of First Street to the west line of Lot no 57 North side addition. thence North on the west line of said Lot no 57 to the South line of the alley

north of First Street. thence east on the south line of said alley and the South line of said alley produced east to the east line of the right of way of the railway operated by the Lake Shore and Michigan Southern Railway Company. thence Southwest following said right of way line to Cass Street. thence South on Cass Street to Wells Street: thence Southeasterly on Wells Street to Superior Street. thence east on Superior Street to the place of beginning.

Section 2: That the ordinance shall be in full force and effect on and after its passage. approval by the Mayor and legal publication

Charles E Wedekind

Done at the Council Chamber in the City of Fort Wayne Indiana this 11th day of April 19

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 11th day of April 1911 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known a General Ordinance no 480

Louis S. C. Schroeder
President

Wm J. Jefferies
City Clerk

Presented to the Mayor for approval on the 15th day of April 1911

Wm J. Jefferies
City Clerk

approved this 17th day of April 1911

Jesse Grice
Mayor

General Ordinance No 481

An ordinance amending Section 12 of Chapter 25 of General ordinance No 390 known as the Building code

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that section 12 of Chapter 25 of General ordinance No 390 known as the Building Code shall be changed to read as follows: Section 12. all tanks used for storage of gasoline or other oils now located on side walks or above the ground shall be removed and installed in accordance with this ordinance on or before May 1st 1915. any and all tanks used for Storage of Gasoline or other oils that are installed on and after the passage of this ordinance must be installed below the ground in accordance with this ordinance.

Section 2 This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Harry G. Cininger

Done at the Council Chamber in the City of Fort Wayne Indiana this 11th day of April 1911

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 11th day of April 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 481

Louis S. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 15th day of April 1911

Wm. J. Jefferies
City Clerk

approved this 17th day of April 1911

Jesse Grice
Mayor.

General Ordinance no 482

An ordinance prohibiting the sale or use of dangerous explosives for the purpose of celebrating Independence day.

Whereas the celebration of the Fourth of July last year resulted in the loss of at least 131 lives and the production of 2.792 Non-fatal injuries. including 7 made totally blind. 33 blinded in one eye. 26 who lost legs. arm or hands and 114 who lost one or more fingers. and

Whereas. the causes of these deaths and injuries in most cases from the use of firearms. torpedoes. giant crackers canons and others dangerous explosives. and

Whereas. the cause of Patriotism is much better subserved by other less dangerous methods of Celebration. as the parades of soldiers and historic floats. childrens picnics etc. and

Whereas. the responsibility for these deaths and injuries clearly rests with the City Government in most cases. therefor.

Section 1 Be is ordained by the Common Council of the City of Fort Wayne that it shall be unlawful for any merchant to sell or expose for sale from the 15th day of June to the 15th day of July of any year or for the purpose of celebrating the Fourth of July. any instrument designed to explode a blank cartridge. any firecracker. torpedo or cannon or any other explosive capable of causing injury.

Section 2: It shall be unlawful for any one to purchase any such article and explode it within the limits of the city

Section 3. any person violating this ordinance shall be deemed guilty of a Misdemeanor and on conviction thereof be fined in any sum not less than $5.00 or more than $100.00.

Section 4. This ordinance to be in full force and effect from and after its passage and approval by the Mayor.

B. Van Zweringen

Done at the Council Chamber in the city of Fort Wayne this 11th day of april 1911

We hereby Certify That the common council of the city of Fort Wayne did at a Regular Meeting held on the 11th day of april 1911. by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 482

Louis S. C. Schroeder.
President

Wm. J. Jefferis
City Clerk

(over)

Presented to the Mayor for approval on the 15th day of April 1911

Wm. S. Jeffries
City Clerk

Approved this 17th day of April 1911
Jesse Grice
Mayor.

General Ordinance no 483

An ordinance to amend section ten of General Ordinance no 162 entitled "An ordinance relating to the taxing of dogs and repealing General Ordinance no 35 relating to the same subject matter"
approved august 14. 1900
Section 1. Be it ordained by the Common Council of the city of Fort Wayne Ind that section ten of said ordinance be and the same is hereby amended to read as follows: Section 10 any person residing within the corporate limits of the city of Fort Wayne who on the 1st day of March of any year owns harbors or has the care of any dog. Male or female. refuses to pay the annual ~~tax~~ or taxes thereon to the Township assessor. as in this ordinance provided. shall upon conviction be fined in any sum not to exceed five dollars ($5.00) and cost of prosecution.
Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication
E. A. Wagner.

Done in the council chamber in the city of Fort Wayne Ind this 11th day of April 1911
We hereby Certify That the Common Council of the city of Fort Wayne Ind at a Regular meeting held on the 11th day April 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as
General Ordinance no 483

Louis S. C. Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval on the 15th day of April 1911

Wm. S. Jeffries
City Clerk

Approved this 17th day of April 1911
Jesse Grice
Mayor.

General Ordinance no 484

An ordinance to provide for the codification. annotation indexing. printing and publication of the charter of the City of Fort Wayne as amended by the acts of 1907 and 1911 and for the codification. annotation. indexing. printing and publication of the ordinances of the city of Fort Wayne subsequent to the revision of 1901 which shall constitute a supplement of the laws and ordinances of 1901: Providing for a method to prepare the same and appropriating money to defray the expense thereof.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana. that the City attorney of said City be and he is hereby directed. authorized and empowered to employ. at the expense of said City and all necessary help to assist him in making a complete revision. codification and annotation of the charter of the city of Fort Wayne as amended by the acts of 1907 and 1911. and a complete revision. codification and annotation of all the ordinances of said City now in force that were passed subsequently to the general revision of the laws and ordinances of 1901. and to prepare index and superintend the publication thereof. Said revision codification and publication shall be made to the approval of said City attorney. the council committee on printing and any other committee that may be appointed by the council to supervise said work and said revision shall constitute and be known as a Supplement to the laws and ordinances of 1901. The amount of compensation to be used by the said City attorney for services of a Stenographer and other help employed in indexing. annotating and proof reading shall not exceed the sum of $125.00 all of which money shall be paid directly to the persons so employed

Section 2. That the City Comptroller be and he is hereby authorized and directed when said City attorney shall submit said work of revision and codification complete and shall report to the said city Comptroller that said work was by him approved. to procure the printing and and binding at the lowest obtainable rate of not less than five hundred nor more than one thousand copies of said revision and for that purpose to incur the necessary expense on behalf of said City. and said Comptroller is hereby authorized to receive bids and enter into a contract for the printing of said revision.

Said contract to be approved by the common council.
When printed the Comptroller shall furnish to members of the common council and to the members of the executive and other departments of the city government a sufficient number of copies for the convenient use of each and shall also furnish one copy to each of the courts located in Allen County and may dispose of the remaining copies in such manner as in his judgment will best serve the public interest.
Section 3. For the payment of the necessary help to be hired hereunder authority is hereby given to the Department of Law to use not more than One hundred and Twenty five dollars ($125.00) from the fund already appropriated to that Department and for the printing binding and publication of said revision there is hereby appropriated to the City Controller the further sum of Twelve Hundred dollars ($1200.00)
Section 4. This ordinance shall be in full force and effect from and after its passage.

P M. Braun

Done in the council chamber in the City of Fort Wayne Indiana this 11th day of april 1911

We hereby certify that the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 11th day of april 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 484

Louis A. C. Schroeder
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 15th day of april 1911

Wm. J. Jefferis
City Clerk

approved this 17th day of april 1911

Jesse Grice
Mayor

General Ordinance no 485

An ordinance authorizing the Board of Public ~~Works~~ Safety to employ a clerk for the Police Department

Section 1: Be it ordained by the common council of the city of Fort Wayne and that the Board of Public Safety is hereby authorized and empowered to employ a qualified Stenographer as clerk for the Police Department whose term of employment however shall not begin until the first day of May 1911.

Section 2: The salary of the clerk so employed shall be Sixty five dollars ($65.00) per month

Sec 3: That this ordinance be in full force and effect from and after its passage and approval by the Mayor

Allen Hamilton

Done at the council chamber in the city of Fort Wayne Indiana this 25th day of April 1911

We hereby Certify That the Common Council of the City of Fort Wayne Indiana, at a Regular meeting held on the 25th day April 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 485

Louis D. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 29th day of April 1911

Wm. J. Jefferies
City Clerk

Approved this 29th day of April 1911

Jesse Bruce
Mayor

General Ordinance No 486

An ordinance providing for the inspection of scales weights and measures in the City of Fort Wayne Ind providing for the appointment of a City Sealer of weights and measures and defining his duties and Compensation: providing penalties for the violation thereof and fixing a time when the same is to take effect.

Standard of weights and measures.

Section 1: Be it ordained by the Common Council of the City of Fort Wayne Indiana. That from and after the taking effect of this ordinance there shall be a regulation of Scales weights and measures within the city of Fort Wayne Indiana and the Standard adopted by the state of Indiana and by the United States shall be the test by which they shall be Compared and determined.

City Sealer - How appointed - Term and Bond of Office

Section 2: There shall be appointed by the Mayor of the City of Fort Wayne Indiana. a competent person as City Sealer of Weights and Measures. who shall hold his office for the term of two (2) years or until a successor is appointed and qualified. The Mayor shall have the power to remove the City Sealer and vacancies shall be filled by the Mayor for the unexpired term. The duty of the city sealer shall be to preserve and safely keep the standards provided for him by the city and when required to deliver them to the Mayor or such other person as may be appointed to receive them. and to faithfully perform the several duties of said Office. and before he shall enter upon the duties of his office he shall be qualified as is required in other city departments. He shall also give bond to the City of Fort Wayne in the penal sum of Two Thousand dollars ($2000.00) with surety to be approved by the Mayor. conditioned for the faithful performance of all the duties appertaining to his office and for the safe return of the Citys Property.

Employment of assistants.

Section 3: The City sealer of weights and measures shall employ. with the approval and consent of the Mayor when authorized by the Common Council. Suitable and competent person or persons as assistants who

who shall recive for their services the sum of Two dollars ($2.00) per day each to be paid out of a fund created for that purpose to said assistants for the number of days employed during any month. but said assistant or assistants shall be under the direction and control of the city sealer of weight and measures and shall perform such duties as the city sealer of weights and measures shall direct and he may. whenever in his opinion the interest of the city shall be subserved thereby dismiss any of said assistant or assistants and may appoint other assistants in their stead with the approval of the Mayor.

Salary of city Sealer of weights and measures

Section 4. The city Sealer of weights and measures shall receive from the city as compensation for his services the sum of Twelve hundred dollars ($1200.00) per annum. payable Monthly.

Standard-Beams-Scales and other instruments secured

Section 5. The Comptroller. upon the requisition of the city Sealer of weights and measures. shall procure or cause to be procured at the expense of the city as provided by law correct and approved Standards with their several necessary subdivisions to gether with the proper beams. scales and measures for the purpose of testing and approving the scales. weights and measures to be used in the City of Fort Wayne.

City Sealers Duties

Section 6: It shall be the duty of said city Sealer of weights and measures to test all weights. Measures. scales. beams. Steelyards. and other Machinery used for weights or measuring within such City at least once in every six months or oftener if it is deemed necessary. and upon being notified in writing by any person that any weight. scale. beam. Steelyard or other Machinery for weighing or measuring any article intended to be purchased or sold or offered or exposed for sale in said city is inaccurate or believed to be so. or not according to the Standard. he will at once make an examination of the same. and after he shall have found such Weights and measures to be correct and according to the standard prescribed by law he shall seal or mark the same with a stamp or by pasting a cord thereon. as he may deem most proper with the letters "Ind S"

Meaning Indiana Standard which said cards and seals shall be provided by the city.
any person or persons counterfeiting said brand or stamps or branding any measure any other letters for the purpose of deception shall forfeit and pay for very such offence not less than five dollars ($5.00) nor more than one hundred dollars together with the costs of prosecution.

Penalty for refusing to exhibit

Section 7. Any person refusing to exhibit any scales weights or measures. or beams. or other weighing instruments to the City Sealer of weights and measures on his demand for the purpose of having them so examined. shall be deemed guilty of a misdemeanor and on conviction thereof shall be fined in any sum not less than Five dollars ($5.00) nor more than One hundred dollars ($100.00)

Where test to be made

Section 8. The testing required of said weights. Measures scales. beams. Steelyards and other machinery. May be made by. such Sealer at the store or other place where the same are used. and upon demand thereof the owner or user thereon shall exhibit the same to said City Sealer for the purpose of having such test made: provided. however that on Monday of each week said City Sealer shall be and remain at the office of the City Sealer during office hours. for the purpose of testing and stamping any of said weights. Measures. Scales. beams. Steelyards or other Machinery that may be presented at such office Therefor.

Records of all tests to be kept.

Section 9. The said City Sealer of weights and Measures shall keep a record of all weights. Measures. Scales beams. Steelyards and other Machinery inspected or tested by him. including those found to be incorrect in which record shall be shown the names of the owners or users of the same and the respective dates of his inspection or testing and marking or sealing. or his rejection thereof. and said book of records shall at all proper times be opened to public inspection

None but sealed scales to be used

Section 10. No person firm or corporation shall use or permit to be used by any person in his. their or its employ. nor shall any employe use. any weights. measures. scales. beams. Steelyards. balances or other instruments or machinery for weighing articles or commodities. unless the same shall have been tested and sealed or marked as herein required. and no person firm or corporation with intent to use the same for weighing and measuring as aforesaid. shall alter or permit to be altered or knowingly use or permit to be used after the same shall have been altered. any such weights measures. scales. beams. Steelyards. balances and other instruments or machinery for weighing or measuring after the same shall have been so tested and marked or sealed as aforesaid. Any person. firm or corporation who shall violate any provision of this section shall be deemed guilty of an offense and on conviction thereof may be fined in any sum not less than five dollars ($5.00) nor more than one hundred dollars ($100.00).

No person shall sell other than tested weights etc

Section 11. No person shall sell. or offer for sale or give away within the city of Fort Wayne, any weight. Measure. scale beam.. patent balance. Steelyard or other instrument to be used in weighing or measuring. unless the same shall have been tested sealed and marked by the city sealer of weights and measures of the City of Fort Wayne under a fine of one hundred dollars ($100.00) for each offense.

No Alterations

Section 12. No person shall alter or change in any manner any weight. Measure Scale beam. patent balance Steelyard. or other instrument to be used in weighing or measuring any commodity or article of Merchandise after the same has been tested. sealed and marked by the City Sealer of weights and measures of said City so that the same shall weigh or measure inaccurately. Any firm or corporation who shall violate any provision of this section shall be deemed guilty of an offense and on conviction thereof may be fined in any sum not less than five dollars ($5.00) Nor More than one hundred dollars ($100.00)

No Sale "ect" except Goods "ect" weighed or Measured on tested Scales or Measures

Section 13. No person shall sell or offer for sale any commodity or article of Merchandise in any Market or in any public Streets or in any other place in the City of Fort Wayne, at or for a less weight or measure than the true measure or weight thereof and all ice, coal, coke, meats poultry, butter and butter in prints, provisions and all other commodities and articles of Merchandise. (except vegetable sold by the head or bunch) Sold in the streets or elsewhere in the city of Fort Wayne, Shall be weighed or measured by scales, measures or balances duly tested, sealed and Marked by the city sealer of weights and measures: Provided, that poultry may be offered for sale and sold in other manner than by weight, but in all cases where the person intending to purchase shall so desire and request poultry shall be weighed as hereinbefore provided.

No person shall violate any of the provisions of this Section under a fine of not less than five dollars ($5.00) nor more than one hundred dollars ($100.00) for each offense.

Penalty for use of false weights

Section 14. A person who injures another or defrauds another by using a false weight, measure or other apparatus used in weighing or measuring of any commodity or article of Merchandise or who delivers less than the quantity he represents, shall forfeit and pay not less than five dollars ($5.00) nor more than one hundred dollars ($100.00) for each offense.

Ice weighing of

Section 15. Every person, firm or corporation that is now or may hereafter be engaged in the business of delivering or selling and delivering ice within the city of Fort Wayne shall furnish and securely place upon the rear of each of its wagons used in the delivery of ice one set of scales of at least one hundred and twenty five (125) pounds capacity. Every such person, firm or corporation engaged in the business of delivering or of selling and delivering ice within said city shall cause each quantity of ice delivered to be weighed by

said scales so attached to said wagon. Every person engaged in delivering ice from such delivery wagon shall cause any quantity of ice delivered to any purchaser to be weighed on one of said scales and in the presence of such purchaser, or a member of his family or any employe of such purchaser, whenever so requested by such purchaser or by such member of his family or by such employe of said purchaser. Each and every set of ice tongs used in the delivery of ice in said city shall have prominently and conspicuously stamped thereon the exact and true weight of said tongs.

Coal. certificate of weight of

Section 16. No person firm or corporation shall deliver or sell and deliver any coal or coke within the limits of the city of Fort Wayne unless there shall be delivered to the person in charge of the wagon or vehicle used in delivering the same a certificate written entirely with ink or an indelible pencil. or partly printed and partly written with ink or an indelible pencil. duly signed by the person. firm or corporation selling said coal or coke and showing the weight of the coal or coke purported to be delivered the weight of the wagon or vehicle used in such delivery. the date of weighing of same and the name of the purchaser which said certificate shall be delivered by the person in charge of said wagon or vehicle to the purchaser of said coal or coke, or to the person in charge of the premises where said coal or coke is to be delivered. prior to the unloading of the same from wagon or other vehicle provided. however that this section shall not apply when coal or coke is purchased in carload lots and the purchaser has agreed to accept mine weights.

Certificate to be exhibited

Section 17. No person in charge of the wagon or vehicle used in delivering coal. to whom the certificate mentioned in the preceding Section has been delivered shall refuse or neglect upon demand. to exhibit said certificate to said City Sealer of weights and measures or the Chief of Police or any Policeman in uniform and when said City Sealer of weights and measures or Chief of Police or any such Policeman in uniform shall demand that the weight shown by such

Certificate be verified. it shall be the duty of the person delivering such coal to convey the same forthwith to some public scale of the city. if any such there be or to any private scale in the city other than a scale owned or controlled by the seller of said coal. when the owner thereof shall consent to such use. and to permit the verification of the weight shown. and shall after the delivery of said coal. return forthwith with the wagon or vehicle used. to the same scale and verify the weight of said wagon or vehicle. The cost of the use of such scale so used for the purpose of such verification shall be paid by the officer demanding the verification. and the said officer shall be reimbursed for such expenditure by the Board of Public Safety. Any person firm or corporation who shall violate any provision of this section shall be deemed guilty of an offense and on conviction thereof may be fined in any sum not less than five dollars ($5.00) nor more than one hundred dollars ($100.00)

Measures and containers to conform to Standard.

Section 18. No person shall manufacture. construct. sell offer for sale. or give away. and dry measure or liquid measure nor any barrel. pail. basket. Vessel. Container intended to be used in the purchase or sale of any commodity or article of Merchandise which shall not be so constructed as to conform with the Standards provided by Statute. Nor shall any person use any barrel. cask. pail. basket. Vessel or container of any kind in the sale of any commodity or article of Merchandise which does not conform to the Standards provided by law. including inspection herein required and sealing by the city inspector. any person. firm or corporation who shall violate any provision of this Section shall be deemed guilty of an offense and on conviction thereof may be fined in any sum not less than five dollars ($5.00) nor more than one hundred dollars ($100.00)

Dairymen. Hawkers "etc" Duties of.

Section 19. All dairymen using measures in the sale of milk. hawkers. peddlers. junk or rag dealers. who have no regularly established place of business. using scales weights and measures or other things to weigh or measure

by. shall have the same inspected and tested by the city Sealer of weights and measures at his office between the hours of 9 and 11 a. m.

Repealing

Section 20. All ordinances or parts of ordinances in conflict herewith are hereby repealed.

Penalty

Section 21. Any pirn or corporation violating any of the provisions of the foregoing sections of this ordinance. when not otherwise therein provided shall on conviction thereof be fined not more than One hundred dollars($100.00) nor less than five dollars($5.00)

Section 22. This ordinance shall be in full force and take effect from and after its passage and approval by the mayor and legal publication

Harry G. Pinnigar

Done at the Council Chamber in the city of Fort Wayne Indiana this 25th day of april 1911

We hereby Certify. That the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 25th day of april 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 486

Louis S. G. Schroeder
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval this 29th day of april 1911

Wm. S. Jefferis
City Clerk

Approved this 29th day of april 1911

Jesse Grice
Mayor

General Ordinance no 487

An ordinance to amend section 1 of General ordinance no 482 entitled. "an ordinance prohibiting the sale and use of dangerous explosives for the purpose of celebrating Independence day" passed by the common council april 11-09

Section 1. Be it ordained by the common council of the leity of Fort Wayne Indiana That section 1 of said ordinance be and the same is hereby amended to read as follows:

Section 2. No person firm or corporation shall sell. offer or expose for sale loan or give away. within the leity of Fort Wayne. nor shall any person fire or explode within the city of Fort Wayne. any blank cartridges blank cartridge pistols. toy cannon or any firecracker exceeding three inches in length by one half of an inch in diameter or any firecracker of any size loaded with dynamite or other high explosive or any potash and sulphur tablets. exceeding one-half inch in diameter and three sixteenths of an inch in thickness. or any device for exploding any tablet or pellet herein prohibited. or any torpedo exceeding one inch in diameter or of greater force than the commercial toy cap.

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

Charles W. Lettol

Done at the Council Chamber in the leity of Fort Wayne Ind this 9th day of May 1911

We hereby certify That the common council of the city of Fort Wayne Ind at a Regular meeting held on the 9th day of May 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known a

General Ordinance no 487

Louis S. Schroeder
President.

Wm S. Jeffries
leity Clerk

Presented to the mayor for approval on the 13th day
of May 1911

Wm. J. Jappino
City Clerk

Approved this 15th day of May 1911
Jesse Grice
Mayor

General Ordinance no 488.

An ordinance making it unlawful for dogs to run at large in the city of Fort Wayne and providing penalties for the violation thereof.

Be it ordained by the Common Council of the City of Fort Wayne that

Section 1. It shall be unlawful for any person to keep or harber any dog. either Male or female. whether taxed or untaxed in the city of Fort Wayne except upon premises owned or occupied by himself or upon premises owned or occupied by one who has given permission to have said dog kept or harbored upon the same.

Section 2. It shall be unlawful for any person being the owner of. or having the immediate custody or control of any dog Male or female whether taxed or untaxed. to Suffer or permit such dog to be at large upon the streets highways. alleys or other public places in the city of Fort Wayne. unless accompanied by such owner or person having the immediate custody and control of said dog.

Section 3. It shall be the duty of the Poundmaster or any Police Officer or other proper Officer of said city to take said dog and kep it under the control of said city for a period of forty eight hours after the said dog has been taken in custody and afterwards killed unless within the forty eight hours period the owner or his duly authorized agent shall call at the place where said dog is kept and said dog may be released and turned over to said owner or his authorized agent on payment of two dollars to the Poundmaster for the benefit of the city to pay the expenses of the care and custody of said dog.

Section 4. This ordinance shall be in full force and effect thirty (30) days after its passage and during said thirty (30) days the City clerk is directed to mak publication thereof. in the daily papers of the city of Fort Wayne by one (1) insertion in each daily paper. once (1) each week for three (3) successive weeks.

Henry W. Felger

Leone at the Council Chamber in the city of Fort Wayne this 9th day of May 1911

We hereby certify That the common Council of the city of Fort Wayne Ind at a Regular session held on the 9th day of may 1911. by a majority vote of all the members elect did pass the ordinance hereunto attached. and known as General Ordinance no 488

Louis A. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 13th day of may 1911

Wm. J. Jeffries
City Clerk

Approved this 15th day of may 1911

Jesse Grice
Mayor

General Ordinance no 489

An ordinance approving Railroad Track Elevation Resolution no 3. adopted by the Board of Public works of the City of Fort Wayne April 3d 1911 and ratified and confirmed by said Board on May 3d 1911.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana That Railroad Track Elevation Resolution no 3 adopted by the Board of Public works of said city on April 3d 1911 and confirmed by said Board on May 3d 1911 be and the same is hereby in all things ratified confirmed and approved

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor and legal publication

P. M. Braun

Done at the Council Chamber in the City of Fort Wayne Indiana this 23d day of May 1911

We hereby certify that the Common council of the city of Fort Wayne Indiana at a Regular meeting held on the 23d day of May 1911 by a Majority vote of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 489

Louis S. C. Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval on the 27th day of May 1911

Wm. S. Jeffries
City Clerk

approved this 27th day of May 1911

Jesse Grice
Mayor

General Ordinance no 490

An ordinance ratifying and approving a certain contract entered into by the city of Fort Wayne and the Fort Wayne Electric works relative to the purchase of certain Electrical apparatus and pump

Whereas on the 16th day of May 1911 the city of Fort Wayne by and through its Board of Public works entered into a certain contract with the Fort Wayne Electric Works relative to the purchase of certain electrical apparatus and pump. ~~which contract is as follows.~~

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore on the 16th day of May 1911 entered into by and between the city of Fort Wayne by and through its Board of Public works and the Fort Wayne Electric Works as fully set forth in the preamble hereto be and in all things is hereby ratified and approved

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor

P. M. Braun

Leon at the council chamber in the city of Fort Wayne Ind this 13th day of June 1911

We hereby certify that the common council of the city of Fort Wayne Indiana at a regular meeting held on the 13th day of June 1911 by a Majority vote of all the members elect. did pass the ordinance hereto attached and known as General Ordinance no 490

Louis A. C. Schroeder
President

Wm. S. Jefferies
City Clerk

Presented to the Mayor for approval on the 16th day of June 1911

Wm. S. Jefferies
City Clerk

approved this 19th day of June 1911

Jesse Eric
Mayor

General Ordinance No 491

An ordinance authorizing the Employment of five additional Policemen by the Board of Public Safety

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the Board of Public Safety of said city be authorized to employ five additional Policeman from the 1st of July 1911.
Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor

Charles W. Lentlow

We hereby certify that the common council of the city of Fort Wayne Indiana at a regular meeting held on the 13th day of June 1911 by a majority of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance No 491

Louis S. G. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 15th day of June 1911

Wm. J. Jeffries
City Clerk

Approved this 19 day of June 1911

Jesse Grice
Mayor.

General Ordinance no 492

an ordinance confirming and approving a contract entered into on the 8th day of June 1911 by and between the City of Fort Wayne by and through its Board of Public works and Henry R. Worthington

Whereas heretofore on the 8th day of June 1911 the City of Fort Wayne by and through its Board of Public works entered into a contract with Henry R. Worthington a corporation for the purchase of a certain number of meters which contract is in the following words.
Whereas said contract and agreement were submitted by said Board of Public works of the City of Fort Wayne to the common council of said City for its consideration and action therein. Now Therefore
Section 1. Be it ordained by the Common Council of the city of Fort Wayne That the contract heretofore entered into by and between the city of Fort Wayne by and through its Board of Public works and Henry R Worthington as fully set forth in the preamble hereto be and the same is hereby in all things confirmed and approved
Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor and legal publication

Paul P. Kinder

Done at the Council Chamber in the City of Fort Wayne this 27th day of June 1911
We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 27th day of June 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 492

Louis A. C. Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval this 1st day of July 1911

Wm. S. Jeffries
City Clerk

approved this 8th day of July 1911

Jesse Grice
Mayor.

General Ordinance no 493

An Ordinance approving Railroad Track Elevation Resolution no 4 adopted by the Board of Public works of the city of Fort Wayne april 20th 1911 as amended. Modified and confirmed by said Board on May 17-1911

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana. That Railroad Track elevation Resolution no 4 as adopted by the Board of Public works of said city on april 20th 1911 and as amended. Modified and confirmed on May 17-1911 be and the same is hereby in all things ratified. confirmed and approved.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor and legal publication

Charles W. Zeitler

Done at the council chamber in the city of Fort Wayne this 5th day of July 1911

We hereby certify That the common council of the City of Fort Wayne Indiana at a Special meeting held on the 5th day of July 1911 by a Majority vote of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 493

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 7th day of July 1911

Wm. J. Jeffries
City Clerk

approved this 7th day of July 1911

Jesse Grice
Mayor

General Ordinance no 494

An ordinance providing for the Erection and Maintenance of pumps. automatic valves measuring devices. or other apparatus for the distribution by sale or otherwise of oil Gasoline. or Volatile fluids of any kind. on the side walks of the city of Fort Wayne Indiana.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that any person. firm or corporation desiring to erect or maintain any pump. automatic valve measuring device or other apparatus. on the side walks of this city. for the distribution. by sale or otherwise. of oil. Gasoline. or Volatile fluids of any kind. may do so by complying with the requirements as in the ordinance set out.

Section 2. Such person. firm or corporation. shall file a written application to ~~Exect~~ such apparatus. as set forth in section 1 with the Building inspector of this city. which said application shall contain a description of the apparatus. and all pipes. tanks and other appliances. connected therewith giving full dimensions. Specifications. and describing the methods of and manner of operation and the location of the same by Street and number. and also the location of the storage and supply tanks. together with all connecting pipes and other appliances in any way connected with said apparatus to be erected. and any other information relating to said apparatus. tanks. pipes or other connections and the installation of the same which may be requested by the building Inspector.

Section 3. Said apparatus shall not be erected or Maintained at any location where it interferes with the convenience or safety of the general public in the use of the streets and side walks and shall in all cases be placed upon the outer edge of the side walk next to the curb and shall not occupy a space on said side walk of more than fourteen inches. measuring from the curb to the building line. nor more than eighteen inches measuring parallel with the curb: nor extend more than five feet above the surface of the said side walk. It shall be constructed in a workmanlike Manner. present an even surface. contain no sharp points. bolts or other projections and all corners of the same shall be rounded and smooth.

Section 4 Said apparatus. the pipes. tanks. and other appliances connected therewith. and the installation of the same shall conform with all requirments and provisions of the laws and ordinances of this city regulating the construction of building and the sale of oil. Gasoline. or Volatile fluids of any kind. and in particular the ordinance known as "the Building Code" the same being General Ordinance no 390. passed May 5-1909 and all other ordinances of this city.

Section 5. Before any permit to erect any such apparatus as set forth in section 1 of this ordinance. Shall be granted by the Building Inspector as in the ordinance provided. Said application. showing the location of said apparatus together with all tanks. connecting pipes. and other appliances in connection therewith. shall be presented by said applicant to the Board of Public works of this city. Said Board of Public works is hereby authorized to examine and inspect said application and the location of said apparatus and pipes and tanks in connection therewith. If said Board of Public works shall approve the location of said apparatus and the pipes. tanks and other appliances in connection therewith as set forth in said application, Then said Board of Public works shall endorse such approval on said application. No permit to erect or Maintain any such apparatus shall be issued without such approval of the Board of Public works as herein provided.

Section 6. If it shall appear to the satisfaction of the Building Inspector that the location of said apparatus has been properly approved by the Board of Public works as set forth in section 5 hereof and if it shall further appear to such Building Inspector that said apparatus and the installation of the same together with all pipes and tanks in connection therewith. conforms to the requirments of the laws and ordinances of the city. Said Building Inspector shall issue to said applicant a permit to erect and Maintain said apparatus. according to the plans and Specifications set forth in said application. upon the payment to the Comptroller of this City a fee of five dollars ($5.00) for the issuing of said permit. That every person firm or corporation erecting or maintaining any such apparatus. as set forth in section 1 of this ordinance shall thereafter pay an annual fee to the Comptroller

of this city of Five dollars ($5.00) which fee may be changed at any time by an amendment to this ordinance

Section 7. Whenever it shall appear that the erecting or Maintenance of any such apparatus as set forth in section 1 of this ordinance interferes with the convenience or safety of the general public in the use of Streets and side walks. where such apparatus may be located. Such apparatus so erected and maintaind shall be removed by order of the Board of Public works of this city.

Section 8. Such person firm or corporation erecting or maintaining any apparatus as provided for in this ordinance shall be liable and answerable for any and all damages that may be occasioned to persons or property by reason of the erection and Maintenance of such apparatus

Section 9. Any person firm or corporation violating any of the provisions of this ordinance shall be subject to a penalty of Twenty five dollars ($25.00)

Section 10. This ordinance shall be in full force and effect from and after its passage and approval by the Mayor

Charles E. Wiley

Done at the council chamber in the City of Fort Wayne Ind this 25th day of July 1911

We hereby certify that the common Council of the city of Fort Wayne Indiana at a Regular meeting held on the 25th day of July 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 494

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 29th day of July 1911

Wm. J. Jeffries
City Clerk

approved this 29th day of July 1911

Jose Grieve
Mayor

General Ordinance no 495

An ordinance to amend Section 1. of an ordinance Regulating the use of Automobiles and Motor Vehicles upon the Streets. alleys and public highways of the City of Fort Wayne Indiana and providing Penalties. for the Violation Thereof and Repealing General Ordinance no 448 and fixing a time when the same shall take effect and known as General Ordinance no 472

Section 1. Be it ordained by the Common Council of the City Fort Wayne Indiana. That section 1 of General Ordinance #472 being an ordinance Regulating the use of Automobiles and Motor Vehicles upon the Streets. alleys and public Highways of the City of Fort Wayne Indiana and providing penalties for the Violation thereof and repealing General Ordinance no 448 and fixing a time when the same shall take effect be amended to read as follows:
Section 2. That it shall be unlawful for any person firm or corporation to run. operate. drive. propel or leave standing in upon or along any public Street. alley or highway within the limits of the City of Fort Wayne from one half hour after sunset to one half hour before sunrise. any Automobile. Motor Vehicle or other conveyance. carriage. Wagon. engine or machine. the motor power of which shall be electricity. Steam Gasoline or any source of energy other than human or animal power. unless there shall be kept burning on the front of said Vehicle at least one white light visible for a distance of not less than two hundred feet and on the rear on said Vehicle at least one red light visible for a distance of not less than two hundred feet.
Sec 3. That this ordinance be in full force and effect from and after its passage legal publication and approval by the Mayor

J. J. Bauer

Done at the Council chamber in the City of Fort Wayne Indiana this 25th day of July 1911

Wm J. Jefferies
City Clerk

We hereby certify that the common council of the City of Fort Wayne Ind at a Regular meeting held on the 25th day of July 1911 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 495

Louis S. C. Schroeder
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 29th day of July 1911

Wm. J. Jefferis
City Clerk.

Approved this 29th day of July 1911

Jesse Grice
Mayor

General Ordinance no 496

An ordinance to amend Section 23 of ~~of~~ General Ordinance #143 entitled "an ordinance defining certain Offenses

Section 1. Be it ordained by the common Council of the city of Fort Wayne Indiana That Section 23 of General Ordinance #143 entitled "an ordinance defining certain Offenses" be amended to read as follows: Section 23. It shall be unlawful for any person to build. or cause to be built. within the limits of said city. any privy Vaults. or to use for such purpose any Vault unless the same is built of brick Stone or Metallic Substances and made water tight. and not less than four feet deep. And it shall be unlawful to construct or Maintain any such privy Vault or other Vault used for that purpose within a distance less than fifty feet from any dwelling place It shall be the duty of the Board of Health to report all cases when the said Vaults are not built as herein provided to the Building inspector who shall after due notice to the owner of said Vault proced to condemn any vault not constructed as herein provided.
Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

B. Van Zwerningen

Done at the council chamber in the city of Fort Wayne Indiana this 25th day of July 1911

We hereby Testify that the Common Council of the city of Fort Wayne Indiana at a Regular meeting held on the 25 day July 1911 by a Majority vote of all the members elect dis pass the ordinance hereunto attached and known as General Ordinance no 496

Louis S. G. Schroeder
President

Wm J. Jeffries
City Clerk.

Presented to the Mayor for approval on the 29th day of July 1911

Wm J. Jeffries City Clerk

approved this 29th day of July 1911

Jesse Grice
Mayor

General Ordinance no 497

An ordinance changing the name of Force street to Weisser Park Avenue

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. That the name of Force street shall be changed to and hereafter known as Weisser Park Avenue
Section 2. That this ordinance be in full force and effect from and after its passage. Legal publication and approval by the Mayor

Henry W. Felger

Read at the council chamber in the city of Fort Wayne Ind. this 25th day of July 1911

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 25th day of July 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 497

Louis S. & Schroeder
President

Wm J. Jefferis
city Clerk

Presented to the mayor for approval on the 29th day of July 1911

Wm J. Jefferis
city Clerk

approved this 29th day of July 1911

Jesse Grice
Mayor

General Ordinance No 498

An ordinance authorizing the Board of Public works to maintain a system of ornamental lamp posts and providing for the maintenance thereof

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana That the Board of Public works be authorized and empowered to operate and maintain a system of ornamental Lamp Posts as provided for under Lamp Post Resolution Numbered one - two - three - four and the same to be paid out of the General fund of the City to be provided for in the annual appropriations as fixed by the Common Council

Section 2. That this ordinance be in full force from and after its passage and approval by the Mayor

Louis S. C. Schroeder

Done at the Council Chamber in the City of Fort Wayne Indiana this 25th day of July 1911

We hereby certify that the Common Council of the city of Fort Wayne Indiana at a Regular Meeting held on the 25th day of July 1911 by a Majority vote of all the Members Elect did pass the ordinance hereunto attached and known as General ordinance no 498

Louis S. C. Schroeder
President

Wm. S. Jefferies
City Clerk

Presented to the Mayor for approval the 29th day of July 1911

Wm. S. Jefferies
City Clerk

approved this 29th day of July 1911

Jesse Grice
Mayor

General Ordinance no 499

An ordinance approving and ratifying a contract entered into between the city of Fort Wayne Indiana by and through its Board of Public works and Leonard Metcalf and Harrison P. Eddy. partners doing business under the firm name of Metcalf + Eddy of Boston Massachusetts. relative to the investigation inspection. Etc of the sewer system in the city of Fort Wayne

Whereas heretofore on the 22d day of June 1911 the City of Fort Wayne by and through its Board of Public works entered into a contract with Metcalf and Eddy. relative to the investigation inspection etc. of the sewer System in the city of Fort Wayne which contract is in the following words.

This agreement. Made and entered into this 22d day of June 1911. by and between the city of Fort Wayne by and through its Board of Public works. party of the first part (for convenience hereinafter called the city) and Leonard ~~and~~ Metcalf and Harrison. P. Eddy. partners doing business under the firm name of Metcalf and Eddy of Boston Massachusetts. party of the second part (for convenience hereinafter called "Contractor" Witnesseth.

In consideration of the sums to be paid by the city to the Contractor at the time and in the manner as hereinafter set out. the Contractor agrees that is will make such surveys a may be necessary to determine the feasibility of providing a dam or dams for impounding the waters of the rivers within the city for park and boating purposes. and furnish suggestions and general plans for the improvement of the rivers.

It being further understood that the report and plans will include suggestions as to the water ways which should be provided for flood rivers. and the said Contractor will also give suggestions and its opinions as to the effect of the admission of the overflow of Sewage into the rivers during times of Storm and heavy rain fall.

It is further understood that the said Contractor will make a study with respect to the adequacy of the trunk sewers of the present sewer System. including Special Studies of such individual trunks or lateral Sewers as may have or appear to be inadequate or insufficient in depth. which study will be followed by a

report. and will include suggestions and opinions as to the method of relief in all instances where relief is necessary.

It being further agreed that said Contractor will Make such study of the topographical condition of the city as to enable it to outline the trunk sewers that will be necessary to adequately serve those portions of the city not at the present time probided with sewers and will extend this study so as to include districts lying without or outside the city. which may now need sewers. or which may within a reasonable period in the future be likely to be annexed to the city

It being further agreed that the contractor will make a study or survey of the present intercepting sewers to ascertain their adequacy. and make such suggestions in the report to follow as to what may be necessary for their improvement both with reference to new construction and Maintenance. Such Contractor is also to Make such Studies or Surveys as may be necessary to determine what policy the city should adopt with reference to the disposal and ultimate purification of the sewage a make a report of such Studies and suggestions relative thereto.

In consideration of the things to be done by the Contractor as aforesaid the city agrees to pay for all of said work. plans. investigations. Surveys and report the sum of Five thousand dollars ($5000.00) in the following Manner "to wit" Two thousand dollars ($2000.00) is to be paid two months after the work is begun and the remaining three thousand dollars ($3000.00) to be paid on the presentation of the report of the aforesaid work and things to be done.

In witness whereof the parties have hereunto set their hands and seals this 22d day of June 1911

attest
H. W. Becker
Clerk

City of Fort Wayne
Frank. J. Benny
G. A. Swegeman
E. J. Zimmer
its Board of Public works

Metcalf and Eddy. by
Harrison P. Eddy.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. That the contract heretofore entered into on the 22d day of June 1911 by and between the city of Fort Wayne by and through its Board of Public works and Metcalf and Eddy. as fully set out in the preamble hereto be and the same is hereby in all things ratified and approved.

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles. W. Sittler

Done at the Council Chamber in the City of Fort Wayne Ind this 8th day of aug 1911

We hereby certify that the common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 8th day of aug 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 499

Louis D. Schroder
President

Wm. J. Jefferis
Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 15th day of aug 1911

Wm. J. Jefferis
City Clerk

approved this 16th day of august 1911

Jesse Grice
Mayor.

General Ordinance No 500.

An Ordinance confirming and approving a contract entered into on the 27th day of June 1911 by and between the city of Fort Wayne Indiana by and through its Board of Public works and the Lake Shore & Michigan Southern Railway Company concerning the granting of a water pipe to said Company over and along certain Streets.

Whereas heretofore on the 27th day of June 1911 the City of Fort Wayne by and through its Board of Public works entered into a contract with the Lake Shore and Michigan Southern Railway Company concerning the granting of a water pipe line to said Company over and along certain streets.

Whereas said contract and agreement is submitted by said Board of Public works of the city of Fort Wayne Ind to the Common council of said city for its consideration and action thereon. Now therefore.

Section 1. Be it ordained by the common council of the City of Fort Wayne that the contract heretofore entered into by and between the city of Fort Wayne. by and through its Board of Public works and the Lake Shore and Michigan Southern Railroad Company concerning the granting of a water pipe line to said company over and along certain streets is hereby in all things approved

Section 2. That this ordinance shall be in full force from and after its passage. approval by the Mayor and Legal Publication

Charles W. Settle

Done at the Council Chamber in the city of Fort Wayne this 8th day of aug 1911

We hereby certify that the common council of the city of Fort Wayne Indiana. at a Regular meeting held on the 8th day of august 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 500

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 15th day of august 1911

Wm S. Jefferies
City Clerk

Approved this 16th day of august 1911

Jesse Grice
Mayor.

General Ordinance No 501

An ordinance amending section 3 of an ordinance entitled "an ordinance providing for the destruction of weeds and noxious plants within the city of Fort Wayne" approved June 28-1898

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana! That section 3 of said ordinance being section 781 of the revised Ordinances of the city of Fort Wayne of 1901. be and the same is hereby amended to read as follows: Section 3. That it shall be the duty of the Board of Public Health of said city through the Sanitary Officers employed by said department from time to time to make careful inspection of all the lots. grounds streets and alleys situated within the city of Fort Wayne for the purpose of determining whether or not any weeds or noxious plants have been permitted to grow thereon of a character or to such an extent that they are or about to become injurious to the health and Comfort of the citizens of said city that is shall be the duty of said sanitary officers. from time to time to make report to said Board of Public Health of the result of their investigations. Whenever such officer or officers shall discover any lot. ground. Street or alley upon which weeds or noxious plants have been permitted to grow of a character or to such an extent as to be about to become injurious to public health they shall make prompt report thereof. in writing to said Board of Public health. Giving the names or Name of the owner or owners of such lot or ground upon which said weeds have been permitted to grow or the Name or Names of the owner or owners of the lot or ground abutting upon the street or alley upon which said weeds have bede permitted to grow. Thereupon said Board of Public health shall make full examination

Into the facts so reported and if in their judgment the weeds or noxious plants therein referred to are injurious to Public Health they shall so find and order such weeds abated and destroyed as a nuisance Their conclusions shall in all cases be reduced to writing and placed on record in the office of the Board of Public Health.
Thereupon said Board of Public Health shall require a written notice to be mailed to the owner or owners of said lot or ground. directing that the weeds growing on said lot or grounds or in the streets or alley upon which said lot or ground abuts as the case may be shall be cut or burned or otherwise removed therefrom in the manner in which said Board of public health shall order in said notice. The proof of the Mailing of said notice shall be deemed as sufficient and conclusive proof of notice. Said notice shall be delivered. by Mail to the defendant. or by leaving a copy thereof at his last and usual place of residence. In case such owner is unknown, or is not a resident of said city said Board shall cause a notice to be published in a daily newspaper of general circulation for three days in one week.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Henry W. Felger

Leone at the Council Chamber in the city of Fort Wayne this 8th day of august 1911

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 8th day of august 1911 by a Majority Vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 531

Louis D. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 15th day of august 1911

Wm S. Jefferies
City Clerk

approved this 16th day of august 1911

Jesse Grice
Mayor

General Ordinance No 502.

An ordinance approving a contract entered into by and between the City of Fort Wayne. by and through its Board of Public works. and the Fort Wayne and Northern Indiana Traction Company on the 25th day of July 1911 relative to the granting a right to lay a single track over the Spy Run avenue bridge when it crosses the St Marys River.

Whereas on the 25th day of July 1911. the City of Fort Wayne by and through its Board of Public works and the Northern Indiana Traction Company entered into a contract relative to the granting a right to lay an additional track over the Spy Run avenue Bridge where it crosses the St Mary's River. which contract is in the following words.

This agreement. Made and entered into this 25th day of July 1911 by and between the city of Fort Wayne. Allen County Indiana. hereinafter called "the city". by and through its Board of Public works. party of the first part. and the Fort Wayne Northern Indiana Traction Company. hereinafter called "the Traction Company. party of the second part. Witnesseth.
That Whereas the Traction Company now has and maintains a double track street railroad on spy run avenue except over the St. Mary's river Bridge and for a short distance on each side of said Bridge on said avenue and with switches on each side of and near to said Bridge on said avenue: and
Whereas it will facilitate and under safer the travel on said avenue to have said double tracks extended across said bridge and to avoid the necessity for said switches;
Wherefore. in consideration of the several and mutual covenants and agreements herein contained. it is hereby mutually and severally agreed between said parties as follows:
1. Consent. authority and permission are hereby given and granted to and vested in the said party of the second part. its successors and assigns. to construct. connect. Maintain and operate an additional street railroad track on said spy run avenue and over and across said St Marys river bridge and so as to connect the same with the double tracks on each side thereof in accordance with the plan thereof

hereto attached and made part thereof. together with all the necessary appliances therefor: Subject however. to all the terms conditions. limitations and agreements contained and set forth in the order of the Board of Commissioners of the County of Allen under and by virtue of which said Company now owns maintains and operates its said street railroad tracks on said avenue.

2. In consideration of the grant hereby made and said City the said party of the second part hereby covenants and agrees at its own cost and expense to Strenghten the floor system of said bridge if the same shall be deemed necessary by the City engineer and the Board of Public Works. and also to rebuild at once with creosote block. and thereafter Maintain. the entire floor of the roadway of said bridge in accordance with the plans to be made and approved by the city Engineer and said Board of Public works. And in the event that said bridge should need Strengthening because of the additional use to which it is subjected by reason of this grant. said Traction Company its Successors and assigns. agree that such additional Strengthening made necessary. by such use of said bridge for street railroad purposes will be done by them and that they will pay any and all cost of said work. It being understood that the grant herein is to continue and exist during the life or existence of the present bridge at the aforesaid point so that should a new bridge be constructed or the present one reconstructed. the grant herein is to be terminated without notice to said Traction Company. but in such event said present track and Switches may be replaced and connected by said Company as the same now are.

It is also understood that said Traction Company will locate said track in the place and in the manner as ordered and directed by said city. In the event said Company should fail after reasonable notice and demand to Strengthen said bridge and build a floor or to pay any cost of Strengthening said bridge or floor that might be required all as herein agreed or on its failure to perform any of the covenants or agreements herein contained then said Company shall forfeit all right to use or Maintain said additional

Track. but in such event said present track and switches may be replaced and connected as the same now are

3. This contract shall be in full force and effect from and after the passage of an ordinance approving and confirming the same and the approval by the Mayor of said City.

In witness whereof the said parties hereto have hereunto set their hands and seals the day and year above written

City of Fort Wayne
By Frank J. Zeroy.
G. A. Swygman
E. J. Zeimen
Its Board of Public works

Fort Wayne & Northern Indiana
Traction Company
By Robert A. Watson
Vice President

Section 1. Be it ordained by the Common Council of the city of Fort Wayne that the Contract heretofore entered into on the 25th day of July 1911 by and between the City of Fort Wayne. by and through its Board of Public works and the Fort Wayne Northern Indiana Traction Company. relative to the granting a right to lay a single Track over the Spy run avenue bridge when it crosses the St. Marys River as fully set forth in the preamble hereto be and the same is hereby in all things ratified and approved

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor

P M Braden

Done at the Council Chamber in the City of Fort Wayne this 22d day of aug 1911

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 22d day of aug 19[illegible] by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 502

Louis D. C Schroeder President Wm. J. Jefferis City Clerk

Presented to the Mayor for approval on the 25th day of aug 1911

Wm. J. Jefferis City Clerk

Approved this 25th day of august 1911

Jesse Grice
Mayor

General Ordinance no 503

An ordinance relating to the location of Slaughter houses

Section 1. Be it ordained by the Common Council of the city of Fort Wayne that from and after the passage and due publication of the ordinance it shall be unlawful for any person to slaughter cattle. sheep. hogs or other animals in any house. shed or building not now in use for such purpose
Section 2. That from and after the passage and due publication of this ordinance it shall be unlawful for any person to use or cause to be used for a slaughter house any house. shed or building not now or then in use for such purpose. within the limits of said city provided that this ordinance shall in no wise affect any business or slaughter house where slaughtering is now or at the passage and due publication of this ordinance being carried on and conducted.
Section 3. Any person violating this ordinance shall upon conviction be fined therefor in the sum of fifty dollars ($50.00) and the same sum for every twenty four hours continuance or permission of said nuisance or slaughter houses
Section 4. This ordinance to repeal all ordinances or parts of ordinances in conflict hereunto
Section 5. This ordinance to be in full force and effect from and after its passage approval by the Mayor and legal publication

Harry G. Pennington

Done at the Council Chamber in the City of Fort Wayne Indiana this 12th day of sept 1911

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 12th day of sept 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 503

Louis L. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 16th day of sept 1911

Wm J. Jeffries City clerk

approved this 12th day of sept 1911. Josse Grice
Mayor

General Ordinance 504.

An ordinance Ratifying and approving the Contract between the City of Fort Wayne Indiana. and Bernard Borkenstein. relative to the Building of an additional to no 3 pumping Station for the Fort Wayne Water works System.

Whereas heretofore on the 7th day of august 1911 the City of Fort Wayne Indiana by and through its Board of Public works entered into a contract with Bernard Borkenstein relative to the construction of an additive to no 3 pumping Station for the Fort Wayne Water works System which Contract is as follows:

Contract

This agreement made and entered into this 7th day of august 1911 by and between the City of Fort Wayne Ind by and through its Board of Public works. party of the first part. and for convenience hereinafter refered to as the "Board" and Bernard Borkenstein. party of the second part. and for convenience hereinafter refered to as "Contractor" witnesseth:

That for and in consideration of the payment by the Board to the Contractor of the sum of Money hereinafter refered to the Contractor hereby agrees to erect and construct an addition to no 3 pumping Station for the Fort Wayne Waterworks System. Said Building to be built and constructed as set forth in the plans and Specifications for the same. all of which are made a part and parcel of this contract and binding upon the parties hereto the same as if fully copied herein. Said plans and Specifications for the purpose of indentification and for the purpose of more fully Making the same a part hereof. have been signed by the parties hereto as of even date herewith.

The contractor agrees that he will. within ten days after the execution of this contract and its approval by the Common Council of said City. Execute a bond to said City for the faithful performance of the contract and indemnify the City against all damages arising out of said contract. Said bond or bonds to be satisfactory to the Board.

The Board shall have the right to make any alterations. additions to or omissions of work or Material

in such contract as herein specified that may be deemed advisable and the same shall be acceded to by the Contractor and carried into effect by him without in any way violating or vitiating the Contract or any bond given by the Contractor: That no alterations, additions to or omissions of work or Material shall be made unless the same shall first be ordered by the Board in writing, and the written agreement entered into between the Board and the Contractor as to the amount of money to be allowed or deducted for such alterations or additions.

The Contractor further agrees that in the prosecution of said work all proper skill and care will be exercised that said contractor will properly and fully guard and protect all excavations and dangerous places and will use all due and proper precaution to prevent injury to the property, person or persons, what or whomsoever and during the time of making such improvement the City of Fort Wayne shall be saved harmless from any and all liability whatsoever growing out of any injury or damage to property or persons because of any neglect or fault of the contractor his agent or employee in the execution of this contract or any matter connected thereto or relating thereto and to pay any judgment with cost which may be obtained against said City growing out of any such injury or damages.

Said Contractor further contracts and agrees to pay any and all Moneys due any contractor, person or persons furnishing any material for said work and pay any laborers employed by him for any work done in the prosecution of said improvement and that in the event any liens are filed with this Board for any such Material, Men or Laborers, this Board is authorized to hold out of the amount of money due said contractor an amount equal to the amount of the liens or claims filed.

That before said contractor shall receive his Money for the performance of this work he agrees to fully satisfy the Board that all liens and claims have been paid.

The Board to determine for itself whether the evidence of said payment is or is not Satisfactory.

It is hereby expressly understood that no assignment of this contract shall be made to any party without the consent of said Board in writing and that said work shall be completed in thirty days after the execution and approval of this contract.

The contractor agrees to pay the City as liquidated damages the sum of Five dollars ($5.00) for each and every day that said contract is unfinished after aforesaid time. The City reserving the right after five days' notice to contractor after expiration of aforesaid time to take possession of the premises and all materials thereon and provide work and material to complete said work and deduct the cost and charges thereof from any sum that may be due said contractor

It is agreed by the Board that for and in consideration of the furnishing of said Material and for the performance of said work it will pay the contractor the sum of Four Hundred sixty ($460.00) dollars on the completion and final acceptance of the work by the Board.

In witness whereof the parties have hereunto set their hands and seals this 7th day of august 1911

The City of Fort Wayne
By Frank J. Benoy.
G. A. Schwegman
E. J. Lennon
Its Board of Public works
Bernard Berkenstein
Contractor

attest Martin Metzger
Sec'y

Section 1. Be it ordained by the Common Council of the City of Fort Wayne that a contract heretofore on the 7th day of august 1911 entered into by and between the city of Fort Wayne by and through its Board of Public works and Bernard Berkenstein as fully set forth in the preamble. be and the same is in all things ratified and approved.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor.

Harry S. Pfeiffer

Done at the Council Chamber in the City of Fort Wayne

This 12th day of Sept 1911

We hereby Certify that the common Council of the city of Fort Wayne Indiana at a Regular meeting held on the 12th day of Sept 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 504

Louis D. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 16th day of Sept 1911

Wm. J. Jeffries
City Clerk

approved this 16th day of Sept 1911

Jesse Bruce
Mayor

General Ordinance no 505

An ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana

Section 1. Be it enacted by the common council of the city of Fort Wayne Ind. That the territorial limits of the city be and are hereby extended and fixed as follows:

Commencing at the intersection of the city limits at Holton ave and McKee Street. thence west to Smith street. thence South to Eckert st. thence east to Holton ave. thence north to the beginning

Be it further enacted. That the property included within the lines herein indicated shall hereafter be within the corporate limits of the city of Fort Wayne Indiana and subject to taxation for city purposes.

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

Henry W. Felger

Done at the council chamber in the city of Fort Wayne Indiana this 26th day of Sept 1911

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 26th day of Sept 1911 by a majority vote of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 505

Louis A. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 29th day of Sept 1911

Wm. J. Jeffries
City Clerk

Approved this 30th day of Sept 1911

Jesse Grice
Mayor

General Ordinance no 506

An ordinance fixing the tax levy for city purposes for the year 1911.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that a levy of one dollar and twelve cents ($1.12) upon each one hundred dollars ($100.) assessed valuation of all property within the corporate limit of the City of Fort Wayne Indiana be made for the year of 1911 That the above levy be divided as follows

General purposes and interest	.85 3/4
Sinking Fund	.05
Track Elevation Fund	.05
Municipal Electric Light Plant fund	.05
Park Fund	.05
Park fund for river Bank improvement	.04
Police Pension Fund	.01
Firemens Penson Fund	.01
Monument Fund	.00 1/4
Total	$1.12

Also that there shall be collected from each male inhabitant liable according to law a poll tax of two dollars ($2.00)

Section 2. That all taxes shall be collected in Semi-annual installments.

Sec 3. This ordinance shall be in full force and effect from and after its passage and approval by the Mayor

Harry G. Pfleger
Chas. E. Welch
Paul P. Kinder
Gust. F. Rogge
Finance committee

Done at the Council Chamber in the City of Fort Wayne Indiana this 26th day of Sept 1911

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 26th day of Sept 1911. by a Majority Vote of all the members elect did pass the ordinance hereunto attached and known as General

Ordinance no 506

Louis L. C. Schroeder
President

Wm S. Jeffries
City Clerk

Presented to the mayor for approval on the 29th day of Sept 1911

Wm S. Jeffries
City Clerk

Approved this 30th day of Sept, 1911

Jesse Bruce
Mayor.

General Ordinance No 507

An ordinance amending Section 7 of General Ordinance No 486 being "An ordinance providing for the inspection of scales. weights and measures in the City of Fort Wayne Indiana providing for the appointment of a City Sealer of weights and measures and defining his duties and Compensation: Providing penalties for the violation thereof. and fixing a time when the same is to take effect.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that Section 7 of General Ordinance No 486 being an ordinance providing for the inspection of scales weights and measures in the City of Fort Wayne Indiana. providing for the appointment of a City Sealer of weights and measures and defining his duties and Compensation: Providing penalties for the violation thereof. and fixing a time when the same is to take effect: be amended to read as follows:

Section 7. That if upon any examination. the City Sealer of weights and Measures shall find any balances. platforms. beams or any other character of scales weights and measures untrue. he shall notify the owner. or his agent and any person who shall afterward use or cause to be used condemned balances platforms. scales or measures. unless the same shall have been adjusted and stamped or branded by the City Sealer of weights and Measures. shall forfeit and pay for each offence a sum not less than $10.00. nor more than one hundred dollars ($100.00) for every day they are so used and it shall be the duty of the City Sealer of weights and measures and he shall have the power to seize said false scales. Weights. and measures. and after having the same adjusted to notify the person firm or corporation owning such scales. weights or measures. that the same have been adjusted and are held subject to the payment of the cost of adjustment and a Specified penalty thereon. and if the owner or owners of such scales shall call for the same within the thirty days succeeding the service of said notice and shall pay. the City Sealer of weights and measures the cost of such adjustment together with a penalty of ten (10) per cent on such cost.

their such scales. weights or measures shall be delivered to such owner or owners. (And if such scales. weights and measures shall not be so called for within said thirty days and said cost of adjustment and penalty be not paid aforesaid then said City Sealer of weights and measures shall sell said scales. weights or measures at public auction to the highest bidder and turn the proceeds of such sale over to the Controller of said City and any person refusing to exhibit any scales weights and measures or beams. or other weighing instruments to the City Sealer of weights and measures on his demand. for the purpose of having them so examined. shall be deemed guilty of a misdemeanor. and on conviction thereof shall be fined in any sum not less than five dollars ($5.00) nor more than one hundred dollars ($100.00).

Section 2. That this ordinance shall be in full force and effect from and after its passage approval by the Mayor and legal publication.

Harry E. Zwinger

Done at the Council Chamber in the City of Fort Wayne Indiana this 26th day of Sept 1911

We Hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 26th day of Sept 1911. by a Majority Vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 507.

Louis. J. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 29th day of Sept 1911

Wm J. Jeffries
City Clerk

approved this 30th day of Sept 1911

Jesse Grice
Mayor

General Ordinance no 508

An ordinance amending Section two of General ordinance no. 438 being an ordinance regulating wholesaling and retailing of provisions and articles of food on the Barr Street Market and providing a penalty for the violation of the provisions of the ordinance

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind That section two of General ordinance no 438 being an ordinance regulating wholesaling and retailing of provisions and articles of food on the Barr street Market and providing a penalty for the violation of the provisions of this ordinance be amended to read as follows.

Section 2. All articles intended and held for sale on said Market may be offered for sale at retail on every morning of the week except Sunday. from daylight until one O'clock p. m. of each day.

Section 3. That this ordinance be in full force and effect from and after its passage approval by the Mayor and legal publication.

P. M. Braun

Done at the Council Chambers in the City of Fort Wayne Ind this 26th day of sept 1911

We hereby certify that the Common Council of the city of Fort Wayne Ind at a Regular meeting held on the 26th day of Sept 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 508

Louis S. C. Schroeder
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval on the 29th day of Sept 1911

Wm. S. Jefferis
City Clerk

Approved this 30th day of Sept 1911

Jesse Grice
Mayor

General Ordinance no 509

An ordinance requiring Wabash Railroad Company to keep a man operating the gates from 6 A.M. to 11 P.M at the point where its right of way crosses Walton avenue.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind that Wabash Railroad Company is hereby required to employ a reliable and competent man to operate from 6:00 A.M. to 11:00 P.M. the safety gates on each side of its tracks where the same crosses Walton avenue in the aforesaid city.

Section 2. Said Company failing to have said gates operated and cared for in the manner herein provided shall be fined in the sum of Ten dollars ($10.00) on the complaint of any citizen of said City and every day the crossing is allowed to remain without a man to care for the safety-gates as herein provided shall be deemed a seperate offense. This ordinance hereby provides that ten days time shall be given to said Wabash Railroad Company to have said gates operated as herein provided

Section 3 That this ordinance shall be in full force and effect from and after its passage approval by the Mayor and legal publication

P. M. Foreman

Done at the Council Chamber in the City of Fort Wayne Ind this 26th day of Sept 1911

We hereby Certify that the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 26th Day of Sept 1911 by a Majority Vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 509

Louis S. G. Schroeder
President

Wm J. Jefferis
City Clerk

Presented to the Mayor for approval on the 29th day of Sept 1911

Wm J. Jefferis
City Clerk

Approved this 30th day of Sept 1911

Jesse Grice
Mayor

General Ordinance No 570.

An ordinance approving and ratifying a contract Made and entered into on the 10th day of Oct 1911 by and between the city of Fort Wayne Ind by and through its Board of Public works and the Fort Wayne and Northern Indiana Traction Company. relative to the construction of certain spurs and switches from its tracks on Spy run avenue to the plant of the C. L. Centlivre Brewing Company and other Matters therein contained.

Whereas heretofore on the 10th day of Oct 1911 the City of Fort Wayne by and through its Board of Public works entered into a Contract and agreement with the Fort Wayne and Northern Indiana Traction Company.

Whereas. Said Contract has been submitted by said city of Fort Wayne. by and through its Board of Public works. to the Fort Wayne & Northern Indiana Traction Company for its consideration and approval now therefor.

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that a contract heretofore on the 10th day of Oct 1911 entered into by and between the City of Fort Wayne by and through its Board of Public works and the Fort Wayne and Northern Indiana Traction Company as fully set forth in the preamble be and the same is in all things ratified and approved

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Allen Hamilton

Done at the council Chamber in the city of Fort Wayne this 10th day of October 1911

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 10th day of Oct 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 570

Louis A. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 13th day of Oct 1911

Wm J. Jeffries
City Clerk

approved this 14th day of Oct 1911

Jesse Grice
Mayor.

General Ordinance no 511

An Ordinance confirming and approving a contract and agreement entered into on the 4th day of august 1911 by and between the city of Fort Wayne. by and through its Board of Public works and the Wabash Railroad Company. a corporation by Henry Miller. its Vice president and Gunral Manager. as approved by M. S. Brown its assistant attorney. relative to the consideration by Grand street relocated. Harrison and Lolinton Streets and the vacation of Certain parts Grand Street. Webster Street. Kansas Strick. Hoagland avenue. and the separation of the grades at Fairfield avenue. Lolinton Street and Harrison street and other matters therein contained.

Whereas heretofore on the 4th day of august 1911 the City of Fort Wayne. by and through its Board of Public works entered into a contract and agreement with the Wabash Railroad Company a corporation. by Henry Miller. Its vice President and General Manager. as approved by M. S. Brown its assistant attorney Whereas said Contract and agreement has been submitted by said Board of Public Works of the city of Fort Wayne to the Common council of said city for its consideration and approval. Therefore.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind that the contract heretofore entered into by and between the city of Fort Wayne by and through its Board of Public works and the Wabash Railroad Company. as fully set forth in the preamble hereto be and the same is hereby in all things confirmed and approved

Section 2. That this Ordinance be in full force and take effect from and after its passage and approval by the Mayor

Henry G. Pinniger

Done at the Council Chamber in the City of Fort Wayne this 10th day of Oct. 1911

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 10th day of Oct 1911 by a Majority Vote of all the members elect did pass the ordinance hereunto attached and known as Gennal Ordinance no 511

Louis H. C. Schroeder President Wm. S. Jefferis City Clerk

Presented to the Mayor for approval on the 13th day of Oct 1911

Wm. S. Jefferis City Clerk

approved this 14th day of Oct 1911

Jesse Grice

Mayor.

General Ordinance No 512.

An Ordinance approving a contract entered into between the City of Fort Wayne by and through its Board of Public works and the Wabash Railroad Company relative to the condemnation of a strip of land thirty feet wide from the west line of Kansas street to the east line of Hoagland avenue for the purpose of extending Grand street relocated: releiving the city from vacating a certain part of Hoagland avenue heretofore agreed to by the city and said Company. and to the separation of grades at Broadway.

Whereas on the 18th day of September 1911 a contract was entered into between the City of Fort Wayne by and through its Board of Public works and the Wabash Railroad Company relative to extending Grand street relocated and relieving the City from vacating a certain part of Hoagland avenue and providing for the separation of the grades at Broadway. whereas said contract and agreement has been Submitted by said Board of Public works of the City of Fort Wayne to the Common council of said city for its consideration and approval: Therefore

Section 1. Be it ordained by the Common council of the City of Fort Wayne Indiana. That the contract heretofore entered into by and between the City of Fort Wayne. by and through its Board of Public works and the Wabash Railroad Company as fully set forth in the preamble hereto be and the same is hereby in all things confirmed and approved.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor

Charles W. Zittoe

Done at the Council Chamber in the City of Fort Wayne Ind this 10th day of Oct. 1911

We hereby certify that the Common comncil of the city of Fort Wayne Ind at a regular meeting held on the 10th day of Oct 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 512

Louis A. C. Schroeder President. Wm. S. Jefferis City Clerk

Presented to the Mayor for approval on the 13th day of Oct 1911

Wm. S. Jefferis City Clerk

Approved this 14th day of Oct 1911

Jesse Grice

Mayor.

General Ordinance 513

An ordinance amending Sections 32 and 33 of General Ordinance no 438 being "An Ordinance regulating the wholesaling and retailing of provisions and articles of food upon the Barr Street market and providing a penalty for the violation of the provisions of the ordinance.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne. That Section 32 of General Ordinance no 438 being an ordinance regulating wholesaling and retailing of provisions and articles of food upon the Barr Street Market and providing a penalty for the violation of the provisions of this ordinance be amended to read as follows:

Section 32 It shall be the duty of the Market Master to assign any person who shall desire it for the purpose of selling at retail his wares or produce any stall or stand not rented or occupied and collect therefor the sum of twenty cents (.20¢) per day

Section 2. That Section 33 of General Ordinance no 438 being an ordinance regulating wholesaling and retailing of provisions and articles of food upon the Barr Street Market and providing a penalty for the violations of the provisions of this ordinance be amended to read as follows:

Section 33. That the rental price for the use of the Stands or Stalls in the covered Market for Tuesdays Thursdays and Saturdays shall be Twenty dollars ($20.00) per annum. however no Stand in Covered Market to be rented for less than a period of one year unless otherwise herein provided.

Section 3. That this ordinance shall be in full force and effect from and after its passage and approval by the Mayor

Louis S. C. Schroeder.

Come at the Council Chamber in the City of Fort Wayne this 24th day of Oct 1911

We Hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 24th day of Oct 1911 by a Majority vote

of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 573

Louis H. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 27th day of Oct 1911

Wm. J. Jeffries
City Clerk

approved this 27th day of Oct 1911

Jesse Price
Mayor

General Ordinance no 514

An ordinance authorizing the Board of Public works of the Ceity of Fort Wayne to furnish water to the Parochial Schools of the Ceity for the price of .2¢ per thousand gallons

Section 1. Be it ordained by the Common Council of the Ceity of Fort Wayne that the Board of Public works be authorized and empowered to furnish water from the Ceity water works Department. to any church association for water to be used in the parocial Schools for the price of two (2) cents per 1000 gallons and said Board shall not be compelled to account or pay for water so furnished except at the prices herein provided

Section 2. Be it further provided that the Board of Public works shall require such water to be measured by a meter to be installed and furnished by said school and inspected by said Ceity

Section 3. This ordinance to be in full force and effect from and after its passage approval by the Mayor and legal publication

Paul-P. Kinder

Done at the Council Chamber in the Ceity of Fort Wayne this 24th day of Oct 1911

We hereby Ceirtify That the Common Council of the Ceity of Fort Wayne Indiana at a Regular meeting held on the 24th day of Oct 1911 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 514

Louis D. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 27th day of Oct 1911

Wm S. Jefferies
City Clerk

approved this 27th day of Oct 1911

Jesse Grice
Mayor

General Ordinance no 515

An ordinance to license and regulate itinerant Vendors

Section 1. Be it ordained by the common council of the city of Fort Wayne Ind. That no person shall engage in the business or trade of an itinerant vender without having first obtained a license from the city Controller.
Section 2. The words "itinerant Vendor" shall be contorued to mean and include all persons. firms or corporations who themselves or by their agents engage in a temporary or transient business in the city of Fort Wayne selling goods wares and Merchandise. and who. for the purpose of the securing of such business. hires. leases or occupies any room. building or Structure for the occupation or sale of such goods. wares or merchandise: and the person or firm so engaged shall not be released from the provisions of the ordinance by reason of association temporarily with any local dealer. trader. Merchant or auctioneer. or by conducting such temporary or transient business in connection with or as a part of the business of or in the name of any local dealer. trader. Merchant or auctioneer.
Section 3. The provisions of this ordinance shall not apply to bona fide sales of goods. wares and Merchandise by Samples for future delivery by commercial travelers or selling agents or to hawkers on the streets. or to peddlers from vehicles or baskets or packs carried on backs. or to sheriffs. constables. or other public officers selling goods wares. Merchandise according to law. nor to bona fide assignees or receivers appointed in the state. selling goods wares Merchandise for the benefit of creditors.
Section 4. any itinerant Vendor desiring to engage in do or transact business in Fort Wayne Indiana shall file his application for a license for that purpose with the controller of the city which application shall state his name his proposed place of business. the kind of business proposed to be conducted and the length of time for which he desires to do business. such itinerant vendor shall pay to the city controller a license fee of One hundred dollars per day for the days or any part thereof for which application is made who shall thereupon issue to said itinerant Vendor a license to do business as such at the

place discribed in his application and the kind of business discribed therein and for the length of time for which payment is made to the city controller aforesaid. No license shall be good for more than one person unless such person shall be co-partners nor for more than one place. or authorize any other person than the one mentioned therein to sell. or authorize any other class of articles than Specified in the application. The city controller shall keep a record of such license in a book provided for that purpose which shall at all times be open to public inspection

Section 5. Every person. firm or corporation. either a principal or agent who shall in any manner engage in do or transact any business as an itinerant Vendor without having first obtained a license as before provided. or who shall conduct any sale or who shall sell or expose for sale any goods. wares and merchandise contrary to the provisions of this ordinance or who shall advertise. represent or hold forth any sale of goods. wares and Merchandise to be conducted contrary to the provisions of this ordinance. shall be punished by a fine not to exceed one hundred dollars. and the Mayor may on proof of such violation of any person licensed under this ordinance. revoke the license issued to the Vendor to which may be added imprisonment for not less than ten days and not more than thirty days.

Section 6. This ordinance shall be in full force and effect from and after its passage and approval by the Mayor and legal publication

Louis H. C. Schroeder.

Done at the council chamber in the city of Fort Wayne Indiana the 14th day of Nov 1911

We hereby Certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 14th day of Nov 1911 by a Majority vote of all the Members elect. did pass the ordinance hereunto attached and known as General Ordinance No 515

Louis H. C. Schroeder President Wm. J. Jefferies City Clerk

Presented to the Mayor for approval on the 17th day of Nov 1911

Wm. J. Jefferies City clerk

approved. this 18th day of Nov 1911

Jose Price

Mayor

General Ordinance No 516.

An ordinance making it unlawful for any person firm or corporation to conduct a parade through the streets of Fort Wayne for the purpose of gain on decoration day.

Section 1. Be it ordained by the common council of the City of Fort Wayne Ind that it is hereby made unlawful for any person firm or corporation to conduct a circus show or theatrical parade for the purpose of gain on the 30th day of May commonly called decoration day that will in any way obstruct or interfere with the parade or procession of the Soldiers Organization or any other Organization that may have in charge the proper and usual Celebration for that day.

Section 2. Any person firm or corporation violating the provisions of this ordinance shall be fined in any sum not more than one hundred dollars.

Section 3. That this ordinance shall be in full force and effect from and after its passage approval by the Mayor and legal publication

Paul .P. Kunder

Done at the council chamber in the city of Fort Wayne Ind this 14th day of Nov 1911

I We hereby Certify that the common council of the City of Fort Wayne Ind at a regular meeting held on the 14th day of Nov 1911 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 516

Louis D. Co. Schneider
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 17th day of Nov 1911

Wm J. Jeffries
City Clerk

approved this 18th day of Nov 1911

Josh Grice
Mayor

General Ordinance no 517

An ordinance authorizing the alienation by the Mayor of certain personal property.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind. That the Mayor be and is hereby authorized to alienate. sell and dispose of for said city a covered and uncovered patrol wagon formerly used by the Police Department but now stored at no 3 Engine House and one road wagon now stored in the barn adjoining the City Hall.
Section 2. That the City attorney be authorized to apply to the Judge of the Circuit court for the appointment of appraisers and that said sale be made after said appraisement according to law.
Section 3. That this ordinance be in full force and effect from and after its passage. approval by the Mayor and legal publication

Allen Hamilton

Done at the Council Chamber in the City of Fort Wayne Indiana this 14th day of Nov 1911

We Hereby Certify that the Common Council of the City of Fort Wayne did at a Regular Meeting held on the 14th day of nov 1911 by a majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 517

Louis S. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 17th day of Nov 1911

Wm S. Jefferies
City Clerk

approved this 18th day of nov 1911

Jesse Grice
Mayor

General Ordinance 518

An ordinance approving and ratifying a contract Made and entered into on the 30th day of Oct 1911 by and between the City of Fort Wayne Ind by and through its Board of Public works and the Fort Wayne & Northern Indiana Traction Company relative to the construction of a certain spur and switch on its tracks on Superior Street to the property of G. E. Bursley & Company and other matters therein contained

Whereas heretofore on the 30th day of Oct 1911 the city of Fort Wayne by and through its Board of Public Works entered into a contract and agreement with the Fort Wayne & Northern Indiana Traction Company.

Whereas said contract has been submitted by said city of Fort Wayne by and through its Board of Public Works to the Common Council for its consideration and approval

Now Therefore

Section 1. Be it ordained by the Common Council of the city of Fort Wayne. That a contract heretofore on the 30th day of Oct 1911 entered into by and between the city of Fort by and through its Board of Public Works and the Fort Wayne & Northern Indiana Traction Company as fully set forth in the preamble be and the same is in all things approved

Section 2. That this ordinance be in full force and effect from and after its passage. approval by the Mayor and legal Publication

Charles W. Settles

Done in the Council Chamber in the city of Fort Wayne this 28th day of Nov 1911

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 28th day of Nov 1911 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 518

Louis H. C. Schroeder
President

Wm. S. Jefferies
City Clerk

Presented to the Mayor for approval on the 1st day of Dec 1911

Wm. S. Jefferies City Clerk

Approved this 1st day of Dec 1911

Jesse Grice Mayor.

General Ordinance No 519

An ordinance authorizing the employment of one detective Sergeant and five additional Policemen by the Board of Public Safety and fixing the salary of each.

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana That the Board of Public Safety of said City be authorized to employ one detective Sergeant to whom shall be paid a salary of $85.00 per month from the 1st day of January 1st 1912 and five additional Policeman to whom shall be paid a salary of $65.00 per month each. from the 1st day of January 1912 as provided by General Ordinance No 450

Section 2. That this Ordinance be in full force and effect from and after its passage and approval by the Mayor.

P. M. Braun.

Done at the Council Chamber in the City of Fort Wayne Indiana this 12th day of Dec 1911

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 12th day of Dec 1911. by a Majority vote of two thirds of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 519

Louis H. C. Schroeder
President

Wm J. Jefferis
City Clerk.

Presented to the Mayor for approval on the 16th day of Dec 1911

Wm J. Jefferis
City Clerk

approved this 14th day of Dec 1911

Jesse Grice
Mayor

General Ordinance No 520

An ordinance authorizing the employment of five additional firemen by the Board of Public Safety and fixing the salary of each

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana the the Board of Safety of said City be authorized to employ five additional firemen to whom shall be paid a salary of $65.00 per month each from the 1st day of January 1912 as provided by appropriation Ordinance No 450

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor.

Harry C. Pflieger

Done at the Council Chamber in the City of Fort Wayne Indiana this 12th day of Dec 1911

We hereby Certify That the Common Council of the city of Fort Wayne Indiana at a Regular Meeting held on the 12th day of Dec 1911 by a Majority vote of two thirds of all the Members elect did pass the ordinance hereunto attached and known as Genral Ordinance 520

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 16th day of Dec 1911

Wm. J. Jeffries
City Clerk

approved this 19th day of Dec 1911

Jesse Brice
Mayor

General Ordinance No 521

An Ordinance authorizing the employment of an engineer and fixing his salary.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne and that the Board of Public works of said city be authorized to employ an assistant engineer subject to the approval of the city engineer who shall be paid a salary of Two Thousand dollars ($2000.00) per annum

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor

Edward E. Wilde

Done at the council chamber in the City of Fort Wayne this 9th day of June, 1913.

We hereby certify that the common council of the City of Fort Wayne took at a regular meeting held on the 9th day of June, 1913 by a majority vote of all the members elect this pass the ordinance hereinto attached and known as General Ordinance No 521

Louis E. Schneider
President

Wm. J. Griffin
City Clerk

Presented to the Mayor for approval on the 10th day of June, 1913.

Wm. J. Griffin
City Clerk

Approved this 13th day of June, 1913.

Edward E. Wilde
Mayor

General Ordinance No 522.

An ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne and William H. Lemon on the 20th day of December 1911 relative to the purchase by the city of coal

Whereas heretofore on the 20th day of December 1911 the city of Fort Wayne entered into a contract with William H. Lemon providing for the purchase of twelve thousand tons of coal by the city

Section 1. Be it ordained by the Common Council of the City of Fort Wayne and IT IS the contract heretofore entered into on the 20th day of December 1911 by and between the city of Fort Wayne and William H. Lemon as more fully set out in the preamble hereto be and the same is in all things confirmed and approved

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles C. Welch

Passed at the council chamber in the City of Fort Wayne this 9th day Jan 1912

We hereby certify that the Common Council of the City of Fort Wayne met at a Regular Meeting held on the 9th day of Jan 1912 by a majority vote of all the members that did pass the ordinance hereto attached and known as General Ordinance No 522.

Louis K. L. Schmidt
President.

Wm. J. Hoffman
City Clerk.

Presented to the Mayor for approval on the 13th day of January 1912

Wm. J. Hoffman
City Clerk

Approved this 13th day of Jan 1912

Jesse Grice
Mayor.

General Ordinance no 523

An ordinance ratifying and approving a contract intered into on the 26th day of December 1911 by and between the City of Fort Wayne and the Kaough coal co

Whereas. heretofore on the 26th day December 1911 the city of Fort Wayne Ind by and through its Board of Public works entered into a contract with the Kaough coal co providing for the purchase of its year supply of coal to be used at its number 2 pumping station

Section 1. Be it ordained by the common council of the city of Fort Wayne Ind that the contract heretofore entered into on the 26th day of December 1911 by and between the city of Fort Wayne and the Kaough coal company. as fully set out in the preamble hereto. be and the same is in all things confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

P. M. Braun

Done at the council chamber in the city of Fort Wayne Indiana this 9th day of January 1912

We hereby Certify That the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 9th day of January 1912 by a Majority vote of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 523

Louis S. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 13th day of January 1912

Wm. J. Jefferies
City Clerk

Approved this 13th day of Jan 1912

Jesse Grice
Mayor

General Ordinance No 524

An ordinance approving a contract entered into on the 14th day of December 1911 by and between the city of Fort Wayne party of the first part and Fort Wayne Electric works party of the second part.

Whereas on the 14th day of December 1911 the city of Fort Wayne by and through its Board of Public works entered into a contract with Fort Wayne Electric works for furnishing Meters

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered in to by and between the city of Fort Wayne and Fort Wayne Electric works on the 14th day of Dec 1911 as more fully set out in the preamble hereto be in all things fully confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Allen Hamilton

Read at the council chamber in the city of Fort Wayne and this 9th day of Jan 1912

We hereby certify that the common council of the city of Fort Wayne did at a regular meeting held on the 9th day of Jan 1912 by a Majority vote of all the members elect duly pass the ordinance hereunto attached and known as General Ordinance No 524

Louis D. C. Schroeder
President

Wm J. Jeffries
City Clerk.

Presented to the Mayor for approval on the 13th day of January 1912

Wm J. Jeffries
City Clerk

Approved this 13th day of January 1912

Allen Hamilton
Mayor

General Ordinance no 525

An ordinance approving a contract entered into on the 14th day of December 1911 by and between the city of Fort Wayne party of the first part. and Fort Wayne Electric works. party of the second part.

Whereas on the 14th day of December 1911 the city of Fort Wayne by and through its Board of Public works entered into a contract with Fort Wayne Electric works for furnishing transformers.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. That the contract heretofore entered into by and between the city of Fort Wayne and Fort Wayne Electric works on the 14th day of December 1911 as more fully set out in the preamble hereto be in all things fully confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

P. M. Brann.

Done at the council chamber in the city of Fort Wayne Indiana at a Regular meeting held on the 9th day of January 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 525

Louis S. C. Schroeder
President

Wm. S. Jefferis
City clerk

Presented to the Mayor for approval on the 13th day of January 1912

Wm. S. Jefferis
City Clerk

approved this 13th day of Jan 1912

Jesse Grice
Mayor

General Ordinance No 526

An ordinance authorizing the alienation of certain personal property and ordering an appraisement of same

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that the Mayor be and he is hereby authorized to sell one Sorrel Horse (Leick) of no 2 Engine House one Sorrel Horse (Leick) of no 4 Engine House. 2 Sorrel Horses (Pete and Jess) of no 6 Engine House: Two bay horses (George and Lewey) of no 5 Engine House and one chiefs or asst. chiefs Horse and Buggy and one old Hose wagon at no 3 Engine House: and to sign any and all necessary instruments to consummate such sale: provided that such sale shall not be made until said property has been appraised by appraisers appointed by the Judge of the Allen Circuit Court.
Section 2: That the City attorney be and he is hereby authorized to petition the Judge of the Allen County circuit court for the appointment of three appraisers to appraise the property referred to in section 1 of this ordinance
Section 3. That this ordinance shall be in full force and effect from and after its passage and approval by the Mayor

Charles W. Lettick

Done at the Council Chamber in the City of Fort Wayne Indiana this 22d day of January 1912

We hereby certify That the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 23d day of Jan 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 526

Louis S. & Schroeder
Presidents

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 26th day of Jan 1912

Wm J. Jeffries
City Clerk

Approved this 27th day of Jan 1912

Josh Grice
Mayor

General Ordinance No 527.

An ordinance districting all the territory within the corporate limits of the City of Fort Wayne Indiana into Park districts. to be known as North east park district. North west park district South west park district and South east park district. defining and discribing the boundaries thereof and designating the same by names.

Whereas. The Board of Park Commissioners at their regular meeting held on the 8th day of January 1912 have passed a resolution dividing the Corporate limits of the city of Fort Wayne Indiana into four park districts Namely:- North east park district: North West Park District: South West Park District and South East Park District. Therefore

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that all the territory now lying within the Corporate limits of said City. be districted and divided into four Park Districts. each of said districts to consist of the following described territory according to their names and their respective descriptions hereinafter set forth The North East Park District as follows. To wit

North East Park District

Commencing at the intersection of the center line of Calhoun Street and the South right of way line of Pittsburg Fort Wayne and Chicago Railway as now located: thence in an easterly direction and along said South right of way line to its intersection with the center line of Hanna Street: thence in a northerly direction and along the center line of Hanna Street to a point where said center line intersects the north right of way line of the Wabash Railroad as now located. lying east of Hanna Street. produced west to the center line of Hanna Street: thence in an easterly direction and along the said north right-of-way line to its intersection with the present East City limits: thence in a northerly and westerly direction along the present east and north City limits to its intersection with the west property line of the Lake Shore and Michigan Southern Railway as now located: thence in a Southerly direction and along said west property line to its intersection with the center line of North Calhoun Street produced South: thence in a Southerly direction and along said center line to the west side of the St. Marys River: thence in a North Easterly direction to where the center line of South Calhoun Street intersects the East

side of the St. Marys River: Thence in a Southerly direction and along the center line of South Calhoun Street to the place of beginning. The North west Park District as follows "to wit":

North West Park District

Commencing at the intersection of the center line of Calhoun Street and the South right of way line of the Pittsburg Fort Wayne and Chicago Railway as now located: thence in a northerly direction and along the center line of Calhoun street to where said center line of Calhoun Street intersects the East side of St Marys River: Thence in a South Westerly direction and across the St Marys River to where the center line of North Calhoun Street produced South intersects the west side of the St. Marys River: thence in a Northerly direction and along said center line of said North Calhoun street to the South west and North east property line of the Lake Shore and Michigan Southern Railway as now located: Thence in a Northerly direction and along the said South west and North east property line of said Railway to its intersection with the present North City limits: Thence in a westerly and Southerly direction and along the present North and west City limits to its intersection with the South right of way line of the Pittsburg Fort Wayne and Chicago Railway as now located: thence in an easterly direction and along said South right of way line to the Place of beginning. The South West Park District as follows "to wit"

South West Park District

Commencing at the intersection of the center line of Calhoun Street and the South right of way of the Pittsburg Fort Wayne and Chicago Railway as now located: Thence in a Westerly direction and along said South right of way line to its intersection with the present west City limits: thence in Southerly and Easterly direction along the present west and South City limits to its intersection with the center line of Calhoun Street: Thence in a Northerly direction and along the center line of Calhoun street to the place of beginning. The South east park District as follows "to wit"

South East Park District

Commencing at the intersection of the center line of Calhoun Street and the South right of way line of the Pittsburg Fort Wayne and Chicago Railway as now located

thence in a Southerly direction and along said center line of Calhoun Street to its intersection with the present South City limits: thence in an easterly and northerly direction along the present South and East City limits to its intersection with the North right of way line of the Wabash Railroad as now located thence in a westerly direction along said north right of way line to its intersection with the center line of Hanna Street: thence in a Southerly direction and along the said center line of Hanna Street to a point where said center line intersects the South right of way line of the Pittsburg Fort Wayne and Chicago Railway. as now located thence West & N. and East parallel to the center line of Hanna Street: thence in a Westerly direction and along the said right of way line to the place of beginning.

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor

P. M. Braun

Done at the Council Chamber in the City of Fort Wayne Indiana this 23rd day of January

We hereby certify that the Common Council of the City of Fort Wayne did at a Regular meeting held on the 23rd day of January 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 527

Louis S. C. Schroder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 26th day of January 1912

Wm. J. Jeffries
City Clerk

Approved this 27th day of January 1912

Jesse Brice
Mayor

General Ordinance no 528

An ordinance fixing the Compensation of certain employees of the water Works Department and authorizing the payment of the same by the Board of Public works.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind that certain employees of the water works be paid the salaries therein set out and that the Board of Public works be authorized to pay the same.
The two watchmans and meter tenders at no 3 Pumping Station at the rate of fifty five dollars per month each
For the foreman of the Maintenance and Construction Department of the water works Department at the rate of one hundred dollars ($100.00) per month.
Section 2. This ordinance to repeal all parts of any ordinance in conflict herewith.
Section 3. This ordinance to be in full force and effect from and after its passage approval by the Mayor and legal publication

Charles W. Zuttor

Done at the Council Chamber in the City of Fort Wayne Indiana this 23d day of January 1912

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 23d day of January 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 528

Louis S. C. Schroeder
President

Wm S. Jefferis
City Clerk

Presented to the mayor for approval on the 26th day of January 1912

Wm S. Jefferis
City Clerk

Approved this 27th day of January 1912

Lesse Bruce
Mayor

General Ordinance no 529

An ordinance approving and ratifying a certain contract entered into by and between the city of Fort Wayne by and through its city Controller and the Fort Wayne Printing Company for the printing and binding of the revision of the city ordinances.

Whereas heretofore on the 9th day of January 1912 the city of Fort Wayne Indiana by and through its city Controller entered into a contract with the Fort Wayne Printing Company relative to the printing and binding of the revision of the city ordinances

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that the Contract heretofore entered into on the 9th day of January 1912 by and between the city of Fort Wayne by and through the city Controller and the Fort Wayne Printing Company as fully set out in the preamble hereto be and the same is in all things ratified and approved

Section 2 This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles W Zetter

Done at the Council Chamber in the City of Fort Wayne this 23d day of January 1912

We hereby Certify That the Common Council of the city of Fort Wayne did at a Regular Meeting held on the 23d day of January 1912 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 529

Louis B. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval this 26th day of January 1912

Wm. J. Jefferies
City Clerk

Approved this 27th day of January 1912

Jesse Eisen
Mayor

General Ordinance no 530

An ordinance fixing the salary of the clerk of the health Department.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana That the salary of the Clerk of the Health Department be fixed at the sum of Forty five Dollars ($45.00) per month and that the department of health be and are hereby authorized to pay the same
Section 2. This ordinance shall repeal all parts of any ordinance in conflict herewith
Section 3. That this ordinance be in full force and take effect from and after its passage and approval by ~~this~~ Mayor and legal publication

H. W. Felger

Done at the Council Chamber in the City of Fort Wayne Ind this 13th day of Feb 1912.

We hereby Certify That the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 13th day of Feb 1912 by a Majority vote of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 530.

Louis S. C. Schroder
President

Wm. S. Jeffries
Wm. S. Jeffries

Presented to the Mayor for approval on the 16th day of Feb 1912

Wm. S. Jeffries
City Clerk

approved this 16th day of Feb 1912

Jesse Grice
Mayor

General Ordinance no 531

An ordinance approving a contract entered into on the 26th day of December 1911 by and between the city of Fort Wayne party of the first part and David M. Winburn party of the second part. relative to the collection of Garbage

Whereas on the 26th day of December 1911 the city of Fort Wayne by and through its board of Public works entered into a Contract with David M. Winburn for the collection of garbage tin cans. glassware etc. which contract is as follows

This agreement. made this 26th day of December 1911 by and between the City of Fort Wayne by and through its Board of Public works party of the First part. for convenience hereinafter known as "City" and David. M. Winburn of the City of Fort Wayne Indiana party of the second part for convenience hereinafter known as Contractor. Witnesseth:

That for the consideration hereinafter set out. the Contractor hereby agrees to collect and remove all kitchen garbage tin cans broken dishes. glassware table. household and general refuse in said City of Fort Wayne. during the year 1912 as more fully set out in the Specifications which for identification have been signed by the parties hereto which Specifications are hereby made a part of this contract and all the conditions terms and provisions of said Specifications shall be complied with and performed by the parties hereto the same as if such Specifications and provisions were set forth in full in the body of this contract. In the event of any conflict between the terms and provisions in this Contract and the provisions of said Specifications the former shall control.

In consideration of the covenants and agreements herein expressed. The City agrees to pay said contractor the sum of Eleven Thousand two hundred and fifty dollars ($11250.00) which sum is to be paid in equal monthly installments at the end of each month for the work performed under this contract during such month less such deductions as said city may be authorized to make under the provisions of this Contract.

It is further agreed by the parties hereto that this contract shall not be assigned by said contractor in whole or in Part without the written consent of said Board of Public works and the said contractor shall and hereby agrees to

furnish a bond in the sum of Four Thousand dollars ($4000.00) Satisfactory to said city conditioned that he will faithfully comply with and carry out the terms and stipulations of the contract.
Said contractor agrees that he will keep in service during the months of May. June. July. august. September and October not less than ten (10) garbage wagons of the regulation size. drawn by two horses. and during the other remanning months of the year he will keep in services not less than seven (7) of such wagons. in addition to the wagons to be kept in service by the contractor as here in set out. He will also keep in service during the entire year two (2) other wagons one of which shall be a light wagon which shall contain a metal box which will hold about six (6) ordinary cans of garbage which wagon is to be used as a call wagon where garbage has been overlooked and missed by the regular collector. It is also to be used by the contractor or an overseer appointed by him to go over the entire city for the purpose of seeing that the collections of the garbage as herein provided is being properly done and said overseer or driver of said wagon is to report at the office of the board of Public works each day. to secure a list of any complaints that may have been made for failure to collect garbage. so that the same can be cared for by him. The second wagon is to be. in addition to the regulation garbage wagon and "call" wagon used for the purpose of collecting tin cans. dishes. glassware Etc as more fully set out in said Specifications.
It being understood that the contractor and his drivers and employees will while in the execution of the written contract obey and conform to all said ordinance and for any violation of the same the contractor will be liable on his bond for the payment of any penalties that may be found against him or his employees. It being also understood that the contractor will see to it that the top of the wagons used by him in carrying garbage shall be covered at all times while the same are passing through the streets and shall at no time be so loaded that the cover cannot be closed. It is further understood that he will see to it that his employees and drivers

will report to the Board of Health all places where proper receptacles for the holding of garbage are not provided. or any other violation of any other city ordinance relating to the Manner in which garbage shall be kept by the householder for which purpose each employee of said contractor shall be supplied by said contractor. with a book containing blank slips or notices on which shall be placed the name and address of the offender and the same turned in to the superintendent of the Crematory. It is also understood that said contractor will file with the Board of Public works a routing showing the said points the way and detail in which the route is covered by the driver so that the driver of any garbage wagon can be found practically at any time be consulting the route sheet; Contractor agreeing not to make any change in such route until the same is appoved by the Board of Public works for any failure to file said routing or to follow the same or for making any changes therein without first receiving permission from said city. or for failing to collect garbage properly. as herein provided. said contractor agrees that he shall pay to the city as liquidated damages the sum of one dollar ($1.00) for each and every failure or violation of said provision.

It is further understood that the city may at any time arrange for and order the contractor to haul the garbage so collected at points other than the crematory. without any additional consideration being paid to said contractor. provided that said change of the place of delivery shall not increase the distance of the haul of said contractor.

Witness our hands and seals the day and year first above written

City of Fort Wayne by.
Frank. J. Benoy
G. A. Schwegmann
E. J Lennon
Its Board of Public works

David. M. Winburn

attest H. W. Becker
Clerk

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana That the contract heretofore entered into by and between the city of Fort Wayne and David M. Winburn on the 26th day of December 1911 as more fully set out in the preamble hereto be in all things fully confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

P. M. Braun

Done at the Council Chamber in the City of Fort Wayne Indiana this 12th day of Feb 1912

We hereby certify that the common council of the city of Fort Wayne Indiana at a regular meeting held on the 13th day of Feb 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 531

Louis H. C. Schroeder
President

Wm. S. Jefferies
City Clerk

Presented to the Mayor for approval on the 16th day of Feb 1912

Wm. S. Jefferies
City Clerk

approved this 16th day of Feb 1912

Jesse Grice
Mayor

General Ordinance No 532

An ordinance approving and ratifying a certain contract entered into by and between the city of Fort Wayne and the Fort Wayne and Northern Indiana Traction company for the laying of certain tracks on Ewing and Webster streets between Main and Pearl Streets. certain curves and switches for same and for the construction of certain Y's for the operation of "Pay as you enter cars"

Whereas on the 9th day of January 1912 the beity of Fort Wayne entered into a contract with the Fort Wayne and Northern Indiana Traction Company for the laying of certain tracks on Ewing and Webster streets between Main and Pearl Streets certain curves and switches for same and for the construction of certain Y's for the operation of "Pay as you enter cars"

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered into by and between the beity of Fort Wayne and the Fort Wayne and Northern Indiana Traction Company on the 9th day of January 1912 as more fully set out in the preamble hereto be in all things confirmed and approved

Section 2. That the ordinance be in full force and take effect from and after its passage approval by the mayor and legal Publication

Charles W. Zittlar

Done at the council chamber in the city of Fort Wayne Indiana this 13th day of February 1912.

We hereby certify that the common council of the city of Fort Wayne Ind at a regular meeting held on the 13th day of February 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 532

Louis S. B. Schroeder
President

Wm. S. Jefferis
City Clerk

Presented to the mayor for approval on the 16th day of February 1912

Wm. S. Jefferis City Clerk

Approved this 16th day of February 1912

Jesse Grice
Mayor

General Ordinance no 533

An ordinance approving a contract entered into on the 8th day of January 1912 by and between the city of Fort Wayne by and through its Board of Public Safety party of the first part. and the Safety insulated wire and Cable company of New Jersey party of the second part.

Whereas on the 8th day of January 1912 the city of Fort Wayne by and through its Board of Public Safety entered into a contract with the Safety insulated wire and cable company of New Jersey for the Manufacture delivery and installing the Underground alloy covered cables for the signal and Telephone circuits for the Fire Department.

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that the contract heretofore entered into by and between the city of Fort Wayne and the Safety insulated wire and Cable company of New Jersey on the 8th day of January 1912 as more fully set out in the preamble hereto be in all things fully confirmed and approved

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles E. Welch

Done at the council chamber in the city of Fort Wayne Indiana this 13th day of Feb 1912

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 13th day of Feb 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 533

Louis S. E. Schroeder
President

Wm. J. Jeffries
City clerk

Presented to the Mayor for approval on the 16th day of Feb 1912

Wm. J. Jeffries
City clerk

Approved this 16th day of Feb 1912

Jesse Grice
Mayor

General Ordinance 534

An ordinance regulating the trimming. removal. planting and cutting of trees. shrubs. vines. hedges and plants within the limits of public streets. alleys. thoroughfares. lawns and parks conferring authority over the same upon the Board of park commissioners providing for the issuance of licenses to tree trimmers and the assessment of fines for violation thereof.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana That the Board of park Commissioners shall have power from time to time to adopt and enforce rules. regulations and specifications for the trimming. removal and planting and protection of all trees. shrubs. vines flowers. hedges and plants within the limits of any public street alley thoroughfare or lawn in said city. and shall have power to regulate and prescribe terms and conditions upon which permits to trim. remove or plant any such trees shrubs. vines. flowers or plants within said city shall be granted.

Section 2. That hereafter it shall be unlawful for any person firm or corporation to trim. remove or plant. injure or destroy any tree. vine. shrub. flower or plant within the limits of any public streets. alley. thoroughfare. lawn park parkway. or boulevard without first obtaining written permission from the board of park commissioners of the city of Fort Wayne.

Section 3. That said Board of Park Commissioners shall hereafter be empowered and authorized to require the owner or occupant of property. abutting any street or alley to remove or trim any tree, shrub. vine. flower or plant or part thereof. in front of the property of any such owner or occupant which may be dead or in unsightly or in a dangerous condition or which may project over such street beyond the property line of such owner or occupant. to a height of ten (10) feet or less. according to size or any tree obstructing the free passage of pedestrians on the sidewalk by first causing notice to be served upon such owner or occupant of the premises adjoining said street or alley ten (10) days prior to the time designated for the removal or trimming of any such tree. shrub. vine. flower or plant. and said Board shall have power to require the owners or occupants of property abutting any street or alley to plant such trees. vines flowers and plants in front of the property

of any such owner or occupant as said board shall deem advisable by first causing notice to be served upon such owner or occupant of the premises adjoining any street or alley in said city sixty (60) days prior to the time designated for the planting of such trees. Vines. flowers or plants. If after sixty (60) days from the service of such notice any such owner or occupant shall fail or refuse to so plant such trees. Vines. flowers, or plants then said board of Park Commissioners may plant the same and the expense thereof shall become a lien against the adjoining property as provided by section 234 of the act of the General assembly of Indiana of 1905 entitled "an act concerning Municipal corporations"

Section 4. It shall be unlawful for any person to engage in the business of planting. cutting. removing. trimming or spraying trees. shrubs. vines. etc. in the city of Fort Wayne without first procuring from the city controller on an application approved by the Board of Park Commissioners a license each year authorizing any such person so to engage in any such business. And said Board of Park Commissioners shall not approve of any such application without first being satisfied of the competency of the applicant to engage in such business. Upon the issuance of such license by the City controller. the applicant shall pay a license fee of one dollars ($1.00) which shall entitle him to conduct any such business during the calender year within which the license is issued. The board of park commissioners within said city shall have power to revoke any such license whenever it shall appear to such board that the licensee has violated any of the rules of said board which may be adopted in accordance with the provisions of this ordinance or has violated any ordinance of such city or any laws of the state of Indiana pertaining to the care preservation. trimming or removal of trees. etc. in such city.

Section 5. Any person firm or corporation Violating any of the provisions of this ordinance shall be fined in any sum not less than one dollar ($1.00) nor not more than twenty five dollars ($25.00).

Section 6. Any laws or parts of laws in conflict herewith are hereby repealed

Section 7. This ordinance to be in full force and effect

from and after its passage and approval by the Mayor and legal publication

E. A. Wagner.

Done at the Council Chamber in the City of Fort Wayne and this 12th day of March 1912

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 12th day of March 1912 by a Majority Vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 534

Louis S. E. Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval on the 15th day of March 1912

Wm. S. Jeffries
City Clerk

Approved this 15th day of March 1912

Jesse Grice
Mayor

General Ordinance No 535

An ordinance providing for the better protection of property by fire

Section 1. Limits to approaching fire.

Be it ordained by the Common Council of the City of Fort Wayne Indiana That the Chief of the Fire Department or assistant in charge at any fire, may prescribe limits in the vicinity of such fire, within which no person except those whose property may be within such limits. Shall be allowed unless by permission of said chief or assistant in charge or the chief or captain of Police of the City: and it shall be the duty of the police force of the City to enforce the orders of said chief or the chief or Captain of Police respecting the occupation of said limits during the progress of the fire. Every person who may be present at such fire shall be subject to the orders of said chief or assistant in charge or chief or Captain of Police of the City. and shall do and perform such duty as may be required of him by either of said officers in the extinguishing of such fire or the removal or protection of property endangered thereby. Any person violating any of the provisions of this section or who shall disobey the orders given him by either of said Officers. or failing to perform such duties as may be required by him by either of said Officers. shall be deemed guilty of a Misdemeanor and upon conviction shall be fined in any sum not less than five dollars nor more than twenty five dollars at the discretion of the court.

Section 2. Investigation of cause of fire

It shall be the duty of the chief or assistant in charge of any fire to make prompt and through investigation of the cause of such fire: and for that purpose he is hereby authorized to requist the Mayor to require the attendance of witnesses and the production of books and papers property. or other evidence. at such time and place as shall be deemed by the Mayor convenient and proper such witnesses shall be required to give their evidence under oath which shall be reduced to writing and placed on file with the chief: And a record of such proceedings shall be kept by said officers and shall be authenticated by the chief or assistant Making

the investigation
Section 3. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

H. W. Fetzer.

Leone at the council chamber in the city of Fort Wayne Ind this 12th day of March 1912

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 12th day of March 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance 535

Louis S. B. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 13th day on March 1912

Wm. J. Jeffries
City Clerk

Approved this 15th day of March 1912

Jesse Grice
Mayor

General Ordinance no 536

An ordinance amending Sections one (1) and two (2) of General Ordinance no 573. and an ordinance amending Sections thirty two (32) and thirty three (33) of General Ordinance no 438 being "an Ordinance regulating the wholesaling and retailing of provisions and articles of food on the Barr street Market and providing a penalty for the provisions of this ordinance"

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana That section one of General Ordinance no 573 being an ordinance amending section thirty two (32) and thirty three (33) of General Ordinance no 438 being an ordinance regulating the wholesailing and retailing of provisions and articles of food on the Barr street Market and providing a penalty for the provisions of the ordinance" be and the same is hereby amended to read as follows:

Section 32. It shall be the duty of the Market Master to assign any person who shall desire it. for the purpose of selling at retail his wares or products any stall or stand not rented or occupied and collect therefor the sum of fifteen cents (.15) per day.

Section 11. That section two (2) of General Ordinance no 573 being an ordinance amending Sections thirty two (32) and thirty three (33) of General Ordinance no 438 being "an ordinance regulating the wholesailing and retailing of provisions and articles of food on the Barr Street Market and providing a penalty for the violation of the provisions of this ordinance be and the same is hereby amended to read as follows.

Section 33. That the rental price for the use of the stands or stalls in the covered Market for Tuesdays Thursdays and Saturdays shall be fifteen dollars ($15.00) per annum however. no stand in the covered Market to be rented for less than a period of one year. unless otherwise herein provided.

Section 3. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

H. W. Felger.

Done at the Council Chamber in the city of Fort Wayne this 26th day of March 1912.

We hereby Certify That the common council of the City of Fort Wayne Indiana at a Regular Meeting held on the 26th day of March 1912 by a majority vote of all the members elect. did pass the ordinance hereunto attached. and known as General Ordinance no 536

Louis A. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 29th day of March 1912

Wm J. Jeffries
City Clerk

approved this 30th day of April 1912

Jesse Grice
Mayor

General Ordinance no 537

An ordinance defining and prohibiting dis-orderly and offensive conduct in the streets and public places. or anywhere in the city of Fort Wayne. and providing a penalty therefor and fixing a time for the same to take effect.

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana. That whoever utters an opprobious or vile epithet involving moral turpitude not profaning God. Jesus Christ or the Holy Ghost in the presence of anyone. or whoever uses vile or indecent language or makes any noise. disorder or tumult disturbing the public peace or the quietude of the City shall be deemed guilty of disorderly conduct and upon conviction shall be fined in any sum not exceeding one hundred dollars ($100.00) to which may be added imprisonment not exceeding thirty (30) days.

Section 2. That whoever accosts or approaches any person of the opposite sex unknown to such person. any by word, sign or gesture attempts to speak to or become acquainted with said person against his or her will. on a public street or other public place in said City. except in the transaction of legitimate business. or whoever attempts to entice or procure a person of the opposite sex to commit an unlawful act or whoever accosts or approaches any person and by word. sign or gesture. suggests or invites the doing of any indecent or unnatural act shall be deemed guilty of offending persons on the street. and upon conviction shall be fined in any sum not exceeding fifty dollars ($50.00) to which may be added imprisonment in the county jail not exceeding thirty (30) days.

Section 3 This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

John. J. Bauer.

Done at the council chamber in the City of Fort Wayne Indiana this 26th day of March 1912

We hereby certify that the common council of the City of Fort Wayne Indiana at a regular Meeting held on the 26th day of March 1912

by a majority vote of all the members elect did pass the
Ordinance hereunto attached and known as
Annual Ordinance no 537

Louis A. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 29th day
of March 1912

Wm. J. Jeffries
City Clerk

Approved this 30th day of March 1912

Jesse Price
Mayor

General Ordinance No 538

An ordinance prohibiting and regulating the erection of Signs. Sign boards or other structures to be used for advertising purposes.

Section 1. Be it ordained by the common council of the Leity of Fort Wayne Indiana, That it shall be unlawful for any person firm. corporation or association. to erect or cause or permit to be erected. within the leity of Fort Wayne. any signs. or Signboards. to be used for advertising purposes without first obtaining a permit therefor from the Building inspector. Applications for permits shall be upon printed blanks. furnished by the building inspector and signed by the owner of the sign.

Section 2. " Inspection of Signs.

All signs for which a permit has been issued shall be inspected by the Building inspector when erected and if found to have been supported. braced and constructed according to the provisions of this ordinance a certificate of inspection shall be issued by the said Building inspector without further charge to the owner. all signs attached to any building and larger than fifteen (15) Square feet. also all projecting signs larger than six (6) Square feet shall be examined and inspected by the Building inspector once a year as to their safety and if found to be well supported braced and secured to the building. a certificate of such inspection shall be issued to the owner.

Should any such sign be found unsafe or insecure the owner shall be required to make it safe and secure within forty eight (48) hours from the time of notification to that effect in writing from the Building inspector and if said notice is not complied with within the time Specified the Building inspector shall cause the same to be removed at the expense of the owner.

Section 3. " Definitions

The term "signs" shall apply to displays boards or Screens used as such having characters. letters or illustrations painted. enameled. written, cut of fastened thereon. The term "banner signs" shall apply to all display signs painted. printed, or written upon cloth or canvas with or without frame.

Section 4. Swing Signs

No solid swing sign projecting over a public highway shall have a greater area than six (6) square feet. Larger swing signs shall be constructed of open wire work with letters or illustrations attached thereto.

No swing sign projecting over a highway shall have a greater area than sixteen (16) square feet.

Section 5. Projecting electric illuminated and transparent signs

All parts of any electric illuminated or transparent signs shall be of metal or other non-combustible meterials.

No transparent sign which is attached to and placed flat against a building shall have a greater area than forty (40) Square feet and no part thereof shall extend more than eight (8) inches from the wall

Section 6. The lower edge of all signs shall be at least twelve (12) feet above the grade of the sidewalk and in no event shall the inner edge of any sign be more than eighteen (18) inches from the building wall or property line nor shall the outer edge of any sign project more than four (4) feet over public highway or sidewalk from the building wall or property line. nor extend higher than the upper coping of that part of any building to which it may be attached. and if hung over an alley the lower edge shall be at least twenty (20) feet above the grade of such alley.

Section 7. Weight of Signs

No projecting sign of any class hereinbefore referred to. mentioned or described. shall have a greater weight than one thousand (1000) pounds.

Section 8. Sky or roof electric signs.

All sky or roof signs having the bottom edge placed Twenty five (25) feet or more above the ground or grade level and all other sky or roof signs over twenty five (25) square feet in area. shall be made entirely of Metal or other Non-combustible Materials.

All sky or roof electric signs of a greater area than one hundred (100) square feet shall be constructed of fabricated steel shapes or of wire netting on a metal frame. all such sky or roof electric signs must have electric characters. letters or illustrations thereon.

No sky or roof electric sign shall be placed so that the face of said sign shall come within three (3) feet of the inner plane of the outer wall of such building. nor shall it be constructed so that the bottom of such sky or roof electric sign shall be less than four (4) feet nor more than six (6) feet above the surface of such roof.

Section 9. Supports and anchors.

All signs refered to in this ordinance attached to or placed upon any building shall be thoroughly secured thereto by iron or metal anchors. bolts. supports. chains Stranded cable or braces. No staple shall be used for securing any projecting sign to a building. All sky or roof electric signs shall be constructed and braced to withstand a horizontal wind pressure of thirty (30) pounds for every square foot of surface exposed from the ground to the top. including the roof.

Section 10- Banner Signs.

No banner sign of any character shall be permitted to project or be suspended across any public highway and no person shall paint. print or nail any banner sign any advertisement or notice of any kind whatsoever. or cause same to be done on any curbstone flagstone or on any other portion or part of any sidewalk or street or upon any tree. lamp post. hitching post. telegraph pole. telephone pole. hydrant. bridge. or upon any other structure within the limits of any street within the city.

Section 11. Every sign now existing whether erected upon or above the roof of any building or attached or fastened to the wall or walls of any building so as to project over any public street avenue. alley. lane or public highway. which is now erected or which is now maintained contrary to the provisions of this ordinance. Shall be forthwith removed or altered changed or cut down so as to fully comply with the provisions of this ordinance: And any sign now existing and not complying with the provisions of this ordinance which shall not have been removed or torn down or so altered and changed within six (6) months from and after the passage of this ordinance so as to be brought within the provisions hereof by the owner thereof or by the person. firm or corporation in charge possession or control thereof. Shall be torn down by the building inspector

and the cost and expense of tearing down such sign shall be charged to the owner. or to the person. firm or corporation in charge possession or control thereof. and shall be recovered from such person firm or corporation by any appropriate proceedings therefor.

Section 12. Any person firm or corporation failing to remove any sign when so ordered by the building inspector or violating any of the provisions of this ordinance shall upon conviction thereof be fined in any sum not less than ten dollars ($10.00) nor more than one hundred dollars ($100.00). Section (2) two of chapter eighteen (18) of General Ordinance no 390 known as the building code is hereby repealed.

Section 13. That this ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

H. W. Felger.

Done at the council chamber in the City of Fort Wayne Indiana this 9th day of april 1912

We hereby Certify That the Common council of the City of Fort Wayne Indiana at a Regular meeting held on the 9th day of april 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 538

Louis B. G. Schroeder
President

Wm. J. Jeffries
City clerk

Presented to the Mayor for approval on the 12th day of april 1912

Wm. J. Jeffries
City Clerk

Approved this 13th day of april 1912

Jesse Grice
Mayor.

Repealed July 23-1918 See page 258 Book 4

General Ordinance No 539

An ordinance ordering the improvement of Superior Street from the East property line of Calhoun Street to the west property line of Wells Street by paving the same.

Whereas heretofore on the 1st day of February 1912 the Board of Public Works duly adopted a resolution deeming it necessary to improve Superior Street from the East property line of Calhoun Street to the west property line of Wells Street by paving the roadway to a width of 42 feet according to the plans and specifications therefor on file in the office of the Board of Public works: the cost thereof to be assessed upon the real estate abutting on said Superior Street above described and,

Whereas. on the 29th day of February said Board of public works duly and in all things. confirmed said resolution and within ten days thereafter. namely March 10th 1912 a majority of the resident freeholders upon that part of Superior Street above described filed with said Board of Public works a remonstrance. signed by them against the making of such improvement. Now therefore:

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind. That a necessity existing therefor Superior Street from the East property line of Calhoun Street to the west property line of Wells Street be and the same is hereby ordered improved by paving the roadway thereof to a width of 42 feet according to the plans and specifications on file in the Office of the Board of Public Works. And the said Board of Public works are hereby Authorized and directed to cause said improvement to be made in accordance with the resolutions so adopted by it as set forth in the preamble hereto. and in accordance with the provisions of an act entitled "an act concerning Municipal Corporations" passed by the General assembly of the State of Indiana at the Sixty fourth regular session thereof. and all acts amendatory and Supplementary thereto

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and Legal Publication

B. Van Zweringen

Done at the Council Chamber in the City of Fort Wayne Indiana this 9th day of April 1912

We hereby certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 9th day of april 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as Special Ordinance no 539

Louis S. & Schroder
President

Wm S. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of april 1912

Wm S. Jeffries
City Clerk

approved this 13th day of april 1912

Jesse Grice
Mayor.

General Ordinance 540

An ordinance ratifying and approving a Contract entered into by and between the City of Fort Wayne Ind and the Kelly Springfield Road Roller Company of Springfield Ohio for the construction and delivery of a Tandem Steam Street Roller.

Whereas Heretofore on the 13th day of March 1912. the City of Fort Wayne by and through its Board of Public works entered into a contract with the Kelly Springfield Road Roller Company for one of the latest improved Tandem Steam Street Rollers which contract is as follows:

This agreement made and entered into this, 13th day of March 1912 by and between the city of Fort Wayne Ind by and through its Board of Public works party of the first part and for convenience hereinafter referred to as the "purchaser" and The Kelly Springfield Road Roller Company of Springfield Ohio. party of the second part and for convenience hereinafter called the "Seller"

In consideration of the payment of Fifteen Hundred and Seventy five ($1575.00) dollars the "Seller" agrees to furnish and deliver to said "purchaser" one Latest improved Tandem Steam Street Roller. F. O. B. Fort Wayne Ind. according to the bids. plans Specifications. all of which are made a part of this Contract as if fully copied herein at full length. The "purchaser" is to pay for said Roller as follows: One third of the purchase price thirty (30) days after delivery. one third sixty (60) days and one third in Seventy five (75) days thereafter.

The "Seller" guarantees that said Roller will be made of the best material and workmanship throughout and that it will do first-class work if properly operated and will be durable if properly cared for.

The "Seller" agrees to furnish to said purchaser free of charge for a period of one year from date of delivery any part that may prove defective in either workmanship or material upon receipt of notice and return of said defective part to the factory of said "Seller"

Said "Seller" also further agrees to furnish free

of expenses" a competent operator to assist to unload and will operate said Roller for three days and at the same time give instructions in the use and Management of same. It is understood that said Roller will be delivered to said purchaser on or before June 1st 1912.
In witness whereof we hereunto set our hands and seals this 13th day of March 1912

The City of Fort Wayne
by Frank J. Benoy.
G. A. Schwegmann
E. J. Lennon
Its Board of Public works
party of the first part.
The Kelly Springfield Road Roller Co
By C. M Greiner President

attest H. W. Becker clerk.

Section 1. Be it ordained by the common Council of the City of Fort Wayne Ind that the contract heretofore entered into on the 13th day of March 1912 by and between the City of Fort Wayne by and through its Board of Public works and the Kelly Springfield Road Roller Company as more fully set out in the preamble hereto be and the same in all things confirmed and approved.
Section 2 This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

P. M. Braun

Done at the Council Chamber in the City of Fort Wayne Ind this 9th day of April 1912
We hereby certify that the common Council of the City of Fort Wayne Ind at a Regular meeting held on the 9th day of April 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 540

Louis J. C Schroeder
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 12th day of April 1912

Wm. J. Jefferis
City Clerk

approved this 13th day of April 1912

Jesse Grice
Mayor

General Ordinance no 541

An ordinance ratifying and approving a certain contract entered into on the 25th day of March 1912 by and between the City of Fort Wayne by and through its Board of Public works and the Olds Coal Company.

Whereas heretofore on the 25th day of March 1912 the City of Fort Wayne did by and through its Board of Public works entered into a contract with the Olds Coal Company for a traveling crane across the alley between Murray and Wallace Street.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind That the contract heretofore entered into on the 25th day of March 1912 by and between the City of Fort Wayne Indiana by and through its Board of Public works party of the first part and the Old Coal Company party of the second part, as fully set out in the preamble hereto be and is in all things hereby approved.

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

H. W Fillgor

Done at the Council Chamber in the City of Fort Wayne Ind this 9th day of April 1912

We hereby certify that the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 9th day of April 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as

General Ordinance no 541

Louis S. & Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval this 12th day of April 1912

Wm. S. Jeffries
City Clerk

approved this 13th day of April 1912

Jesse Grice
Mayor

General Ordinance No 542

An ordinance Ratifying and approving a contract by and between the City of Fort Wayne Indiana. and James B. Clow and Sons of Chicago Illinois. relative to cast iron water pipe for the water works Department

Whereas on the 23d day of March 1912 the City of Fort Wayne by and through its Board of Public works. entered into a contract is in the following words.

This agreement. Made and entered into this 23d day of March 1912 by and between the City of Fort Wayne by and through its Board of Public works. party of the first part and James B. Clow & Sons of Chicago Illinois. party of the second part. Witnesseth:

That the party of the first part agrees and binds itself to buy and the party of the second part agrees to sell and deliver to the party of the first part the following

300 tons twelve inch (12") cast iron water pipe for which said first party agrees to pay twenty-two dollars and eighty-five cents ($22.85) per ton and two hundred (200) tons six inch (6") cast iron water pipe for which the party of the first part agrees to pay twenty three dollars ($23.00) per ton and such special castings as said board may deem proper and necessary during the delivery and laying of said pipes for which castings the said first party agrees to pay two and one-half cents (.02½) per pound.

Said first party shall also have the privilege of increasing the amount of each of the above items of pipe and Specials twenty five per cent (25%) and the price of said increase shall be the same as for the original order, all of said pipe and castings shall be delivered at said price F.O.B. Fort Wayne Indiana.

Said pipe to conform with the American Waterworks association which Specifications and bid of said second party and the advertisement for said bids are made apart of the contract as such as if all the same were fully copied herein at full length.

Said second party to furnish all of said pipes to said City from time to time as ordered by said city through its board of public works so that each and every request for shipment shall be fullfilled within ten (10) working days from the time the request is made. It is further agreed and understood that said pipe shall be of the kind and Material and Manufactured

in the Manner Specifically described in the Specifications thereof.
It is also agreed that said Specials aforesaid shall include hubs and Spigots which shall be of Standard weight according to Standard Specifications.
Said second party further agrees to furnish said first party a bond in the sum of One thousand dollars ($1000.00) guaranteeing faithful performance of the within contract with sureties to be approved by said first party.
In witness whereof we have hereunto set our hands and seals this 23rd day of March 1912

City of Fort Wayne by.
Frank J. Bevy.
G. A. Schneyemann
E. J. Levinson
Its Board of Public works
James B. Clow & sons
W. O. Clow pres
J. McLean
Assist Sec.

Attest Walter Leitzer
Sec.

Section 1. Be it ordained by the Common council of the city of Fort Wayne Ind that a contract heretofore entered into the 23d day of March 1912 by and between the city of Fort Wayne Ind by and through its Board of Public works and James B. Clow and sons of Chicago Illinois as fully set forth in the preamble be and the same is in all things ratified and approved.
Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor.

B. F. Harvey.

Read at the council chamber in the city of Fort Wayne Ind this 9th day of April 1912.
We hereby Certify that the Common Council of the city of Fort Wayne Ind at a Regular Meeting held on the 9th day of April 1912 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 542
Louis A. C. Schroeder President Wm J. Jeffries City Clerk
Presented to the Mayor for approval on the 12th day of April 1912

Wm J. Jeffries
City Clerk

Approved this 13th day of April 1912
Jesse Grice Mayor

General Ordinance No 542.

An ordinance approving and Ratifying a contract entered into by and between the City of Fort Wayne by and through its Board of Public works and the New York Chicago & St Louis Railroad Company on the 25th day of March 1912 relative to the construction. Maintenance and operation of additional Track over and across Harrison Street.

Whereas on the 25th day of march 1912 the City of Fort Wayne by and through its Board of Public works entered into a contract with the new york Chicago & St Louis Railroad Company Granting to the said company permission and authority to construct maintain and operate an additional steam railroad track over Harrison Street. which contract is in the following words:

This agreement made this 25th day of March 1912 by and between the City of Fort Wayne by and through its Board of Public works party of the first part and the New york Chicago & St Louis Railroad Company party of the second part Witnesseth;

That is consideration of the covenants and agreements to be performed and complied with by the party of the second part as hereinafter provided. consent and permission and authority are hereby granted and given by the party of the first part to the party of the second part. to construct Maintain and operate or cause to be operated an additional single track railroad across Harrison Street in the City of Fort Wayne. in accordance with and as shown by a plat thereof attached hereto and made a part hereof and on which plat the line and route of said track is marked and indicated by a red line: and permission and Authority is hereby also granted to remove and relay the tracks across said Street that now exists therein as shown by said plat.

It is understood and agreed that the consent permission and authority herein granted are upon the following terms and conditions:

1. The party of the second part if it desire to avail itself of the benefits of the consent permission and authority herein granted shall cause the complete construction of the track within Ninety (90) days from the date hereof and in the event that it so avails itself of said grant permission and authority then it shall cause the complete construction of such track within sixty day from the time

it commences working thereon and within the period of Ninety (90) days as above stated, and shall at no time in the construction of said track occupy for such purpose any of the streets above mentioned for any length of time in excess of five days but in the event that party of second part is prevented from complying with any of the above conditions by reason of any judgment of any court said Board of Public Works may grant a reasonable extension of time as to anyone of the above provisions.

2. Said track shall not be elevated above and shall be constructed and maintained so as to at all times conform with the established grade of the street hereinbefore named as such grade shall from time to time exist and in such manner as to in no way be an impediment to the ordinary and proper use thereof for all purposes by the public in passing along upon and across said track at any point thelon. That said track and the rails thereof shall conform with the grades of the streets now established or to be established hereafter by said city and subject at all times to be taken up and relaid by said second party at its own expense for the purpose of regrading, paving, repaving or repairing such streets and for the purpose of constructing and repairing sewers laying or repairing water mains or other pipes or for any public improvement and in case it becomes necessary in opinion of said Board of Public works, to take up said track for any of the purposes above enumerated or in case said track shall not conform with the grade of said streets as above provided. Said Board of Public works shall notify said party of the second part that it is in the opinion of said Board necessary to take up said track for any of said purposes or that said track does not conform with the grade of said street as the case may be and said party of the second part shall take up said track for such purpose within such time and for such length of time as the said Board may in said notice require. in case such notice is as to repairs or improvements as above stated or shall make said track conform to any such grade within thirty days time from receiving such notice in case such notice is as to grade of such street and upon failure of second party so to do said Board of Public

works shall have the right to take up such track to make such improvements or repairs or to make such track conform to such grade and at the cost thereof to said second party and in case said party shall fail to pay such cost or expense within thirty days from the time said Board shall have rendred a bill therefor the said leity shall have a right of action to recover cost or effense against said second party together with a reasonable attorney fee with the collection thereof.

3. If in the construction of said track it shall become necessary to change the now existing grade of such street in order to have said track of the same grade of the other tracks of said second party and in so doing it shall become necessary to change the grade of any part or parts of the remainder of such street or the sidewalk adjacent thereto then said party of the second part shall at its own effense under the plans and specifications of the civil Engineer of the first party and under the orders and direction of the Board of Public works cause the remainder of said street to be properly graded so as to conform to such grade.

And the party of the second part agrees to keep all parts of said street crossed by the right of way of second party in a proper and sufficient state of repair at all times at its own effense and in a manner that the Board of Public works of said city may from time to time order.

And at the time of the construction of said track and the relaying of said existing tracks the party of the second part shall place that part of said street crossed by its right of way in a first class and sufficient state of repair of the kinds of materials now used therein placing under the rails of said tracks a twelve inch concrete foundation and in accordance with plans and specifications therefor of the civil Engineer of said first party, and to the Satisfaction and under the direction of the said Board of Public works.

4. That the said party of the second part shall not at any time load or unload or cause or permit to be loaded or unloaded cars or leave the same stand on the street mentioned in this contract at any time whatever without the written permission of the Board of Public works. and

shall not at any time operate its trains over and across said street so as to interfere with the free use of the same by the public and shall in the operation of its trains over and across said street conform to all the ordinances of the party of the first part now in operation or which may hereafter be passed by the council of said City in relation to the running and operation of steam railroads within said city

5. Party of the second part shall so construct and maintain its track in such manner as to not in any way interfere with the drainage of the surface waters on the streets herein mentioned. and shall when constructing said tracks over and across said street do the same under the direction of the said Board of Public works.

6. Party of the second part further agrees and binds itself to keep and hold the city free and harmless from any and all liability from any and all damages that may accrue to any person. persons or property. on account of any injury to their person or property growing out of the construction. Maintenance or operation of said track or the operation of any cars thereon. by any person or Corporation and in case suit shall be filed against said city on account thereof. said party of the second upon notice to it by said City. shall defend said action at its own expense and in the event that Judgment be rendered in said action against said city the party of the second part shall pay such judgment with all costs, and hold the city harmless therefrom. and said second party shall execute a to the party of the first part a bond with sufficient surety to be approved by said Board of Public works payable to said City in the sum of Ten Thousand Dollars. conditioned for the faithful performance by said second party of all conditions and provisions contained in this contract to be performed on its part and will from time to time whenever desired by said Board of Public works renew said Bond.

7. It is further agreed that if said second party fails to comply with and perform any of the provisions of section 1. 2. 3. 4. 5. + 6 of this contract the consent permission and authority herein granted shall at once terminate and second party shall forfeit all rights here in and shall cause the removal at its expense. of

Said track and place said Street is as good and safe condition for travel and of the same material as the remainder thereof is.
8 This contract shall not in any manner enter into or effect the question of the elevation of the tracks of the second party and all or any laws that may now or hereafter prescribe the manner of or affect the elevation of the now existing tracks of the party of the second part shall apply to and affect the track to be constructed under this contract. and said second party also agree that when its said tracks now crossing Harrison Street should be elevated or the grades separated at said point it will pay the entire cost of the work necessary to elevate the additional track herein granted and all cost in the separation of the grade made necessary by said additional track.
9. The consent permission and authority hereby granted shall continue for the period of twenty five (25) years from the date hereof.
10. It is further understood and agreed that this contract and the provisions thereof shall be binding upon the successors and assigns of the party of the second part.
Witness our hands and seals the day and year first above written

City of Fort Wayne by
Frank. J. Benoy.
G. A. Schwegmann
E. J. Lehnon
its Board of Public works

Attest H. W. Becker
Clerk

The New York Chicago & St. Louis Railroad Company By
S. K Blair
its Superintendent

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind That the contract entered into by and between the City of Fort Wayne by and through its Board of Public works and the New York Chicago and St Louis Railroad Company on the 25th day of March 1912 relative to the construction. Maintenance and operation of an additional steam railroad track across Harrison Street in said City of Fort Wayne as fully set forth in the preamble hereto. be and the same is hereby in all things ratified confirmed and approved

Section 2 That this ordinance shall be in full force and take effect on and after its passage and approval by the Mayor.

Louis S. & Schroeder

approved J. J. Zurn.
H. C. Fleger.
C. F. Farver.
Paul F. Kinder

Done at the council chamber in the city of Fort Wayne ind this 9th day of april 1912

We hereby certify that the Common Council of the city of Fort Wayne Ind at a Regular meeting held on the 9th day of april 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 543

Louis S. & Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of april 1912

Wm. S. Jeffries
City Clerk

Approved this 13th day of april 1912

Jesse Grice
Mayor

General Ordinance no 544

An ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne and Hetherington and Berner of Indianapolis Indiana for the construction and delivery of an asphalt Repair Plant.

Whereas heretofore on the 6th day of march 1912 the city of Fort Wayne by and through its Board of Public works entered into a contract with Hetherington & Berner for an asphalt repair plant which contract =

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered into on the 6th day of march 1912 by and between the city of Fort Wayne by and through its Board of Public works and Hetherington & Berner as more fully set out in the preamble hereto be and same in all things confirmed and approved

Sec 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

E F Berner

Done at the council chamber in the city of Fort Wayne this 9th day of april 1912

We hereby Certify That the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 9th day of april 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 544.

Louis D. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of april 1912

Wm. J. Jeffries
City Clerk

Approved this 13th day of April 1912

Jesse Eice
Mayor

General Ordinance No 545

An ordinance requiring persons. firms or corporations living within the city of Fort Wayne and within four miles of the Corporate limits thereof. to obtain a city license to sell intoxicating liquors as amended ——— 1912

Section 1. Be it ordained by the Common Council of the City of Fort Wayne. That the Mayor of the City of Fort Wayne in his discretion is hereby authorized to grant to any person firm or corporation who shall have just obtain a State license to sell intoxicating liquors, a city license to sell intoxicating liquors in less quantity than a quart at a time. to be used in and upon the premises wherein such liquors are sold upon such persons. firms or corporations making application therefor, and producing his State license and depositing in the treasury of said City for the use of said City the sum of three hundred dollars. which said license shall run for a period of one current year its beginning being on the same day as the day on which the said state license was granted and shall designate therein the place at which such sale shall be made. Such license shall be issued under the corporate seal of said City. and be signed by the Mayor and. countersigned by the City Comptroller.

Section 2. That it shall be unlawful for any person to sell or offer for sale. within the limits of the City of Fort Wayne or within a distance of four Miles from the Corporate limits thereof any intoxicating liquors in a less quantity than a quart at a time to be used by the purchaser thereof upon the premises wherein such liquor is sold. without first having procured a license so to do as provided in section 1 of this ordinance.

Section 3. Any person. firm or corporation now holding a retail liquor license or a renewal thereof. granting the privilege of selling Malt. vinous and Spirituous liquors at retail in said City or within four Miles of the Corporate limits thereof. and whose City license as described in section one now held by said person firm or corporation does not expire at the same time that his or their City license so expires. then said person firm or corporation shall immediately upon the passage of this ordinance. pay to said City a

sum of money which shall be to the sum charged for a yearly license as the time from which said city license expires to the time at which said state license expires is to a current year. Provided that if the said license of any applicant now in force and as above described expires after said state license expires then said applicant shall pay said fractional amount and receive said fractional year license at the time said state license is renewed. Said applicant shall receive a certificate for such fractional year. issued under the corporate seal of the city and be signed by the Mayor and countersigned by the city Comptroller. Each applicant shall be required to pay a filing fee of two dollars ($2.00) to said Comptroller for the use of the city.
Section 4. Any person who shall violate any of the provisions of this ordinance shall upon conviction forfeit and pay a fine of not less than one hundred dollars.
Section 5. That General Ordinance no 325 being an ordinance entitled. "An ordinance requiring persons living within the city of Fort Wayne and within four miles of the corporate limits thereof to obtain a city license to sell intoxicating liquors as amended on June 11-1907 be and the same is hereby repealed.
Section 6. That this ordinance shall be in full force and take effect from and after its passage and approval by the Mayor and legal publication

C M. Francis

Done at the council chamber in the city of Fort Wayne Ind this 23d day of april 1912
We hereby Certify that the Common Council of the city of Fort Wayne Indiana at a Regular Meeting held on the 23d day of April 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 545

Louis S. G. Schroeder.
President.

Wm. J. Jefferis
City Clerk

Presented to the mayor for approval on the 26th day of april 1912

Wm. J. Jefferis City Clerk

approved this 27th day of april 1912

Jesse Grice
Mayor.

General Ordinance No 546.

An ordinance authorizing the Alienation of certain personal property.

Section 1. Be it ordained by the common council of the city of Fort Wayne Ind. That the Mayor is hereby authorized to sell certain quantities of scrap iron. difficult to describe. but located on the citys property at no 1 Pumping Station and elsewhere and to sign any and all necessary instruments to consumate such sale: provided that such sale shall be made without an appraisment. Should the council. through its proper committee find such property worth less than one hundred dollars ($100.) otherwise appraisers shall be appointed according to law by the Judge of the Allen County Circuit court.

section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor

Herman Stroddt

Done at the Council Chamber in the City of Fort Wayne and this 23d day of April 1912

We hereby Certify That the Common Council of the city of Fort Wayne Indiana at a regular meeting held on the 23d day of April 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 546

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 26th day of April 1912

Wm. J. Jeffries
City Clerk

Approved this 27th day of April 1912

Jno. Price
Mayor

General Ordinance No 547

An ordinance transferring and vesting in the Department of the Public Parks of the city of Fort Wayne Indiana certain parts of Walton avenue in the said city to be converted by the Board of Park Commissioners into a boulevard with full power of control the management thereof and the changing of the name of Walton Avenue to Anthony Boulevard.

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana That that part of the street in said city known as Walton Avenue from the South line of Pontiac Street to the North line of Townley Avenue and that part of said Walton avenue between the South line of State Street and the North bank of the Maumee river be and the same is hereby placed under the government, management and control of the Department of Public Parks of said city for the purpose and with the right upon the part of the Board of Park Commissioners of said city to to convert the same into a boulevard: and said Board of Park Commissioners shall have full power upon the acceptance by it of those parts of said Street herein described for the purpose aforesaid, to govern, manage, maintain regulate and direct the public use thereof as a boulevard and to subject the same to its rules and regulations: subject however to the laws of the State, and to the powers of the Common Council in relation thereto.

Section 2. That Walton Avenue from the South line of State Street to the North line of Townley Avenue shall be changed to and hereafter be known as Anthony Boulevard.

Section 3. This ordinance shall be in full force and effect from and after its passage, legal publication and approval by the Mayor.

H. W. Felger
P. M. Foran

Done at the Council Chamber in the City of Fort Wayne Indiana this 14th day of May 1912.

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a regular Meeting held on the 14th day of May 1912 by a Majority Vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 547

(over)

Gottlieb Haller
Vice President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 17th day of May
, 1912

Wm. J. Jeffries
City Clerk

Approved this 18th day of May 1912

Jesse Grice
Mayor

General Ordinance No 548

An Ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana

Section 1. Be it ordained by the Common Council of the City of Fort Wayne That the territorial limits of the City of Fort Wayne be and hereby are fixed and extended as follows:
Commencing on the west line of the road extending South from Broadway in the City of Fort Wayne and running through the Richardville Reserve at a point where said west line intersects with the North line of said Richardville Reserve: Thence in a Southwesterly direction following the west line of said road. 205 1/2 feet to a point: Thence continuing along the west line of said road in a Southerly direction 219.01 feet to a point: Thence in a westerly direction with an angle of 99 degrees. 27 Minutes to the right a distance of 1277.75 feet to a point: Thence in a Southwesterly direction with an angle of 30 degrees to the left a distance of 717.38 feet to a point: Thence in a Southwesterly direction with an angle of 36 degrees and 37 Minutes to the left a distance of 741.45 feet to a point: Thence in a Southeasterly direction with an angle of 42 degrees and 7 Minutes to the left a distance of 397.16 feet to a point: Thence in an Easterly direction and with an angle of 71 degrees and 14 Minutes to the left a distance of 416.10 feet to a point: Thence in a Southerly direction with an angle of 70 degrees and 9 minutes to the right. a distance of 815 feet to a point: Thence in an easterly direction with an angle of 90 degrees and 9 Minutes to the left. a distance of 520 feet to a point: Thence in a Southerly direction with an angle of 90 degrees and 9 Minutes to the right. a distance of 1060 feet to a point: Thence in a Southeasterly direction with an angle of 68 degrees and 7 Minutes to the left a distance of 1135.98 feet to a point: Thence in a Southerly direction with an angle of 68 degrees and 7 minutes to the right to the east side of the St Marys River: Thence in a Northerly direction along the East side of the St. Marys River and following the Meanderings of the St Marys River to a point where the said North line of said Richardville Reserve intersects said east side of the St Marys River: Thence in an easterly direction an along

the said North line of said Richardville Reserve to the place of beginning that the property included within said territory shall hereafter be within the Corporate limits of said City of Fort Wayne said territory being the land purchased and deeded to the City by David N and Samuel M. Foster and known as "Foster Park"

Section 2. This ordinance shall be in full force and effect from and after its passage. approval by the Mayor and legal publication

E. A. Wagner

Done at the Council Chamber in the City of Fort Wayne Indiana this 14th day of May 1912

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 14th day of May 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance 548

Gottlieb Haller
Vice President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 17th day of May 1912

Wm. J. Jeffries
City Clerk

Approved this 18th day of May 1912

Jesse Grice
Mayor

Generad Ordinance No 549

An ordinance providing for Railroad Track Elevation Resolution no 5 and 6 adopted by the Board of Public works on the 28th day of august 1911.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana That Railroad Track Elevation Resolutions no 5 and 6 adopted by the Board of Public works of said City on august 28th 1911 and confirmed by the Board on October 26th 1911 be and the same is hereby in all things ratified. Confirmed, approved.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor and legal publication

P. M. Braun.

Done at the Council Chamber in the City of Fort Wayne Indiana this 28th day of May 1912.

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 28th day of May 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 549.

Gottlieb Haller Vice president Wm. J. Jeffries City Clerk.

Presented to the Mayor for approval on the 1st day of June 1912

Wm. J. Jeffries City Clerk

Approved this 1st day of June 1912

Jesse Grice Mayor.

General Ordinance no 550

An ordinance approving a certain agreement entered into by and between the city of Fort Wayne and John Joseph Auth for the construction of a spur track from lot no 11 Wildings addition to the Pennsylvania Railroad right of way.

Whereas on the 9th day of May 1912 the city of Fort Wayne Indiana entered into an agreement with John Joseph Auth for the construction of a spur track from lot no 11 Wildings additions to the Plunsylvania Railroad's right-of-way which agreement is in the following words.

This agreement made and entered into this 9th day of May 1912 by and between the city of Fort Wayne by and through its board of public works party of the first part and John Joseph Auth party of the second part.
Witnesseth!
In consideration of the covanants and agreements to be performed and complied with by the party of the second part as here-in after provided. consent permission and authority are hereby given by the first party to the second party and assigns to do and perform the following things

A. To elevate to a height of five feet and grade the north 20 feet of Euclid Avenue in said city being that portion of said street in front of lot no 11 in wildings first addition to the city of Fort Wayne and the alley along the north side of said lot and in such manner as not to interfere with use by the public of said street and alley.
B. To construct across the steet from said lot to the Pennsylvania right of way a rail road spur track and to use the same in connection with track on second party's said lot.
C. To use for purpose of scale a small plat of ground bounded on the north by the alley along said lot on west by the alley along the west side of said lot and on the north east by said lot no 11. Said track being piece of land immediately north east of said intersection and supposed to be part of said alley but no properly platted. It is understood and agreed that the consent permission and authority herein given and granted are upon

the following conditions.
1st The party of the second part. if he desires to avail himself of the rights herein granted shall elevate and regrade said portions of said Street and alley. and build said spur track within 3 months from date of ratification of this contract by the city council.
2d Said work shall be done in such manner as to not in any way interfere with the drainage of the surface waters of said Street or alley. and shall in all respects be under supervision and direction of said board of public works and in a manner required by said Board.
3d The second party agrees and binds himself to keep and hold said city free and harmless from any and all damages that may accrue to any person or persons or property on account of any injury to their persons or property growing out of the construction. Maintenance and operation of said spur track or the elevation or grading of said street and alley by any person or corporation and in case suit shall be filed against said city on account thereof said second party upon notice to him by said city shall defend said action at his own expense. and in the event that judgment be rendered in said action against said city the party of the second part shall pay such judgment with all costs and hold the city harmless thereon. and said second party shall execute to first party a bond in the sum of $5000.00 with sufficient surety to be approved by the Board of Public works. payable to said city conditioned for the faithful performance by said second party of all the conditions and provisions contained in this contract to be performed on its part. and will from time to time. whenever desired by said Board of Public works renew said bond which is to be continuing.
4th It is further agreed that if second party fails to comply with and perform Sections 1. 2. & 3. of this contract the consent permission and authority herein granted shall at once terminate and the second party shall forfeit all right hereunder and shall cause the removal at his expense of said spur track and place said street and alley in good and proper

Condition.
5th It is further agreed that this contract and provisions thereof shall enure to benefit of secnd partys assigns and shall be binding upon his assigns
6th The consent permission and authority shall continue for a period of 25 years from date of ratification.

In witness whereof we have hereunto set our hands and seals this day and year first above written.

Frank. J. Benoy
G. A. Schurgmann
E. J Lenhoff
Jr Board of Public works
John Joseph Auth

Attest H. W. Becker
Clerk

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that an agreement heretofore entered into by and between the City of Fort Wayne and John Joseph Auth on the 9th day of May 1912 as more fully set out in the preamble hereto be in all things confirmed and approved.
Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor and legal publication

C. M. Braun

Done at the council chamber in the city of Fort Wayne Indiana this 28th day of May 1912
We hereby certify that the Common council of the city of Fort Wayne Indiana at a Regular meeting held on the 28th day of May 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No. 550

Gottlieb Haller
Vice President

Wm S. Jeffries
City Clerk

Presented to the Mayor for approval on the 1st day of June 1912

Wm S. Jeffries
City Clerk

Approved this 1st day of June 1912

Jesse Brice
Mayor.

General Ordinance no 551

An ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana.

Section 1. Be it ordained by the Common council of the city of Fort Wayne Indiana That the territorial limits of the city be and are hereby extended as follows:

Commencing at a point where the center line of Walton avenue intersects the center line of Pontiac Street: Thence East to the West line of Huestis and Taylor Sub-devision of Abbotts out lots: Thence South along the west line of Huestis an Taylor Sub-devision of Abbotts out lots and Abbotts out lots to the South line of Abbotts out lots: Thence East on the south line of Abbotts out lots to the center line. North and South of section eighteen (18) Township thirty (30) North. Range thirteen (13) East: Thence South along said center section line to the center of said section eighteen (18): Thence west on the center line East and West of said section eighteen (18) to the center line of Anthony Boulevard. formerly Walton avenue: Thence North on the center line of Anthony Boulevard formerly Walton avenue To the place of beginning.

Be it further enacted that the property included within the lines herein indicated shall hereafter be within the Corporate limits of the city of Fort Wayne Indiana and Subject to taxation for city purposes.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Henry W. Felger.

Done at the council chamber in the city of Fort Wayne Indiana this 28th day of May 1912

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 28th day of June 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 551

Gottlieb Haller Vice President Wm. J. Jeffries City Clerk

Presented to the Mayor for approval on the 1st day of June 1912

Wm. J. Jeffries City Clerk

Approved this 1st day of June 1912

Jno. Price Mayor.

General Ordinance 552.

An ordinance amending Section one of an ordinance entitled: An ordinance requiring Circuses. Shows. Menageries. parading the streets of the City with elephants camels. dromedaries or Steam calliopes to give bonds and providing a penalty for the violation thereof.

Section 1. Be it enacted by the Common Council of the City of Fort Wayne that section one of General Ordinance no 78 being an ordinance entitled: An ordinance requiring circuses. Shows Menageries parading the streets of the City with elephants. camels. dromedaries. or Steam calliopes to give bonds and providing a penalty for the violation thereof. be amended to read as follows:
Be it enacted by the Common Council of the City of Fort Wayne that on and after its passage of this ordinance it shall be unlawful for any show circus or Menagerie to walk over and along the Streets in the City of Fort Wayne in its parade elephants. camels. dromedaries or other animals liable to frighten horses. or to make use of a Calliope in the same manner without prior executing to the City of Fort Wayne a bond in the sum of Ten Thousand dollars ($10.000.00) with an approved Surety Company or otherwise to the approval of the City Controller.
Section 2 That this ordinance be in full force and effect from and after its passage. legal publication and approval by the Mayor

Herman Strodel

Leave at the Council Chamber in the city of Fort Wayne Indiana this 28th day of May 1912
We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 28th day of May 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 552

Gottlieb Haller Vice President Wm. J. Jeffries City Clerk

Presented to the Mayor for approval on the 1st day June 1912
Wm. J. Jeffries City Clerk

Approved this 1st day of June 1912
Jesse Grice
Mayor.

General Ordinance no 553.

An ordinance authorizing the alienation of certain personal Property

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana. That the Mayor is hereby authorized to sell certain quantities of copper and brass difficult to describe. but located on the City's property at the Fort Wayne Municipal Electric light and power works and elsewhere. and to sign any and all necessary instruments to consummate such sale! provided that such sale shall be made without an appraisement. Should the council. through its proper committee. find such property worth less than one hundred ($100.) dollars otherwise appraisers shall be appointed according to law by the Judge of the Allen county circuit court.
Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor.

Allen Hamilton

Done at the Council Chamber in the City of Fort Wayne Indiana this 28th day of May 1912

We hereby certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 28th day of May 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 553

Gottlieb Haller
Vice President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 1st day of June 1912

Wm. J. Jefferies
City Clerk

approved this 1st day of June 1912

Jesse Grice
Mayor

General Ordinance no 554

An ordinance amending Section 1. 25 and 34 of an ordinance regulating Wholesaling and retailing of provisions and articles of food upon the Barr Street Market and providing a penalty for the violation of the provisions of this ordinance

Section 1. Be it ordained by the Common Council of the of Fort Wayne that section one of "An ordinance Regulating Wholesaling and Retailing of provisions and articles of food upon the Barr Street Market and providing a penalty for the violation of the provisions of this Ordinance to be amended to read as follows: That all that portion of Barr street between the north line of Washington street and the south right of way line of the New York. Chicago and St Louis Railroad be used as a public retail Market in said city subject to the following provisions, in this ordinance contained.

Section 2. That section 25 be amended to read as follows It shall be unlawful for any person to loiter sit. stand lounge. or walk about the Market during Market hours or to ride. lead or push any bicycle wagon or cart along in or through said Market House or Market space during Market hours.

Section 3. That section 34 be amended to read as follows: All persons desiring to renew the rental of stands or stalls shall file notice of their desire to so renew with the clerk of the Board of Public Safety between the first day of May and the first day of June of each and every year. Thereupon the clerk shall immediately issue an order to the applicant for said stand or stall and upon the immediate presentation of the same and upon the immediate payment of $15.00 by the applicant to the City Controller he shall issue a certificate to the applicant entitling him to use said stand or stall for a period of one year from the date of said certificate which certificate shall be dated the 3d Saturday of June. all stands or stalls not rented before the 3d Saturday of June shall be rented on said day or thereafter to applicant in the order in which applicant is made provided

however that no application for the rental of Stands shall be received before 10.00 Oclock A.M of the last Named date. upon the issuing of an order by the clerk to said applicant he shall present said certificate to said Controller as hereinbefore provided.
Section 4. That this ordinance be in full force and to take effect from and after its passage and appoval by the Mayor

Henry W. Felger

Done at the Council chamber in the City of Fort Wayne Indiana this 28th day of May 1912

We hereby Certify That the Common council of the city of Fort Wayne Indiana at a Regular Meeting held on the 28th day of May 1912 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as Gneral Ordinance no 504

Gottlieb Haller
Vice President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 1st day of June 1912

Wm. J. Jeffries
City Clerk

Approved this 1st day of June 1912

Jno. Price
Mayor

General Ordinance No 555

An ordinance amending section five of General Ordinance #147 being "an ordinance regulating the use of streets and alleys"

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana. That section five of General Ordinance no #147 being "an ordinance regulating the use of streets and alleys" be amended to read as follows:
Section 5. It shall be unlawful for any person except the employees of the street repairing department or the contractors for street improvement. to feed or to place any trough for feeding or watering draft animals in the streets. alleys or public places in the city, and it shall also be unlawful for any person to fasten. tie or hitch a horse or horses to any lamp post or fire plug along or in any public street or alley within said city.
Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Herman Stroedel

Done at the Council Chamber in the City of Fort Wayne Indiana this 11th day of June 1912

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a regular meeting held on the 11th day of June 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 555

Gottlieb Haller
Vice President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 15th day of June 1912

Wm. J. Jeffries
City Clerk

Approved this 15th day of June 1912

Jesse Grice
Mayor

General Ordinance no 556

An ordinance amending Section 4 of General Ordinance no # 318 being an ordinance requiring Peddlers and Hawkers to take out a license and fixing the penalty for the Violation of the same as amended april 23d 1907

Section 1. Be it ordained by the Common Council of the Ceity of Fort Wayne Indiana that section 4 of General Ordinance no 318 being an ordinance Requiring Peddlers and Hawkers to take out a license and fixing the penalty for the Violation of the same as amended april 23d 1907 Sec 4. Every. Person licensed to sell. barter. or exchange any article of Value whatsoever under any provision of this ordinance or any state Statute concerning peddlers shall procure at his own expense and have conspicuously posted or painted on each Vehicle so used a sign made of wood or tin bearing the name of the person so licensed and the words. "Licensed Vender" in plain English letters: and said sign shall not be less than two feet in length and twelve in in width. It shall be the duty of every person Selling bartering or exchanging any goods or other articles of Value as aforsaid to carry his license or permit with him while so selling. bartering or exchanging of goods. Merchandise or other articles of value upon and along the Streets and alleys or other places in said city and such person shall. when so requested either by an officer or private citizen produce or show to such person or officer either the license or permit under which he claims to be Selling. Section 2. This ordinance shall be in full force and effect from and after its passage. approval by the Mayor and legal publication

Herman Stroede

Done at the Council Chamber in the Ceity of Fort Wayne Indiana this 11th day of June 1912

We hereby Certify That the Common Council of the Ceity of Fort Wayne Indiana at a Regular Meeting held on the 11th day of June 1912 by a Majority vote of all the Members elect ded pass the ordinance hereunto attached and known as General Ordinance no 556
Gottlieb Haller Vice President Wm J. Jeffries Ceity Clerk

over

Presented to the Mayor for approval on the 15th day of June 1912

Wm. J. Jeffries City Clerk

Approved this 15th day of June 1912

Jesse Grice
Mayor

General Ordinance no 557

An ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. That the territorial limits of the city of Fort Wayne Indiana be and hereby are fixed and extended as follows: Commencing at a point on the west line of Walton avenue intersecting the north line of state street: thence one hundred and fifty two (152) feet directly North; thence west to the west property line of Fort Wayne Driving association thence directly one hundred and fifty two (152) feet to the north line of state street: thence East along the north line of state street to the place of beginning:

Section 2. This ordinance to be in full force and take effect from and after its passage. approval by the Mayor and legal publication

B. Van Swearingen

Done at the council chamber in the city of Fort Wayne Indiana this 11th day of June 1912

We hereby certify that the common council of the city of Fort Wayne Indiana at a regular meeting held on the 11th day of June 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 557

Gottlieb Haller
Vice President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 15th day of June 1912

Wm. J. Jeffries City Clerk

Approved this 10th day of June 1912

Jesse Grice
Mayor.

General Ordinance no 558

An ordinance transferring and vesting in the Department of Public Parks of the City of Fort Wayne Indiana. Control of Rudisill avenue in the said city to be converted by the Board of Park Commissioners into a boulevard. with the management thereof and the changing of the name of Rudisill avenue to Rudisill Boulevard.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana That that part of the Street in said City known as Rudisill Avenue from the west line of Broadway to the East line of Piqua Avenue. be and the Same is hereby placed under the Government. Management and control of the Department of Public Parks of said City for the purpose and with the right upon the part of the Board of Park Commissioners of said City to convert the same into a boulevard: And said Board of Park Commissioners Shall have full power upon the acceptance by it of those parts of said Street herein described. for the purpose aforesaid. to govern. Manage. Maintain. regulate and direct the public use thereof as a boulevard. and to Subject the same to its rules and regulations: Subject however to the laws of the State and to the powers of the Common Council in relation thereto.
Section 2. That Rudisill avenue from the west line of Broadway to the East line of Piqua avenue. Shall be changed to and hereafter known as Rudisill Boulevard
Section 3. This ordinance shall be in full force and effect from and after its passage. legal publication and approval by the Mayor.

Allen Hamilton

Done at the Council Chamber in the City of Fort Wayne Indiana this 11th day of June 1912

We hereby Certify. That the common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 11th day of June 1912 by a Majority vote of all the members elect did pass the Ordinance hereunto attached and known as General Ordinance no 558

Gottlieb Haller
Vice President

Wm. J. Jeffries
City Clerk

(over)

Presented to the Mayor for approval on the 15th day of June 1912

Wm S. Jeffries City Clerk

approved this 15th day of June 1912

Jesse Grice Mayor.

General Ordinance no 559

An ordinance approving a certain Contract entered into by and between the City of Fort Wayne Ind by and through its Board of Public works and the Pennsylvania Company on the 25th day of March 1912 providing for a Spur from the Pennsylvania tracks on Murray Street to the property of the Olds coal Company.

Whereas on the 25th day of March 1912 a Contract was entered into between the City of Fort Wayne by and through its Board of Public works and the Pennsylvania Company providing for a Spur from the Pennsylvania tracks on Murray Street to the property own by the Olds Coal Company which Contract is as follows:

This agreement Made and entered into on the 25th day of March 1912 by and between the City of Fort Wayne by and through its Board of Public works party of the first part and the Pennsylvania Company party of the second part.

Witnesseth:

That the party of the first part by and through its Board of Public works under and by virtue of the powers conferred upon it and the said Board of Public works by the laws of the State of Indiana. does hereby. Subject to the conditions herein expressed authorize and empower the said party of the second part. its Successors and assigns. from and after the approval and ratification of this contract by an ordinance of the Common Council of said City to construct. use and Maintain a single track Steam railroad of Standard with over and along Murray Street in the City of Fort Wayne so that the center line of said proposed track shall begin at a point in the center of the Murray Street industrial track as now constructed and laid on Murray Street. Said point

being about 83 feet distant eastwardly from the west line of Barr street thence Southeastwardly by a curve and in a circle to the right 175 feet More or less to a point. Said center line crossing the south line of Murray Street at a point 165 feet more or less eastwardley from its intersection with the west line of Barr. Street thence Southwardly parallel with a distance westwardly 7 feet measured along a line parallel with the south line of Murray Street from the west line of the alley between Barr and Lafayette Streets 78 feet more or less. to a point in the North line of the alley between Murray and Wallace Street thence Continuing Southwardly parallel with aforesaid west line 12 feet More or less. to the south line of alley between Murray and Wallace Street.
The said track herein authorized to be laid and Maintained is to be used for the switching and moving of freight cars to and from the Olds Coal Company property to said Main track of said Pennsylvania Company in Murray Street. The consent and permission herein given is upon the following Conditions:
1st That said track shall not be elevated above the grade of Murray Street. and the same shall be laid and Maintained so as to conform with the established grade of said Street as the same shall from time to time exist and in such way as not to be a Nuisance and impediment to the ordinary and proper use thereof by wagons. Carriages or other Vehicles along upon or across such track at any point thereon: that the track and rails shall conform with the grade of the Streets as now established or as may hereafter be established by said City and subject at all times to be taken up and relaid by the said company. its Successors and assigns at its own expense whenever Necessary for the purpose of regrading. paving or repaving or repairing such Street Constructing Sewers laying or repairing water Mains or other pipes. or any other public improvement. In case the rails of such track shall not conform with the grade of the Street as above provided the Board of Public works shall notify the party of the second part thereof. The party of the second part shall do the necessary work and make such track

conform to any such grade within 30 days time from receiving such notice. and upon failure so to do. the Board of Public works shall have the right of change such tracks and make such improvement and charge the cost thereof to said company. its successors and assigns and in case such company its successors and assigns shall fail to pay such expense within thirty days from the time said Board has rendered a bill therefor said city shall have a right of action to recover said amount against the said company its successors and assigns and in case of such failure to pay such bill and if suit is brought to recover the same said city shall be entitled to recover in addition to the cost of such improvement a reasonable attorneys fee.

2d Said company shall pave between the rails of said track herein provided for on Murray Street and two feet on the outside of each rail from the intersection of said track with said main track to the curb stone on the south side of said Murray Street as said stone may now exist or be hereinafter established. Said pavement to be a Vetrified paving brick made in accordance with plans and Specifications to be furnished by the Board of Public works and at the time said track is laid in said street. The said company shall repair said Section of said Street herein authorized to be occupied in the Manner and to the extent herein set out at such time as the Board of Public works of the City may require. and shall at all times keep said portion of said Street in a good condition and repair. Said company shall also pave between the rails and two feet on the outside of each rail and to the full width of any sidewalk that may hereafter be constructed on the south side of said Murray Street: Said pavement to be of Material used in the balance of said sidewalk, and to be constructed according to the plans and Specifications provided by the Board of Public works or the City Civil Engineer of said City. The drainage made Necessary by the laying of said track shall be done and maintained by said second party according to and under the direction of said Board.

It is further agreed that the party of the second part

shall cause to be constructed and properly maintained a suitable crossing over said proposed track in the alley between Wallace and Murray Street. said crossing and track not to be elevated above the grade of said alley and to at all times conform with the grade of said alley as the same shall from time to time exist.

3. That the use of said track by the party of the second part its successors and assigns herein authorized to be laid and maintained is limited and restricted to hours between 11:00 P.M. and 6:00 A.M. on each day and during all other hours of the day said track shall be clear and unobstructed for public use.

4. That said company. its successors and assigns shall not at any time haul to exceed six cars over and along said track herein authorized to be laid. and shall not load or unload any car upon said track and shall not allow cars loaded or unloaded to stand upon said street or sidewalk.

5. It is further agreed by and between the parties to this contract that if said second party its successors and assigns fail to comply with any of the provisions of Sub-divisions three and four of this Contract said second party. its successors and assigns shall forfeit all rights and privileges in this contract granted. The rights. privileges and franchises hereby and herein granted shall be vested in the Pennsylvania Company its successors and assigns for a period of twenty five years from the 25th day of March 1912.

6. It is agreed by and between the parties hereto that the tracks herein authorized shall be located to the approval of the Board of Public works and that the ties upon which the rails rest shall be laid upon not less than ten inches of Concrete.

7. That said party of the second part further agrees and binds itself its successors and assigns. to keep and hold said city free and harmless from liability from any and all damages that may accrue to any person or persons on account of injury to their persons or property. growing out of the construction of Maintenance of said track or from the operation of cars thereon and in case suit shall be filed against

said City on account thereof. Said party of the second part upon notice to it by said city will defend said suits against the said city and in event that judgment is obtained against the city the second party its successors and assigns shall pay such judgment with all its costs and hold the city harmless therefrom. providing said Judgment can be enforced in law against said city.

5. It is further agreed and understood that if said party of the second part its successors and assigns does not occupy said Street herein designated for the purpose provided within one year after the approval of the contract by the common council. then in that case said second part its successors and assigns shall forfeit all the rights and privilege herein granted. Provided however that if said second party is prevented from taking possession of said Street within the time herein stipulated by reason of the judgment of any court: then in that event said Board of Public works may grant a reasonable extension of time.

In witness whereof we have hereunto set our hands and seals the day and year first above written.

City of Fort Wayne by
Frank J. Benoy
G. A. Sweg mann
E. J. Lennon
Jr Board of Public works

Pennsylvania Company.
By G. R. Peck

Approved R. Trimble
Chief Engineer M of W.

Section 1. Be it ordained by the common council of the City of Fort Wayne that a contract entered into by and between the City of Fort Wayne by and through its Board of Public works and the Pennsylvania Company on the 25th day of March 1912 providing for a Spur from the Pennsylvania tracks on Murray Street to the property owned by the Olds Coal Company as fully set forth in the preamble hereto be and the same is hereby in all things confirmed and approved.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor

Charles. W. Leitzoe

Done at the Council Chamber in the City of Fort.

Wayne Indiana this 9th day of July 1912

We hereby certify that the common council of the city of Fort Wayne Ind at a Regular Meeting held on the 9th day of July 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 559

Louis D. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of July 1912

Wm. J. Jeffries
City Clerk

Approved this 12th day of July 1912

Jesse Grile
Mayor

General Ordinance 560

An ordinance ratifying and approving a Contract entered into by and between the city of Fort Wayne and the Bass Foundry + Machine Company on the 1st day of July 1912 providing for the construction and erection of certain boilers. Stokes. etc. for the Municipal Electric Light and Power Plant.

Whereas heretofore on the 1st day of July 1912 the City of Fort Wayne by and through its Board of Public works entered into a contract with the Bass Foundry and Machine Company for the construction and installation by said Company of certain boilers for the Municipal Electric light and Power Plant which Contract is in the following words

This agreement made and entered into this 1st day of July 1912 by and between the City of Fort Wayne by and through its Board of Public works party of the first part for convenince hereinafter designated as City and the Bass Foundry and Machine Company party of the secord part for convenince hereinafter designated as contractor. Witnesseth:
That for and in consideration of the payment by the said city to the said contractor of the sum of Money hereinafter reperred to said contractor agrees and hereby binds itself to furnish all the Materials and Labor and to construct. deliver and install for said city two (2) five hundred (500) Horse Power Horizontal Sectional Bass Water tube Boilers with Detroit Stokers and Foster Superheaters all of said Materials and Labor to be of the kind and to be constructed in the Manner described in and in accordance with the plans and Specification filed by said Company with said City reference to all of which plans and Specifications is hereby made as a part hereof and the provisions of the same are made parts of this contract and binding upon the parties hereto the same as if copied herein at full lingth.
It is understood that said boilers and the Equipment thereto shall be installed complete and ready for Operation and said installation shall include all necessary brick work.

The Company agrees to hold the purchaser harmless and indemnified against all sums which the purchaser shall be adjudged to pay in any suit brought against it alleging the infringment of Patents by the use of the equipment hereinbefore mentioned provided that the party of the first part be given immediate written notice of suits and pelmission to its counsel to defend the same
It is further agreed by and between the said parties that the acceptance of the work provided for in this contract or the payment therefor for the whole or a part shall not constitute a waiver on the part of the city of any of the provisions of the contract. nor shall it release said contractor or the sureties upon its bond for the faithful performance thereof. nor shall the acceptance be even prima facie evidence of the performance of any provisions of such contract except to the extent of entitling said contractor to receive the price therefor. It is further understood that the failure of the City to exercise its rights of inspection or rejection of material and work or the exercise of such right shall not in any sense be considered an acceptance of any part of said work or material.
The Contractor further contracts and agrees that in the prosecution of said work all proper skill and care will be exercised that said party will properly and fully guard all excavations and dangerous places and will use all due and proper precautions to prevent injury to any property. person or persons. what or whomsoever. That for and during the period of the Making of such improvements and the period for which the same is to be Maintained and kept in repair by the contractor. the City shall be saved harmless from any and all liability whatsoever growing out of any injury or damage to property or persons because of any Neglect or Fault of the said Contractor its agents or employees in the execution of this contract or any Matters connected therewith or related thereto and to pay any judgment with costs which may be obtained against said city. growing out of any such injury or damage.

It is agreed by said city that for and in consideration of the furnishing of said Material and completion of said work it will pay to said contractor the sum of Seventeen thousand five hundred dollars ($17,500.00) in the following Manner one-third (⅓) on delivery of Material on ground one third (⅓) on the installation and completion of said equipment and balance within five (5) days after acceptance of said work by said city.

Said Contractor hereby agrees that it will within ten (10) days after the execution of this contract and its approval by the Common Council of said city. execute a bond to said city for the faithful performance of said contract in the sum of five thousand dollars ($5000.00)

Witness our hands and seals the day and year first above Written

City of Fort Wayne by
Frank J. Bunoy
G. A. Schwegmann
E. J. Lennon
Its Board of Public works

attest H. W. Becker
Clerk

Bass Foundry & Machine co by.
W. O. Barrett.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind That the contract heretofore entered into by and between the city of Fort Wayne by and through its Board of Public works and the Bass Foundry and Machine Company providing for the Construction and installation of boilers ~~etc~~. by said Company at the Municipal light and Power Plant. as more fully set forth in the contract and in the preamble hereto be and the same is hereby in all things ratified and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Allen Hamilton

Leone at the Council chamber in the city of Fort Wayne Indiana this 9th day of July 1912

We hereby certify That the Common Council of the the City of Fort Wayne Ind at a Regular Meeting held on the 9th day of July 1912 by a Majority

vote of all members elect did pass the ordinance hereunto attached and known as General Ordinance No 560

Louis S.C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of July 1912

Wm. J. Jeffries
City Clerk

Approved this 12th day of July 1912

Jesse Grice
Mayor

General Ordinance no 561

An ordinance approving a contract entered into by and between the city of Fort Wayne by and through its Board of Public works and the Fort Wayne Electric works

Whereas on the 30th day of March 1912 the Board of Public works of the City of Fort Wayne Indiana in behalf of the city entered into a contract with the Fort Wayne Electric Works for the purchase of Electric lamps for use in the Municipal Electric Light and Power works

Section 1. Be it ordained by the common council of the City of Fort Wayne Ind that the contract heretofore entered into on the 30th day of March 1912 by and between the city of Fort Wayne by and through its Board of Public works and the Fort Wayne Electric works as fully set fourth in the preamble hereto be and the same is in all things ratified and approved.

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

B. Van Orsdel

Done at the council chamber in the City of Fort Wayne Indiana this 9th day of July 1912

We hereby certify that the common Council of the city of Fort Wayne Indiana at a Regular Meeting held on the 9th day of July 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 561

Louis S. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 12th day of July 1912

Wm S. Jefferies
City Clerk

Approved this 12th day of July 1912

Jesse Grice
Mayor

General Ordinance no 562

An ordinance providing for Railroad Track Elevation Resolutions no 7+8 adopted by the Board of Public works on the 23d day of May 1912

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana That Railroad Track Elevation Resolutions no 7+8 adopted by the Board of Public works of said city on May 23d 1912 and confirmed by the Board on June 3d 1912 be and the same are hereby in all things ratified. confirmed. and approved

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor and legal publication

Gottlieb Haller.

Done at the council chamber in the city of Fort Wayne this 9th day of July 1912

We hereby certify That the common council of the city of Fort Wayne Indiana at a regular meeting held on the 9th day of July 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 562

Louis D. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of July 1912

Wm J. Jeffries
City Clerk

Approved this 12th day of July 1912

Jesse Grice
Mayor.

General Ordinance no 563

An ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne Indiana by and through its Board of Public works and the Pennsylvania Company. operating the Pittsburg. Fort Wayne & Chicago Railway on the 1st day of June 1912 providing for the vacation of parts of Chicago. Webster and McClellan Streets and parts of the Alley between Baker and Chicago Streets. granting track rights across Calhoun Street. Fairfield avenue. Broadway College and Union Streets and the opening of Harrison Street. the separation of the grade at said Street and at College and Union Street and the Building of a Passenger Station on Baker Street.

Whereas heretofore on the 1st day of June 1912 the City of Fort Wayne by and through its Board of Public works entered into a contract with the Pennsylvania Company operating the Pittsburg. Fort Wayne and Chicago Railway providing for the Vacation of parts of Chicago. Webster and McClellan Streets and parts of the alley between Baker and Chicago Streets. granting track rights across Calhoun Street. Fairfield avenue. Broadway. College and Union Streets and the opening of Harrison Street. the separation of the grade at said Street and at College and Union Street and the building of a Passenger Station on Baker Street which contract is in the following words:

This agreement Made and entered into this 1st day of June 1912 between the City of Fort Wayne by the through its Board of Public works hereinafter designated first party and Pennsylvania Company. Operating the Pittsburg. Fort Wayne and Chicago Railway hereinafter designated as second party Witnesseth. That.

Whereas both parties are and have been engaged in the elevation of the railroad tracks of said second party and the separation of grades at various Streets within the City of Fort Wayne Allen County State of Indiana and

Whereas by reason of said improvements and by reason of additional improvements contemplated by said second party it has become and is necessary that said second party have additional tracks over and

across Calhoun Street. Fairfield avenue. Broadway. Union and College Streets not only for the purpose of enabling said second party to take care of its Freight and Passenger traffic. but to enable it to have ample access to and from the new passenger Station proposed to be erected by it between Fairfield avenue and Calhoun Street along said second party's right of way. and in consideration of the mutual benefits which will accrue not only by reason of the improvements now being made by both parties but also by reason of the improvements proposed it is agreed.

First That said second party shall have and is hereby given the right to erect. construct and maintain such additional elevated tracks and such abutments as may be necessary therefor across Calhoun Street. Harrison Street. Fairfield avenue and Broadway North of and adjacent to its existing tracks. Provided however that the tracks and abutments exclusive of wing walls. at the east side of Calhoun Street shall not extend North from the South line of the right of way of the second party more than 128 feet: at the west side of the street the tracks and abutment. exclusive of wing walls. shall not extend North from the South right of way line of second party more than 137 feet: at Harrison Street the necessary tracks and abutments. exclusive of wing walls. on either side of the street shall not extend North from the South right of wayline of said second party more than 176 feet: At Fairfield avenue the necessary tracks and abutments. exclusive of wing walls. on the East side of said street shall not extend North from the South right of way line of said second party more than 100 feet: On the west side of said avenue the tracks and abutments exclusive of wing walls. shall not extend North from the South right of way line of said second party more than 109 feet. At Broadway the necessary tracks and abutment. exclusive of wing walls. on the east side of said Street shall not extend North from the South right of way line of said second party more than 91 feet: measured at right angles thereto. and on the west side of said Street the tracks and abutments. exclusive of wing walls shall not extend north from the South right of way line of said second party more than 70 feet measured at right angles thereto: The said second party

shall have and is hereby given the right to and will extend the subway in said streets including piers for columns. north a sufficient distance under the additional tracks so as to make said additional subways the same uniform width and height as the subways provided for in the original plans and specifications for the elevation of the tracks at said streets said additional width of tracks being simply an extension of the subways at said streets.

It is further understood and agreed that said party shall have the right to construct and maintain one additional elevated track. together with the necessary abutments therefor. across College and Union streets. north of its existing main tracks making a total of four tracks across those streets upon the conditions however that the abutments for said additional track on either side of said Street shall not extend north of the north line of said second party's right of way. meaning and intending hereby to give to said second party the right to extend the subways proposed under the original. elevation proceedings said distance of the same uniform width and height as provided for the original subways and to lay. Maintain and operate an additional track over said Street upon said abutments.

It being the understanding and intention of the parties hereto that the right extended to said second party shall authorize and enable said second party to extend the subways upon the various streets north the several distance herein specified including the extension of the abutments depression of the streets and the additional superstructure all abutments and superstructure to be in harmony with the original abutments and superstructures agreed upon and adopted under the original proceedings for elevation of tracks across said streets upon the conditions however that all the cost and expense for the construction of such additional subways and tracks shall be paid for by said second party which said additional cost and expense said second party hereby agrees and binds itself to pay. said second party further agrees to pay any and all damages done to

adjoining property if any caused by the extension of said subways beyond the point contemplated in the original elevation proceedings and the extension of the depression in the various streets aforesaid for which the city may be held liable. Provided however that before said second party can be held liable in case damage is occasioned to adjoining property for which it is claimed the city is responsible that said second party shall be at once notified in writing by said first party and shall have a full opportunity to investigate and determine for itself whether or not it will voluntarily settle such damage. and in case it is decided by it that said city is not responsible and suit shall be instituted by any person claiming to have suffered such damage. said first party shall at once give to said second party notice in writing of the pendency of such suit and thereafter shall give and extend to said second party full power and authority without hindrance to appear for and in behalf of said party if any such suit be filed and contest the right of the claimants to recover therein. and said city shall at all times extend to said second party, or its attorneys. all assistance within its power whenever requested so to do.

Provided however that the right to cross said various streets hereby extended to said second party shall first be approved by the common council of the city of Fort Wayne

Second: It is further agreed by and between said parties in order to enable said second party to carry out construct and complete the proposed improvements along its right of way at the points hereinbefore specified that said second party shall have and is hereby granted the right to construct and maintain footings for retaining walls and abutments as follows.

1. In the alley parallel with and South of Baker street from a point 138 feet west of the west line of Webster Street to a point 203 feet west of the west line of McClellan St.
2. In the alley parallel with the south of Hendricks Street from the west line of the first alley west of Fairfield avenue west along said alley a distance of three hundred and ten (310) feet.
3. In the alley adjoining the south right of way line of second party from the west line of Monell street to the east line of Union Street and from the west line

of Union Street to the east line of College street and from the west line of College Street to a point 100 feet west in the alleys north and south of the right of way of said second party. and all of said footings to be laid erected and constructed so as not to interfere with the use of said alleys. and all of said alleys to be put in as good condition as before said work was done.

4. Said second party is also given and hereby granted the right to lay its private water pipe lines on the various streets and alleys from the west line of Clinton street to the west line of Swinney Park place west. as more particularly shown by the blue prints of the same filed with the Board of Public works of said City.

The streets and alleys however so used shall be put in as good condition after said work is completed as they were before the work was commenced.

Said It is further agreed by and between said parties that upon or before the common council approving this agreement so far as the right of said second party to cross the various streets with its tracks as hereinbefore Specified that said first party hereto will immediately vacate the following streets and alleys "towit" Brooklyn avenue from the west line of Calhoun Street to a point twelve (12) feet west of the east line of Harrison street: thence from a point twelve (12) west of the west line of Harrison Street to the east line of Fairfield avenue.

Also Webster Street from the south line of Baker Street to the north line of Brooklyn Avenue.

Also McClellan Street from the south line of the alley south of Baker Street to the north line of Brooklin avenue.

Also for the purpose of Straightening Harrison Street south of Baker Street a Strip of ground twelve (12) feet wide commencing at a point where the south line of Baker street intersects the east line of Harrison Street South of Baker Street thence south to the north line of Brooklyn avenue thence west twelve (12) feet parallel with Brooklin avenue. thence north to the south line of Baker Street thence twelve (12) feet east along the south line of Baker Street to the place of beginning.

And said first party will at the same time Vacate or cause to be vacated the alley running east and west between Baker Street and Brooklyn avenue between the following Points. "to wit: Commencing at a point one

hundred and sixty (160) feet west of the west line of Calhoun Street to the east line of Harrison Street and from a point twelve (12) feet west of the west line of Harrison Street to a point 138 feet west of the west line of Webster Street. Said alley not to be vacated until the north and south outlet alley herein provided for is condemned and established.

Fourth It is further provided understood and agreed that the first party shall have and is hereby granted the right and authority for the purpose of opening and extending Harrison Street south over the right of way of said second party for Street purposes from the south line of Brooklyn avenue to the south right of way line of said second party to condemn a Strip of ground sixty (60) feet wide. Commencing at a point on the south line of Brooklyn Avenue three hundred and twelve (312) feet west of the original west line of Calhoun Street thence south parallel with west line of Calhoun Street to the south line of the right of way of the said second party. thence west on said right of way line sixty (60) feet. thence north parallel with the west line of Calhoun Street to the south line of Brooklyn Avenue. thence east on the south line of Brooklyn avenue sixty (60) feet to the place of beginning all of said vacations and condemnations hereinafter and hereinbefore set out to be as shown by a plan of the same which is hereto attached. Marked exhibit "A" and made a part of this contract as fully as if copied herein at full length.

It is further agreed for the purpose of Straightening Harrison Street from Baker Street to Brooklyn avenue and to provide an alley outlet from the alley South of Baker Street the city shall have and is hereby granted the right and authority to condemn. at once. a Strip of ground twelve (12) feet wide commencing at the south west corner of Baker and Harrison Street. thence South along west line of Harrison Street to the north line of Brooklyn avenue. thence west twelve (12) feet. thence north parallel with west line of Harrison Street to the South line of Baker Street. thence twelve (12) feet east to the place of beginning. also a Strip of ground twelve (12) feet wide. Commencing at a point on the South line of Baker Street 138 feet west of the west line

of the present Webster Street. thence south parallel with west line of Webster Street to the north line of the alley south of Baker Street. thence west twelve (12) feet along the north line of said alley. thence north parallel with the west line of Webster Street to the south line of Baker Street. thence east to the place of beginning. including the necessary ground at the south end of said proposed alley to provide a suitable turn at the junction of said alley with the alley south of Baker street. as shown by the plan of said alley which is hereto attached.

The aforesaid Harrison Street and the said Strips being entirely located in Fort Wayne Allen County Indiana.

And it is hereby further agreed by said second party that it will. and does hereby give. donate and dedicate said above described Strips of Ground for the extension of said Harrison Street and the other Strips here in mentioned. to said city to have and to hold forever.

Fifth It is understood and agreed that the said first party will immediately take such action. by resolution or otherwise as may be required by law for the vacation of the parts of Streets as set forth herein. and will also at the earliest practical date. take such action as may be required by law. for the confirmation of said Street vacation. And the first party may at said time or at any subsequent date proceed to adopt resolutions for the condemnations of the Strips of ground hereinbefore Mentioned and may proceed with said condemnation proceedings without objection on the part of said second party. all rights of said second party to so object or to claim or to collect damages because of said proceedings or Taking being hereby expressly waived.

Sixth It is further understood and agreed by the parties hereto in consideration of the various things herein that said City may and is hereby given the right and authority at any time to adopt resolutions or take any other action for the separation of the grades at Harrison Street College and Union Street where crossed by tracks of said second party. It being further agreed that said second party will not contest or litigate the right of said first party to carry out the work of separating said grades as provided in certain resolutions

known as track elevation Resolutions no 4 heretofore adopted and confirmed by the city and number 9 providing for the separation of the grades at Harrison Street adopted by said city concurrently with the execution of this contract and according to the plans. profiles and estimates filed. adopted and approved by the parties hereto under the aforesaid resolutions. all of which are on file in the office of the Board of Public works and made a part of this contract as much as if fully copied herein at full length. which are to be considered and passed upon by the first party after the giving of notices and taking the other steps required by the track elevation law. The second party agrees to do all the work required of it under said resolutions and to waive all the formal steps required by the track elevation statues in so far as its interests may be affected in the way of giving notices of the adoption of said resolutions to file plans and estimates and the other formal and legal steps required. and does. in this contract agree that all formal steps legally required have been taken. It is also further agreed by the parties hereto that the work under said resolutions is to be commenced at College and Union Streets within thirty (30) days from the approval by the Council. of this contract and at Harrison Street within 60 days.

Seventh Said second party agrees that the execution of this contract shall not in any way interfere or be considered as an abridgement of the right of the first party to proceed with the carrying out of Declaratory Resolution number 213 providing for the extension of Clinton Street South over its right of way and said second party further agrees in connection with said declaratory resolution number 213. in consideration of the things herein. that it will not build. place. permit or construct. or permit to be built. placed or constructed, any building. or buildings. of any kind over and across or under the route or line of the proposed extension of Clinton Street within its present right of way or property limits or otherwise. before January 1st 1913

Eighth. The second party further agrees to cancel discharge and release the first party from paying the sum of Two thousand ($2000.00) dollars as agreed to by the first party for the grant of ground from said second party for the widening of Calhoun Street and Broadway under the subways at these points as more fully set out in a certain contract

entered into between the first and second parties on the 8th day of July 1902

The execution of this contract to serve as a complete cancellation and discharge of said obligation

Ninth It is further understood and agreed by and between the parties hereto that said streets aforesaid are to be vacated so as to enable said second party to put in along and over its property between Fairfield avenue and Calhoun Street north of its right of way. Necessary of proper fills in order to bring the proposed new tracks on a level with its old tracks and also to enable it to erect its proposed new depot upon the property owned by it and now intersected with the streets herein agreed to be vacated and it is agreed by and between said parties that said streets are vacated wholly and solely for the purpose afresaid and in consideration of which said second party agrees to construct within reasonable time on the south side of Baker street west of Harrison street a passenger depot approximately one hundred and ninty six (196) feet by one hundred (100) feet according to the plans submitted by said second party to said first party and now on file in the local office of said second party; the building of said depot to be commenced not later than 60 days after the approval of this contract by the council. and to be finished within eighteen (18) months thereafter.

Tenth It is further agreed that the work of the separation of the grades at Harrison Street as opened and extended as provided in resolutions or other actions which may be adopted by the city as provided herein is to be done under the terms of the present track elevation law passed by the legislature of the State of Indiana in 1907. and amended by the same body in 1911. to apply to cities having a population of not less than sixty thousand (60.000) nor more than sixty eight thousand (68.000) provided that said law at the time said work is to be done is still in force and still applies to said City otherwise said work is to be done under any law that is then existing and applicable.

Eleventh It is further understood and agreed that the failure or delay of the first party to secure and carry forth the extensions of Harrison Street further

South than the south right of way line of said second party or the failure or delay of the first party to improve for use or to use any part of said Harrison Street as condemned across the right of way of said second party or the delay in the doing of any other work hereunder is not to abridge. bar. limit or affect the future right of said first party to improve and use said street or any part thereof as a public street as provided for herein. nor shall such failure to use any part thereof be construed as an abandonment nor be construed as creating a title by adverse possession. or presumptive grant in said second party and that the agreement promises and obligations herein contained as to such separation of grades shall be continuing until such separation of grades and full extension of said Street is completed

Twelfth It is further understood and agreed that in the event the said first party fully performs the terms of this contract on its part to be performed and said second party shall fail to commence or complete the building of the passenger depot as herein provided or fail to give the city the right and privilege to cross its right of way at Harrison Street. or interfers with the securing of the right of way or the carrying out of the work of the separation of the grades at said point and at College and Union Streets in the manner as herein provided or fails to proceed with its share of the work as herein contemplated and provided for. or fails to carry out any other of its covenants under this contract. and any such default on the part of such second party shall continue for a period of thirty (30) days after the giving by the first party of a notice to said second party of such defaults. Specifying with reasonable clearness the nature of the particulars in which the said second party is in default. then and in that event of said first party may at its option thereafter proceed to have such work done and collect the cost for doing of the same from the said second party and may also if it so elects proceed to condem said parts of Webster Street Brooklyn avenue and McClellan Street herein vacated and the said second party hereby agrees to waive any right it may have to contest said right of said first party to condemn and also waive any claim it might have for damages therefor. Not withstanding. when the first party ejercises its said right to condemn it may.

have a fill. tracks buildings or other improvements over and on said parts of Streets about to be reopened and condemned In event said company has improvements or buildings thereon, it agrees to remove the same at its expense or if it should fail. then it agrees said first party shall have the right to remove the same and collect the expense therefor from said second party.

Thirteenth It is further understood and agreed that for the purpose of understanding and determining at any time the within descriptions and the points referred to. That the streets and alleys herein. shall be known at all times by the names and locations they are now commonly designated by and as they are named and described on the public records of the city and county. The said second party further agrees that it will not at any time question the sufficiency of the consideration on which this contract is based.

This contract shall be binding upon the parties hereto their successors lessees and assigns.

In witness whereof the said parties have hereunto set their hands and seals the day and year above written.

City of Fort Wayne By
Frank. T. Denby.
G. A. Schwegmann
E. J Lennon
Its Board of Public works

Attest H. W. Becker
Clerk

Pennsylvania Company By.
J. J. Turner
Its Vice President

S. H. Church
assist Secretary

approved A. M Schoyer
Gen Supt.

approved C. B. Hiseman
Gen Solicitor

approved Thos Rodd
Chief Engineer

approved R. Trimble
Chief Eng M of W.

approved G. C. Urquhart.
Real Estate agt.

approved G. V. Peck
Gen Manager.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that the contract heretofore entered into by and between the city of Fort Wayne by and through its Board of Public works and the Pennsylvania Company operating the Pittsburg Fort Wayne & Chicago Railway providing for the vacation of parts of Chicago. Webster and McClellan streets and parts of alley between Baker and Chicago Streets. granting track rights across Calhoun Street. Fairfield avenue Broadway. College and Union Streets and the opening of Harrison Street. the separation of the grade at said street and a College and Union Street and the building of a Passenger Station on Baker Street. all as more fully set out in the contract and in the preamble hereto be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

H. W. Felger.

Done at the Council Chamber in the City of Fort Wayne Indiana this 19th day of July 1912

We hereby certify that the Common Council of the city of Fort Wayne Indiana at a Special Meeting held on the 19th day of July 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 563

Louis S. & Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 20th day of July 1912

Wm. J. Jeffries
City Clerk

Approved this 20th day of July 1912

Jesse Grice
Mayor

General Ordinance no 564

An ordinance extending the city limits and annexing certain territory to the City of Fort Wayne Ind.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind that the territorial limits of the City of Fort Wayne be and are hereby extended as follows

Commencing at a point where the center line of Lafayette Street intersects the center line of McKinnie avenue: thence North along the center line of Lafayette street to a point directly west of the Southwest corner of lot number thirty three (33) Avondale addition: thence East along the South line of lots numbered 33. 72. 137. 176. 241. 280. 345 and 384 of said Avondale addition and to the center line of Hanna Street: thence north along the center line of Hanna Street to a point directly west of the Southwest corner of Weisser Park: thence east along the South line of Weisser Park to the west line of the alley west of ~~Sixth~~ Street: thence North along the west line of said alley to the center line of Eckart Street: thence east along the center line of Eckart Street to the center line of Holton avenue: thence North along the center line of Holton ave to the center line of McKee Street. thence east along the center line of McKee Street extended east to the center line of Anthony Boulevard: thence South along the center line of Anthony Boulevard to its intersection with the center line of McKinnie avenue, thence west along the center line of McKinnie avenue to the place of beginning.

Be it further enacted that the property included within the lines herein indicated shall hereafter be within the corporate limits of the City of Fort Wayne Indiana and subject to taxation for city purposes.

Section 2. This ordinance shall be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

H. W. Felger.

Done at the council chamber in the City of Fort Wayne this 13th day of august 1912

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting

held on the 13th day of august 1912 by a Majority Vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 564

Louis S. C. Schroeder
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval on the 19th day of august 1912

Wm. S. Jefferis
City Clerk

Approved this 20th day of august 1912

Jesse Grice
Mayor.

General Ordinance no 565

An ordinance approving a certain Contract entered into by and between the City of Fort Wayne Indiana by and through its Board of Public Works and Brooks Construction Company providing for the Citys share of Track Elevation work at College and Union Street

Whereas on the 9th day of July 1912 a contract was entered into between the city of Fort Wayne by and through its Board of Public works and the Brooks Construction Company. providing for the Citys share of the work under Track Elevation resolution no 4 a College and Union Streets. which contract is as follows

This agreement Made and entered into this 9th day of July. 1912 by and between the city of Fort Wayne by and through its Board of Public works party of the first part for convenience hereinafter refered to as the "Board" and the Brooks Construction Company of Fort Wayne Indiana party of the secord part. for convenience hereinafter called the contractor. Witnesseth

That for and in consideration of the payment by the said Board to the said contractor of the prices per item hereinafter set out and refered to. the said contractor agrees and binds itself to furnish all the portion and share of work to be done by said Board at College and Union Streets in the city of Fort Wayne Indiana as provided for in track Elevation Resolution Number four (No 4) - All under and by Virtue of an act of the General Assembly of the state of Indiana entitled. "an act providing for the changing of the grades of Streets and highways in cities having a population of not less than forty three thousand nor more than forty nine thousand etc" approved March 12 - 1907. Amended March 18 - 1911 and also an act of the General assembly of the State of Indiana entitled. "an act concerning Municipal Corporations" approved March 6 - 1905 and all acts supplementary and amendatory to the aforesaid acts.

The contractor hereby agrees to perform all work in the prosecution of the above discribed improvements according to the terms and conditions of this Contract and the plans. estimates. profiles. Specifications and bid submitted by said contractor on said work to the entire satisfaction of the said Board.

which said plans. estimates. profiles. Specifications and bids are hereby made a part of this contract as fully and effectually as if copied herein at full length all of which for the purpose of identification and making them a part of this contract are signed by the parties hereto as of even date herewith and if there be any conflict between the prices set out in the aforesaid bids and as set out in this Contract. then the latter is to control

The work to be performed by the said contractor under this contract consists of brick pavement. excavation concrete retaining walls cement sidewalks. resetting of curbing when necessary laying sewers and all necessary connections. Manholes. and catch basins and other work. all of which is more specifically described and set out in the plans and specifications. which work is to be performed by the contractor for the following prices.

At Union Street:

Street excavation per cubic yard fifty five (.55) cents: Wall excavations per cubic yard sixty five (.65) cents: concrete in place. per cubic yard six dollars ($6.00): New Berea Sandstone Curbing. 5"x20" furnished and set per lineal foot. Sixty cents (.60): Heading plank. No 1 White oak furnished and set per lineal foot. twenty (.20) cents: Street paving per square yard. one dollar and ninety two cents ($1.92): Sidewalks paving per square foot eleven (.11) cents: iron pipe railing in place. per lineal foot one dollar ($1.00): New Manholes. each twenty-four ($24.00) dollars: New catch basins. each Thirty eight ($38.00) dollars: 12" Vitrified sewer pipe. in place per lineal foot. Seventy five (.75) cents:

At College Street

Street excavation per cubic yard fifty two (.52) cents: Wall excavation per cubic yard sixty two (.62) cents: concrete in place. per cubic yard four dollars and seventy five ($5.75): New Berea sandstone curbing 5"x20" furnished and set per lineal foot twenty cents (.20): Limestone circular curbing in place per lineal foot. one dollars and ten cents ($1.10): Heading plank no 1 white oak. furnished and set. per lineal foot twenty cents (.20): Street paving per square yard.

One dollar and ninety two cents ($1.92): Sidewalks paving per square foot eleven (11) cents: iron pipe railing in place per lineal foot one dollar ($1.00): New Manholes each: twenty four dollars ($24.00): New catch basins each thirty-eight ($38.00) dollars: 12" vitrified sewer pipe in place per lineal foot Seventy five cents (.75);
It is further understood and agreed that the contractor is to commence said work not later than ten (10) days after being notified to commence by said Board and he further covenants and agrees to complete said work within 60 days after the commencement of same in event said contractor fails to begin said work within said time or to furnish said work within said time or fails at that time or any time thereafter to furnish a sufficient number of skilled workman or adequate equipment to properly push and furnish said work then the said Board may at its option consider said contract void and re-let said work or use the materials tools and Equipment of the contractor in the use for said work and furnish the work itself and deduct from any money that might be due the contractor a sufficient sum to cover the expenditure made by said Board in the performance of said work, It being understood that any extension of time for the commencement or completion of this work is not in any way to affect this contractor release the sureties on any bond given by the contractor to said Board nor will it be necessary to give notice of any extension to said Sureties It is hereby agreed that no assignment of this contract shall be made without the written consent of the said Board and any assignment in violation of this provision will be absolutely void. The Board reserves the right to alter or change any detail in the materials or method of construction which will not Materially increase or decrease the cost of the work without any additional compensation to the contractor. More important changes or alterations may be Made by the Board should the exigency arise and become Apparent during the progress of the work through faulty design as provided by the plans and Specifications or by reason of obstructions met with which could not reasonably have been forseen before the work was

begun. Notwithstanding such changes or alterations may
Materially increase or decrease the cost of the work;
but the Contractor shall not proceed with such changes
or alterations without a written order from the Board
the price agreed upon to be added to or deducted
from the contract price being stated in the order.
In case the Board and contractor cannot agree as to the
price it shall be taken as the estimated actual cost.
plus fifteen per cent. (15%). as determined by the engineer.
No claims shall be allowed for extra Materials or labor
furnished unless the same shall have been ordered in
writing. It is expressly agreed and understood that
any alterations or changes made shall not in any
way violate or annul the contract or affect any bond
hereafter given by the contractor or release his Sureties
therein. Any claim for damages or for any other matter
or cause must be made in writing to the Board at the time
the alleged damage occurs or the cause for the claim arises:
and unless such claim is so presented. it shall be held that
the contractor has waived such claim and it shall not
be entitled to receive pay for the same.
It is agreed that in the event the work to be performed
under the contract is for any reason not commenced or
discontinued after the commencement. the contractor will
not be entitled to any damage for any loss he might
be put thereto by reason thereof. and he hereby waives
and releases the City from any claim that he might
have against it for any such failure to begin or for
the discontinuation of said work except he will be
entitled to payment for the estimated value of work
performed. It is understood that all the Materials and
workmanship of whatever description shall be subject
to the inspection and rejection of the engineer. and
the Contractor shall recognize and assistant or
inspector that the Board may appoint. under the
direction of the engineer. to inspect the Materials
furnished or labor performed. Such inspection by
the said Board. however is not to be considered in any
sense as such an acceptance of the work that the
contractor might demand his money for the same.
It is further agreed by and between the parties that

the acceptance of the work provided for in this contract or the payment therefor. shall not constitute a waiver on the part of the City of any of the provisions of the Contract. plans and Specifications. nor shall it release said contractor or his sureties upon their bond for the faithful performance or guarantee thereof nor shall the final acceptance of the work be even prima facie evidence of the performance of any of the provisions of this contract except to the extent of entitling said contractor to receive the prices therefor and then only shall such acceptance and payment be considered prima facie evidence payment to be made within twenty (20) days after the performance of all conditions of the contract and acceptance and approval of the work by the Board.

The contractor further agrees to pay any and all Moneys due to the contractor or any person or persons furnishing any Material whatever and to pay all laborers for any work done by the contractor or any person in the prosecution of said improvement and the contractor and his sureties on his Liability bond shall be jointly and severally liable on such bond to such contractor Material. Men and laborer for any monies due or becoming due to them or either of them. The Board reserving the right in event any lien or claim is filed or that any work or Material remains unpaid them to hold from the sum due and owing the contractor a sum sufficient to pay any and all such claims. The Board to refuse payment to said contractor until it has been satisfactorily and sufficiently assured that all such liens and claims have been paid The decision of the Board as to the sufficiency of the proof offered as to the payment of said claim or liens is to be final and binding.

The contractor further agrees to waive any right to have issued to him monthly estimates of work and certificates of sixty-five (65%) per cent of the amount shown by such estimates and shall receive no compensation from said city for the performance of said work until after the completion thereof and the performance of all the conditions hereinbefore and hereinafter set out and the acceptance of the work by the Board

To each of the aforesaid conditions and stipulations of

This contract the undersigned bind themselves their successors and assigns

In witness whereof we the foregoing named parties hereunto set our hands and seals this 9th day of July 1912

City of Fort Wayne Indiana
By Frank J. Bunoy
Geo A. Schwagmann
E. J. Lennon
Board of Public works
Brooks construction Company.
By J F. Brookes
Pres

attest W. W. Becker
Clerk

Section 1. Be it ordained by the common council of the city of Fort Wayne that a contract entered into by and between the City of Fort Wayne Ind by and through its Board of Public works and the Brooks Construction Company on the 9th day of July 1912 for the Citys share of the work under Track Elevation Resolution No 4. as fully set forth in the preamble hereto be and the same is hereby in all things confirmed and approved.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor.

Herman Strodel

Done at the Council Chamber in the city of Fort Wayne Ind this 13th day of August 1912.

We hereby Certify that the common Council of the city of Fort Wayne Indiana at a Regular Meeting held on the 13th day of aug 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 565

Louis S. C. Schroeder President Wm J. Jefferies City Clerk

Presented to the Mayor for approval on the 19th day of aug 1912

Wm J. Jefferies
City Clerk

approved this 20th day of August 1912

Jesse Grice
Mayor

General Ordinance no 566

An ordinance approving a certain contract entered into by and between the city of Fort Wayne by and through its Board of Public works and the Moelleing Construction Company on the 10th day of June 1912 providing for the City share of Track Elevation work at Fairfield avenue.
Whereas on the 10th day of June 1912 a Contract was entered into between the city of Fort Wayne by and through its Board of Public works and the Moelleing Construction Company providing for the doing of the Citys share of the work under Track Elevation Resolution no 3 at Fairfield Avenue.
Section 1. Be it ordained by the common council of the Ceity of Fort Wayne that a Contract entered into by and between the city of Fort Wayne by and through its Board of Public works and the Moelleing Construction Company on the 10th day of June 1912 for the citys share of the work under track elevation Resolution no 3 as fully set forth in the preamble hereto be and the same is hereby in all things confirmed and approved.
Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor.

Allen Hamilton.

Done at the council chamber in the Ceity of Fort Wayne this 13th day of august 1912

We hereby certify that the common Council of the city of Fort Wayne Indiana at a Regular meeting held on the 13th day of august 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 566

Louis D. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 19th day of august 1912

Wm J. Jeffries
City Clerk

Approved this 20th day of august 1912

Jesse Grice
Mayor.

General Ordinance No 567

An Ordinance amending Section 1 of General Ordinance No 480 being an ordinance amending section 1. Chapter 4 of an ordinance entitled "an ordinance providing for all matters concerning. affecting or Relating to Construction Equipment. Alteration Repairs or Removal of Buildings. Structure and appurtenances thereof. erected or to be erected in the city of Fort Wayne Indiana as amended May 25th 1909 the same to be known and cited as Building Code adopted May 25th 1904 and being General Ordinance no 390.

Section 1. Be it ordained by the common counsil of the leity of Fort Wayne That section 1 of an ordinance amending section 1 chapter 4 of an ordinance entitled "an ordinance providing for all matters concerning affecting or relating to construction equipment alteration. repairs or removal of buildings. Structure and appurtenances thereof erected or to be erected in the leity of Fort Wayne Indiana as amended May 25.-1909 the same to be known and cited as Building code adopted May 25th 1902 and being Gunral Ordinance no 390. be and the same is hereby amended to read as follows:

Section 1. The Fire limits are and shall be that territory in the city of Fort Wayne contained within the boundry limits described as follows: Beginning at the intersection of superior street and the East line of County addition: thence south along the East line of county addition to Columbia Street: thence east on Columbia Street to Clay Street: thence south on Clay street to Old Fort Place: thence west on Old Fort Place to Lafayette Street: thence south on Lafayette Street to Murray Street: thence west on Murray Street to Calhoun Street: thence North on Calhoun Street to the first alley south of Grand Street: thence west along the first alley south of Grand Street to Webster street: thence North of Webster Street and Webster Street produced North across the lands of the Wabash Railway Company and the Pitsburg. Fort Wayne and Chicago Railway Company to Webster Street on the north side of said Pittsburg Fort Wayne and Chicago Railway Company. thence North on Webster Street to the St. Marys River: thence in a

Straight line crossing the St. Marys river to a point fifty (50) feet north of the Main track of the L. S + M. S. Railway where the first alley west of wells Street extented intersects said Main track: thence west on a line fifty (50) feet North of and parallel with the aforesaid track to a point sixty-one (61) feet east of the west line of Hannas out lot 15: thence directly North One hundred (100) feet: Thence easterly following the south line of P. A. Randalls Subdivision to the first alley west of wells Street and north along said alley to Fairmont Place thence east on Farmont Place to wells street: thence north on wells Stuet to the south line of lot no 57 north side addition: Thence east on the South line of lots numbered 57-58-61-North Side addition: to the alley east of Cass Street: thence North in the alley east of Cass Street to the north line of first Street: thence east on the North line of first Street to the west line of lot no 70 North side addition: thence north of the west line of said lot no 70 to the south line of alley North of first Street thence east on the South line of said alley and the south line of said alley produced. East to the east line of the right of way of the railway operated by the L. S. + M. S. Railway Company: Thence Southwest following said right of way line to Cass Street. Thence South on Cass Street to wells Street: thence Southeasterly on wells Street to Superior Street: thence east on Superior Street to the place of Beginning: Section 2. That this ordinance shall be in full force and effect on and after its passage. approval by the Mayor and legal publication

Herman Strodel

Done at the council chamber in the city of Fort Wayne this 13th day of august 1912

We hereby certify that the Common Council of the City of Fort Wayne Ind at a Regular Meeting held on the 13th day of august 1912 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as Annual Ordinance

No 567
Louis S. Le. Schroeder
Prisident

Wm S. Jeffries
Ceity Clerk

Presented to the mayor for approval on the 19th
day of august 1912

Wm S. Jeffries
Ceity Clerk

Approved this 20th day of august 1912
Jesse Bruce
Mayor.

General Ordinance no 568

An ordinance amending Section 1 of General Ordinance no 557 being an ordinance entitled "an ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that section 1. of General ordinance no 557 being an ordinance entitled an ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana be amended to read as follows.

Section 1. Be it ordained by the common counsel of the City of Fort Wayne Indiana that the territorial limits of the city of Fort Wayne be and are hereby extended to read as follows

Commencing at a point where the west line of Anthony boulevard extended north intersects the center line of State Street: thence due north two hundred seven feet (207): thence parallel with State Street to the center line of Malcolm Street: thence due south along the center line of Malcolm Street two hundred and seven (207) feet to the center line of State Street: thence east along the center line of State street to the place of beginning.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the mayor and legal publication

J. J. Bacon.

Done at the council chamber in the city of Fort Wayne Ind this 13th day of august 1912

We hereby Certify that the common council of the City of Fort Wayne Indiana at a Regular Meeting held on the 13th day of august 1912 by a Majority vote of all the members elect did pass the ordinance thereunto attached and known as Genral Ordinance no 568

Louis S. & Schroeder
Prusident

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 19th day of aug 1912

Wm. J. Jeffries
City Clerk

Approved this 20th day of august 1912

Jesse Grice
Mayor

General Ordinance no 569

An ordinance transferring and vesting in the Department of Public Parks of the City of Fort Wayne Indiana. the boulevard along the East bank of the St Marys River from New Main Street to Berry street. as opened by the Board of Public works under Declatory Resolution #177 and Berry Street. along the East bank of the St. Marys River. from Nelson street to Swinney Park as extended by the Board of Public works. under Declaratory Resolution #163 in the said City to be converted by the Board of Park Commissioners into a parkway with full power of control the management thereof and naming said boulevard and said extension of Berry Street "Thieme Drive"

Section 1. Be it ordained by the Common council of the City of Fort Wayne Ind that the boulevard along the east bank of the St Marys River from New Main Street to Berry Street. as opened by the Board of Public works under declatory Resolution no 177 and Berry street. along the east bank of the St. Marys river from Nelson Street to Swinney Park as extended by the Board of Public works under declatory Resolution #163 be and the same are hereby placed under the government. Management and control of the Department of Public Parks of said City for the purpose and with the right upon the part of the Board of Park commissioners of said City to convert the same into a parkway: and the said Board of Park Commissioners shall have full power upon the acceptance by it of said boulevard and said Street herein described for the purpose aforesaid. to govern. Manage. Maintain regulate and direct the public use thereof as a parkway and to subject the same to its rules and regulations: Subject however to the laws of the State and to the powers of the common council in relation thereto.

Section 2. That said boulevard from New Main Street to Berry street and said Berry Street from Nelson Street to Swinney Park shall be named and hereafter be known as Thieme Drive.

Section 3. This ordinance shall be in full force and effect from and after its passage approval by the Mayor and Legal publication

Charles W. Lettow

(over)

Leone at the council chamber in the city of Fort Wayne
this 10th day of sept 1912

We hereby certify that the common council of the city of Fort
Wayne Indiana at a Regular Meeting held on the 10th day
of sept 1912 by a Majority vote of all the members elect did
pass the ordinance hereunto attached and known as
General Ordinance no 569

Louis R. C. Schroder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 14th day of
sept 1912

Wm. J. Jefferies
City Clerk

Approved this 14th day of sept 1912

Jesse Price
Mayor

General Ordinance no 570

An ordinance amending section thirteen of General Ordinance no 337 being an ordinance requiring the inspection. authorizing the condemnation if unwholesome and regulating the sale of milk and cream: requiring persons engaged in the sale of the same to obtain a license so to do: providing for the appointment of a Dairy and meat inspector: prescribing his powers. duties and Compensation: providing a penalty for its violation and repealing all laws in conflict with the same as amended august 27th 1907"

Section 1. Be it ordained by the Common council of the city of Fort Wayne Indiana that section thirteen of General Ordinance no 337 being "an ordinance requiring the inspection. authorizing the condemnation if unwholesome and regulating the sale of milk and cream: requiring persons engaged in the sale of the same to obtain a license so to do: providing for the appointment of a dairy and meat inspector: prescribing his powers. duties and compensation: providing a pinalty for its violation and repealing all laws in conflict with the same as amended august 27, 1907" be amended to read as follows.

Section 13. That the Department of Public Safety of the City of Fort Wayne shall appoint a competent person as dairy and meat inspector who shall be nominated by the Department of Health and Charities and who shall be well versed in the examination of cattle milk and dairy products and shall have a Sufficient knowledge of Sanitary Science to carry out the provisions of this ordinance. Such dairy and meat inspector shall receive a salary at the rate of fifteen hundred dollars ($1500.00) per annum and shall not engage in any other occupation and may be removed from office by the Department of Health and Charities for incompetency or inefficiency. Such dairy and meat inspector shall execute to said city a bond in the sum of Two Thousand dollars ($2000.00) with surety to the approval of the Department of Public Safety conditioned for the faithful performance of his duties. as such dairy and meat inspector

Sec. 2 This ordinance to be in full force and take effect from and after its passage and approval by the Mayor

(over)

and legal publication

P. Van Zweringen

Done at the council chamber in the city of Fort Wayne Ind this 10th day of sept 1912

We hereby certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 10th day of sept 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 570

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 14th day of sept 1912

Wm. J. Jeffries
City Clerk

Approved this 14th day of sept 1912

Jesse Bruce
Mayor.

General Ordinance No 571

An ordinance transferring and vesting in the Department of Public parks of the city of Fort Wayne Indiana a certain part of Broadway in the said city to be converted by the Board of Park Commissioners into a parkway with full power of control and the Management thereof.

Section 1. Be it ordained by the Common council of the city of Fort Wayne Indiana that the street in said city known as Broadway from the north line of the Bluffton road to the South line of Rudisill Boulevard. be and the same is hereby placed under the government and control of the Department of Public Parks of said city for the purpose and with the right upon the part of the Board of Park Commissioners of said city to convert the same into a parkway: and said Board of Park Commissioners shall have power upon the acceptance by it of said street herein described, for the purpose aforesaid to govern, manage, Maintain. regulate and direct the public use thereof as a parkway and to subject the same to its rules regulations: Subject however to the laws of the state and to the powers of the Common Council in relation thereto

Section 2. This ordinance shall be in full force and effect from and after its passage approval of the Mayor and legal publication

Charles W. Cittore

Done at the Council Chamber in the city of Fort Wayne Indiana this 10th day of Sept 1912

We hereby Certify That the Common Council of the city of Fort Wayne Ind at a Regular Meeting held on the 10th day of Sept 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as

General Ordinance no 571

Louis S. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 14th day of Sept 1912

Wm. J. Jefferies
City Clerk

approved this 14th day of Sept 1912

Jesse Grice
Mayor

General Ordinance No 572

An ordinance authorizing the Board of Park Commissions to improve East Wayne Street from the East line of Barr Street to the west line of Grant Avenue. and Washington Boulevard East from the east line of Barr Street to the west line of Glasgow Avenue be removing dead trees. by pruning and preserving trees requiring the same and by planting Norway Maples in all open places.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana That the Board of Park Commissioners of the City of Fort Wayne be and they are hereby authorized and ordered to take the necessary steps. adopt resolutions. if necessary. providing for the improvement of East Wayne Street from the east line of Barr Street to the west line of Grant Avenue and Washington Boulevard east from the east line of Barr street to the west line of Glasgow Avenue by removing all dead trees. by pruning and preserving all the trees requiring the same along the aforesaid Streets and by planting good. healthy. nursery. grown Norway Maples uniformly in all open places and by doing all the other things necessary to put the trees along said Street in first class condition said work to be done in accordance with Section 234 of "an act concerning Municipal Corporations" passed by the General assembly of the state of Indiana. in 1905 and according to all other laws of said State and ordinances of the City of Fort Wayne.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the mayor and Legal Publication

Charles W. Lettick

Done at the Council chamber in the City of Fort Wayne Indiana this 10th day of Sept 1912

We hereby certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 10th day of sept 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 572

Louis S. C. Schroeder
President

Wm. J. Uffenis
City Clerk

Presented to the Mayor for approval on the 14th day of Sept. 1912

Wm. J. Uffenis
City Clerk

approved this 10th day of sept 1912

Jesse Grice
Mayor.

General Ordinance no 573

An ordinance transferring and vesting in the Department of Public Parks of the City of Fort Wayne Indiana Pfeiffer avenue Centlivre avenue and State street in the said city to be converted by the Board of Park Commissioners into a boulevard with full power of control the management thereof and the changing of the names of Pfeiffer avenue. Centlivre avenue and State Street to Pfeiffer Boulevard

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the streets in said city known as Pfeiffer avenue from Sherman Street to the Lake Shore and Michigan Southern Railroad. Centlivre avenue from the west line of C. L. Centlivre addition to Spy run avenue and State Street from Spy run avenue to Anthony Boulevard. be and the same is hereby placed under the government management and control of the Department of Public Parks of said city for the purpose and with the right upon the part of the Board of Park Commissioners of said City to convert the same into a boulevard: And said Board of Park Commissioners shall have full power upon the acceptance by it of said Streets herein described for the purpose aforesaid. to govern manage Maintain regulate and direct the public use thereof as a boulevard and to subject the same to its rules and regulations: subject however to the laws of the State and to the powers of the Common Council in relation thereto.

Section 2. That Pfeiffer avenue from Sherman Street to the Lake Shore & Michigan Southern Railroad Centlivre avenue from the west line of C. L. Centlivre addition to Spy run avenue and State Street from Spy run avenue to Anthony Boulevard shall be changed to and hereafter be known as Pfeiffer Boulevard.

Section 3. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Herman Stroodel

Done at the Council Chamber in the City of Fort Wayne Indiana this 10th day of sept 1912.

We hereby Certify that the common Council of the City of Fort Wayne at a regular meeting held on the 10th day of sept 1912 by a Majority vote of all the members

elect did pass the ordinance hereunto attached and known as General Ordinance no 573

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 14th day of Sept 1912

Wm. J. Jeffries
City Clerk

Approved this 14th day of Sept 1912

Jesse Price
Mayor

General Ordinance no 574

An ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne by and through its Board of Public works and John Suelzer providing for an extension to the boiler room of the Municipal light and power plant.

Whereas heretofore on the 20th day of August 1912 the city of Fort Wayne by and through its Board of Public works entered into a contract with John Suelzer providing for the construction of an extension to the boiler room of the Municipal light and power plant.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. That the contract heretofore entered into on the 20th day of august 1912 by and between the city of Fort Wayne by and through its Board of Public works and John Suelzer as more fully set forth in the preamble hereto be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Louis S. C. Schroeder.

Done at the Council Chamber in the City of Fort Wayne Indiana this 10th day of Sept 1912

We hereby Certify that the Common Council of the city of Fort Wayne did at a Regular Meeting held on the 10th day of sept 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 574

Louis S. C. Schroeder
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval on the 14th day of sept 1912

Wm. S. Jefferis
City Clerk

Approved this 14th day of sept 1912

Jesse Grice
Mayor

General Ordinance 575

An ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne by and through its Board of Public works and Wm H. Dunn providing for the furnishing of a years supply of coal for the city Crematory.

Whereas heretofore on the 1st day of august 1912 the City of Fort Wayne by and through its Board of Public works entered into a contract with Wm H. Dunn providing for the furnishing of a years supply of coal for the city Crematory

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that the contract heretofore entered into on the 1st day of august 1912 by and between the city of Fort Wayne by and through its Board of Public works and Wm H. Dunn as more fully set forth in the preamble hereto be and the same is in all things ratified and approved

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Louis H. C. Schroeder.

Done at the council chamber in the city of Fort Wayne Indiana this 10th day of Sept 1912

We hereby Certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 10th day of Sept 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 575

Louis H. C. Schroeder
President

Wm. J. Supphris
City Clerk

Presented to the Mayor for approval on the 14th day of Sept 1912

Wm. J. Supphris
City Clerk

Approved this 14th day of Sept. 1912

Isaac Strice
Mayor.

General Ordinance no 576

An ordinance fixing the tax levy for city purposes for the year 1913

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. That a levy of one dollar and sixteen cents ($1.16) upon each one hundred dollars ($100) of assessed valuation of all property within the corporate limits of the city of Fort Wayne Indiana be made for the year 1913. That the above levy be devided as follows:

General purposes and interest	.86¼
Track Elevation	.10
Park Fund	.08
Garbage Plant Fund	.02
Sinking Fund	.05
Electric Light Plant Fund	.02½
Firemens Pension Fund	.01
Policemens Pension Fund	.01
Monument Fund	.00¼
	$1.16

Also that there shall be collected from each male inhabitant liable according to law. a poll tax of two dollars ($2.00)

Section 2. That all taxes shall be collected in semi-annual installments.

Section 3. This ordinance shall be in full force and effect from and after its passage and approval by the Mayor

H. G. Pfleger.

Done at the council chamber in the city of Fort Wayne Indiana this 24th day of sept 1912

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 24th day of sept 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 576.

Louis A. C. Schroeder
President.

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 28th day of sept 1912

Wm. C. Jeffries
City Clerk

approved this 28th day of sept 1912

Isaac Price
Mayor

General Ordinance No 577

An ordinance transferring and vesting in the Department of Public Parks of the City of Fort Wayne Indiana. Beaver Avenue from the North line of Home avenue to the north line of Rudisill Boulevard in the said City to be converted by the Board of Park Commissioners into a pleasure driveway with full power of control and Management thereof.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that Beaver Avenue from the North line of Home Avenue to the North line of Rudisill Boulevard in said City be and the same is hereby placed under the Government Management and control of the Department of Public Parks of said City for the purpose and with the right upon the part of the Board of Park Commissioners of said City to convert the same into a pleasure driveway: and said Board of Park Commissioners shall have full power upon the acceptance by it of said street herein described for the purpose aforesaid to govern, manage, maintain, regulate and direct the public use thereof as a pleasure driveway, and to subject the same to its rules and regulations: Subject however to the laws of the state and to the powers of the Common Council in relation thereto

Section 2. This ordinance shall be in full force and effect from and after its passage approval by the Mayor and legal publication

E. A. Wagner.

Done at the Council Chamber in the City of Fort Wayne Indiana this 24th day of Sept 1912

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 24th day of Sept 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 577

Louis A. C. Schroeder
President

Wm. S. Jefferis
City Clerk

Presented to the Mayor for approval on the 28th day of Sept 1912

Wm. S. Jefferis
City Clerk

Approved this 28th day of Sept 1912

Jesse Grice
Mayor

General Ordinance no 578

An ordinance transferring and vesting in the Department of Public Parks of the City of Fort Wayne Indiana. Rudisill Boulevard from the west line of Hanna Street to the East line of Grand Boulevard addition said east line being the west line of the alley West of Thomas Street in the said City to be converted by the Board of Park Commissioners into a boulevard with full power of Control and the management thereof.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that Rudisill boulevard from the west line of Hanna Street to the east line of the Grand Boulevard addition said east line being the west line of the alley west of Thomas Street be and the same is hereby placed under the government Management and Control of the Department of Public Parks of said City for the purpose and with the right upon the part of the Board of Park Commissioners of said City to convert the same into a boulevard: and the said Board of Park Commissioners shall have full power upon the acceptance by it of said boulevard herein described for the purpose aforesaid. to govern. Manage. Maintain regulate and direct the public use thereof as a boulevard and to subject the same to its rules and regulations: Subject however to the laws of the state. and to the powers of the Common Council in relation thereto.

Section 2. This ordinance shall be in full force and effect from and after its passage approval by the Mayor and legal publication

Jas. W. Fulger

Done at the Council Chamber in the City of Fort Wayne Indiana this 24th day of Sept 1912

We hereby Certify that the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 24th day of Sept 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 578

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 28th day of Sept 1912

Wm. J. Jeffries City Clerk

approved this 28th day of Sept 1912

Jesse Grice
Mayor

General Ordinance no 574

An ordinance approving a contract entered into on the 10th day of sept 1912 by and between the City of Fort Wayne Indiana party of the first part and the White Company of Cleveland Ohio. by and through its agent. George S. Fox party of the second part.

Whereas on the 10th day of September 1912 the City of Fort Wayne by and through its Board of Public Safety entered into a Contract with the White Company of Cleveland Ohio by an through its agent George S. Fox for the purchase and delivery to said City of one Combination Chemical and hose wagon

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that the contract heretofore entered into by and between the City of Fort Wayne and the White Company of Cleveland Ohio on the 10th day of Sept 1912 as more fully set out in the preamble hereto be in all things fully confirmed and approved.

Section 2. This ordinance to be in full force and effect from and after its passage approval by the Mayor and legal publication

Allen Hamilton

Done at the Council Chamber in the City of Fort Wayne Indiana this 24th day of Sept 1912

We hereby certify That the Common Council of the City of Fort Wayne at a Regular election held on the 24th day of Sept 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 574

Louis S. C. Schroeder
President

Wm S. Jefferis
City Clerk

Presented to the Mayor for approval on the 28th day of Sept 1912

Wm S. Jefferis
City Clerk

Approved this 28th day of sept 1912

Jesse Grice
Mayor

General Ordinance no 580

An ordinance providing for the appointment of weighers of hay grain and other articles by dealers and warehouse men on application to the Board of Public Safety.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that any dealer or warehouse man selling handling or storing hay grain or other such articles desiring the appointment by the city of a weigher and Measurer to weigh and measure such articles as they come into or go out of the possession of said dealer or warehouse man. shall file a written application with the Board of Public Safety asking said Board that a Weighmaster and Measurer be appointed.

Section 2. Upon the application by any dealer. Warehouse man or any person firm or corporation asking for the appointment of a Weighmaster and measurer of Weigh-Masters and Measurers. Said Board May and is hereby given the power and authority to appoint such Weigh-Master and measurer or Weighmasters and measurers to weigh or measure the different grain or other articles received by such dealer and Warehouse man or any other person. firm or corporation. which person so appointed shall be subject to removal by said Board of public Safety whenever in the opinion of said Board he or they shall fail to faithfully perform the duties of his or their employment. Each such Weighmaster and measurer shall execute to the City of Fort Wayne a bond in the sum of One thousand dollars ($1000.00) with sufficient surety to be approved by said Board of Public Safety for the faithful performance of his duties as such Weighmaster and measurer. Said Weighmaster and measurer or Weighmasters and measurers shall receive no compensation from the said City but shall be paid by the party requesting said appointment.

Section 3. Every such Weighmaster and measurer or weighmasters and measurers appointed as herein provided shall be required to have his scales accurate at all times and at any time they appear to be defective or out of order he shall at once notify the City Sealer and inspector of weights and Measures to test the same and shall not use said scales until the same have

been tested and put in good accurate working order.
Said weighmaster and measurer or weighmasters and measurers are also authorized to issue to any person firm or corporation. Certificates showing the weight of the hay. grain. or other articles received by his employer. or any other person firm or corporation and weighed by him.
Section 4. Any person so appointed weighmaster and measurer as herein provided or any person firm or Corporation so employing any such weighmaster and measurer as herein provided who shall in any way issue false statements of weights or connive or arrange to issue false certificates or statements of weight shall in addition to the other penalties provided by ordinance of law for the giving of false weights and measures. be fined not less than ten dolland($10.00) nore more than one hundred dollars($100.00) and the appointment of said weighmaster and measurer or weighmasters and measurers revoked and said employer shall not be granted the appointment of another weighmaster and measurer or weighmasters and measurers.
Section 5. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles W. Lettoe

Done at the council chamber in the city of Fort Wayne Ind this 3th day of Oct 1912

We hereby certify that the Common council of the city of Fort Wayne Ind at a Regular meeting held on the 8th day of Oct 1912 by a Majority vote of all the members elected did pass the ordinance hereunto attached and known as General Ordinance no 580

Louis S. C. Schroeder
President

Wm S. Jeffries
City Clerk

Presented to the Mayor for approval this 12th day of Oct 1912

Wm S. Jeffries City Clerk

Approved this 12th day of Oct 1912

Jesse Grice
Mayor

General Ordinance no 581

An ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the territorial limits of the city of Fort Wayne be and are hereby extended and the land included thereby annexed to said city which land so annexed and the limits so extended are described as follows. "to wit" Commencing at a point where the west line of the right of way of the Lake Shore and Michigan Southern Railroad Company intersects the present city limits at the north side of the creek or run known as Junk ditch or creek: thence Southwesterly along the north line of said right of way to a point where the same intersects the east line of the right of way of the Grand Rapids and Indiana Railroad Company: thence north along the east line of the right of way of the Grand Rapids and Indiana Railroad Company to a point where the same would intersect the present city limits at the north side of the ditch or creek aforesaid: thence east and Southerly along the present city limits following the meandering line of said creek to the place of beginning.

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the mayor and legal publication Charles W. Cittor

Done at the Council Chamber in the city of Fort Wayne and this 8th day of Oct 1912.

We hereby certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 8th day of Oct 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 581

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval this 12th day of Oct 1912.

Wm. J. Jeffries
City Clerk

approved this 12th day of Oct 1912

Jesse Grice
Mayor

General Ordinance no 582.

An ordinance empowering and authorizing the chief of the Fire Department of the City of Fort Wayne Indiana to inspect buildings and other Structures; to order the correction of the conditions therein which he may find to tend toward endangering property and life by fire; to appoint Deputy inspectors to make such inspection and punishing disobedience of such orders.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind That the chief of the Fire Department is hereby empowered and authorized to at any and all reasonable times to enter upon and into any premises. buildings or Structure within the corporate limits of the City of Fort Wayne for the purpose of examining and inspecting the same to ascertain the condition thereof with regard to the presence. arrangements of deposit of any articles. Materials. Substances. goods. wares. or Merchandise which May have a tendency to create danger of or from fire in said premises. building or Structure or to create danger in case of fire on or in the same. or personal injury to or loss of life of the occupants of or persons on or in said premises. building or Structure; also with regard to the conditions. size. arrangements and efficiency of any and all appliances for protection against fire on or in such premises. building or Structures.

Section 2. If he shall find on such inspection of such premises. building or Structure any rubbish. debris. waste or inflamable or combustible Materials. and that the same is not so arranged or disposed as to afford reasonable safeguard against the danger of fire. or if he shall find that the articles. Materials. goods. wares and Merchandise on or in said premises. building or Structure are so arranged and disposed that the occupants thereof or persons rightfully on or in the same would not. because of such arrangement and disposition be afforded reasonable access to the exits of said premises. building or Structure in case of fire, or if he shall find that by reason of such arrangement or disposition the members of the Fire Department would unnecessarily and unreasonably

be interfered with in the exercise of their duties in and about such premises. building or Structure in case of fire in the same. he may order in writing the removal of such rubbish. debris, waste or inflammable or combustible Materials from said premises. building or Structure. or the disposing and arranging of the same on or in said premises. building or Structure in such manner as will remove such danger from fire. He may also order in writing that such articles Materials. goods. wares or merchandise be so arranged and disposed on or in said premises. building or Structure that the occupants thereof or the persons rightfully on or in the case. will be afforded all reasonable access to the exits from the same in case of fire. and the members of the Fire Department will be afforded all reasonable facilities for the discharge of their duties in and about said premises. building or Structure in case of Fire.

Section 3. The chief of the Fire Department hereby is empowered and authorized to appoint such and as many deputies Employees of the fire department to make the inspections hereinbefore provided for. who shall report in writing the results of their inspections to the chief of the Fire Department and who are hereby empowered and authorized to make such orders in respect to the conditions found by them on inspection as are hereby authorized to be made by the chief of the Fire Department. Should any owner lessee or occupant of any premises. building or Structure or the owner or person in control of any Materials. good. wares or merchandise consider themselves aggrieved by such order of such deputy. he may. within twenty-four hours after the said order has been served on him. appeal to the chief of the Fire Department who shall thereupon make such order in the premises as in his discretion he may deem right and reasonable. and said order shall be final.

Section 4. Such order or orders hereinbefore mentioned shall be directed to the owner. lessee or occupant of such premises. building or Structure or to the person in control of the articles. Materials. good. ware or merchandise herein referred to. or to the owner thereof as the circumstances may require. and it is hereby made the duty of

Such owner. lessee or occupant of such premises. building or Structures, and of such person in control of such articles. Materials goods. wares and Merchandise. or the owner thereof to comply with such order or orders with all reasonable dispatch and diligence
Section 5. Any owner. lessee or occupant of such building premises or Structure or any person in control of such articles. Materials goods. Wares or Merchandise as hereinabove referred to. or the owner thereof who shall fail or neglect to discharge the duties imposed by this ordinance and the orders of the chief of the Fire Department or the deputies appointed by him under this ordinance. on conviction thereof. shall be fined not less than ten dollars ($10.) or not more than One hundred dollars ($100.00) for each day of failure or neglect.
Section 6. The terms "owner" "lessee". "occupant" person in control of" as used in the foregoing shall be construed to include the plural as well as the singular and artificial persons as well as real
Section 7. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

Charles. E. Welch

Done at the Council chamber in the city of Fort Wayne Indiana this 12th day of Nov 1912

We hereby certify that the common council of the City of Fort Wayne Indiana at a Regular meeting held on the 12th day of Nov 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 582

Louis A. C. Schroeder
President

Wm. S. Jeffries
City Clerk

Presented to the Mayor for approval on the 16th day of Nov 1912

Wm. S. Jeffries
City Clerk

Approved this 18th day of Nov 1912

Jesse Grice
Mayor

General Ordinance No 583.

An ordinance authorizing the employment of certain Officers and Employees of the Police Department of the City of Fort Wayne and fixing their compensation.

Section 1. Be it ordained by the common council of the City of Fort Wayne that the Officers and Employees of the Police Department of the City of Fort Wayne Indiana shall respectively receive the Compensation and Salaries as hereinafter in this ordinance provided. The employment of such Officers and employees as herein after named are hereby authorzid and the Compensation and Salaries of such Officers and employees are hereby fixed at the sums and amounts respectfully named for such Officers and Employees.

The Chief of Police shall receive a Salary at the rate of Eighteen Hundred dollars ($1800) per annum.

The Captain of Police shall receive a Salary at the rate of Thirteen Hundred Twenty dollars ($1320.) per annum.

The Lieutenant of Police shall receive a Salary at the rate of Eleven Hundred Forty dollars ($1140) per annum

Two Sergeants of Police shall each receive a Salary at the rate of Ten Hundred eighty dollars ($1080) per annum.

Three Detective Sergeants of Police shall receive a Salary at the rate of ten hundred eighty ($1080) per annum.

Each Patrolman. Court Bailiff of the City Court. Police Stationmaster. Patrol Driver and Police Station clerk. during the first year of his services in the City of Fort Wayne under the Board of Public Safety in any of the capacities above mentioned shall receive a Salary at the rate of Eight Hundred Forty dollars ($840) per annum.

Each Patrolman. Court Bailiff of the city court. Police Stationmaster. Patrol Driver and Police Station clerk during the second year of his service in the City of Fort Wayne under the Board of Public Safety in any of the capacities above mentioned shall receive a Salary at the rate of Nine hundred dollars ($900) per annum.

Each Patrolman. Court Bailiff of the City court. Police Stationmaster. Patrol Driver. and Police Station clerk. during the third year of his Services in the city of Fort Wayne under the Board of Safety in any of the

Capacities above Mentioned. Shall receive a Salary at the rate of Nine hundred Sixty dollars ($960.) per annum
The Chief Office clerk shall receive a Salary at the rate of Eight hundred forty ($840) dollars per annum.
The Electrician Shall receive a Salary at the rate of Five Hundred Forty ($540.) dollars per annum.
The Humane Officer shall receive a Salary at the rate of Six Hundred Sixty ($660) dollars per annum.
The Marketmaster Shall receive a Salary at the rate of Six Hundred ($600.) Dollars per annum
The Weighmaster shall receive a Salary at the rate of Eight Hundred forty ($840.) dollars per annum
Section 2. That all ordinances or parts of Ordinances in conflict herewith be and they are hereby repealed.
Section 3. That this ordinance be in full force and take effect on and after the first day of January 1913

Charles W. Lesher

Done at the Council Chamber in the City of Fort Wayne this 10th day of Dec 1912

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 10th day of Dec 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 583.

Louis A. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 13th day of Dec 1912

Wm S. Jefferies
City Clerk

approved this 16th day of Dec 1912

Jesse Grice
Mayor

General Ordinance No 584

An ordinance authorizing the employment of certain Officers and employees of the Fire Department of the City of Fort Wayne and Fixing their Compensation

Section 1. Be it ordained by the Common Council of the City of Fort Wayne that the Officers and employees of the Fire Department of the City of Fort Wayne shall receive the compensation and Salaries as hereinafter in this ordinance provided. The employment of such Officers and employees as hereinafter named are hereby authorized and the compensation and salaries of such Officers and employees are hereby fixed at the sums and amounts respectfully named for such Officers and employees

The Chief of the Fire Department shall receive a Salary at the rate of Eighteen Hundred ($1800.) dollars per annum.

The assistant Chief of Fire Department shall receive a Salary at the rate of Thirteen Hundred Twenty ($1320) dollars per annum

Each Fireman during the first six months of service shall receive a Salary at the rate of Seventy ($70.00) dollars per Month

Each Fireman during the second six months of service shall receive a Salary at the rate of Seventy five ($75.00) dollars per Month

Each Fireman after the first twelve months and thereafter shall receive a Salary at the rate of Eighty ($80.00) dollars per Month.

Each Captain shall receive a Salary of Ninety-Seven dollars and fifty ($97.50) per month. and each engineer shall receive a Salary of Ninety five ($95.00) dollars per month

Section 2. That all ordinances or parts of ordinances in conflict herewith be and they are hereby repealed.

Section 3. That this ordinance be in full force and take effect on and after the first day of January 1913

Charles R. [illegible]

Done at the Council Chamber in the City of Fort Wayne this 10 day of Dec. 1912

We hereby Certify that the Common Council of the City of Fort Wayne did at a Regular Meeting held on the 10th day of Dec 1912 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 584

Louis A. Schneider, President Wm. S. Jeffries City Clerk

Presented to the Mayor for approval on the 13th day of Dec 1912

Wm. S. Jeffries City Clerk

Approved this 16th day of Dec 1912

Jesse Grice

Mayor

General Ordinance No 585

An ordinance protecting the public Health. defining the duties of the City Health Officer and Chief of Police: directing the abatement of nuisances and prescribing penalties.

Section 1. Be it ordained by the City council of Fort Wayne State of Indiana That it shall be unlawful and that it shall be a nuisance for any person. persons. company or corporations to erect. construct. cause. permit. keep or maintain within the limits of said City. anything whatsoever which is injurious to Health. or indecent or offensive to the Senses. or an obstruction to the free use of property. and any person or persons Maintaining any nuisance as above set forth is declared to be the author and Maintainor of a nuisance.

Section 2. It shall be unlawful for any person or persons company or corporation to throw or deposit or suffer to be thrown or deposited. or Suffer or permit any child. Servant. Member of the family or any other person under his. her or their control to throw or deposit any Manure rubbish. Slops putrid. or unsound animal or Vegetable Matter. or any filthy noisome or unwholesome liquid or Slops. or any liquid or slops or Substances that are liable to become unwholesome. in or into or upon any Street lane. alley. sidewalk. gutter. crossing. lot. cellar. premises or common. and it shall also be unlawful for any rank weeds to be allowed to grow on any ground within the corporation of the City. and it shall be unlawful and it shall be a nuisance for any overflowing vault or non fly proof privy to exist

Section 3. All Kitchens shall be provided with Garbage receptacles and said receptacle shall be made of galvanized iron. shall be tightly covered and emptied frequently to prevent fermentation and bad odors: and garbage receptacles and vaults shall be emptied. cleaned and disinfected. and weeds shall be cut and hauled away at any time upon the written order of the Health Officer: Said Officer to fix a reasonable time limit of not more than five days in his order when said garbage receptacles or vaults shall be emptied cleaned and disinfected and when weeds shall be cut and hauled away: and if any owner or lessee being duly ordered as therein provided. shall fail

or refuse to obey said order, it shall be the duty of the Street commissioner upon written notice from the Health officer to cause the garbage receptacle or vaults to be cleaned emptied and disinfected. or the weeds to be cut and hauled away and said commissioner shall keep an accurate account of the expenses thereof. which shall be paid from the city treasury upon the sworn voucher of the commissioner and said expenses shall be a lien on the property and collected by law and turned into the city Treasury. And it shall be unlawful to fill up old privy vaults or sinks without first emptying the same

Section 4. The Secretary of the city Board of Health who is also City Health Officer. all deputy health officers and the city Police shall have full power and authority to enter into or upon any street. lot. alley. premises or ground for the purpose of making a sanitary survey of the same and if a nuisance or any insanitary conditions are found it shall be the duty of the city health officer when informed of the existence of the same to immediately notify the person or persons so offending in writing fixing a time limit to abate the nuisance. If such person shall fail or refuse to abate the nuisance within the time specified it shall be the duty of the Street Commissioner upon notice of the Health officer to cause the same to be abated. keeping an accurate account of the expense thereof which shall be paid from the city treasury upon the sworn voucher of the Street commissioner and said expense shall be a lien on the property and collected as taxes are collected and turned into the City Treasury

Section 5. The City Health Officer and all deputy health officers shall be diligent in inforcing this ordinance and in doing what is reasonable and necessary for the protection and preservation of the Public Health. They shall study the state health laws and the health rules of the State Board of health and be active in enforcing the same. The Vital Statistics shall be carefully collected. duly recorded and reported to the State Board of health for final compilation in the State health reports by the city health officer: and he shall make a monthly report to the Mayor and city

council of all health work done with such recommendations as may seem proper to him.
Section 6. If at anytime the work of prevention of the spread of Infectious & contagious disease is more than can be reasonably expected by the city health Offcer. he may with the consent of the Mayor employ one or more intelligent men to act as deputies to establish quarantine remove patients to the special hospital and conduct disinfection. all houses wherein infectious and contagious diseases may exist or have existed shall at the proper time be disinfected thoroughly with formaldehyde by the health officer or his deputies at the expense of the city as the work is obviously for the benefit of the people. a complete record of all disinfections. all vaccinations and all other health work done shall be kept by the city health Officer in the minute book of the city board of health.
Section 7. When visiting persons known to be infected with smallpox. diptheria and scarlet fever. all physicians and health Offcers shall protect their clothing and hair against infections and shall thoroughly disinfect themselves before coming in contact with the public.
Section 8. It shall be the duty of the city Police at all times to aid the city health Offcer in the work of enforcing this ordinance upon demand of said health Offcer.
Section 9. Any person or persons violating any of the provisions of this ordinance upon conviction thereof shall be fined for each offense in any sum not less than twenty five nor more than one hundred dollars. and be imprisoned for ten days at the option of the court and each days violation shall constitute a seperate Offense.
Section 10. As an emergency exists. this ordinance shall be in effect immediately on and after its passage.

J. J. Baker.

Passed at the Council chamber in the city of Fort Wayne this 10th day of Dec 1912.

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held

on the 10th day of Dec 1912 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 585

Louis A. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the mayor for approval on the 13th day of Dec 1912

Wm. J. Jeffries
City Clerk

Approved this 16th day of Dec 1912

Jesse Price
Mayor

General Ordinance No 586

An ordinance amending Section 11 of General Ordinance No 453 being an ordinance entitled "An ordinance to regulate moving travel and traffic on the streets alleys and public places in the city of Fort Wayne and providing punishment for violation thereof.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that Section 11 of General Ordinance No 453 being an ordinance entitled.

An ordinance to regulate moving travel and traffic on the streets. alleys and public places in the city of Fort Wayne and providing punishment for violation thereof." be amended to read as follows. Section 11. Every vehicle while waiting or standing in any Street shall be so placed so as to have its entire length parallel with the sidewalk with its right side next and within two feet of the curb. any person firm or corporation violating any of the provisions of this section shall be fined in any sum not less than five dollars ($5.00) nor more than twenty five dollars for each offense.

Section 2 This ordinance is to be in full force and take effect from and after its passage and approval by the mayor and legal publication B. Van Zweringen

Done at the council chamber in the City of Fort Wayne Indiana this 23d day of Dec 1912

We hereby Certify that the common council of the City of Fort Wayne Ind at a Regular meeting held on the 23d day of Dec 1912 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 586

Louis A. Schroeder President Wm. S. Jefferis City Clerk

Presented to the Mayor for approval this 28th day of Dec 1912

Wm. S. Jefferis
City Clerk

Approved this 28th day of Dec 1912

Jesse Grice
Mayor

General Ordinance No 587

An ordinance amending Sections 1. 3. 4. 5. and 11. of General Ordinance No 538 being an ordinance entitled "An ordinance prohibiting and regulating the erections of signs. signboards or other Structures to be used for advertising purposes

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that Section 1 of General ordinance No 538 being an ordinance entitled: "An ordinance prohibiting and regulating the erection of Signs. Signboards or the Structures to be used for advertising purposes. be amened to read as follows:

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that it shall be unlawful for any person. firm or corporation or association to erect. or cause or permit to be erected. within the City of Fort Wayne. any signs or signbords. to be used for advertising purposes. without first obtaining a permit therefor from the building inspector. appreciation for permits shall be upon printed blanks. furnished by the building inspector and signed by the owner of the sign. Which permit shall be issued upon the applicant paying to the controller the sum of one dollar.

Section 2. That section 3 of General Ordinance No 538 being an ordinance entitled "An ordinance prohibiting and regulating the erection of Signs. Signboards or other Structures to be used for advertising purposes." be amended to read as follows: Section 3. The term signs shall apply to display boards or Screens used as such having characters. letters or illustrations painted. enameled written. cut or fastened thereon. The term "banner signs" shall apply to all display signs painted. printed or written upon cloth or canvas with or without frame. The term electric sign shall apply to signs constructed entirely of metal or other approved Non-combustible material. and shall have one elpond Socket for each square foot of sign surface. and shall have at least four (4) Candlepower illumination for each square foot of sign surface.

Section 3. That section 4 of General Ordinance No 538 being an ordinance entitled "An ordinance prohibiting and regulating the erection of signs. Signboards or other Structures to be used for advertising purposes. to be amended to read as follows: Section 4 That no swing sign transparent sign or any illuminated sign

except an electric sign shall project or be allowed to project over any sidewalk. Street or alley.
Section 4 That section 5 of Gunral Ordinance no 538 being an ordinance entitled "An ordinance propibiting and regulating the erection of signs. Signboards or other Structures to be used for advertising purposes to be amended to read as follows: Section 5 That all parts of any electric sign shall be of metal or other non-Combustible Materials. That no transparent sign which is attached to or placed flat against a building shall have a greater area than forty (40) Square feet. and no part thereof shall extend or project over the sidewalk.
Section 5. That section 11 of General Ordinance no 538 being an ordinance entitled "an ordinance prohibiting and regulating the erection of signs. Signboards or other Structures to be used for advertising purposes. to be amended to read as follows: Section 11 Every Sign. except existing electric Signs attached or fastened to the wall or walls of any buildings so as to project over any public Street. avenue. alley. lane or public highway. which is now erected or which is now Maintained contrary to the provisions of this ordinance. shall be forthwith removed or altered changed or cut down so as to fully comply with the provisions of this ordinance; and any sign now existing and not complying with the provisions of this ordinance which shall not have been removed or torn down or so altered and changed within ten (10) days from and after the passage of this ordinance so as to be brought within the provisions hereof by the owner thereof or by the person. firm or corporation in charge. possession or control thereof. shall be torn down by the building Inspector and the cost and expense of tearing town such sign shall be charged to the owner or to the person firm or corporation. in charge possession or control thereof and shall be recovered from such person firm or corporation by any appropriate proceedings therefor. Electric signs now in use and coming within the definition of electric signs as herein defined. shall be permitted to be used until condemned by the building inspector whose Judgment as to their being dangerous or further usefulness shall be final and conclusive.

Section 6. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Henry W. Felger

Leave at the council chamber in the city of Fort Wayne Indiana this 23d day of Dec 1912

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 23d day of December 1912 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 587

Louis S. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 28th day of December 1912

Wm J. Jeffries
City Clerk

approved this 28th day of Dec 1912

Jesse Grice
Mayor

General Ordinance no 588

An ordinance changing the name of Pfeiffer Boulevard to State Boulevard

Section 1. Be it ordained by the Common council of the City of Fort Wayne Indiana. That Pfeiffer Boulevard from Sherman Street to the Lake Shore and Michigan Southern Railroad Centline avenue from the west line of C. L. Centline addition to Spy Run avenue. and State Street from Spy Run avenue to Anthony Boulevard shall be changed and hereafter be known as State Boulevard. That Section 2 of General Ordinance no 573 be and is hereby repealed.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Gottlieb Haller
Charles E Welch
Herman Strodel

Done at the counsel chambers in the City of Fort Wayne Indiana this 14th day of Jan 1913.

We hereby certify that the common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 14th day of Jan 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 588

Louis A. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 17th day of January 1913

Wm J. Jeffries
City Clerk

Approved this 17th day of January 1913

Jesse Grice
Mayor

General Ordinance No 589

An ordinance authorizing the alienation of certain personal property.

Section 1. Be it ordained by the common counsel of the city of Fort Wayne Indiana That the Mayor be and he is hereby authorized to sell one fire truck of no 2 Engine House one Chemical of no 3 Engine House and two horses named "Dick" and "Fred" of no 7 Engine House and to sign any and all necessary instruments to consumate such sale: provided that such sale be made without an appraisement should the council through its proper committee find such property worth less than one hundred dollars ($100.00) otherwise appraisers shall be appointed according to law by the Judge of the allen circuit court.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Louis S. C. Schroeder.

Done at the council chamber in the city of Fort Wayne Indiana this 14th day of Jan 1913

We hereby Certify That the common council of the city of Fort Wayne Indiana at a Regular meting held on the 14th day of January 1913 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 589

Louis S. C. Schroeder
President

Wm J. Jefferies
City Clerk

Presented to the Mayor for approval this 17th day of January 1913

Wm J. Jefferies
City Clerk

Approved this 17th day of January 1913

Jesse Grice
Mayor

General Ordinance no 590

An ordinance approving a contract entered into on the 14th day of December 1912 by and between the City of Fort Wayne party of the first part and Fort Wayne Electric Works party of the second part.

Whereas on the 14th day of December 1912 the City of Fort Wayne by and through its Board of Public works. entered into a Contract with Fort Wayne Electric Works for furnishing transformers.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that the contract heretofore entered into by and between the City of Fort Wayne and Fort Wayne Electric Works on the 14th day of December 1913 as more fully set out in the preamble hereto be in all things fully confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and Legal publication

Allen Hamilton

Done at the Council chamber in the City of Fort Wayne Indiana this 14th day of Jan 1913

We hereby Certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 14th day of Jan 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 590

Louis S. C. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval this 17th day of January 1913

Wm S. Jefferies
City Clerk

approved this 17th day of Jan 1913

Jesse Grice
Mayor

General Ordinance No 591

An ordinance approving railroad track elevation resolution No 9 adopted by the Board of Public Works of the City of Fort Wayne July 11th 1912 and ratified and confirmed by said Board on august 5th 1912.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that railroad track elevation resolution No 9 adopted by the Board of Public works of said City on July 11th 1912 and confirmed by said Board august 5th 1912 be and the same is hereby in all things ratified. confirmed and approved.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor and legal publication

B. F. Darwer.

Done at the council chamber in the city of Fort Wayne Ind this 28th day of January 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 28th day of January 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 591

Louis S. L. Schroeder

Wm J. Jefferies
City Clerk

Presented to the Mayor for approval this 31st day of January 1913

Wm J. Jefferies City Clerk.

approved this 1st day of Feb 1913

Jesse Grice
Mayor

General Ordinance no 592

An ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne and Martin - Howe Coal Company a corporation of Chicago Ill on the 14th day of January 1913 relative to the purchase by said city of coal

Whereas heretofore on the 14th day of January 1913 the city of Fort Wayne entered into a contract with Martin - Howe Coal Company providing for the purchase of coal by said city.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered into on the 14th day of January 1913 by and between the city of Fort Wayne by and through its Board of Public works and Martin Howe Coal Company a corporation of Chicago Illinois as more fully set out in the preamble hereto be and the same is in all things ratified and approved

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Gottlieb Haller

Done at the Council chamber in the City of Fort Wayne Indiana this 28th day of January 1913

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a regular meeting held on the 28th day of January 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 592

Louis A. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 31st day of January 1913

Wm. J. Jefferies
City Clerk

Approved this 1st day Feb 1913

Jesse Grice
Mayor.

General Ordinance no 593

An ordinance approving a contract entered into by and between the leity of Fort Wayne by and through its Board of Public Safety and the Robinson Fire apparatus Manufacturing co. a corporation of St Louis Missouri on the 11th day of January 1913 relative to the purchase of a leity Service Motor Hook and Ladder Truck.
Whereas on the 11th day of January 1913 the city of Fort Wayne by and through its Board of Public ~~works~~ Safety and the Robinson Fire apparatus Manufacturing co. entered into a contract relative to the purchase of a City Service Motor Hook and Ladder Truck.
Section 1. Be it ordained by the Common Council of the leity of Fort Wayne That the contract heretofore entered into on the 11th day of January 1913 by and between the city of Fort Wayne by and through its Board of Public Safety and the Robinson Fire apparatus Manufacturing co. relative to the purchase of a leity Service Motor Hook and Ladder Truck set out in the preamble hereto be and the same is hereby in all things ratified and approved.
Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor

Louis S. G. Schroeder.

Done at the Council Chamber in the city of Fort Wayne Indiana this 28th day of January 1913

We hereby Certify That the Common Council of the leity of Fort Wayne Indiana at a Regular Meeting held on the 28th day of January 1913 by a Majority vote of all the Members elect did pass the Ordinance hereunto attached and known as General Ordinance no 593

Louis S. G. Schroeder
President

Wm S. Jefferies
City Clerk

Presented to the Mayor for approval on the 31st day of January 1913

Wm S. Jefferies
City Clerk

Approved this 1st day of Feb 1913

Jesse Grice
Mayor

General Ordinance No 594

An ordinance transfering and vesting in the Department of Public Parks of the city of Fort Wayne Indiana. Tennessee avenue in said city to be converted by the Board of Park Commissioners into a boulevard. with full power of Control the Management thereof and the changing of the name of said Tennessee avenue to Tennessee Boulevard.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that the Street in said city known as Tennessee avenue from the east line of Spy run avenue to the west line of California avenue be and the same is hereby placed under the Government. Management and control of the Department of Public Parks of said city for the purpose and with the right upon the part of the Board of Park Commissioners of said city to convert the same into a boulevard. and said Board of Park Commissions shall have full power upon the acceptance by it of said Streets herein described. for the purpose aforesaid to govern. Manage Maintain. regulate and direct the public use thereof as a boulevard and to subject the same to its rules Regulations: Subject however to the laws of the State and to the powers of the Common Council in relation thereto.

Section 2. That Tennesse avenue from the East line of Spy run avenue to the west line of California avenue shall be changed to and hereafter be known as Tennessee Boulevard.

Section 3. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor. and legal publication

Herman Strodel

Done at the Council Chamber in the City of Fort Wayne Ind this 11th day of Feb 1913

We hereby certify That the common council of the city of Fort Wayne Ind at a Regular Meeting held on the 11th day of Feb 1913 by a Majority vote of all the members elect did pass the ordinance hereto attached and known as General Ordinance no 594

Louis A. C. Schroeder President Wm S. Jefferies City clerk.

Presented to the Mayor for approval this 15th day of Feb 1913

Wm S. Jefferies

City Clerk

approved this 18th day of Feb 1913

Jesse Grice

Mayor.

General Ordinance no 595

An ordinance. authorizing the borrowing of fifteen thousand dollars ($15.000.00) and the sale of bonds therefor for the purchase of real estate for park purposes as described in the ordinance
Section 1 Be it ordained by the common council of the city of Fort Wayne Indiana that said City borrow the sum of Fifteen thousand dollars ($15.000.00) for the purpose of buying. purchasing and securing certain real estate approximately twenty nine (29) acres South of the Maumee River and North of Herbert street. Seneca Street East of Hanover street and north of the New York Chicago and St Louis Railroad and lying in the South East Quarter of section one (1) Township thirty (30) North Range twelve (12) East to be used by the city for park purposes. all as shown in plat hereto attached.
Section 2. That in order to procure said loan that the bonds of said city be issued to the amount of fifteen thousand dollars ($15.000.00) in denominations of one thousand dollars ($1000.00) bearing 4½% interest per annum. payable Semi annually evidenced by a coupon for each six (6) months interest. Signed by the Mayor and countersigned by the Controller of said city and sealed with the seal of the said city. Which bonds shall become due in twenty (20) years and said bonds to be registered with the city controller by the original purchaser and by his assigns. Said city to have the privilege to redeem any or all of said bonds at times prior to Maturity as specified in said bonds as prepared by the city Controller.
Section 3. Said bonds shall be sold by sealed bids to the highest bidder for cash and upon payment therefor shall be delivered to the said bidder. Three weeks notice of said sale shall be given by three insertions once each week in a paper of daily circulations in the city of Fort Wayne
Section 4. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

P. M. Braun

Done at the council chamber in the city of Fort Wayne Indiana this 11th day of Feb 1913

We hereby Certify that the Common Council of the

(over)

City of Fort Wayne Indiana at a Regular Meeting held on the 11th day of Feb 1913 by a Majority vote of all the members elect did pass the ordinance hereto attached and known as General Ordinance no 595

Louis S. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on ~~this~~ 15th day of Feb 1913

Wm J. Jeffries
City Clerk

Approved this 18th day of Feb 1913

Jesse Brice
Mayor

General Ordinance No 596

An ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne by and through its Board of public works and the Perfection Biscuit Company on the 11th day of February 1913.

Whereas. Heretofore on the 11th day of February 1913 the City of Fort Wayne entered into a contract with the Perfection Biscuit Company for the construction of a tunnel under Webster Street in said City which contract is as follows:

This agreement made this 11th day of Feb 1913 by and between the City of Fort Wayne by and through its Board of Public Works for convenience hereinafter called "City" and the Perfection Biscuit Company. a Corporation. for convenience hereinafter designated as "Company" Witnesseth:

1st. The City hereby gives to the said Company consent and permission subject to the conditions hereinafter set out to construct and maintain a tunnel under Webster Street from a point on the East property line of said Street to a point on the west side of said Street. connecting the present building of said company on the East side with the Building to be erected by said company on the West side of said Street: said tunnel to be approximately eight (8) feet by six (6) feet six (6) inches in the clear of brick and concrete. subject to the approval of the City: said tunnel to be used by said company for conveying merchandise from one to the other of the aforesaid buildings and for the purpose of carrying out the permission herein given. consent is granted to said company to make the necessary excavation into said Street while said tunnel is being constructed on the condition however that said Street shall be put in as good condition thereafter as it now is.

2d. The City reserves and shall have the right and power to cause said tunnel to be taken up. removed. in whole or in part. or its use discontinued at any time. whether the removal or dis-continuation of its use be necessary or not. The Company agreeing that upon receiving notice from the city to take up or remove said tunnel that it will so remove or take up. at its expense said tunnel within six (6) months after receiving said notice and will cause said Street to be placed in the same condition as to grade or pavement if the same be thereafter paved. as it shall be in at the time that the removal of said tunnel is ordered and on the

failure of said Company. its successors and assigns so to do said city may cause the removal of said tunnel. and all connections thereto and the repair of the street as above stated and recover the cost and expense of the same by suit from said Company together with liquidated damages in the sum of five hundred dollars ($500.00).

3d In lieu of the consent and permission herein granted the company will at all times save and hold said city free and harmless from any and all loss. liability or damage to any person or property which shall occur or result at any time. or in any manner. growing out of any excavation or change of pavement. or by reason of the construction or Maintenance of said tunnel. its connections or parts. and said Company. its successors and assigns agree that it will defend in the name of said city and without expense to said city any such loss. liability or damage. and will pay and save said City harmless from any and all judgments that may be rendered in any such action against said city and its sureties shall be liable therefor on the bond furnished to the city. as hereinafter provided.

4th Said Company. its successors and assigns agree that it will keep said tunnel and its contents in such repair so as not to at any time interfere with the free and unobstructed use of and travel on said street by the public.

5th Said Company further agrees that it will cause to be executed to the City of Fort Wayne a bond with sureties thereon to the approval of the city guaranteeing the faithful performance of the terms. stipulations and conditions herein set out and covering any loss that may be suffered by said city arising out of said contract. Said City may at any time. demand a new bond with new sureties thereon and the said company agrees to comply with any demand that may hereafter made. it is expressly understood that the amount named in the bond namely five thousand dollars ($5000.00) shall in no way be construed to limit the liability of said Company of any damages hereinbefore described. but in case damages shall accrue in an amount greater that said five thousand dollars ($5000.00) the said Company hereby binds itself to pay the total amount of such damages in whatever sum it may be

6th Inasmuch as the tracks of the New York. Chicago & St Louis Railroad company might be elevated and Webster Street

depressed where it intersects said railroad causing or making necessary a change in the grade of the street between Pearl Street and the aforesaid tracks. it is understood and the company agrees for itself its successors and assigns. in consideration of the things herein that it will not ask for any damages because of the change of the grade of such street. and it hereby releases the city from the payment of all damages or injury that may be caused to it or to property by the change of the grade of said street because of the aforesaid separation of grades.

7th This contract to be binding upon the parties hereto. its successors or assigns

In witness whereof the parties hereto have hereunto set their hands and seals the day and year first above written

City of Fort Wayne by
Frank. J. Benoy
G. A. Swegmann
E. J. Lennon
its Board of public works

Attest H. W. Becker
Clerk

Perfection Biscuit company by
J. R. Franks its president

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana. that the contract heretofore entered into on the 11th day of February 1913 by and between the city of Fort Wayne by and through its Board of Public works and the perfection Biscuit Company as more fully set out in the preamble hereto be and the same is hereby in all things ratified and approved.
Section 2 This ordinance to be in full force and take effect from and after its passage and approval by the mayor and legal publication

Charles W. Kittoe

Done in the council chamber of the City of Fort Wayne Indiana This 28th day of February 1913

Wm J. Hoffman
City Clerk

We hereby certify that the Common Council of the city of Fort Wayne Indiana at a Regular Meeting held on the 28th day of February 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached

(over)

and known as General Ordinance no 596

Louis A. C. Schroeder
President

Wm S. Jeffries
City clerk

Presented to the Mayor for approval on the 1st day of March 1913

Wm S. Jeffries
City clerk

Approved this 1st day of March 1913

Jesse Grice
Mayor.

General Ordinance no 597

An ordinance approving a contract entered into on the 16th day of January 1913 by and between the city of Fort Wayne party of the first part and Fort Wayne Electric Works party of the second part.

Whereas on the 16th day of January 1913 the city of Fort Wayne by and through its Board of Public works entered into a Contract with Fort Wayne Electric works for furnishing Meters.

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that the contract heretofore entered into by and between the city of Fort Wayne and Fort Wayne Electric works on the 16th day of January 1913 as more fully set out in the preamble hereto be in all things fully confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage. approval by the Mayor and legal publication

P. M. Braun

Leone at the council chamber in the city of Fort Wayne Ind this 28th day of Feb 1913

We hereby certify That the common council of the city of Fort Wayne Ind at a Regular meeting held on the 28th day of February 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached an known as General Ordinance 597.

Louis S. & Schroeder
President

Wm J. Jefferies
City Clerk

Presented to the Mayor for approval on the 1st day of March 1913

Wm J. Jefferies
City Clerk

Approved this 1st day of March 1913

Jose Grice
Mayor

General Ordinance no 598

An ordinance approving a contract entered into on the 29th day of November 1912 by and between the city of Fort Wayne party of the first part and Fort Wayne Electric works party of the second part.

Whereas on the 29th day of november 1912 the city of Fort Wayne by and through its Board of Public works entered into a contract with the Fort Wayne Electric works for furnishing Incandescent lamps.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiand that the contract heretofore entered into by and between the city of Fort Wayne and Fort Wayne Electric works on the 29th day of November 1912 as more fully set out in the preamble hereto be in all things fully confirmed and approved.

Section 2 This ordinance to be in full force and take effect from and after its passage. approval by the Mayor and legal publication

P. M. Braun

Done at the council chamber in the city of Fort Wayne Indiana this 28th day of Feb 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 28th day of February 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 598.

Louis S. C. Schroeder
President

Wm J. Jefferies
City clerk

Presented to the Mayor for approval on the 1st day of Mar 1913

Wm J. Jefferies
City Clerk

Approved this 1st day of March 1913

Jesse Grice
Mayor

General Ordinance no 599

An ordinance extending the city limits and annexing certain territory to the city of Fort Wayne Indiana and making same part of the 6th and 7th wards.

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that the territorial limits of the City of Fort Wayne be and are hereby extended as follows:

Commencing at a point where the center line of Rudisill Boulevard intersects the west line of Broadway; thence East along the center line of Rudisill Boulevard and Rudisill Boulevard extended East to the center line of Lafayette Street; thence south South along the center line of Lafayette Street to the South East corner of Section 14 Township 30 north. Range 12 East thence west along the South line of Section 14. Township 30 North Range 12 East. and along said south line of said section 14 extended west. to the East line of Foster Park; thence following the Northerly and Easterly boundry line of Foster Park to Broadway; thence North along the west line of Broadway to the place of beginning.

Section 2. Be it further ordained that the following described property commencing at a point where the center line of Rudisill Boulevard intersects the west line of Broadway; thence east along the center line of Rudisill Boulevard to the center line of Calhoun Street; thence south along the center line of Calhoun Street to the south city limits line; thence west along the said city limits line to the east line of Foster Park; thence northerly along the east line of Foster Park to the place of beginning including Foster Park be and the same is hereby made a part of the 6th ward of said City for all purposes.

Section 3. Be it also further ordained that all the following described territory commencing at a point where Rudisill Boulevard intersects the center line of Calhoun Street; thence South along the center line of Calhoun Strat to the South city limits line; thence east along the south city limits line to the center line of Lafayette Street extended; thence north along the center line of Lafayette Street to the center line of Rudisill Boulevard. thence west along the center line of Rudisill Boulevard to the place of beginning be and the same is hereby made part of the 7th ward for all purposes.

Section 4. That this ordinance be in full force and take effect from and after its passage. legal publication and approval by the Mayor

Charles E. Welch

Done at the council chamber the city of Fort Wayne Indiana this 11th day of March 1913

We hereby certify that the Common Council of the city of Fort Wayne Indiana at a Regular meeting held on the 11th day of March 1913 by a Majority vote of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 599

Louis S. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 14th day of March 1913

Wm. J. Jefferies
City Clerk

Approved this 15th day of March 1913

Jesse Grice
Mayor

General Ordinance no 600.

An ordinance making certain territory heretofore annexed to the city a part of the first ward Fifth ward. Sixth ward. Seventh ward and tenth ward.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the following territory be and the same is hereby made for all purposes. a part of the first ward: Commencing at that point where the west line of Anthony Boulevard extended north intersects the center line of State Street: thence due north two hundred and seven (207) feet: Thence west parallel with State Street to the center line of Malcolm Street: thence due South along the center line of Malcolm Street two hundred and seven (207) feet to the center line of State Street thence east along the center line of State Street to the place of beginning.

Section 2. That the following described territory be and the same is hereby made for all purposes. a part of the fifth ward Commencing at a point where the west line of the right of way of the Lake Shore and Michigan Southern Railroad company intersects the present city limits at the north side of the creek or run known as Junk ditch or creek: thence Southwesterly along the north line of said right of way to a point where the same intersects the east line of the right of way of the Grand Rapids and Indiana Railroad company: thence north along the east line of the right of way of the Grand Rapids and Indiana Railroad company to a point where the same would intersect the present city limits at the north side of the ditch or creek aforesaid: Thence east and Southerly along the present city limits, following the meandering line of said creek to the place of beginning.

Section 3. That the following described territory be and the same is hereby made for all purposes. a part of the sixth ward. Commencing on the west line of the road extending South from Broadway in the city of Fort Wayne. and running through the Richardville reserve at a point where said west line intersects with the north line of said Richardville reserve: thence in a Southwesterly direction following the west line of said road 205½ feet to a point: thence continuing along the west line of said road in a Southerly direction 219.01 feet to a point: thence in a westerly direction

with an angle of 99 degrees. 27 Minutes. to the right a distance of 1.277. 75 feet to a point: Thence in a Southwesterly direction with an angle of 30 degrees to the left a distance of 719. 38 feet to a point: Thence in a Southwesterly direction with an angle of 36 degrees and 39 minutes to the left a distance of 741. 45 feet to a point: Thence in a Southeasterly direction with an angle of 42 degrees and 7 minutes to the left a distance of 397. 16 feet to a point: Thence in an easterly direction and with an angle of 71 degrees and 14 Minutes to the left: a distance of 416. 10 feet to a point: Thence in a Southerly direction with an angle of 90 degrees and 9 Minutes to the right a distance of 815 feet to a point: Thence in an easterly direction with an angle of 90 degrees and 9 minutes to the left a distance of 520 feet to a point: Thence in a Southerly direction with an angle of 90 degrees and 9 Minutes to the right a distance of 1.060 feet to a point: Thence in a Southeasterly direction with an angle of 68 degrees and 9 minutes to the left a distance of 1.135. 98 feet to a point: Thence in a Southerly direction with an angle of 68 degrees and 7 minutes to the right to the east side of the St Marys river: Thence in a northerly direction along the east side of the St. Marys river and following the Meandering of the St. Marys river to a point where the said north line of said Richardville reserve intersects said east side of the St. Marys river: Thence in an easterly direction and along the said north line of said Richardville reserve to the point of beginning: That the property included within said territory shall hereafter be within the corporate limits of said city of Fort Wayne said territory being the land purchased and deeded to the city by David. H. and Samuel M. Foster and known as Foster Park.

Section 4. That the following described territory be and the same is hereby made for all purposes a part of the Seventh ward: Commencing at a point where the center line of Lafayette Street intersects the center line of McKinnie avenue; Thence north along the center line of Lafayette street to a point west of the Southwest corner of lot number thirty three (33) Avondale addition: Thence east along the Avondale addition and to center line of Hanna Street: Thence South along the center line of Hanna Street to the center line of McKinnie avenue

To the center line of Lafayette Street: Thence north along the center line of Lafayette to the place of beginning
Section 5 That the following described territory be and the same is hereby made for all purposes. a part of the Tenth ward Commencing at the intersection of the city limits at Holton avenue and McKee Street: Thence west to Smith street: Thence south to Eckert Street: thence east to Holton avenue: Thence north to the beginning:
also the following described territory Commencing at a point where the center line of Walton Avenue intersects the center line of Pontiac street: Thence east to the west line of Hustis and Taylor Sub-division of abbotts out lots: Thence South along the west line of Hustis and Taylor Sub-division of Abbotts out lots and abbotts out lots to the south line of Abbotts out lots Thence east on the South line of Abbotts out lots to the center line north and south of Section eighteen (18) township thirty (30) north. Range thirteen (13) East: Thence South along said center Section line to the center of said Section eighteen (18): Thence west on the center line east and west of said Section eighteen (18) to the center line of Anthony Boulevard. formerly Walton avenue: Thence north of the center line of Anthony Boulevard formerly Walton avenue. to the place of beginning
Also the following territory: Commencing at a point where the south line of lots numbes 33. 72. 137. 176. 241. 280. 345 and 384 of Avondale addition intersects the center line of Hanna Street: Thence North along the center line of Hanna Street to a point directly west of the Southwest corner of Weisser park: Thence east along the south line of Weisser park to the west line of the alley west of Smith Street:
Thence north along the west line of said alley to the center line of Eckert Street: Thence east along the center line of Eckert Street to the center line of Holton avenue: thence north along the center line of Holton avenue to the center line of McKee Street:
Thence east along the center line of McKee Street extended east to the center line of Anthony boulevard: Thence South along the center line of Anthony boulevard to its intersection with the center line of McKinnie avenue: Thence west along the center line of McKinnie avenue to the center line of Hanna Street. Thence north along the center line of Hanna ~~Section 6.~~ Street to place of beginning
Section 6. This ordinance to be in full force and take

effect from and after its passage and approval by the Mayor and legal publication

Louis S. C. Schroeder

Done at the Council chamber in the City of Fort Wayne this 11th day of March 1913

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 11th day of March 1913 by a Majority vote of all the members elect did pass the Ordinance hereunto attached and known as General Ordinance No 600.

Louis S. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 14th day of March 1913

Wm J. Jeffries
City Clerk

Approved this 15th day of March 1913

Jesse Grice
Mayor

General Ordinance no 601

An ordinance authorizing the Board of Park Commissioners to improve Edgewater Avenue. from Columbia Avenue to Crescent Avenue: Columbia Avenue. from the St Joseph River to Crescent Avenue: Lake avenue from St Joseph Boulevard to Crescent Avenue: Rivermet avenue. from St Joseph Boulevard to Crescent Avenue:. Elmwood avenue. from St Joseph Boulevard to Tennessee Boulevard: Old Fort Street from Edgewater Avenue to Lake Avenue: Force Street. from Edgewater Avenue to Rivermet Avenue: Dearborn Street. from Edgewater Avenue to St Joseph Boulevard: Oneida Street. from Edgewater avenue to Tennessee Boulevard: Tecumseh Street. from Edgewater avenue to Tennessee Boulevard; Crescent avenue from Edgewater avenue avenue to Tennessee Boulevard; and California avenue. from Lake avenue to Tennessee Boulevard. by removing all dead and objectionable trees. by pruning and preserving trees requiring the same and by planting trees in all open places

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana. That the Board of Park Commissioners of the City of Fort Wayne Indiana be and they are hereby authorized and ordered to take the necessary steps. adopt resolutions. if necessary. providing for the improvement of Edgewater Avenue from Columbia avenue to Crescent avenue: Columbia Avenue from the St Joseph River to Crescent Avenue: Lake Avenue from St Joseph Boulevard to Crescent Avenue: Rivermet Avenue from St Joseph Boulevard to Crescent Avenue: Elmwood Avenue from St Joseph Boulevard To Tennessee Boulvard Old Fort Street from Edgewater avenue to Lake avenue: Force Street from Edgewater Avenue to Rivermet Avenue. Dearborn Street. from Edgewater Avenue to St Joseph Boulevard: Oneida Street. from Edgewater Avenue to Tennessee Boulevard: Tecumseh Street from Edgewater Avenue to Tennessee Boulevard: Crescent Avenuue from Edgewater avenue to Tennessee Boulevard and California avenue from Lake avenue to Tennessee Boulevard. by removing all dead and objectionable trees. by pruning and preserving all the trees requiring the same along the aforesaid Streets and by planting good

healthy nursery grown trees uniformly in all open places and by doing all the other things necessary to put the trees along said Streets in first class condition Said work to be done in accordance with section 234 of an act entitled "an act concerning Municipal Corporations" passed by the assembly of the state of Indiana in 1905. and according to all other laws of said state. and ordinances of the City of Fort Wayne

Section 2. This ordinance to be in full force and take effect from and after its passage approval by the Mayor and legal publication

Charles W. Lattoe

Done at the Council Chamber in the City of Fort Wayne this 25th day of March 1913

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 25th day of March 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 601

Louis S. C. Schneider
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 29th day of March 1913

Wm. J. Jefferis
City Clerk

Approved this 1st day of April 1913

Jesse Grice
Mayor

Section 1 Resolved by the Common Council of the city of Fort Wayne that the contract hereto for and

General Ordinance no 602.

An Ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne by and through its Board of Public works and the United states cast iron pipe Foundry Company. relative to purchasing cast iron water pipe for the Waterworks Department.

Whereas on the 22d day of march 1913 the city of Fort Wayne by and through its Board of Public works entered into a contract with the United States cast iron pipe and Foundry Company relative to the purchase of cast iron water pipe for the Waterworks department. which contract is in the following words:

This agreement Made and entered into this 22d day of March 1913 by and between the City of Fort Wayne by and through its Board of Public works. for convenience hereinafter designated as party of the first part and the United States cast iron pipe and Foundry Company for convenience hereinafter designated as party of the secend part. Witnesseth:

That the party of the first part agrees and binds itself to buy and the party of the secend part agrees to sell and deliver to the party of the first part the following: Three hundred (300) tons of six inch (6") cast iron water pipe and one hundred and twenty (120) tons of (12") inch cast iron water pipe for which the party of the first part agrees to pay twenty-four dollars and fifty-five cents ($24.55) per ton and such special castings as said Board may deem proper and necessary during the delivery and laying of said pipe. for which castings said first party agrees to pay two and three fourths cents (2 3/4) per pound. Said first party shall have the privilege of increasing the amount of each of the above items of pipe and Specials fifty per cent (50%) if ordered by July first 1913 and the price of said increase shall be the same as for the original order. all of said pipe and castings shall be delivered at said price F. O. B. Fort Wayne Indiana.

Said pipe and castings to conform with the American water works association standard Specifications and to the Specifications hereto attached which Specifications and bid of said secend party and the advertisement for bids are Made a part of this Contract as much as if all the same were copied herein at full length and the certificate of test provided for in the Specifications shall accompany each shipment

said second party to furnish all of said pipes to said city from time to time as ordered by said city through its Board of Public works so that each and every request for shipment shall be fulfilled within ten (10) working days from the time the request is made. It is further agreed and understood that said pipe shall be of the kind and material and manufactured in the manner specifically described in the specifications thereof. It is also agreed that said specials aforesaid shall include hubs and spigots which shall be of Standard weight according to Standard Specifications.

Said second party further agrees to furnish to said first party a bond in the sum of one thousand dollars ($1000.00) Guaranteeing faithful performance of the within contract with sureties to be approved by said first party.

In witness whereof the parties hereto have hereunto set their hands and seals the day and year above written

City of Fort Wayne by.
Frank. J. Benoy.
G. A. Schwegmann
E. J. Lennon
Its Board of Public works
United States cast iron pipe and
Foundry company by.
A. J. Woodhull
its Western Sales Mgr.

attest Martin Leitzinger
Clerk

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered into on the — day of March 1913 by and between the city of Fort Wayne by and through its Board of Public works and the United States Cast iron pipe and Foundry Company as more fully set out in the preamble hereto be and the same is in all things ratified and approved

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles E. Welch

Done at the council chamber in the City of Fort Wayne Indiana this 22d day of april 1913

We hereby certify that the common council of the City of Fort Wayne Indiana at a Regular meeting held on the 22d day of april 1913 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 607

Louis A C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 25th day of april 1913

Wm J. Jeffries
City Clerk

approved this 26th day of april 1913

Jesse Grice
Mayor

General Ordinance No 603

An ordinance ratifying and approving a contract entered into on the 8th day of april 1913 by and between the city of Fort Wayne and the Pioneer Coal Company.

Whereas heretofore on the 8th day of april 1913 the city of Fort Wayne by and through its Board of Public works entered into a contract with the Pioneer Coal Company providing for the purchase of its years supply of coal to be at its Number two (2) pumping station which contract is in the following words:

This agreement Made and entered into this 8th day of april 1913. by and between the city of Fort Wayne. by and through its Board of Public works. party of the first part and the pioneer Coal Company party of the second part Witnesseth: That in consideration of the purchase by said city from the party of the second part of its years supply of coal to be used at its no 2 Pumping station from the 1st day of January 1913 to the 31st day of December 1913 in the manner hereinafter provided. the party of the second part agrees to furnish to said city during said period of time one thousand two hundred (1.200) tons or more of Smithers Creek 3/4 lump coal Mined by the Sunday Creek Coal Company at the price of one dollar and nine cents ($1.09) per ton of two thousands (2000) pounds. F. O. B. Mines. all as shown by the bid of said second party which is filed in the office of the waterworks department of said city.

Said City to have the privilege of buying from said Company all of the coal used by it at its said no 2 pumping station during said period of time at the price named herein. so long as the kind quality and quantity is satisfactory to said Board of Public works and the same to be shipped and billed on flat bottom cars from the mines to said city at its said pumping Station on the New York. Chicago and St Louis Railroad said city to pay all freight on all coal so purchased. It is mutually agreed between the parties that payments by the first party shall be made to second party on or before the 15th day of each Month. based upon invoice weights on all coal delivered as aforesaid during the month previous thereto. The strict performance of this contract by the party of the second part and the prompt deliveries of coal herein on cars at said mines as aforesaid shall be subject to delays occasioned by strikes and want

of car supply and failure of railway companies to deliver and place cars at the mines for loading.
It is further agreed between the parties hereto that upon the delivery of said coal on board of said cars by said party of the second part. said party at the request of the first party and as the agent of the party of the first part will use its best endeavors with the carriers to have said cars of coal delivered as aforesaid. billed and sent forward promptly to destination. The prices made in this contract are based upon the present mining rate and shall advance or decline as said rate of mining may advance or decline during the period of this contract. This contract shall not be binding or take effect until the second party shall execute to the party of the first part a bond in the sum of One Thousand dollars ($1000.) with sufficient surety thereon to be approved by the Mayor and city controller of party of the first part and conditioned for the faithful performance by the party of the second part of all terms. conditions and agreements herein to be performed by it and until the contract has been ratified and approved by the common council of said City.

Witness our hands and seals the 8th day of april 1913

Pioneer Coal Company by
L. E. Mollering Its Pres
attest Martin Leitzig Secy

City of Fort Wayne by
Frank T. Bixby
Geo A. Schwegmann
E. J. Lennon
Its Board of Public works

Done at the council chamber in the city of Fort Wayne Ind this 22d day of april 1913

We hereby Certify That the common council of the city of Fort Wayne Ind at a Regular meeting held on the 22d day of april 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 603

Louis A. L. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 25th day of april 1913

Wm. J. Jeffries
City Clerk

approved this 26th day of april 1913

Jesse Grice
Mayor

General Ordinance no 604

An ordinance ratifying and approving a certain Contract between the city of Fort Wayne and the Moellering Construction Company relative to the work to be done by the City at Broadway under Track Elevation Resolution no six (6)

Whereas heretofore on the 19th day of august 1912 the city of Fort Wayne by and through its Board of Public works entered into a contract with the Moellering Construction Company relative to work to be done by the city under Track Elevation Resolution no six (6)

Section 1. Be it ordained by the Common council of the city of Fort Wayne that the contract heretofore on the 19th day of april 1913 entered into by and between the city of Fort Wayne Indiana by and through its Board of Public works and the Moellering Construction Company as fully set forth in the preamble providing for the work to be done by the city at Broadway under Track Elevation Resolution no six (6) be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publications

F. M. Brann

Done at the Council Chamber in the city of Fort Wayne Indiana this 22d day of april 1913

We hereby Certify That the Common Council of the city of Fort Wayne did at a Regular Meeting held on the 22d day of april 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 604

Louis S. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval this 25th day of april 1913

Wm. J. Jeffries
City Clerk

approved this 25th day of april 1913

Jesse Grice
Mayor

General Ordinance no 605

An ordinance ratifying and approving a certain Contract between the City of Fort Wayne and the Brooks Construction Company relative to the work to be done by the city at Taylor street under Track Elevation Resolution number five (5)

Whereas heretofore on the 8th day of april 1913 the City of Fort Wayne by and through its Board of Public works entered into a contract with the Brooks Construction Company relative to work to be done by the City under Track Elevation Resolution no five (5) at Taylor Street

Section 1. Be it ordained by the common council of the city of Fort Wayne that the contract heretofore on the 8th day of april 1913 entered into by and between the city of Fort Wayne Indiana by and through its Board of Public works and the Brooks Construction Company as fully set forth in the preamble providing for the work to be done by the city at Taylor street under Track Elevation Resolution number five (5) be and the same is in all things ratified and approved

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal Publication

B. F Clarke

Done at the council chamber in the city of Fort Wayne this 22d day of april 1913

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 22d day of april 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 605

Louis A. C Schroeder
President

Wm S. Jeffries
City Clerk

Presented to the Mayor for approval on the 25th day of april 1913

Wm S. Jeffries
City Clerk

Approved this 26th day of april 1913

Jesse Grice
Mayor

General Ordinance no 606

An ordinance ratifying and approving a certain Contract between the City of Fort Wayne and the Brooks Construction Company relative to the work to be done by the City at Thompsons avenue under Track Elevation Resolution no Seven (7)

Whereas heretofore on the 8th day of april 1913 the City of Fort Wayne by and through its Board of Public works entered into a contract with the Brooks Construction Company relative to work to be done by the City under Track Elevation Resolution no Seven (7) at Thompson avenue

Section 1. Be it ordained by the Common council of the city of Fort Wayne that the contract heretofore on the 8th day april 1913 entered into by and between the city of Fort Wayne Indiana by and through its Board of Public works and the Brooks Construction Company as fully set forth in the preamble providing for the work to be done by the city at Thompson avenue under Track Elevation Resolution Number Seven (7) be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication.

Henry W Folger

Done at the council chamber in the city of Fort Wayne this 22d day of april 1913

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 22d day of april 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 606

Louis S. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 25th day of april 1913

Wm J. Jeffries
City Clerk

approved this 26th day of april 1913

Jesse Grice
Mayor

General Ordinance No 607

An ordinance ratifying and approving a certain Contract between the City of Fort Wayne and the Moellering Construction Company relative to the work to be done by the City at Harrison Street under Track Elevation Resolution number eight (8) and nine (9)

Whereas heretofore on the 8th day of April 1913 the City of Fort Wayne by and through its Board of Public works entered into a Contract with the Moellering Construction Company relative to work to be done by the City under Track Elevation Resolutions number eight (8) and nine (9) at Harrison Street

Section 1. Be it ordained by the Common Council of the City of Fort Wayne that the Contract heretofore on the 8th day of April 1913 entered into by and between the City of Fort Wayne Indiana by and through its Board of Public works and the Moellering Construction Company. as fully set forth in the preamble providing for the work to be done by the city at Harrison Street under Track Elevation Resolutions numbers 8 and 9 be and the same is in all things ratified & approved

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

B. F. Harvey

Done at the council chamber in the City of Fort Wayne this 22d day of April 1913

We hereby Certify That the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 22d day of April 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 607

Louis H. C. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 25th day of April 1913

Wm. J. Jeffries
City Clerk

approved this 26th day of April 1913

Jesse Grice
Mayor

General Ordinance no 608

An ordinance fixing the time when the employees of the City of Fort Wayne Indiana shall receive their Salaries or Compensation: repealing conflicting ordinances and fixing the time when the same shall take effect as amended May 26—1913

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that the employees of the City of Fort Wayne Indiana shall receive their salaries or Compensation Semi-Monthly upon the fifth and twentieth of each months Section 2. All ordinances and parts of ordinances in conflict herewith are hereby repealed.

Section 3. This ordinance to be in full force and effect on and after its passage and approval by the Mayor

Herman Stroebel

Done at the council chamber in the city of Fort Wayne this 13th day of May 1913

We hereby certify That the Common council of the city of Fort Wayne Indiana at a Regular meeting held on the 13th day of May 1913 by a Majority vote of all the Members Elect did pass the ordinance hereunto attached and known as General Ordinance no 608

Louis S. C. Schroeder
President

Wm. S. Jefferies
City Clerk

Presented to the Mayor for approval on the 16th day of May 1913

Wm. S. Jefferies
City Clerk

approved this 17th day of May 1913

Jesse Grice
Mayor

General Ordinance no 609

An ordinance extending the city limits and annexing certain territory to the city of Fort Wayne making the same a part of ——— ward.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. that the territorial limits of the city of Fort Wayne be and are hereby extended as follows: Beginning at the northwest corner of section six (6) Township thirty (30) North Range thirteen (13) East. Allen County. Indiana Thence directly East one hundred and ninety eight (198) feet along the north line of said section six (6): Thence directly south along the East line of the first alley East of Anthony boulevard. to the Maumee river: Thence in a Northeasterly direction following the meanderings of said Maumee river to the east line of the Hermann Michael tract: thence directly north along the east line of said Michael tract and along the East line of Lakeside Park Place to the North line of Lake avenue extended East: Thence directly west 102.25 feet along the North line of Lake avenue to the west line of lot no four (4) in Randalls farm Sub-devision: Thence directly north 714 feet to the south line of lot no five (5) in said Randall's farm Sub-devision: Thence directly west 173.25 feet to the west line of lot no five (5) in Randall's farm Sub-devision: Thence directly north along the west line of lots 5. 6. 9. 10. 13. 14. 17 and 18. to the south line of State Street extended East: Thence directly East along the south line of said State Street to the East line of the Fort Wayne Driving Park extended South: Thence North along the East line of said Fort Wayne Driving Park to the South line of lot E. in St. Joe Park addition: Thence west along the south line of said lot E in St Joe Park addition to the west line of Crescent ave Thence in a Southwesterly direction along the west line of said Crescent Avenue to meet the present city limits at Crescent and Charlotte Avenues: Thence following the lots of the presents city limits to the point of beginning.

Section 2. Be it further ordained the property set out and described in the above section be and is hereby made for Election and all other purposes a part of the — ward of said City

Section 3. This ordinance to be in full force and take effect from and after its passage and approval by

by the Mayor and legal publication

E. A. Wagner.

Done at the council chamber in the city of Fort Wayne Indiana this 13th day of May 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 13th day of May 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 609

Louis A. G Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 16th day of May 1913

Wm. J. Jeffries
City Clerk

Approved this 17th day of May 1913

Jesse Grice
Mayor

General Ordinance no 610

An ordinance authorizing the alienation of certain property and ordering an appraisement of the same

Section 1. Be it ordained by the common council of the City of Fort Wayne that the Mayor be and he is hereby authorized to sell a certain frame dwelling house, barn and other real fixtures located and situated on lot number 194 north side addition Extended formerly belonging to Luella Derbyshire and condemned and appropriated by the city under Declaratory Resolution #226 providing for the opening and extending of Cass ~~Street~~ North in said city: That the Mayor be authorized to sign any and all necessary instruments to consummate such sale provided such sale shall not be made until said property shall be appraised by appraisers appointed by the Judge of the Allen circuit Court: That the money received from the sale of said property is to be placed in the general fund to be used in applying on the judgment secured against said city by said Luella Derbyshire.

Section 2. That the city attorney be and he is hereby authorized to petition the Judge of the Allen Circuit court for the appointment of three (3) appraisers to appraise the property referred to in Section one (1) of this ordinance.

Section 3d This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

C. M. Braun

Done at the council chamber in the city of Fort Wayne this 27th day of May 1913

We hereby Certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 27th day of May 1913 by a Majority vote of all the members elect did pass the ordinance hereto attached and known as General Ordinance no 610

Louis A. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 31st day of May 1913

Wm. J. Jeffries
City Clerk

approved this 3d day of June 1913

Jesse Grice
Mayor.

General Ordinance no 611

An ordinance providing for the control of Public Improvement on State Boulevard east at a point beginning at the east end of the bridge to a point ending at east side of Florida drive intersection.

Section 1. Be it ordained by the common council of the city of Fort Wayne Ind. That the Board of Public works is to have full power and control for all public Improvements on State Boulevard beginning at a point at east end of bridge to the east side of Florida drive intersection.

Section 2. Any and all parts of ordinances conflicting with this ordinance is hereby repealed.

Section 3. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles W. Zeltor

Done in the Council Chamber in the City of Fort Wayne Ind This 27th day of May 1913

We hereby Certify That the Common Council of the City of Fort Wayne Ind at a Regular meeting held on the 27th day of May 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 611

Louis D. D. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 31st day of May 1913

Wm. J. Jeffries
City Clerk

approved this 3d day of June 1913

Jesse Grice
Mayor

General Ordinance No 612

An Ordinance ordering the improvement of Webster Street from the South property line of Jefferson street to the North property line of Baker Street by paving the same.

Whereas heretofore on the 22d day of May 1913 the Board of Public Works duly adopted a resolution deeming it necessary to improve Webster Street from the South property line of Jefferson Street to the North property line of Baker Street by paving the roadway to a width of 28 feet according to the plans and specifications therefor on file in the office of the Board of Public Works the cost thereof to be assessed upon the real estate abutting on said Webster Street above described. and Whereas on the 12th day of June 1913 a Majority of the resident free holders upon that of Webster Street above described. filed with said Board of Public works a remonstrance signed by them against the making of such improvement now Therefore.

Section 1. Be it ordained by the Common Council of the Leity of Fort Wayne Indiana that a necessity existing therefor. Webster Street from the South property line of Jefferson Street to the North property line of Baker Street be and the same is hereby ordered improved by paving the roadway thereof to a widith of 28 feet according to the plans and Specifications on file in the office of the Board of Public works and the said Board of Public Works is hereby authorized and directed to cause said improvement to be made in accordance with the resolutions so adopted by it as set forth in the preamble hereto and in accordance with the provisions of an act entitled "an act concerning Municipal Corporations" passed by the General assembly of the State of Indiana at the Sixty fourth regular session thereof and all acts amendatory and supplementary thereto.

Section 2 This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

B. Van Zweringen

Leone at the Council chamber in the city of Fort Wayne this 8th day of July 1913

(over)

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a Regular meeting held on the 8th day of July 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 612

Louis A. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 12th day of July 1913

Wm J. Jeffries
City Clerk

Approved this 12th day of July 1913

Jesse Grice
Mayor

General Ordinance No 613

An ordinance regulating the use of bicycles and tricycles upon the streets of Fort Wayne and providing lights and signals therefor and repealing "an ordinance regulating the use of bicycles and tricycles upon the streets of Fort Wayne and providing lights therefor" passed by the Common Council July 1st 1892

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana. That is shall be unlawful for any person to ride upon any street within the corporate limits of the City of Fort Wayne upon any bicycle or tricycle during the period of one-half hour after sunset to one-half hour before sunrise without having on said bicycle or tricycle a lighted lamp on the front of said bicycle or tricycle and every such bicycle or tricycle shall also be provided with a suitable bell. horn or other signalling device. and every person riding on a bicycle or tricycle on the public streets or other public places in said City shall also when approaching a cross street sound said bell horn or other device for signalling in such a manner as to give notice and warning of his approach.

Section 2. That a certain ordinance passed by the Common Council July 1. 1892 the same being an ordinance entitled "An ordinance regulating the use of bicycles and tricycles upon the Streets of Fort Wayne and providing lights therefor." be and the same is hereby repealed.

Section 3. Any person violating any of the provisions of this ordinance shall pay a penalty of not more than Fifty dollars ($50.00)

Section 4. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

John J Bauer

Done at the Council chamber in the City of Fort Wayne this 12th day of august 1913

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 12th day of august 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 613

Louis A. Schneider
President

Wm. J. Jeffries
City Clerk

(over)

Presented to the Mayor for approval on the 16th day
of august 1913

Wm. S. Jeffries
City Clerk

Approved this 16th day of august 1913
Jesse Grice
Mayor.

General Ordinance No 614

An ordinance authorizing the employment by the Board of Public Safety of the City of Fort Wayne an additional duty Sergeant and fixing the Salary of same.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne that the Board of Public Safety of said City be authorized and empowered to appoint and employ an additional duty Sergeant to whom shall be paid a Salary of Ninety Dollars per Month.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor.

G. F. Rogge

Leone at the council chamber in the city of Fort Wayne Ind this 26th day of august 1913

We hereby certify That the Common Council of the City of Fort Wayne Indiana at a Regular Meeting held on the 26th day of August 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 614

Louis D. L. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 30 day of August 1913

Wm. J. Jeffries
City Clerk

approved this 2d day of Sept 1913

Jesse Grice
Mayor

General Ordinance No 615

An ordinance fixing the tax levy for City purposes for the year 1914

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Ind that a levy of one dollar and sixteen cents ($1.16) upon each One hundred dollars ($100.00) of assessed valuation of all property within the corporate limits of the city of Fort Wayne Indiana be made for the year 1914. That the above levy be divided as follows

Appropriation account	.855
Park Fund Gen Expenses	.085
Park Fund Park Music	.005
Sinking Fund	.05
Track Elevation Fund	.10
Garbage Plant Fund	.03
Playground Fund	.0125
Policemans Pension Fund	.01
Firemans Pension Fund	.01
Monument Fund	.0025
	$1.16

Also that there shall be collected from each male inhabitant liable according to law a poll tax of $2.00

Section 2. That all taxes shall be collected in Semi annual installments

Section 3. This ordinance shall be in full force and effect from and after its passage and approval by the Mayor.

Harry L. Pflieger

Done at the Council Chamber in the city of Fort Wayne Ind this 26th day of Sept 1913

We hereby certify that the common council of the City of Fort Wayne Indiana at a Regular Meeting held on the 26th day of Sept 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 615

Louis B. L. Schroeder
President

Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 30 day
of august 1913

Wm. J. Jefferies
Corporation Clerk

Approved this 2d day of Sept 1913
Jesse Grice
Mayor

General Ordinance no 616

An ordinance authorizing the borrowing of one hundred and forty thousand dollars ($140.000.00) and sale of bonds therefor.

Section 1. Be it ordained by the Common council of the City of Fort Wayne Indiana that said city borrow the sum of one hundred and forty thousand dollars ($140.000.00) for the purpose of refunding that part of the following bonds that cannot be paid off and retired with the money available in the sinking fund "to wit"
Bonds 1 to 99 for $1000.00 each aggregating $99.000.00.
issued October 10-1888 for twenty five years
Bonds 100 to 199 for $1000.00 each aggregating $100.000.00
issued October 10-1888 for Twenty five years
Bonds 200 to 299 for $1000.00 each aggregating $1000.000.00
issued October 10-1888 for twenty five years
Section 2. That in order to procure said loan Be it ordained that the bonds of said city be issued to the amount of one hundred and forty thousand dollars ($140.000.00) in denominations of one thousand dollars ($1000.00) bearing four and one half per cent (4½%) interest per annum payable Semi annually evidenced by a coupon for each six (6) months interest signed by the Mayor and counter signed by the Controller of said city and sealed with the seal of the city. which bond shall become due and payable in twenty (20) years.
Section 3. Said bonds shall be sold by sealed bids to the highest bidder for cash and upon payment therefor shall be delivered to said bidder two weeks notice of said sale shall be given by one insertion one each week in a paper or papers of daily circulation in the city of Fort Wayne.
Section 4. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Charles W. Lettick

Done at the Council Chamber in the city of Fort Wayne Ind this 9th day of Sept 1913

Wm. C. Jeffries
City Clerk

We hereby certify that the common council of the city of Fort Wayne Indiana at a regular meeting held on the 9th day of Sept 1913 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 616

Louis S. Schneider
President

Wm. J. Fitzpatrick
City Clerk

Presented to the Mayor for approval on the 12th day of Sept 1913

Wm. J. Fitzpatrick
City Clerk

Approved this 12th day of Sept 1913

Mayor

General Ordinance no 617

an ordinance authorizing the Board of Park Commissioners to improve both sides of East Wayne street from the west line of Grant avenue to the west line of Glasgow avenue by removing dead trees by pruning and preserving trees requiring the same and by planting Norway Maples in all open places.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana that the Board of Park Commissioners of the City of Fort Wayne be and they are hereby authorized and ordered to take the necessary steps adopt resolutions if necessary. providing for the improvement of both sides of East Wayne street from the west line of Grant avenue to the west line of Glasgow avenue by removing all dead trees by pruning and preserving all the trees requiring the same along the aforesaid street and by planting good healthy Nursery Grown Norway Maples uniformly in all open places and by doing all the other things necessary to put the trees along said street in firstclass condition; said work to be done in accordance with section 234 of an act entitled "an act concerning municipal corporations" passed by the General assembly of the state of Indiana in 1905 and according to all the laws of said state and ordinances of the City of Fort Wayne.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

P. M. Brann

Done at the Council chamber in the City of Fort Wayne Ind this 9th day of September 1913

We hereby certify that the common council of the City of Fort Wayne Indiana at a Regular meeting held on the 9th day of sept 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 617

Louis A. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 12th day of Sept 1913

Wm. J. Jefferies city clerk

Approved this 12th day of sept 1913
Jesse Grice Mayor.

General Ordinance No 618

An ordinance approving and ratifying a certain Contract entered into by and between the City of Fort Wayne Indiana and Berghoff Brewing Association. for the construction of a Spur track on Wabash avenue from the track of the Fort Wayne and Northern Indiana Traction Company on Washington Boulevard East to the plant of the Berghoff Brewing association on Wabash Avenue.

Whereas on the 4th day of September 1913 the City of Fort Wayne entered into a contract with the Berghoff Brewing association for the construction of a Spur track on Wabash Avenue from the track of the Fort Wayne and Northern Indiana Traction Company of Washington Boulevard East to the plant of the Berghoff Brewing association on Wabash Avenue which Contract is in the following words.

This agreement Made this 4th day of September 1913 between the City of Fort Wayne by and through its Board of Public Works hereinafter called "First Party" and the Berghoff Brewing association. a Corporation hereinafter called the "Second Party" Witnesseth:-

Whereas Second Party desires to procure a Spur track from the track of the Fort Wayne and Northern Indiana Traction Company. on Washington Boulevard East to its plant in order to facilitate shipping to and from said plant. and said Traction Company being willing to construct said Spur for said purpose. Therefor it is agreed in Consideration of the Covenants and agreements on the part of said Second party to be performed by it hereinafter set out. Consent and authority is hereby granted and given by first party to second Party to construct. Maintain and operate a curve and single Steel railroad track from the tracks of the Fort Wayne and Northern Indiana Traction Company at the intersection of

Wabash avenue and Washington Boulevard East
thence South along the east side of Wabash avenue
to the alley south of said Boulevard: thence west into the
alley south of said boulevard. a distance of Seventy five
feet from the east property line of said second party
together with all necessary curves. Switches. Cross-overs
and turnouts to connect the same with the Main
tracks of said Traction Company all as more fully
shown by the plan thereof attached hereto and made
part hereof. and together with all necessary poles
and wire and other appliances for the operation of
electric cars over said Spur.
The second party if it desires to avail itself of the
benefits of the authority herein granted. shall cause
said track to be constructed and completed within
a year from the date hereof. said work of constructing
said track when started shall be completed within
sixty days from the time the same is commenced
and within the period of one year hereinbefore Specified
but if said second party is prevented from complying
with the conditions herein contained by reason of any
court proceedings. said Board of works will grant a
reasonable extension of time as to any one of the
above provisions said track to be constructed and
maintained at all times so as to conform with the
established grade of the Street and alley hereinbefore
named as such grade shall from time to time
exist. and so as to not in any way be an impediment
to the ordinary and proper use thereof for all purposes
of the public in passing along upon a across said tracks
at any point thereon and subject at all times to be
taken up and relaid by said party at its expense
for the purpose of regrading. paving. repaving. or repairing
such street and alley and for the purpose of constructing
or repairing Sewers. laying or repairing watermains or
other pipes or for other public improvements and
whenever. in the opinion of the Board it becomes Necessary
to require said tracks to conform to the grade or to
remove the same for any of the public improvements
hereinbefore enumerated said first party shall
notify said second party that it is in the opinion

of the Board necessary to take up said track. or such portions thereof as may be necessary for such purpose. and that said second party shall take up and relay said track for the purpose specified in the notice within such time as said first party in said notice may require. In case the notice is for the purpose of requiring repairs or improvements or to mack the track conform to the grade. at least thirty days time shall be given to second party to perform the work and in case it fails to perform said work within the time specified and set out in the notice said first party shall have the right to make such improvements and repairs as may be deemed necessary and as set out in the notice and charge the cost thereof to second party and after the Completion of said work render an itemized statement of the cost thereof to said second party and in case second party fails to pay said cost or expense within thirty days after the receipt of such itemized bill or statement. the City of Fort Wayne shall have the right of action against said second party to recover such cost or expense. together with a reasonable attorney fee for the collection thereof.

If said second party accepts the conditions herein Contained and constructs said track. it agrees at its own expense to pave between the rails of said track and on either side thereof for a distance of 160 feet with such Material as the balance of the street may be paved with and in accordance with the plans prepared by the City Engineer and approved by first party and will at its own expense pave Wabash avenue to a width of 36 feet from the intersection of Washington Boulevard East to a point two feet South of where the track herein granted Crosses the west Street line of Wabash avenue. Said pavement to be laid according to plans to be prepared by the City Engineer and approved by first party and to be done concurrently with, or as near Concurrently with the construction of the track as possible.

If said Streets and alleys are hereafter repaved said second party shall pay for so much thereof as lies between the rails of said track and for a space of two feet on either side thereof and if the pavement

shall be reconstructed. second party shall so relay the track as to conform to the new grade of the street or alley all at the expense of said second party including a six inch concrete foundation under the ties of said track and shall keep the part of the street and alley so paved by it as aforesaid in good condition. All of the track to be so constructed as not to interfere with the drainage of surface water on Wabash Avenue or Washington Boulevard east or the alley south of said Boulevard. and to be Constructed under the supervision and as required by said first party. Said second party shall not at any time haul or allow to be hauled to exceed two cars over and along the part of the track herein described and shall not load or unload any cars or leave the same standing upon the streets or where the tracks may cross the sidewalks entering the alley and will not use said track for switching purposes except between the hours of eight P. M. and six A. M. except as such additional permission may be granted by said first party.

Second party further agrees and binds itself to keep and hold said City free and harmless from any and all damages that may accrue to any person persons. or property on account of any injury to their person or property growing out of the Construction. Maintenance or operation of said track or the operation of any cars thereon and in case suit shall be filed against the City of Fort Wayne on account thereof second party upon notice shall defend said action at its own expense and second party shall have the right to appeal from any judgment if it so elects and in case a judgment is finally secured against the city second party agrees to pay the same together with all costs and said second party shall execute to first party a bond with sufficient surety to be approved by first party payable to the city of Fort Wayne for ten thousand dollars. Conditioned upon the faithful performance by second party of all the conditions and provisions herein contained on its part to be performed and will from time to time whenever requested by said first party renew said Bond

In case second party fails to comply with the provisions of this contract on its part to be performed the right herein granted may at once be terminated by said first party and thereupon said second party shall forfeit all rights hereunder and shall at its own expense cause the removal of said siding and all tracks that may be laid hereunder and place said street and alley in as good condition for travel and with the same material as the remainder thereof.

The provisions of the contract shall be binding on the successors and assigns of the parties of the second part.

The consent permission and authority herein granted shall be and continue for a period of twenty five years from the date hereof.

Witness our hands and seals the day and year first above written.

City of Fort Wayne by
C.A. Schwegmann
Geo H Loesch
E.J. Zimmer
Berghoff Brewing association
M.C. Norton Secy
Wm Bremer V. Pres

attest H.W. Becker clerk

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the contract heretofore entered into by and between the city of Fort Wayne and the Berghoff Brewing association on the 4th day of Sept 1913 as more fully set out in the preamble hereto be in all things confirmed and approved

Section 2. This ordinance to be in full force and take effect from and after its passage approval by the Mayor and legal publication

P.M. Brown

Done at the council chamber in the city of Fort Wayne this 16th day of Sept 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Special Meeting held on the 16th day of Sept 1913 by a majority vote of all the members elect did pass the ordinance hereunto

attached and known as Final Ordinance No 618
Louis. A. Schroeder
President
Wm. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 19th day of Sept 1913

Wm. J. Jeffries
City Clerk

approved this 19th day of Sept 1913

Jno. Price
Mayor

General Ordinance No 619

An ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne Indiana by and through its Board of Public works and Wm H. Lemm providing for the furnishing of a years supply of coal for the city Crematory.

Whereas. Heretofore on the 4th day of august 1913 the city of Fort Wayne Indiana by and through its Board of Public works entered into a contract with Wm H. Lemm providing for the furnishing of a years supply of coal for the city Crematory

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that the contract heretofore entered into on the 4th day of august 1913 by and between the city of Fort Wayne Indiana by and through its Board of Public works and Wm H. Lemm as more fully set forth in the preamble hereto be and the same is in all things ratified and approved

Section 2. This ordinance to be in full force and effect from and after its passage approval by the Mayor and legal publication

P. M. Braun.

Read at the council chamber in the city of Fort Wayne this 23d day of Sept 1913.

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular Meeting held on the 23d day of sept 1913 by a Majority vote of all the members. did pass the Ordinance hereunto attached and known as General Ordinance No 619

Louis. A. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 26th day of sept 1913

Wm J. Jeffries
City Clerk

approved this 27th day of sept 1913

Jesse Eccles
Mayor.

General Ordinance 620

An ordinance approving a contract entered into on the 7th day of Oct 1913 by and between the city of Fort Wayne called Buyer and Joe H. Perrine of Fort Wayne called Seller.

Whereas on the 7th day of Oct 1913 the city of Fort Wayne by and through its Board of Public Safety entered into a contract with Joe H. Perrine of Fort Wayne Indiana for the purchase and delivery to said city two (2) Speedwell Roadsters to be used by the chief and assistant chief of the Fire Department of said city.

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that the contract heretofore entered into by and between the city of Fort Wayne and Joe H. Perrine on the 7th day of Oct 1913 as more fully set forth in the preamble hereto be and the same is hereby in all things fully confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Herman Strodel

Done at the council chamber in the city of Fort Wayne Indiana this 14th day of Oct 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 14th day of Oct 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 620

Louis A. C. Schroeder
President

Wm. J. Jeffries
City clerk

Presented to the Mayor for approval on the 17th day of Oct 1913

Wm. J. Jeffries
City clerk

Approved this 17th day of Oct 1913

Jesse Grice
Mayor

General Ordinance no 621

An ordinance providing for the placing of certain wires underground

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that no individual. firm or corporation. Municipal or otherwise. shall place. erect. Maintain or permit to remain. any wires. cables. poles or other appliances used for any electrical purpose on or above the surface of any of the streets. alleys or public grounds within the fire limits of the City as defined by the ordinance or ordinances of said City. This shall be held to apply to the poles and wires used by the City in the transmission of electricity for Commercial light and power. but shall not apply to the poles and wires for arc lights for street lighting or the posts for ornamental street lighting: or to trolley and feed wires used for street cars. or to poles supporting the same. Distributing poles may be set on any of the streets. alleys or public grounds within said fire limits whenever it is impractical to distribute the wires in any other Manner after first. Securing a permit from the Board of Public works of said City so to do.

Section 2. Every individual. firm. Company. or Corporation now or hereafter owning or operating any wires. cables poles or other appliances used for any electrical purposes located on or above the surface of any of the streets. alleys or public grounds within the fire limits of the City of Fort Wayne. Shall remove. or cause to be removed from above the surface of said Streets. alleys and public grounds. all such cables wires, poles and appliances at the rate of 10560 feet Street Measurement. for each individual. Company. firm or Corporation for each and every calender year beginning on the 1st day of January 1914. This shall not be held to apply however. to arc lights used for Street lighting or to the poles and wires for the same or to ornamental lamp post for street lighting or to trolley and feed wires used for street cars or to the poles supporting the same.

Section 3. Every such individual. firm company or Corporation Shall. during the month of October of each year. Submit a plan and Schedule to the Board of Public works of said City showing the particular territory within which the said individual. firm Company or Corporation purpose to remove or place underground

during the following calendar year. its poles. cables. wires and appliances to the extent of 10560 feet Street Measurement. The said plan and schedule for the year 1914. however shall be submitted during January 1914. The Board of Public Works shall have the right to change the schedules and plans submitted. or to substitute therefor other plans and schedules. designating the territory for each individual Company firm or corporation within which its wires Cables. poles and appliances shall be removed or placed underground to the extent of 10560 feet street Measurement. after due consideration of the plans and schedules submitted the said Board of Public Works shall. during the month of November of each year. return to the several individuals firms. Companies or corporations the plans and schedules with such change or substitution as it has seen fit to make. and with its approval and such plans and schedules as approved and returned. whether inaltered or changed. shall be binding upon the several companies firms or individuals. and each such individual firm Company or corporation shall. during the following Calendar year remove its cables. wires poles and appliances in accordance with the schedules and plan approved and returned by the said Board of Public works. The schedules and plans for the year 1914 however shall be returned during February 1914.

Section 4 Whenever in any one calendar year any individual firm. Company or corporation. shall remove or place underground wires cables. poles and appliances to the extent of 10560 feet Street Measurement as required by this ordinance and any amount in excess thereof. the amount in excess. or any part thereof if removed or placed underground with the approval of the Board of Public works. shall in any Subsequent Calendar year that the said individual. firm Company or Corporation may elect be counted a part of the 10560 feet Street Measurement of wires. cables. poles and appliances required by this ordinance to be placed underground or removed in that year.

Section 5. When two or more individuals. firms Companies or corporations shall own jointly and cables wires. poles or appliances and place underground or remove the same in accordance with the plan

and Schedule approved by the Board of Public works each individual firm company or corporation shall be credited with the amount so removed.

Section 6. Whenever all the wires cables. poles and appliances except trolley and feed wires used for Street cars and the poles supporting the same and the arc lights used for Street lighting and the poles and wires for the same and such distributing poles as the Board of Public works has approved. Shall have been removed from above the surface of any of the Streets. alleys or public Grounds of the city of Fort Wayne in accordance with plans and schedules approved by the Board of Public works. all such Streets. alleys and public grounds. or parts thereof. shall thereupon automatically. for the purposes covered by this ordinance. become a part of the fire limits of said city and shall be subject to the provisions of this ordinance concerning cables. wires. poles and appliances upon the same.

Section 7. Any individual. firm company or corporation failing to comply with any of the provisions of this ordinance shall pay to the City of Fort Wayne a penalty in any sum not exceeding five hundred dollars to be recovered by said City as provided by law and each day's failure to comply with any of the provisions of this ordinance shall constitute a Separate violation for which the city shall recover a Separate penalty in Separate or Several actions.

Section 8. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

P. Van Swearingen

Done at the council chamber in the city of Fort Wayne Indiana this 28th day of Oct 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular Meeting held on the 28th day of Oct 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 621

Louis S. La Schroeder
President

Wm J. Jefferies
City clerk

Presented to the Mayor for approval on the 31st day of Oct 1913

Wm. J. Jefferies
City Clerk

Approved this 31st day of Oct 1913

Jesse Grice
Mayor

General Ordinance no 622.

An ordinance authorizing the alienation of certain personal property

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that the Mayor is hereby authorized to sell certain quantities of scrap iron and brass difficult to describe but located on the city's property at no 1 pumping station and elsewhere and to sign any and all necessary instruments to consummate such sale: provided that such sale shall be made without an appraisement. Should the council through its proper committee find such property worth less than one hundred dollars ($100.00) otherwise appraisers shall be appointed according to law by the judge of the allen county Circuit Court.

Section 2. That this ordinance be in full force and effect from and after its passage and approval by the Mayor.

B. Van Sweringen

Leone at the Council Chamber in the City of Fort Wayne this 28th day of Oct 1913

We hereby certify that the Common Council of the city of Fort Wayne Indiana at a regular meeting held on the 28th day of Oct 1913 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 622.

Louis H. C. Schroeder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 31st day of Oct 1913

Wm. J. Jefferies
City Clerk

approved this 31st day of Oct 1913

Jesse Grice
Mayor

General Ordinance no 623

An ordinance transferring and vesting in the Department of Public Parks of the city of Fort Wayne Indiana Anthony Boulevard from State Boulevard to the alley North of Lourdes avenue in said city to be converted by the Board of Park Commissioners into a boulevard with full power of Control and the Management thereof.

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that Anthony Boulevard from State Boulevard to the alley north of Lourdes Avenue be and the same is hereby placed under the government. Management and control of the Department of Public Parks of said City for the purpose and with the right upon the part of the Board of Park Commissioners of said city to convert the same into a boulevard: and the said Board of Park Commissioners shall have full power: upon the acceptance by it of said boulevard herein described for the purpose aforesaid. to govern. Manage. Maintain regulate and direct the public use thereof as a boulevard and to subject the same to its rules and regulations: Subject however to the laws of the State. and to the powers of the Common Council in relation thereto

Section 2. This ordinance shall be in full force and effect from and after its passage approval by the Mayor and legal publication B. VanAllen

Done at the council chamber in the city of Fort Wayne Ind this the 28th day of Oct 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 28th day of Oct 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 623

Louis N. C. Schroeder
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 31st day of Oct 1913

Wm. J. Jefferis
City Clerk

approved this 31st day of Oct 1913

Jesse Grice
Mayor.

General Ordinance no 624

An ordinance fixing the salary of a Police Matron to be employed by the Board of Public Safety.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the salary of the Police Matron shall be and is hereby fixed at fifty ($50.00) dollars per Month
Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

J. J. Davis

Done at the council chamber in the city of Fort Wayne this 25th day of Oct 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular Meeting held on the 25th day of Oct 1913 by a Majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 624

Louis D. C. Schroeder
President

Wm. J. Jefferis
City Clerk

Presented to the Mayor for approval on the 31st day of Oct 1913

Wm. J. Jefferis
City Clerk

Approved this 31st day of Oct 1913

Jesse Grice
Mayor

General Ordinance no 625

An ordinance ratifying the issue. sale and delivery of Refunding Bonds of the city of Fort Wayne to the amount of One hundred and forty Thousand dollars ($140.000)

Whereas by general ordinance no 616 of the city of Fort Wayne there was authorized to be issued the Refunding Bonds of said city to the amount of one hundred and forty Thousand dollars ($140.000) for the purpose of refunding outstanding bonded indebtedness of the city of Fort Wayne

Therefore be it ordained by the Common Council of the city of Fort Wayne Indiana:

Section 1. That the action of the Mayor and city Controller in the matter of the issuance and sale and delivery of the Refunding Bonds of the city of Fort Wayne Indiana to the amount of One hundred and Forty Thousand dollars ($140.000) bearing date the 10th day of October 1913 and becoming due twenty (20) years after date, and bearing interest at the rate of four and one half (4½) per centum per annum payable Semi-annually be and the same is hereby in all things ratified. Confirmed and adopted. The action of said officers in making said Bonds and the interest payable at the United States Mortgage + Trust Company in the city of New York and in executing the coupons evidencing the interest upon said Bonds by means of their fac-simile signatures is also hereby ratified and confirmed.

Section 2. This ordinance shall be in force and effect from and after its passage and approval by the Mayor and legal publication

Chas W. Zetton.

Done at the council chamber in the city of Fort Wayne this 11th day of November 1913

We hereby certify that the common council of the city of Fort Wayne Ind at a Regular Meeting held on the 11th day of Nov 1913 by a ~~two thirds~~ vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No 625

Louis S. & Schroeder President Mrs J. Jefferis City clerk

Presented to the Mayor for approval on the 15th day of Nov 1913

Mrs J. Jefferis City clerk

approved this 15th day of Nov 1913

Jesse Grice

Mayor.

General Ordinance No 626

An ordinance regulating the installation of service lines and meters for electric current.

Be it ordained by the common council of the city of Fort Wayne that Chapter 32 of General Ordinance no 370. known as the Building Code. be amended to read as follows;

Section 1. No electrical wiring. installation. electrical apparatus or appliances furnishing light. heat or power shall be introduced or placed in any building in the city of Fort Wayne except in compliance with the regulations of the National Board of Fire Underwriters and its authorized branches. Known as the National Electrical code
Said rules and regulations are hereby made a part of the requirements of this ordinance
Section 2. In the future in the wiring of new Buildings rewiring of old buildings and in the installation of new wires in old buildings or additions thereto. all service wires supplying electric current within the limits of the city of Fort Wayne shall be enclosed in approved rigid iron Conduit from the point of entrance of service wires to the Meter centers. where wire leaves the end of conduit at meter centers. a meter loop of not less than two (2) feet shall be provided.
If the electric Meter is located on the outside of the building or under a protected roof or porch. approved rigid iron conduit shall be run on the outside of the buildings from the point of attachment or connection of service wires to the meter centers: and when meter is located on the inside of the building the conduit shall turn into building at a point not above the first floor of the Consumers premises
at the entrance end of the service conduit there shall be provided a suitable condulet and at the meter end the conduit shall be suitably threaded and locknut and bushing provided. The Meter end of the conduit shall terminate three and one half (3½) inches to the left of the centers of the meter board and four and one half (4½) inches from the bottom of the meter board.
Section 3. The point of attachment of the service lines to the building shall be subject to the approval of the

building Inspector and shall be brought out at a point nearest the electric service line

Section 4 Electric meters for the measurement of electric current shall be located under protected porch or other suitable protecting cover if there be such; otherwise in the most convenient location inside of the building but electric meters shall not be placed above the first floor on consumers premises. and in any event their location must be subject to the approval of the Building Inspector. No electric meter shall be placed on the wall at a less height than five fet. or not more than seven fet above floor level

Section 5. All meter centers shall be placed ahead of the Main line switch and branch blocks providing the service wires entering any building are so protected by a suitable and approved fuse cutout as to protect all wires ahead of the meter. Said cutout shall be placed at the meter center and shall be furnished and installed by the parties supplying electric current to the consumer's building.

Section 6. There shall be installed at meter centers a suitable meter Board for separate meter which shall be not less than twenty four inches long ten inches wide and seven eights of an inch thick the long dimension to be placed Verticaly.

Section 7. No service wires shall be of smaller size than No 10 B.&S gauge. and when wires are inclosed in iron conduit shall be rubber covered double braid insulation

Section 8. The inspection of all electrical wire shall be subject to the approval of the Electrical and Building Inspector.

Section 9. This ordinance shall be in full force and effect from and after its passage and approval by the Mayor and legal publication

H. W. Folger

Done at the Council chamber in the city of Fort Wayne this 11th day of Nov 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 11th day of Nov 1913 by a Majority vote of all the Members

elect. did pass the ordinance hereunto attached and known as Genral Ordinance no 626

Louis S. C. Schroeder
President

Mrs. J. Jeffries
Cety Clerk

Presented to the Mayor for approval on the 15th day of nov 1913

Mrs. J. Jeffries
Cety Clerk

approved this 15th day of Nov 1913

Jesse Lucas
Mayor.

General Ordinance no 627

An ordinance Authorizing the employment of five additional firemen

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana. That the Board of Safety is hereby empowered and authorized to employ five (5) additional firemen and to pay the salary to said firemen as fixed by ordinance

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

P. M. Brown

Done at the council chamber in the city of Fort Wayne Indiana this 25th day of Dec 1913

We hereby certify that the Common Council of the city of Fort Wayne Indiana at a Regular Meeting held on the 25th day of Dec 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 627

Louis D. C. Schroder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 28th day of Nov 1913

Wm. J. Jefferies City Clerk

approved this 29th day of Nov 1913

Wm. J. Jefferies
City Clerk

General Ordinance No 628

An ordinance declaring certain shade trees a public Nuisance. and prohibiting their planting as a Sidewalk Shade tree: providing for the proper Spacing in planting Shade trees along the Streets: prescribing approved varieties of trees to be planted along the Streets: providing for the removal of dead trees and diseased trees beyond repair: providing against interfering with the city agents in the performance of their duty, and imposing penalties and providing for making Collections for work done by the Board of Park Commissioners.

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana that the planting of certain trees be prohibited along any Street or alley. Namely. Carolina Poplars. Cottonwoods Lombardy Poplars. Catalpas Soft Maples. Basswoods. Mulberry. and all nut bearing trees.

Any owner or owners of real estate planting any of the above Mentioned trees shall remove or cause to remove the same within ten (10) days after receiving a notice from the Board of Park Commissioners.

Section 2. The following varieties of trees may be planted along any Street or alley. Namely Norway Maple. Schwedleri Maple. Scarlet Maple. Sugar Maple. European Sycamore Maple. American Sycamore. Oriental Plane. Red Oak. Pin Oak. Black Oak. Scarlet Oak. Burr Oak. White ash English Elm. and American Elm. Pistillate (female) Ailanthus. Box Elder and Gingko trees may be planted in localities to which they are adapted.

Section 3. All newly-planted trees must be provided with a wire-mesh or other tree protecting device. the tree being securely tied in center of guard. Such tree guard must be securely fastened to an oak stake two (2) by two (2) inches square eight (8) feet long. said stake must be placed on the west side of the tree. outside of the tree guard and driven two (2) feet into the ground. a rope must be passed through a piece of garden hose and placed around the tree the ends of this rope should be securely tied to the stake to keep the tree in line any owner or owners of real estate failing to comply with this section shall cause such guards and stakes to be placed within ten (10) day after receiving a notice

from the Board of Park Commissioners.
Section 4 all shade trees along streets must be planted in accordance to the provisions in this section. The grass plot between the sidewalk and roadway must be measured and the tree planted in such a manner that one third (1/3) of the width of the grass plot will lie between the outer edge of the sidewalk and the center of the tree and two-thirds (2/3) of the grass plot will lie between the center of the tree and the edge of the roadway. curbing. or where the curbing will be when such streets are paved. no tree shall be planted in the corner grass plots of intersecting streets. When the parkway space of a street intersecting a street along which trees are to be planted. is three (3) feet or more in width. then no tree shall be planted closer than ten (10) feet from the inside edge of said intersecting street sidwald. When the width of such parkway space is less than three (3) feet then no tree shall be planted closer than twelve (12) feet from the inside edge of such intersecting street sidwalk. Departure from this spacing may in extreme cases. be authorized by the. Board of Park Commissioners. In all cases trees shall be spaced thirty (30) feet apart. as nearly as possible. inspective of the size of the abutting lots anlong any street.
Section 5. The owner or owners of any real estate along which trees are located that have branches or limbs which obstruct the light from any street light. or which hang over the sidewalk or street lower than ten (10) feet. shall trim or cause the same to be trimmed. and keep them trimmed in such a manner that the limbs or branches thereof will permit free and unobstructed passage of pedestrians and vehicles. and an unobstructed view of the streets lights. The owner or owners upon receiving written notice from the Board of Park Commissioners shall within ten (10) days remove or cause to remove such limbs or branches.
Section 6. It shall be unlawful to permit stumps. dead trees or diseased trees beyond repair. to remain along any street or alley. The owner or owners of the real estate along which such stumps. dead ~~or~~ diseased trees are located must remove or cause their removal within ten (10) days after receiving a notice from the Board of Park Commissioners

Section 7, Upon failure of any owner or owners of real estate to comply with Sections one. three. five and six of this ordinance after being served with notice by the Board of Park Commissioners it shall be the duty of said Board to proceed to do the work so ordered at any time after the expiration of ten (10) days. and the cost of such work together with reasonable attorney fees shall be recovered by an action filed in any Court and said Monies so collected shall become a part of the general park fund to reimburse said fund for money expended for doing said work and making such collections.

Section 8. It shall be unlawful for any owner or owners of real estate to interfere or cause or authorize or procure any interference with the Board of Park Commissioners or its agents while in the engagement of doing any work under the provisions of this ordinance.

Section 9. Any Owner or Owners of real estate who shall violate or Authorize or procure a violation of any of the provisions of this ordinance shall upon conviction thereof be fined not less than one ($1.00) dollar nor more than Twenty five ($25.00) dollars for each and every offense.

Section 10. Nothing in this ordinance shall authorize the Board of Park Commissioners to order the removal of any tree in good condition which has been planted prior to the enactment of this ordinance.

Section 11. This ordinance does not repeal any of the existing Laws but is amendatory thereto.

Section 12. This ordinance shall be in full force and effect from and after its passage. approval by the Mayor and legal publication.

Henry. W. Filger.

Done at the council chamber in the City of Fort Wayne this 25th day of Nov 1913

We hereby certify that the common council of the City of Fort Wayne Indiana at a Regular Meeting held on the 25th day of ~~Nov~~ 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General

Ordinance No 628

Louis S. G Schroder
Prusident

Mrs. J. Jefferies
City clerk

Presented to the Mayor for approval on the 28th day of Nov 1913

Mrs. J. Jefferies
City Clerk

Approved this 29th day of Nov 1913

Jesse Grice
Mayor

General Ordinance no 629.

An ordinance fixing the salary of the city Electrician and assistant fire Chief

Section 1. Be it ordained by the common council of the city of Fort Wayne Ind that the salary of the city electrician employed by the city of Fort Wayne through the Board of Public Safety in the Police and fire departments shall be one hundred and twenty-five dollars ($125.00) per month on and after the first day of January 1914

Section 2. Be it ordained by the common council of the city of Fort Wayne Ind that the salary of the assistant fire chief employed by the city of Fort Wayne through the Board of Public Safety in the fire department shall one hundred and twenty five ($125.00) dollars per month on and after the first day of January 1914

Section 3. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Herman Strodel

Done at the council chamber in the city of Fort Wayne Ind this the 9th day of Dec 1913

We hereby certify That the common council of the city of Fort Wayne Indiana at a Regular meeting held on the 9th day of Dec 1913 by a Majority vote of all the members elect. did pass the ordinance hereunto attached and known as General Ordinance no 629.

Louis N. C. Schroeder
President

Wm. J. Jeffries
City clerk

Presented to the Mayor for approval on the 13th day of Dec 1913

Wm. J. Jeffries
City Clerk

approved this 13th day of Dec 1913

Jesse Grice
Mayor

General Ordinance no 630

An ordinance fixing the Salary of the Deputy State Inspector of Weights and Measures

Section 1. Be it ordained by the Common Council of the City of Fort Wayne that the Salary of the Deputy State Inspector of Weights and Measures be and ~~the~~ is hereby fixed at one hundred and twenty five dollars ($125.00) per month and that the Board of Public Safety is hereby authorized to pay said Salary.
Section 2 This ordinance shall repeal all ordinances or parts of ordinances in conflict therewith
Section 3. This ordinance shall be in full force and effect on and after January 1st 1914 and legal publication and approval by the Mayor

Herman Strodel

Came at the council chamber in the city of Fort Wayne Indiana this 9th day of Dec 1913

We hereby certify that the common council of the city of Fort Wayne at a Regular Meeting held on the 9th day of Dec 1913 by a Majority vote of all the members elect did pass the Ordinance hereunto attached and known as General Ordinance no 630

Louis A. C. Schroeder
President

W. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 13th day of Dec 1913

W. J. Jefferies
City Clerk

Approved this 13th day of Dec 1913

Jesse Grice
Mayor.

General Ordinance no 631

An ordinance requiring the Lake Erie and Western Railroad Company. to Maintain Safety Gates at the crossing of the Lake shore and Michigan Southern Rail Road Companys tracks and west Main Streets and to provide watchman at. said crossing.

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that the Lake Erie and Western Railroad Company be required to erect and Maintain safety gates on each side of the tracks where they cross Main street in the city of Fort Wayne Indiana

Section 2. Reliable and Competent men shall be employed to operate said gates who shall remain at their post of duty every hours of the day and night.

Section 3. All ordinances and parts of ordinances in Conflict herewith are hereby repealed.

Section 3½ Any person or persons violating any of the provisions of this ordinance upon conviction shall be fined in any sum not exceeding fifty dollars ($50.00)

Section 4. That this ordinance be in full force and effect from and after its passage legal publication and approval by the Mayor.

B. Van Auweingen

Done at the Council Chamber in the city of Fort Wayne Indiana this 9th day of Dec 1913

We hereby certify that the common council of the city of Fort Wayne Indiana at a Regular Meeting held on the 9th day of Dec 1913. by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 631

Louis S. C. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 13th day of Dec 1913

Wm J. Jeffries
City Clerk

approved this 13th day of Dec 1913

Jesse Grice
Mayor.

General Ordinance no 632

An ordinance approving Railroad Track Elevation Resolution no 12 adopted by the Board of Public Works on October 23d 1913 as amended November 11th 1913

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that Railroad Track elevation Resolution no 12 adopted by the Board of Public works of said city on October 23d 1913 as amended Nov 11th 1913 and confirmed by the Board on November 11th 1913 be and the same is hereby in all things ratified. confirmed and approved

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication

P. M. Brown.

Done in the Council chamber in the city of Fort Wayne Ind this 9th day of Dec 1913

We hereby certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 9th day of Dec 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 632.

Louis S. C. Schroeder
President

Wm. J. Jefferies
City clerk

Presented to the Mayor for approval this 13th day of Dec 1913

Wm. J. Jefferies City clerk

approved this 13th day of Dec 1913

Jesse Grice
Mayor.

General Ordinance no 633

An ordinance ratifying and approving a contract entered into by and between the city of Fort Wayne by and through its Board of Public works and the Pupfection Biscuit Company on the 13th day of Nov 1913.

Whereas heretofore on the 13th day of November 1913 the city of Fort Wayne entend into a contract with the Pupfection Biscuit Company for the construction of a chute across Webster Street in said city which contract is in the following words:

This agreement made this 13th day of November 1913 by and between the city of Fort Wayne by and through its Board of Public works. for convenince hereinafter called city and the Pupfection Biscuit Company a corporation. for convenince hereinafter designated as "Company" Witnesseth:

First. The City hereby gives to the said Company consent and permission. Subject to the conditions hereinafter set out. to construct and maintain a temporary galvanized Steel chute across Webster Street from the west side of the old building of said Company to the East side of the new building of said Company. according to the plans and Specifications which are heeto attached and made a part of this contract as much as if fully copied herein at full length. Said chute to be used by said Company for conveying Merchandise from one to the other of the aforesaid buildings and the bottom or the lowest part of the same is to be not less than 15 feet from the grade of Webster Street.

Second. The City reserves and shall have the right and power to cause said chute to be taken down. removed in whole or in part or its use discontinued at any time. whether the removal or discontinuation of its use be necessary or not. The Company agreeing that upon receiving notice from the City to take down or remove said chute that it will so remove or take down at its expense said chute within six (6) Months after receiving said notice and in the failure of said Company its successors or assigns so to do said City may cause the removal of said chute and all Connections thereto and recover the cost and expense of the same by suit from said Company together with liquidated damages in the sum of three hundred dollars ($300.00)

Third. In lieu of the consent and permission herein granted the company will at all times save and hold said city free and harmless from any and all loss liability or damage to any person or property which shall occur or result at any time or in any manner growing out of or by reason of the construction or Maintenance of said chute. its connections or parts and said company its successors and assigns agree that it will defend in the name of said city and without expense to said city any such loss liability or damage and will pay and save said city harmless from any and all Judgments that may be rendered in any such actions against said city and its sureties shall be liable thereon or the Bond furnished to the city as hereinafter provided
Fourth Said company its successors and assigns agree that it will keep said chute and its parts in such repair so as not to at any time interfere with the free and unobstructed use of and travel on said public street by the Public
Fifth Said company further agrees that is will cause to be executed to the city of Fort Wayne a bond in the sum of $5000.00 with sureties thereon to the approval of the city. Guaranteeing the faithful performance of the terms. Stipulations and conditions herein set out and covering any loss that may be suffered by said city arising out of said contract. said city may at any time demand a new bond with new sureties thereon and the said company agrees to comply with any demand that may be hereafter Made. It is especially understood that the amount named in this Bond shall in no way be construed to limit the liability of said company of any damages hereinbefore described but in case damages shall accrue in an amount greater than said five thousand dollars ($5000.00) the said Company hereby binds itself to pay the total amount of such damages in whatever sum it may be
Sixth This contract is in no wise to alter. modify. abridge or cancel a contract heretofore entered into by and between the parties hereto on the 11th day of Feb 1913 and approved by General Ordinance No596 of the Common Council or any other contract.
Seventh. This contract is to be binding upon the parties hereto their successors and assigns

In witness whereof the parties hereto have hereunto set their hands and seals the day and year first above written

City of Fort Wayne by.
Ed Schwegmann
George H. Leach
E J. Zinman
Board of Public works
Perfection Biscuit Company by.
F. B. Franke
Its President.

attest W. A. Zecker
Clerk

Section 1. Be it ordained by the common council of the City of Fort Wayne Ind that the contract heretofore entered into on the 13th day of November 1913 by and between the city of Fort Wayne by and through its Board of Public works and the Perfection Biscuit Company as more fully set out in the preamble hereto be and the same is hereby in all things ratified and approved

section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Charles E. Welch

Done at the council chamber in the city of Fort Wayne Ind this 9th day of Dec 1913

We Hereby Certify that the common council of the city of Fort Wayne Ind at a Regular meeting held on the 9th day of Dec 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 633

Louis S. E. Schroeder
President

Wm J. Jeffries
City Clerk

Presented to the Mayor for approval on the 13th day of Dec 1913

Wm J. Jeffries
City Clerk

Approved this 13th day of Dec 1913

Jesse Grice
Mayor

General Ordinance no 634

An ordinance disannexing certain territory from the City of Fort Wayne

Whereas a certain petition has been filed with the common council by Daniel W. Stoner and other requesting that certain territory be disannexed from the city which petition is to be made a part of the ordinance hereinafter set out. Now therefore

Section 1. Be it ordained by the common council of the city of Fort Wayne Indiana that there be and is hereby disannexed and thrown out from the corporate limits of the city of Fort Wayne the following discribed territory.

Commencing at the intersection of center line of Raymond Street and Fenker avenue: thence south on center line of Fenker avenue to its intersection with center line of Felican Street: thence South west on center line of Felican Street and center line of Felican Street produced Sothwest to center line of Pontiac Street: thence east on center line of Pontiac Street and the center line of Pontiac Street produced East to center line of Edsall avenue thence north on center line of Edsall avenue to center line of Raymond Street: Thence west on the center line of Raymond Street to place of beginning;

Section 2. That upon the passage of the within ordinance said above discribed territory shall no longer be considered as forming a part of the corporate limits of said City but shall be entirely outside of said limits as though the same had never been annexed except as otherwise provided by law.

Section 3. This ordinance to be in full force and take effect from and after its passage and approval by the mayor and legal publication

Louis S. & Schroder.

Done at the council chamber in the city of Fort Wayne this 28th day of Dec 1913

We hereby Certify that the common council of the city of Fort Wayne did at a regular Meeting held on the 28th day of Dec 1913 by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance no 634

Louis S. & Schroder
President

Wm. J. Jefferies
City Clerk

Presented to the mayor for approval on the 26th day of Dec 1913

Wm. J. Jefferies
City Clerk

approved this 26th day of Dec 1913

Jesse Grice
Mayor

General Ordinance No 635

An ordinance ratifying and approving a contract entered into on the 18 day of December 1913 by and between the City of Fort Wayne and the Pioneer Coal Company.

Whereas heretofore on the 18th day of December 1913 the City of Fort Wayne by and through its Board of Public works entered into a contract with the Pioneer Coal Company providing for the purchase of its supply of coal for the year 1914 to be used at its Number two (2) Pumping Station. ~~and declaring an emergency~~

Section 1. Be it ordained by the common council of the City of Fort Wayne Indiana. That the contract heretofore entered into on the 18th December 1913 by and between the city of Fort Wayne and the Pioneer Coal company as fully set forth in the preamble hereto be and the same is in all things confirmed and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Allen Hamilton

Done at the council chamber in the city of Fort Wayne Indiana this 23d day Dec 1913

We hereby certify that the common council of the City of Fort Wayne Indiana at a Regular Meeting held on the 23d day of Dec 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance No 635

Louis A. C. Schroder
President

Wm. J. Jefferies
City Clerk

Presented to the Mayor for approval on the 26th day of Dec 1913

Wm. J. Jefferies
City Clerk

approved this 26th day of Dec 1913

Jesse Grice
Mayor

General Ordinance no 636

An ordinance authorizing the alienation of certain personal property

Section 1. Be it ordained by the Common Council of the city of Fort Wayne Indiana that the mayor be and he is hereby authorized to sell one (1) six (6) year old bay horse now used by the Board of Public works and one (1) bay mare nine (9) years old used in the water-works Department. Provided that such sale shall not be made until said property has been appraised by appraisers appointed by the Judge of the Allen circuit court.

Section 2. That the city attorney be and he is hereby authorized to petition the Judge of the Allen county circuit court for the appointment of three appraisers to appraise the property referred to in section (1) one of this ordinance.

Section 3. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

F. E. Coverdale

Done at the council chamber in the City of Fort Wayne Indiana this 23d day of Dec 1913

We hereby Certify that the Common Council of the City of Fort Wayne Indiana at a regular Meeting held on the 23d day of Dec 1913 by a Majority vote of all the Members elect did pass the ordinance hereunto attached and known as General Ordinance no 636

Louis D. G. Schroeder
President

Mrs. J. Jeffries
City Clerk

Presented to the Mayor for approval on the 26th day of Dec 1913

Mrs. J. Jeffries
City Clerk

approved this 26th day of Dec 1913

Jesse Grice
Mayor

General Ordinance No 637.

An ordinance requiring the Fort Wayne and Northern Indiana Traction Company to furnish Street Car Service on the extension of the Leris Street line to the City Limits line.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne that the Fort Wayne and Northern Indiana Traction Company, successors to the Fort Wayne Traction Company, be and it is hereby ordered, directed and required to furnish, give and operate a first class local passenger street car service over and upon the extension of the Leris Street Line of the said Company to Birchwood Avenue being the City Limits line of the City of Fort Wayne, as provided in, and is required by General Ordinance No 198 of said City.

Section 2. That this ordinance be in full force on and after its passage and approval by the Mayor

A. H. Keller

Done at the Council Chamber in the City of Fort Wayne this 10th day of February 1914.

We hereby certify, that the Common Council of the City of Fort Wayne Indiana, at a Regular meeting held on the 10th day of February 1914, by a majority vote of all the members elect did pass the Ordinance hereunto attached, and known as General Ordinance No. 637.

Wm A. Bayer
President

E V Boerger
City Clerk

Presented to the Mayor for approval on the 14th day of February 1914

E V Boerger
City Clerk

approved this 16th day of February 1914

Wm J. Hosey
Mayor

General Ordinance No 638.

An ordinance ratifying and approving a contract entered into on the 19th day of February 1914 by and between the City of Fort Wayne, Indiana, and the Indiana Engineering and Construction Company.

Whereas on the 19th day of February 1914 the city of Fort Wayne Indiana, by and through its Board of Public Works entered into a contract with the Indiana Engineering and Construction Company, which contract is in the following words:

To the Hon. Mayor Hosey,
and
Board of Public Works.
City of Fort Wayne, Ind.

We hereby take pleasure in making the following proposal in connection with the engineering and designing of the proposed addition which will be added to the present municipal electric light plant.

1. To engineer, design and furnish all drawings and specifications pertaining to this work.
2. To superintend construction on above building and electrical work.
3. To advise as consulting engineers in any capacity pertaining to said work.

For the above services we shall expect to receive 4% (four per cent) of the total expenditure on this work.

Very Respectfully submitted,
Indiana Engineering and Construction Co.
By H. P. Morgan Vice President General Mgr.
H.C. Offutt Secy.

This agreement, made this 19th day of February, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, party of the first part, and the Indiana Engineering and Construction Company, party of the second part, Witnesseth:

That in consideration of the mutual covenants hereinafter set out to be performed by each of the parties hereto, it is by them hereby agreed:

1- That said party of first part hereby employs the party of the second part as consulting and

supervising engineer in the construction of the addition to the Municipal Electric Light and Power Plant.

2- The second party to make all necessary preliminary examinations and investigations, get local data so that party of the first part can determine the kind and extent of addition to be constructed, including all electrical and mechanical equipment and building structure, so that said addition will be complete in all detail, and to consult with the party of the first part in procuring instructions from it for the work.

3- Second party to prepare preliminary estimate or estimates of cost, setting forth the general outline of the addition complete, and submit the same to said Board for its approval or alteration and final decision as to the general nature and extent of said addition.

4- In reporting to first party, the general plans and specifications, the party of the first part shall give to the said Board an analysis covering various possibilities as to the method of installation and construction of such addition to the existing power plant, together with the estimated cost of the advantages and disadvantages of each possibility and its recommendations as to the best plan to be adopted.

5- After said general outline of said addition is finally decided upon, the second party shall prepare the final estimated estimated, specifications and plans for said addition complete, including all electrical and mechanical equipment, and building structure to make said addition complete in all detail, and submit the same to the Board of Public Works for alterations and final approval.

6- Party of the second part is to meet with the Board of Public Works at the opening of bids for the construction of said work and to advise with said Board and assist the Board in its decisions in the awarding and making contracts for the work.

7. During the progress of the work, party of the second part will make all necessary inspections of the work, oversee and direct the starting of the addition and machinery therein in operation, make final

inspection and tests and report the work for final acceptance and direct such changes as are necessary, if any, to have all work fully comply with the specifications and plans; that during the active construction of said work and the erection and installation of said addition, party of the second part is to furnish an inspector or representative upon said work to ascertain for and guarantee to said City that the addition and machinery installed therein shall in every way be strictly first class and in full accordance with the specifications and plans.

8- It is understood and agreed that if contracts cannot be let upon the original plans and specifications on account of difference in prices between the estimates and bids, or for any other reasons on account of said plans and specifications, then party of the second part, at its expense and without additional charge, is to revise, alter and modify such plans and specifications so that said contracts may be let for said addition.

9.- Party of the second part agrees that it will submit at the end of each week, to the party of the first part, a a report on the progress of the work on a form to be furnished by the City.

10, In case any representative furnished by second party to supervise the work becomes unsatisfactory to said city, party of the second part agrees, on notice in writing to furnish another representative. The determination of the Board that any such representative is unsatisfactory shall be final.

11. Second party agrees that all Engineering work to be performed hereunder by it including consultation, drawing of plans, preparing of estimates, inspection, tests and reports are to be performed by their K. P. Moran and no other Engineer shall be placed on the work without the consent of the first party.

12. In consideration of the above services first party agrees to pay second party a sum equal to Four (4%) of the total cost of said addition as shown at the time of final inspection, said sum to be paid from time to time whenever partial payments are made to contractors performing the work. The cost of material and installation of any material and equipment

not shown on the plans and specifications as finally provided and in relation to which second party is not consulted shall not enter into the total cost upon which second party percent of compensation is based. This, however, is not to apply to anything placed thereon in substitution for something on the plans or provided for in the specifications.

There shall be no extra compensation of any kind or character paid to, or demanded by second party except the same be provided for by written contract between the parties hereto prior to the performance of the service for which said extra charge is made.

In Witness whereof the foregoing named parties have hereunto set their hands and seals this 19th day of February 1914

City of Fort Wayne, Indiana
By Frank E. Gingery
Robert E. Kelly
Harry Kilgeman
Bds Board of Public Works.
Indiana Engineering & Construction Co.
by H. P. Moran
its
V. P. & Gen Mgr.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne that the contract heretofore entered into on the 19th day of February 1914, executed by and between the City of Fort Wayne, by and through its Board of Public Works and the Indiana Engineering and Construction Company as fully set forth in the preamble be and the same is hereby in all things ratified and confirmed,

Section 2. This ordinance to be in full force and effect from and after its passage and approval by the Mayor

G. F. Rogge.

Done at the Council Chamber in the City of Fort Wayne this 3d day of March 1914, We hereby certify, that the Common Council of the City of Fort Wayne, Indiana at a Special meeting held on the third day of March 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No. 638.

Wm A Berger President
E. F. Berger city clerk.

Presented to the mayor for approval this 7th day of March 1914.

E. F. Berger City clerk.

Approved this 7th day of March 1914 Wm J. Hosey Mayor.

General Ordinance No. 639.

An ordinance extending the City Limits and annexing certain territory to the City of Fort Wayne, Indiana, and making the same a part of the eighth Ward.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the territorial limits of the City of Fort Wayne, Indiana, be and are hereby extended as follows:-

Commencing at the intersection of the center line of Maumee Avenue with the center line of Edsall Avenue, thence north along the center line of Edsall Avenue to its intersection with the south line of of the right-of-way of the New York, Chicago and St. Louis Railroad, thence south-east along said right-of-way line to its intersection with the center line of vacated Park Street (so called), thence along the center line of vacated Park Street (so called) to the south bank of the Maumee River to the intersection of the East line of section 6, Township 30 North, Range 13 East, Adams Township, thence South following said East line of said Section 6, to the center line of Maumee Avenue (so called), thence west along the center line of Maumee Avenue to the center line of Edsall Avenue the place of beginning.

Section 2. This ordinance to be in full force and take effect from and after its passage, approval by the Mayor and legal publication

A. H. Keller

Done at the Council chamber in the City of Fort Wayne this 10th day of March 1914.

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 10th day of March 1914, by a majority vote of all the members elect did pass the ordinance hereunto attached, and known as General Ordinance No. 639.

Wm A. Bayer
President

E. N. Berger
City Clerk.

Presented to the Mayor for approval on the 13th day of March 1914.

E. N. Berger
City Clerk

Approved this 14 day of March 1914

Wm J. Hosey mayor

General Ordinance No 640.

An ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne, by and through its Board of Public Works and American Cast Iron Pipe Co, relative to purchasing cast iron water pipe for waterworks department.

Whereas, on the 3rd day of February 1914, the City of Fort Wayne, by and through its Board of Public Works entered into a contract with the American Cast Iron Pipe Company, relative to the purchase of cast-iron water pipe for the Waterworks department, which contract is in the following words:-

This Agreement, made and entered into this 3rd day of February, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, for convenience hereinafter designated as party of the first part, and the American Cast Iron Pipe Company, for convenience hereinafter designated as party of the second part,

Witnesseth:

That the party of the first part agrees and binds itself to buy, and the party of the second part agrees to sell and deliver to the party of the first part the following: Fourteen (14) tons of four inch (4") cast-iron water pipe for which the party of the first part agrees to pay twenty four dollars and twenty cents ($24.20) per ton, and forty five tons of six inch (6") cast-iron water pipe and twenty five (25) tons of twelve inch (12") cast-iron water pipe for which the party of the first part agrees to pay twenty two dollars and twenty cents $22.20 per ton,

All of said pipe shall be delivered at said price f. o. b. Fort Wayne Indiana.

Said pipe to conform with the American Water Works Association standard specifications hereto attached, which specifications and bid of second party and the advertisement for bids are made a part of this contract as much as if all the same were copied herein at full length, and the certificate of test provided for in the specifications shall accompany each shipment.

Said second party to furnish all of said pipes

to said City from time to time as ordered by said city through its board of public works, so that each and every request for shipment shall be fulfilled within ten (10) working days from the time the request is made.

It is further agreed and understood that said pipe shall be of the kind and material and manufactured in the manner specifically described in the specifications therefor.

It is also agreed that said specials aforesaid shall include hubs and spigots, which shall be of standard weight, according to standard specifications.

Said second party further agrees to furnish to said first party a bond in the sum of Five Hundred dollars ($500.00.) guaranteeing faithful performance of the within contract, with sureties to be approved by said first party.

In Witness Whereof, the parties hereto have hereunto set their hands and the seal the day and year first above written.

City of Fort Wayne, By
Frank E. Gregory
Robert E. Kelley
Henry Hilgeman
Its Board of Public Works

attest
C. A. Beuret
Sec.

American Cast Iron Pipe Co. By
By Paul A. Ivy
General Sales Manager.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the contract hereto fore entered into on the 3rd day of February 1914 by and between the City of Fort Wayne, by and through its Board of Public Works and the American Cast Iron Pipe Company, as more fully set out in the preamble hereto, be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Frank J. Schlebecker

continued from last page

Done at the Council Chamber in the City of Fort Wayne this 10th day of March 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular meting held on the 10th day of March 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 640.

Wm A. Bayer
President.

E W Borger
City Clerk

Presented to the Mayor for approval on the 13th day of March 1914.

E W Borger
City Clerk.

approved this 14th day of March 1914

Wm J. Hosey
mayor.

General Ordinance No 641.

An ordinance fixing the salary of clerk of Building Inspector.
Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the salary of the clerk of the building inspector be fixed at fifty ($50.00,) Dollars per month.
Section 2. This ordinance hereby repudiates any and all ordinances and parts thereof in conflict herewith.
Section 3. This ordinance to be in full force and effect from and after its passage and approval by the Mayor and legal publication.

Jacob Hartman

Done at the Council Chamber in the City of Fort Wayne, this 10th day of March 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana at a Regular meeting, held on the 10th day of March 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 641.

Wm A. Bayer
President

E. F. Berger
City Clerk.

Presented to the Mayor for approval on the 13th day of March 1914

E. F. Berger
City Clerk

approved this 14th day of March 1914

Wm J. Hosey
Mayor

General Ordinance No 642

An ordinance naming a street that was widened and extended adjoining the south right-of-way line of the Wabash Railroad from Wabash Avenue to Lumbard Street, Molitor Street.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the Street that was widened, opened and extended adjoining the south right-of-way line of the Wabash Railroad from Wabash Avenue to Lumbard Street shall be named and hereafter known as Molitor Street.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Done at the Council Chamber in the City of Fort Wayne this 24th day of March 1914

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 24th day of March 1914, by a majority vote of all the members elect, did pass the Ordinance hereinto attached, and known as General Ordinance No. 642.

Wm A. Bayer
President

G W Berger
City Clerk

Presented to the mayor for approval on the 27th day of March 1914

G W Berger
City Clerk

approved this 30th day of March 1914

Wm J. Fosey
mayor

General Ordinance No. 643.

An ordinance naming a street opened by the Board of Public Works between Delaware Avenue and Forest Avenue from Bayer Avenue to Kentucky Avenue, Schorr Street.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the street opened by the Board of Public Works between Delaware Avenue and Forest Avenue, from Bayer Avenue to Kentucky Avenue, shall be named and hereafter known as Schorr Street.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Done at the Council Chamber in the City of Fort Wayne this 24th day of March 1914.

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 24th day of March 1914, by a majority vote of all the members elect did pass the Ordinance hereunto attached, and known as General Ordinance No. 643.

Wm A. Bayer
President.

E. V. Bunger
City Clerk.

Presented to the Mayor for approval on the 27th day of March 1914

E. V. Bunger
City Clerk

approved this 30th day of March 1914

Wm J. Hosey
Mayor

General Ordinance No 6444.

An ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne and the Alberger Condensing Co. relative to the construction of an addition to the Light and Power plant.

Whereas, the City of Fort Wayne, by and through its Board of Public Works on the 1st day April 1914, entered into a contract with the Alberger Condensing Company relative the installation of certain machinery in the addition to the Light and Power plant, which contract is in the following words.

Contract, made this April 1 day of 1914, By and between the City of Fort Wayne, by and through its Board of Public Works, hereinafter called the City, and Alberger Pump and Condenser Co. of New York City N. Y. hereinafter called the Contractor, Witnesseth:

I The Contractor shall do all the work and furnish all labor, tools, materials and transportation, except as otherwise specified, required for performing and completing the work and construction set forth in the plans and specifications hereto attached, which are hereby made a part of this contract, the same as if fully compiled herein. In doing the stipulated work, the Contractor shall adopt his own methods, ways and work and select the tools, machinery and labor therefor and shall not be subject to the City's orders, except as to the results to be obtained as herein after provided for.

2 All the work shall be prosecuted with the diligence and shall be done in a good substantial and workmanlike manner. All material shall be new and the best of their respective kinds, except as otherwise expressly allowed by the specifications.

3 The Contactor shall employ only competent men and, at the request of the Engineer ~~and~~ or the said Board, shall discharge any man on the work who, in the opinion of the Engineer or Board, is incompetent, unfaithful or disorderly, and such man shall not again be employed.

4 All work shall be done strictly in accordance with the plans, specifications and contract and to the approval of the Engineer and said Board. During the progress of the installation of the work, materials and apparatus will be subject to the inspection of the Board and Engineer or his

authorized representative and any work, material or apparatus not in full accord with these specifications and this Contract, and for that reason condemned must be removed and replaced immediately in a satisfactory manner at the expense of the Contractor, or leave such defective material and work remain at the option of said Board and Engineer at an agreed upon price.

5. Except by written consent of the City, the Contractor shall not have, create, establish or allow any mortgage, mechanics or any other lien on any of the tools, appliances, machinery, live stock or materials used or which may be used upon the work, or which are at any time upon the site thereof.

6 Tools, etc, Supplied by the City.

The Contractor shall become immediately responsible for tools, machinery, equipment, appliances and materials and all other property furnished said Contractor by the City from time to time they are so furnished, and he shall become responsible for other tools or materials so furnished by the City immediately upon their arrival at the point to which they are to be delivered by the City hereunder; and the Contractor shall thereafter be solely responsible for all loss or damage or similar charges.

7. All tools, machinery, appliances, equipment and unused material furnished by the City to the Contractor shall be protected and kept in good repair by the Contractor, and shall be returned to the City on completion or other termination of the work in as good order and condition as when received, except ordinary wear and tear.

8 Contractor not to assign or sublet.

Except the written consent of the City be first obtained, the Contractor shall not assign this Contract by power of Attorney or otherwise, nor sublet the work nor any part thereof, nor assign any of the money payable under this Contract, nor shall any assignments or subletting consented to be the City relieve the Contractor or his assignees of any of his obligations hereunder.

9. Payments by Contractor.

The Contractor shall pay punctually for all labor and material and all liabilities incurred by him and if and when required shall furnish the City with satisfactory evidence of such payment.

10 Contractor to Comply with Laws, Ordinances etc.

The Contractor shall comply with all building and sanitary laws and all State, County and Municipal laws, rules, ordinances and regulations.

11. Inspection

Representatives of the City may visit and inspect the work at all times during its progress and the Contractor shall provide sufficient and safe facilities for such inspection.

12 Refuse.

The Contractor shall not permit the accumulation of refuse on the site of the work or at any point contiguous thereto, and shall remove the same whenever required by the Engineer or said Board, and on completion of the work shall leave the premises clean to the satisfaction of the Engineer and said Board.

13 Foremen on Work.

At all times when work is in progress the Contractor shall employ and keep on the work a foremen or head workman and also a copy of the plans and specifications. Notice or directions given to such foremen or headworkmen, by and on behalf of the City or Engineer shall have like effect as if given to the Contractor personally.

14. Contractors Liability for Personal Injuries, etc.

The Contractor shall indemnify and safe harmless the City from any and all claims, demands, suits, actions, proceeding loss, cost and damages of every kind and description including attorney fees which may be brought or made against the City on account or injury to person or property, received or sustained by any person, firms or corporations by reason or any acts or omission of the Contractor or his Agent, or Employees, or by any reason of any explosive used on said work, or the character of or any defect in the method, materials, ways, works, machinery or tools or the work itself arising therefrom.

15. Patent Rights.

All royalties for any patented invention, article or arrangements that may be furnished by the Contractor and used or embraced in the work hereunder, shall be paid solely by the Contractor, and the Contractor shall protect and save harmless the City against any and all claims, demands, proceedings, judgements and costs, including attorneys' fees, on account of any royalties at any time, either before or after the final acceptance of the work hereunder; and the Contractor shall pay all judgements against the City. Should any suits for infringement of

patents be brought against the City before the payments herein provided for, or any of them, are made, the Contractor shall give a bond in amount and with sureties satisfactory to the City, to indemnify the City against judgements, costs and attorney's fees before demanding any balance hereunder.

Should any injunction be treatened or issued which would or might stop, hinder or delay the work, the Contractor shall promptly secure dissolution thereof, by giving bond or otherwise, or at the option of the City shall promptly cease the use of the patented article or arrangement complained of.

16. Time For Work.

The Contractor shall begin the work on or before the day of 1914. The rate of progress shall be such as in the opinion of the Engineer and said Board is necessary for completing it on or before the First day of August 1914. And the Contractor shall finish and complete all work to be done hereunder on or before the said named date.

17. The time is of the essence of this Contract.

18. Delays, Extension of Time.

Should the whole or any part of the work be hindered, delayed or suspended by the City or the Act of God of casualties or by the abandonment of the work by the employees through no fault of the Contractor or other things which the Engineer shall deem sufficient cause the Contractor shall have a corresponding extension of time to be determined by the Engineer and said Board provided the Contractor shall give the City notice in writing of claim for such extension of time within seven days after any such reason therefor shall arise.

19 Payments.

For the work, labor, materials and other things done and furnished by the Contractor in place hereunder the City shall pay to the Contractor

For the delivery and erection complete of one (1) surface condenser and auxilliaries, the sum of Eleven Thousand Nine Hundred and Two Dollars ($11902.00.) The Condensor and auxilliaries are to be the same as called for under Section D 3 of contractors proposition hereinattached.

20 Payments.

Payments shall be made by the City in accordance with the following to wit:

50% Sight Draft, B/L attached.

25% Cash when apparatus is installed.

25% within thirty days of final test and acceptance, which test shall be made within five days from time Contractor reports completion to Engineer and Board of works.

21 The Acceptance.

The acceptance by the Contractor of final payment shall be conclusive evidence of his acceptance and approval of estimates, accounting, and deductings and full payment by the City for all work, labor, materials and service done or furnished hereunder, and of full satisfaction discharge, release, and waiver of all claims and demands of or on behalf of the Contractor against the City arising out of this Contract and the execution thereof.

22. The Boards Rights.

The Board reserves the right to make alterations in the detail of the work and to order said Contractor to comply with same and it is agreed that this Contract shall not be vitiated thereby, nor shall such changes constitute any claim for damages to the Contractor, but he shall furnish the material and complete the work whether it be more or less, provided, however, that the price to be added to or deducted from said contract price or account of such changes shall first be agreed upon between the parties thereto and reduced to writing, and further promise that in case of additional work to be done and on the failure to agree upon the price therefore, prior to doing of said work the Board may elect to itself to furnish the material and to do said additional work.

23. At Contractors Risk.

The City does not guarantee the accuracy of plats of borings nor the position of pipes or other underground objects. The Contractor shall take all risk and responsibilities of the fitness or sufficiency of any methods, ways, works or appliances which the City may have adopted prior to the execution thereof, preliminary to or in aid of the work covered by this contract and shall inform himself by examination of the condition at the site of the work.

24 Contractor shall take all risk and responsibilities on account of quicksand, springs, character and position of dead rock and the like, floods, frost, freezing, fires, all action of the elements, casualties and other difficulties encountered.

25 Time of Delivery by the City.

The City does not guarantee the time of delivery of tools, machinery tools, material or other things nor the continuity of electrical service, but will use its best endeavor to meet the needs of the Contractor in deliveries undertaken by it.

26 Damage To Contractor.

No damages direct or consequential nor anticipated profit upon work not actually completed shall be claimed by or allowed to the Contractor on account of any changes, alterations, or delaying, or suspension of any work hereunder by the City.

27 Other Contractors.

In case other Contractors or the City are engaged upon or in connection with said work or any part thereof, the Contractor shall allow them full access to their work and all proper means for performing the same in connection with his, and shall comply with all directions of the engineer with reference to their proper accommodation.

28 No Waiver of Rights.

Neither the inspection of the City, its Engineer or any of its employees nor order, measurement, or certificate by the Engineer of said Board nor any order by the City for the payment of money, nor any payment for nor acceptance of the whole or any part of the work by the Engineer or said Board or the the City, nor any extension of time, nor any position taken by the City or its employees shall operate as a waiver of any condition of this contract or of any power herein reserved by the City or any right to damages herein provided nor shall any waiver or any branch of this contract to be held to be a waiver of any other subsequent breach. All remedies provided in this contract shall be taken and construed as cumulative, that is, that in addition to each and every other remedy herein provided, and the City shall have any and all equitable and legal remedies which it would in any other case have,

29. Interpretation, Decision by Engineer.

The plans and specifications are intended to be explanatory to each other. Should any discrepancies, errors or omissions in either appear, or further plans and specifications be required, or any misunderstanding arise, or explanations of any part of these plans or specifications or any portion of this Contract be required, the same shall be corrected, furnished or explained by the Engineer and the effect thereof shall date from or written notice by the Engineer to the Contractor.

30. The Contractor will be expected to work in harmony with other Contractors for different portions of the work and co operate with them so as to avoid any interference. In case of any dispute as to the right of different contractors in the prosecution of the work or possession of space, the Board and Engineer's decision shall govern.

31. Definition Engineer

The words "Chief Engineer" or "Engineer" or "Inspector" as used in this Contract refer in every case to the Consulting Engineer of the Board of Public Works of the City of Fort Wayne, Ind.

32 Contractors Bond.

The contractor shall deliver to the City, within ten days after execution hereof, a bond with Surety or Sureties, acceptable to the City in the Sum of Six Thousand Dollars ($6000.00) conditioned upon the faithful performance by the Contractor of all the terms and conditions of this contract including the payment to the City all sums for which the Contractor may become liable to the City hereunder. No payments to the Contractor shall become due or payable hereunder until such Bond has been executed and delivered and accepted by the City.

33. Notice to the Contractors Bondsmen.

No notice need be given by the City to the Surety on the Contractors bond of any act or thing hereunder except herein specifically provided, and lack of such notice to such Bondsmen shall be no defense to any action on the Contractors Bond.

34. This contract and specifications approved agreements and understandings between the parties hereto concerning the subject matter and supercede all previous contracts, understandings or agreements, whether Oral or written relating thereto. This contract shall bind and inure

to the benefit to the heirs, executors, administrators, successors and assigns of the parties hereto but this provision shall not be taken to modify the restrictions against assignment by the Contractor hereinbefore contained.

In Witness Whereof the parties hereto have caused their names to be hereunto affixed by their proper officers and the individual parties have affixed their signatures hereto, the day and year first written above.

Alberger Pump & Condenser Co
Wm S. Doran Vice Pres,

Exhibit of Contract on file
in Board of Works office

By Frank E. Spurgeon
Pres. Board of Public Works
Robt. E. Kelly
Henry Hilgeman

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that the Contract heretofore entered into on the 1st day of April 1914 by and between the City of Fort Wayne, by and through its Board of Public Works and the Alberger Condensing Company, as fully set forth in the preamble hereto be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication,

Wm A. Bayer.

Done at the Council Chamber in the City of Fort Wayne Indiana this 7th day of April 1914,

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Special meeting held on the 7th day of April 1914 by a majority vote of all the members elect, did pass the Ordinance hereunto attached and known as General Ordinance No 6444

Wm A. Bayer
President

E V Boerger
City Clerk

Presented to the Mayor for approval on the 11th day of April 1914

E V Boerger
City Clerk

Approved this 14th day of April 1914
Wm J. Hosey
Mayor

General Ordinance No. 645

An ordinance and ratifying and approving the contract entered into by and between the City of Fort Wayne and the Fort Wayne Electric Works of General Electric Company relative to the construction of an addition to the Light and Power Plant.

Whereas, The City of Fort Wayne, by and through its Board of Public Works on the 30th of March, 1914, entered into a contract with the Fort Wayne Electric Works of General Electric Company relative to the installation of certain machinery in the addition to the Light and Power Plant, which contract is in the following words:

Contract made this 30th day of March 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, hereinafter called the City, and the Fort Wayne Electric Wks. of General Electric Co. of Fort Wayne Ind. Hereinafter called the Contractor,

Witnesseth 1. The contractor shall do all the work and furnish all the labor, tools, materials and transportation, except as otherwise specified, required for performing and completing the work and construction set forth in Section 9, hereof, in the manner and accordance with the specifications adopted by the City therefore, and in the manner and in accordance with Contractor's Supplementary bid 29, except that a 100 K.W. motor generator set will be substituted for the 125 K.W. motor-generator set included in contractors Supplementary bid 29, at a reduction of Three hundred and fifty eight (358.00) dollars from the price named Contractors Supplementary bid 29. All in accordance with Contractors proposals, plans and specifications in so far as they apply herein and are not in conflict with this Contract and City's Specifications which said specifications, plans, proposals and bids are made parts hereof the same as if copied herein. In doing the stipulated work the Contractor shall adopt his own methods, ways and work, and select the tools, machinery and labor therefor, and shall not be subject to the Citys orders except as to the result to be obtained as hereinafter provided for.

2. All the work shall be prosecuted with diligence and shall be done in a good, substantial workmanlike manner. All materials shall be new and the best of their respective kinds, except as otherwise expressly allowed by the Specifications.

3. The Contractor shall employ only competent men, and at the request of the Engineer or said Board, shall discharge any man on the work who, in the opinion of the Board or Engineer is incompetent, unfaithful or disorderly and such man shall not be again employed.

4. All the work shall be done strictly in accordance with the plans, specifications and contract and to the approval of the Engineer and said Board. During the progress of the installation of the work, materials and apparatus will be subject to the inspection of the Board and the Engineer or his authorized representatives, and any work material or apparatus not in full accord with these specifications and this Contract, and for that reason condemned must be removed and replaced immediately in a satisfactory manner at the expense of the Contractor, or leave such defective material and work remain at the option of said Board and Engineer at an agreed upon price.

5. Except by written consent of the City, the Contractor shall not have, create, or establish, or allow any mortgage, mechanics or other lein on any of the tools, appliances machinery, live stock or materials used or which may be used upon the work, or which are at any time upon the site thereof.

6 Tools etc Supplied by the City.

The Contractor shall immediately become responsible for the tools, machinery, equipment, appliances and materials and all other property furnished said Contractor by the City from time to time they are so furnished, and he shall become responsible for other tools or materials so furnished by the City immediately upon their arrival at the point to which they are to be delivered by the City teamsters and the Contractor thereafter shall be solely responsible for and damage or similar charges.

7. All Tools, machinery, appliances, equipment and unused material furnished by the City to the Contractor shall be protected and kept in good repair by the Contractor, and shall be returned to the City on completion or other termination of the work in as good order and condition as when received, except ordinary wear and tear.

8. Contractor not to assign or Sub-Let.

Except the written consent of the City be first obtained, the Contractor shall not assign this Contract by power of Attorney or otherwise, nor sublet the work nor any part thereof, nor assign any of the money payable under this Contract, nor shall any assignments or subletting consented to by the City relieve the Contractor or his assignee's of any of his obligations, hereunder.

9. Payments By Contractor.

The Contractor shall pay punctually for all material and labor and all liabilities incurred by him and if so ordered required shall furnish the City with satisfactory evidence of such payment.

10. Contractor to Comply with Ordinances, Laws, etc.

The Contractor shall comply with all building and sanitary Laws and all State, County and Municipal laws, rules, ordinances and regulations.

12. Inspection.

Representatives of the City may visit and inspect at all times during its progress and the Contractor shall provide sufficient and safe facilities for such inspection.

12 Refuse.

The Contractor shall not permit the accumulation of refuse on the site of the work or at any point contiguous thereto, and shall remove the same whenever required by the Engineer or said Board, and on completion of the work shall leave the premises clean to the satisfaction of the Engineer and said Board.

13 Foreman on Work.

At all times when work is in progress the Contractor shall employ and keep on the work a foremen or head workmen and also a copy of the plans and specifications. Notice given to such foremen or head workmen, by and on behalf of the City or Engineer shall have like effect as if given to the Contractor personally.

14. Contractors Liability for Personal Injuries etc.

The Contractor shall indemnify and save harmless the City from any and all claims, demands, suits, actions, proceeding, loss, cost and damages of every kind and description including Attorneys fees which may be brought

or made against the City on account or injury to person or property, received or sustained by any person, firms or corporations by reason or any acts or omission of the Contractor or his Agent, or his employees, or by any reason of explosive used on said work, or the character of, or any defects in the method, materials, ways, works, machinery or tools or the work itself arising therefrom.

15 Patent Rights.

The contractor is to insure the Purchaser against any losses or expense by reason of adverse claims under patents based upon the use of any of the apparatus covered hereby. The company guarantees that the Purchaser shall not be disturbed in the use of said apparatus by litigation, based upon such adverse claims and to that end will at his at his own expense defend all suits or proceedings instituted against the Purchaser for any infringement of any Patent by the use of said apparatus, provided such infringement shall consist in the use by the Purchaser in the regular course of its business of said apparatus or parts thereof, and provided the Purchaser be not in default in its payments therefore and give the Company immediate notice in writing of the institution of the suit or proceeding and permits the Company through its Counsel to defend the same and give all needed information, assistance and authority to enable the Company to do so, and thereupon in case of an award of damages the Company will pay such an award and in case of an injunction against the Purchaser the Company will pay to the Purchaser any loss or damages to its business caused by such injunction.

16. Time for work.

The contractor shall begin the work on the signing of the Contract and shall finish and complete all work to be done hereunder within twenty three weeks thereafter.

17. The time is the essence of this Contract.

18. Delays, Extension of Time.

Should the whole or any part of the work be hindered, delayed or suspended by the City or the Acts of God of casualties or by the abandonment of the work by the employees through no fault of the Contractor or other things which the Engineer shall deem sufficient

cause the Contractor shall have a corresponding extension of time to be determined by the Engineer and said Board provided the Contractor shall give the City notice in writing of claim for such extension of time within seven days after any such reason therefor shall arise.

19. Payments

For the work, labor, materials and other things done and furnished by the Contractor in place hereunder the City shall pay to the Contractor

For the delivery and erection complete of one (1) 3,000 K. W., 1800 R. P. M. Steam Turbo Generator Set, One (1) Switchboard complete, in accordance with specifications herein, and one (1) 100 K. W. induction Motor Driven Exciter Set.

The sum of thirty-three thousand nine hundred and eighty five dollars. ($33985.00)

20 Payments.

Payments shall be made by the City in accordance with the following to wit:

50% Sight Draft, B/L, attached.

25% cash when apparatus is installed.

25% within thirty days of final test and acceptance, which test shall be made within five days from time Contractor reports completion to Engineer and Board.

21. The acceptance.

The acceptance by the Contractor of final payment or final estimate shall be conclusive evidence of his acceptance and approval of estimates, accountings, and deductings and full payment by the City for all work, labor, materials and service done or furnished hereunder, and of full satisfaction, discharge, release, and waiver of all claims and demands of or on behalf of the Contractor against the City arising out of this contract and the execution thereof.

22 The Boards Rights.

The Board reserves the right to make alterations in the detail of the work and to order said contractor to comply with same and it is agreed that this contract shall not be vitiated thereby, nor shall such changes constitute any claim for damages to the Contractor, but he shall furnish the material and complete the work whether it be more or less, provided, however, that the price to be added to or deducted from said

contract price or account of such changes shall first be agreed upon between the parties thereto and reduced to writing, and further promise that in case of additional work to be done and on the failure to agree upon the price therefor, prior to doing of said work the Board may elect to itself to furnish the material and do said additional work

23, 23. Contractors Risk.

The City does not guarantee the accuracy of plats of borings nor the position of pipes or other underground objects. The contractor shall take all risk and responsibilities of the fitness or sufficiency of any methods, ways, works or appliances which the City may have adopted prior to the execution thereof, preliminary to or in aid of the work covered by this Contract and shall inform itself by examination of the condition at the site of the work.

24, Contractor shall take all risk and responsibilities on account of quicksand, springs, character and position of dead rock and the like, floods, frost, freezing, fires, all action of the elements, casualties and other difficulties encountered.

25 Time of Delivery By The City.

The City does not guarantee the time of delivery of tools, machinery, material, or other things nor the continuity of electrical service, but will use the best endeavor to meet the needs of the Contractor in deliveries undertaken by it.

26 Damage To Contractor

No damages direct or consequential, no anticipated profit upon the work not actually completed shall be claimed by or allowed to the Contractor on account of any changes, alterations, or delay in, or suspension of any of the work hereunder by the City.

27, Other Contractors

In case other contractors or the City are engaged upon or in connection with said or any part thereof, the Contrator shall allow them full access to their work and all proper means for performing the same in connection with his, and shall comply with all directions of the engineer with reference to their proper accommodation.

28 No waiver of rights.

Neither the inspection of the City, its Engineer or any of its employees nor order, measurement, or certificate by the Engineer of said Board nor any order by the City

for the payment of money, nor any payment for nor acceptance of the whole or any part of the work by the Engineer or said Board or the City, nor any extension of time, nor any position taken by the City or its employees shall operate as a waiver of any condition of this Contract or of any power herein reserved by the City or any right to damages herein provided nor shall any waiver or any branch of this Contract to be held to be a waiver of any other or subsequent breach.

All remedies provided in this Contract shall be taken and construed as cumulative, that is, that in addition to each and every other remedy provided and the City shall have any and all equitable and legal remedies which it would in any other case have.

29. Interpretation, Decision by Engineer.

The plans and specifications are intended to be explanatory to each other, should any discrepancies errors or omissions in either appear, or further plans and specifications be required, or any misunderstanding arise, or explanations of any part of the said plans or specifications or of any portion of this contract be required, the same shall be corrected, furnished or explained by the Engineer and the effect thereof shall date from written notice by the Engineer to the Contractor.

30 The contractor shall be expected to work in harmony with other contractors for different portions of the work and co-operate with them so as to avoid any interference. In case of any dispute as to the rights different contractors in the prosecution of the work or possession of space, the said Board and Engineers decision shall govern.

31. Definition Engineer

The words "Chief Engineer" or "Engineer" or "Inspector" as used in this Contract refer in every case to the Consulting Engineer of the said Board of Public Works of the City of Fort Wayne, Ind.

32. Contractors Bond.

The Contractor shall deliver to the City within ten days after execution hereof a bond with Surety or Sureties, acceptable to the City in the sum of Thousan Dollars

$. conditioned upon the faithful performance by the Contractor of all the terms and condition of this contract including the payment to the City all sums for which the contractor may become liable to the City hereunder.

No payments to contractor shall become due or payable hereunder until such Bond has been executed and

delivered and accepted by the City.

33. Notice to the Contractors Bondsmen.

No notice need be given by the City to the Surety on the Contractors Bond of any act or thing hereunder except as herein specifically provided, and lack of such notice to such Bondsmen shall be no defense to any action on the Contractors Bond.

34. This Contract and Specifications express all agreements and understandings between the parties hereto concerning the subject matter and supercede all previous contracts, understandings, or agreements, whether oral or written relating thereto. This contract shall bind and inure to the benefit of the heirs, executors, administrators, successors and assigns of the parties hereto but this provision shall not be taken to modify the restrictions against assignment by the Contractor hereinbefore contained

In Witness Whereof:

The parties hereto have caused their names to be hereunto affixed by their proper officers and the individual parties have fixed their signatures hereto, the day and year first written above

Ft Wayne Electric Works
of General Electric Company.
By F. L. Hunting
General Manager

Exhibit of Contract on file
in Board of Works office
E W Boerger Clerk

By Frank E. Gregory
Pres. Board of Public Works

Robert E. Kelly

Henry Hilgeman

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that the contract heretofore entered into on the 30th of March 19[illegible] by and between the City of Fort Wayne by and through its Board of Public Works, and the Fort Wayne Electric Works of General Electric Company, as fully set forth in the preamble hereto be and the same is in all things ratified and approved.

continued to next page

Section II. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal Publication.

Charles E. Welch.

Done at the Council Chamber in the City of Fort Wayne Indiana this 7th day of April 1914.

We hereby certify that the Common Council of the City of Fort Wayne, Indiana, at a Special meeting, held on the 7th day of April 1914, by a majority vote of all the members elect, did pass the ordinance hereto attached, and known as General Ordinance No. 645.

Wm A. Bayer
President

E W Borgner
City Clerk

Presented to the mayor for approval on the 11th day of April 1914

E W Borgner
City Clerk

Approved this 14th day of April 1914

Wm J. Hosey
mayor

General Ordinance No. 646

An ordinance ratifying and approving a contract entered into on the 26th day of January 1914 by and between the City of Fort Wayne, Indiana and the Fort Wayne Electric Works of Fort Wayne, Indiana.

Whereas, on the 26th day of January 1914, the City of Fort Wayne, Indiana, by and through its Board of Public Works entered into a contract with the Fort Wayne Electric Works, which contract is in the following words:

Future Delivery Meter Contract

This contract and agreement, executed in duplicate, made and entered into this 26th day of January 1914, by and between the Fort Wayne Electric Works of General Electric Company, Fort Wayne, Indiana, party of the first part, and Board of Public Works, of Fort Wayne, Indiana, party of the second part, their successors and assigns:- Witnesseth

That for and in consideration of One Dollar and other valuable considerations, paid by said party of the first part to said party of the second part, the receipt of which is hereby acknowledged, the said part of the second part hereby agrees to purchase of the said party of the first part, all electric alternating current watthour meters which the said party of the second part may need during a period of one year from the date of this contract, for use by them in the operation of the electric plants controlled by them and to pay for all meters purchased under this contract within thirty (30) days from date of shipment thereof the price hereinafter set forth; and all said meters to be used as above mentioned shall be type K alternating current watthour meters as manufactured by the said party of the first part at Fort Wayne, Indiana.

For and in consideration of the exclusive purchase of alternating current watthour meters, as hereinbefore mentioned, from the said party of the first part, the said party of the second part, the said party of the first part agrees that all meters purchased under this contract shall be free from all inherent electrical and mechanical defects, and to hold said party of the second part harmless and indemnified against all sums which the said party of the second part shall be adjudged to pay in any suit brought against them alleging infringement of patents by the use of meters hereinbefore mentioned, provided that the party of the first part be given immediate written notice of suits and permission through their counsel to defend the same;

and provided further that the said party of the second part is not in default in their payments.

The said party of the first part hereby agrees to sell to the said party of the second part alternating current at the hour meters as hereinbefore mentioned, new and in good condition, delivered F. O. B. Fort Wayne, Indiana, consigned to the address of the said party of the second part, at a discount of

60 per cent, from Schedule A
60 per cent, from Schedule E
60 per cent, from Schedule H
Net Retail from Schedule F

Said schedule being attached hereto and made a part of this contract.

The party of the second part agrees that he is under no obligations inconsistent with the carrying out of the conditions of this agreement.

This contract is not binding unless approved by the General Manager, Sales Manager or Treasurer of the party of the First Part.

Fort Wayne Electric Works
of General Electric Company.
By A. M. Miller

accepted, Fort Wayne Municipal Electric Light and Power Works.
By Frank E. Gregory
Robert E. Kelly
Henry Kilgeman

The above Contract and agreement is hereby fully ratified and approved by us at Fort Wayne Indiana this 27th of January 1914

Fort Wayne Electric Works
of General Electric Company.
By A. A. Lerda
Sales manager.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne Indiana, that the Contract heretofore entered into on the 26th day of January 1914, by and between the City of Fort Wayne, by and through its Board of Public Works and the Fort Wayne Electric Works as more fully set out in the preamble hereto, be and the same is all things ratified and approved.

Section 2. This ordinance to be in force and take effect from and after its passage and approval by the Mayor and legal publication.

Charles E. Welch.

Done at the Council Chamber in the City of Fort Wayne Indiana this 14th day of April 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, at a Regular meeting held on the 14th day of April 1914, by a majority ~~of the two thirds~~ vote of all the members elect, did pass the ordinance hereto attached, and known as General Ordinance No. 646.

Wm A. Bayer
President

E. J. Boerger
City Clerk.

Presented to the Mayor for approval on the 16th day of April 1914.

E. J. Boerger
City Clerk.

Approved this 17th day of April 1914

Wm J. Hosey
Mayor.

General Ordinance No 647.

An ordinance ratifying and approving a contract entered into on the 26th day of January 1914, by and between the City of Fort Wayne, Indiana, and the Fort Wayne Electric Works of Fort Wayne, Indiana.

Whereas, on the 26th day of January 1914, the City of Fort Wayne Indiana, by and through its Board of Public Works entered into a contract with the Fort Wayne Electric Works, which contract is in the following words:

Future Delivery Transformer Contract.

This contract and agreement, executed in duplicate, made and entered into this 26th day of January 1914, by and between the Fort Wayne Electric Works of General Electric Company, Fort Wayne, Indiana, party of the first part and Board of Public Works of Fort Wayne, Indiana, party of the second part, their successors and assigns:-

Witnesseth That for and in consideration of One Dollar and other valuable considerations, paid by said party of the first to said party of the second part, the receipt of which is hereby acknowledged the said party of the second part hereby agrees to purchase of the party of the first part, all multiple transformers that the said party of the second part may require during the period of one year from the date of this contract, for use by them in the operation of the electric plants controlled by them all standard transformers to be rated 1100-2200 volts primary, 110-220 volts secondary.

The party of the second part agrees to pay to the party of the first part for all transformers purchased under this contract within thirty (30) days from date of shipment there of the price hereinafter set forth, and all transformers to be used as above mentioned shall be type A transformer as manufactured by the said party of the first part at Fort Wayne, Indiana.

For and in consideration of the exclusive purchase of transformers as hereinbefore mentioned from the said party of the first part, the said party of the second part, the said party of the second part hereby agrees that all transformers purchased under this contract shall be free from all inherent electrical and mechanical defects, and to hold said party of the second part harmless and indemnified against all sums which the said party of the second part shall be adjudged to pay in any suit brought against them alleging infringement of patents by use of the transformers hereinbefore mentioned, provided that the party of the first part be given immediate written notice of suits or information through their counsel to defend same; and provided further that the said party of the second part is not in default in their payments.

Said party of the first part hereby agrees to sell to the said party of the second part Standard multiple transformers as hereinbefore mentioned, new and in good condition, delivered F. O. B. Fort Wayne, Indiana consigned to the address of the said party of the second part, at a discount of 50 - 10 - 10 - 5, per cent from Schedule A.
Rebate per cent from Schedule, Rebate,
Said Transformer Schedules being attached hereto and made a part of this Contract.
Should transformers other than Standard be required they will be furnished at prices comparable with prices on transformers as specified in the attached Schedules.

The party of the second part agrees that he is under no obligations inconsistent with the carrying out of the conditions of this agreement.

This Contract is not Binding unless approved by the General Manager, Sales Manager or Treasurer of the Party of the First Part.

Fort Wayne Electric Works
of General Electric Company.
By N. W. Miller

Accepted Fort Wayne Municipal Electric Light & Power Works.
By Frank E. Gregory
Robert E. Kelley
Henry Hilgeman

The above contract and agreement is hereby ratified and approved by us at Fort Wayne, Indiana, on the 28th day of January 1914.

Fort Wayne Electric Works
of General Electric Company.
By A. A. Lerda
Sales Manager.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the Contract heretofore entered into on the 26th day of January 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, and the Fort Wayne Electric Works, as more fully set out in the preamble hereto, be and the same is in all things ratified and approved,

Section 2. This ordinance to be in full force and effect from and take

its passage and approval by the Mayor and legal publication.

Jacob Hartman

Done at the Council Chamber in the City of Fort Wayne, Indiana, this 14th day of April 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 14th day of April 1914, by a majority vote of all the members elect, did pass the ordinance hereto attached, and known as General Ordinance No 647.

Wm A. Bayer
President

G W Borgner
City Clerk.

Presented to the Mayor for approval on the 16th day of April 1914.

G W Borgner
City Clerk

Approved this 17th day of April 1914

Wm J. Hosey
Mayor.

General Ordinance No 648.

An ordinance ratifying and approving a contract entered into on the 19th day of March 1914, by and between the City of Fort Wayne by and through its Board of Public Works, party of the first part and the Fort Wayne Electric Works of General Electric Company, party of the second part.

Whereas, on the 19th day of March 1914, the City of Fort Wayne, by and through its Board of Public Works entered into a contract with the Fort Wayne Electric Works of General Electric Company which contract is in the following words:

This Agreement, made this 19th day of March 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, party of the first part and the Fort Wayne Electric Works of the General Electric Company, party of the second part,

Witnesseth: Whereas, party of the second part desires to procure a side track connecting the main track of the Pittsburgh, Fort Wayne and Chicago Railroad Company, owner, and the Pennsylvania Company, lessee, with that portion of the plant of the second party lying west of Union Street, in order to facilitate the shipping of property of second party, to and from the said portion of said plant, and

Whereas, said Railroad Company are willing in their name to construct and operate said side track for said purposes,

Now Therefore, In consideration of the covenants and agreements to be performed and complied with by the party of the second part as hereinafter provided, consent, permission and authority are hereby given and granted by the party of the first part to the party of the second part to construct, maintain and operate or cause to be constructed, maintained and operated, a single track railroad across Union Street in the City of Fort Wayne within the right-of-way lines of said railroad companies.

It is agreed, and understood, that the consent, permission and authority herein given and granted are upon the following terms and conditions:

1. The part of the second part, if it desires to avail itself of the benefits of the consent, permission and authority herein granted, shall cause the complete construction of said railroad track without incumbering, using or occupying any portion of Union Street.

2. Said track is to be constructed and maintained by second over and upon the abutments as now existing and within the lines of the right-of-way of the Pittsburgh, Fort Wayne and Chicago Railroad Company at said Street and in such manner as the bottom part of the bridge structure upon which said track is to be placed shall be at least twelve and one-half (12½) feet above the grade of said Union Street as now established and as from time to time to be established. The superstructure portion of said railroad, including the trackage and bridgework shall at all times conform with and be the same as the superstructure now and hereafter maintained by said railroad companies over and across said Street at said point and the entire cost of installing, maintaining, changing and repairing said superstructure shall be paid by the party of the second part.

It is understood that no additional abutments are to be constructed under this grant at the sides of the street in the construction, installation and maintenance of the railroad, the franchise for which is hereby given.

3. In the event that it becomes necessary at any time to reconstruct said superstructure including the trackage and bridgework for any reason whatever, the expense thereof shall be borne by the party of the second part, as well as the expense of repairing and maintaining the same.

4. Before the commencement of the work and installation of said superstructure work for the construction of said railroad, the party of the second part shall file with the Board of Public Works specifications showing the kind and nature of the bridge work to be installed, which shall be approved by said Board of Public Works before the construction of said Railroad, but the approval of the said Board of Public Works shall not relieve the party of the second part from installing and maintaining the superstructure work as required by the provisions of section two hereof. If at any time it becomes necessary to remove the superstructure work constructed hereunder by the party of the second part so as to make it conform to the superstructure or track and clearance now and hereafter maintained by said Railroad companies, the said party of the second part shall remove the same and place such superstructure work so as to conform with said superstructure work or clearance maintained by said Railroad companies or either of them without fifty

(60) days after receiving written notice so to do by said Board of Public Works.

5. In the event that any street is opened or established at any point across the said railroad right of way in connection with which this permission is granted, second party shall cause, at its expense, the elevation of its tracks in accordance with plans and specifications therefor adopted by the said Board of Public Works, and in determining the damages to second party for land taken for such street, no damage on account of or connected with the elevation of the tracks shall be considered.

6, The party of the second part further agrees and binds itself to keep and hold said City free and harmless from any and all liability from any and all damages that may accrue to any and all persons or property on account of any injury to their persons or property growing out of or directly or indirectly connected with the construction, maintenance or operation of said railroad or any cars thereon by any person or corporation, and in case any suit shall be filed against said City on account thereof, said party of the second part, upon notice to it by said City, shall defend said action at its own expense and pay any judgement with costs that may be rendered in said action against said City.

7. In the event party of the second part fails to comply with and perform any of the provisions of this contract, the consent, permission and authority herein granted shall cease terminate, and said second party shall forfeit all rights hereunder and shall cause the removal, at its expense, of all track and superstructure work that may be laid hereunder.

6, It is further understood and agreed that all the provisions of this contract shall be binding upon the successors and assigns of the party of the second part and that this grant, permission and authority shall continue for a period of twenty five years (25) years from the date hereof.

Witness Our Hands and seals the day and year first above written

City of Fort Wayne By
Frank E. Lingsey
Harry Kilgerman
Its Board of Public Works
Fort Wayne Electric Works of
General Electric Company
By F. S. Hunting
Its General Manager

Attest H. M. Becker
Clerk

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the contract heretofore entered into by and between the City of Fort Wayne, by and through its Board of Public Works and the Fort Wayne Electric Works of General Electric Company, as fully set forth in the preamble hereto, be and the same is hereby in all things ratified and approved.

Section 2. That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Jacob Hartman.

Done at the Council Chamber in the City of Fort Wayne, Indiana this 14th day of April 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 14th day of April 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 648.

Wm A. Bayer
President

E W Boerger
City Clerk

Presented to the Mayor for approval on the 16th day of April 1914

E W Boerger
City Clerk.

Approved this 17th day of April 1914

Wm J. Hosey
Mayor

General Ordinance No. 649.

An ordinance regulating Sale of Ice.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that whoever, being engaged in the business of selling ice at retail, fails or refuses to sell from any place or vehicle used at the time in the regular distribution of ice at retail to any to any person other than an ice dealer, a piece of ice of the fair retail value of not less than five nor more than fifty cents as demanded by such person, shall if such person tenders in payment therefore the fair retail value thereof in legal money of the United States be punished by a fine of not less than Twenty five ($25.00) Dollars and not more than One Hundred ($100.00) Dollars.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the mayor and legal publication.

A. N. Keller

Done at the Council Chamber at the City of Fort Wayne, Indiana this 14th day of April 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 14th day of April 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 649.

Wm A. Bayer, President, E. W. Borgner City Clerk.

Presented to the mayor for approval on the 16th day of April 1914.

E. W. Borgner
City Clerk.

Approved this 17th day of April 1914.

John J. Hosey
Mayor.

General Ordinance No. 650

An ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne, by and through its Board of Public Works and the United States Cast Iron Pipe and Foundry Company, relative to purchasing cast iron water pipe for the Water Works Department.

Whereas, on the 3rd day of March, 1914, the City of Fort Wayne, by and through its Board of Public Works entered into a contract with the United States Cast Iron Pipe and Foundry Company relative to the purchase of cast iron water pipe for the water works department, which contract is in the following words:

This agreement, made and entered into this 3d day of March, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, for convenience hereinafter designated as party of the first part, and the United States Cast Iron Pipe and Foundry Company, for convenience hereinafter designated as party of the second part, Witnesseth:

That the party of the first part agrees and binds itself to buy, and the party of the second part agrees to sell and deliver to the party of the first part the following:

three hundred (300) tons of six inch (6") to twelve (12") inch Cast Iron Bell and Spigot Water Pipe, for which the party of the first part agrees to pay twenty-two dollars and forty-five cents ($22.45) per ton, and such quantities of Bell and Spigot special castings as said Board may deem proper and necessary during the delivery and laying of said pipe, for which castings said first party agrees to pay two and three-fourths cents (2¾) per pound. Said first party shall have the privilege of increasing the amount of each of the above items of pipe and specials fifty per cent. (50%) at the same price. All of said pipe and castings shall be delivered f. o. b. Fort Wayne, Indiana.

Said pipe and castings to conform with the American Water Works Association standard specifications hereto attached, which specifications and bid of said second party and the advertisement for bids are made a part of this contract as much as if all the same were

copied herein at full length, and the certificate of test provided for in the specifications shall accompany each shipment.

Said second party to furnish all of said pipes to to said City from time to time as ordered by said City through its Board of Public Works, so that each and every request for shipment shall be fulfilled within ten (10) working days from the time the request is made.

It is further agreed and understood that said pipe shall be of the kind and material and manufactured in the manner specifically described in the specifications therefore.

It is also agreed said specials aforesaid shall include hubs and spigots, which shall be of standard weight, according to standard specifications.

Said second party further agrees to furnish to said first party a bond in the sum of one thousand dollars ($1000.00) guaranteeing faithful performance of the within contract, with sureties to be approved by said first party.

Payment for said pipe and special castings to be net cash, within thirty days (30) from date of invoices.

In Witness Whereof, the parties hereto have hereunto set their hands and seals the day and year first above written.

City of Fort Wayne, By
Frank E. Gregory
Robert E. Kelly
Henry Hilgeman
Its Board of Public Works
United States Cast Iron Pipe
and Foundry Company, By
A. J. Goodhue
Western Sales Manager

Attest
C. A. Beuret
Secretary.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the contract heretofore entered into on the 31 day of March, 1914, by and between the City of Fort Wayne, by and through its Board

of Public Works and the United States Cast Iron Pipe and Foundry Company, as more fully set out in the preamble hereto, be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Jacob Hartman.

Passed at the Council Chamber in the City of Fort Wayne, Indiana this 12th day of May 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting, held on the 12th day of May 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No 650,

Wm C. Bayer
President

Ed Boerger
City Clerk.

Presented to the Mayor for approval on the 14th day of May 1914.

Ed Boerger
City Clerk.

Approved this 15th day of May 1914,

Wm J. Hosey
Mayor.

Special Ordinance No. 65,

An ordinance ratifying and approving a contract entered into on the 24th day of April, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works and N. J. Stevenson.

Whereas, heretofore on the 24th day of April 1914, the City of Fort Wayne, by and through its Board of Public Works and N. J. Stevenson of Milwaukee Wisconsin, entered into a contract for the purchase by said City of one N. J. Stevenson Improved Sewer cleaning machine and parts, which contract is in the following words:

This agreement, made this 24th day of April, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, party of the first part, and N. J. Stevenson of Milwaukee, Wisconsin and Fort Wayne, Indiana, party of the second part, Witnesseth; That in consideration of the payment by the City of Fort Wayne to the party of the second part of the sum of eight hundred ($800.00) Dollars in cash, on the ratification and approval of this contract by an ordinance of the Common Council of the City of Fort Wayne, the party of the second agrees to and does hereby sell to the party of the first part the N. J. Stevenson Improved Sewer Cleaning Machine now in possession of the City of Fort Wayne and the following accompanying parts thereof:

1 Bronze brass tube mounted on small wheels, working parts enclosed.

4 Sets of extra extension legs to extend wheels from sizes 6" to 20".

10 Sets blades for 8", 12", 15", 18" and 20" pipe made of machine steel.

115--31 1/2" by 1 1/2" by 1 5/8" sewer rods, making 400 feet. These rods have cast connections and are very positive and cannot become unbuckled in the pipe. The wood part is made of Oregon fir dipped in Creosote. The castings are dipped in Asphaltum.

2 Steel frame windlasses mounted on wheels with detachable drums and shaft and compound gear.

450 feet steel cable on each windlass 3/8" in diameter,

1 set tradeum with 450 feet 1/4 galvanized cable.
2 or 3 inches,
8 chain clamps to chain near cable to hose connection.
1 set shoes to hold pulley block.
2 pulley blocks, and
Set struts to hold shoe in place from 8" to 24" pipe.
The party of the second part agrees that all bronze brass parts or connections broken or becoming defective within three (3) years from passage of ordinance approving this contract which are broken or become defective on account of faulty or defective material or construction shall be replaced by him without cost to the City.

Party of the second part agrees to save the City harmless from all damage or cost on account of any infringement or alleged infringement in the use of said machine or any of its parts and to save City harmless against any Royalties or Claims for Royalties growing out of the use by said City of said machine or any part thereof. and in the event any person or Company, by action or otherwise, seeks any damage or royalties from said City on account of any connection with the use of said machine or any parts thereof, that said second party will defend said claim or claims in his or in the name of said city and at his expense upon notice of such claim from said city, and without any expense to said City,

City of Fort Wayne, By
Frank E. Gregory
Robert E. Kelly
Henry Kildeman
Bd Board of Public Works.

Attest N. W. Becker
Clerk.

W. J. Stevenson
Owner

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that the contract heretofore entered into by and between the City of Fort Wayne, by and through its Board of Public Works, and W. J. Stevenson, for the purchase of one W. J. Stevenson Improved Sewer Cleaning

Machine as fully set forth in the preamble hereto, be and the same is in all things ratified and approved.

Section 2. This ordinance to be in force and take effect from and after its passage and approval by the mayor and legal publication

Jacob Agne.

Done at the Council Chamber in the City of Fort Wayne this 12th day of May 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 12th day of May 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached and known as General Ordinance #651.

Wm A. Bayer
President.

E V Buesser
City Clerk

Presented to the Mayor for approval ~~this~~ on the 14th day of May 1914.

E V Buesser
City Clerk

Approved this 15th day of May 1914

Wm J. Hosey
mayor.

General Ordinance No 652.

An ordinance regulating the tapping directly or indirectly into main sewers.

Section 1. No owner or occupant of any real estate shall tap or drain, either directly or indirectly, into any main sewer, nor shall any such owner tap or drain, directly or indirectly into any lateral or local sewer connected or to be thereafter connected directly or indirectly with such main sewer, when said Real Estate at the time of of the construction of said main sewer was not directly assessed for the construction thereof, until he shall have first complied with the provisions of this Ordinance and paid to the Controller of the City of Fort Wayne for said City, the sum of Ten (10.00) Dollars, and no person shall be allowed to drain into any connection with such main or lateral sewer of his or any other person except by paying a like sum to said Controller upon permission so to do by the Board of Public Works.

Section 2. That section 10 of General Ordinance No 31 approved May 14-1895, being an Ordinance entitled "An ordinance authorizing the issuing of permits to tap sewers and drains constructed by the order of the City, prescribing the manner of making such connections and specifying the kind of material to be used; also authorizing the issueing of licenses to sewer builders, fixing the standard for the qualifications of such persons and providing for their examination; also forbidding the deporoting of certain substances, such as garbage, rags, etc, into sewers or drains; prescribing the manner of such permits and licenses and providing generally for the violation of any of the provisions of this ordinance", be and the same is hereby repealed.

Section 3. That this ordinance shall not be construed as repealing any of the provisions, except as herein expressly provided of General Ordinance No 31, approved May 14-1895 being an ordinance entitled, "An ordinance authorizing the issueing of permits to tap sewers and drains constructed by order of the City, prescribing the manner of making such connections and specifying the kind of material to be used; also authorizing the issueing of licenses to sewer builders, fixing the standard for the qualifications of such persons and providing for their examination; also prohibiting the deporoting of certain substances, such as garbage, rags, etc, into sewers or drains; prescribing the manner of such permits and licenses and providing generally

for the violation of any of the provisions of General Ordinance No 380 passed March 9, 1909 being an ordinance entitled "An ordinance prohibiting the tapping of, or making any comections with any public sewers or drains by any person other than the City Sewer Inspector, prescribing the manner of making such connections and the material with which such connections shall be made and providing a penalty for the violation thereof," but the provisions hereof shall be taken as cumulative to the requirements of said ordinance.

Section 4. That any one failing to comply with or violating any of the provisions of this ordinance shall be fined in any sum not less than Twenty five ($ 25.00) Dollars and not exceeding One Hundred ($ 100.00) Dollars.

Section 5. That this ordinance to be in full effect from and after its on and after its passage and approval by the Mayor and by publication

J. B. Mills

Done at the Council Chamber in the City of Fort Wayne Indiana this 12 th day of May 1914.

I hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 12 day of May, 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 652.

Wm A. Bayer
President

E W Borgner
City Clerk

Presented to the mayor for approval on the 14 th day of May 1914.

E W Borgner
City Clerk

Approved this 15 th day of May 1914

Wm J. Fosey
Mayor

General Ordinance No 653.

An ordinance amending Section 2. of an ordinance amending Section 3 of General Ordinance #538 passed by the Common Council on the 23rd day of December 1912.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, That Section 2 of General Ordinance #587, being an ordinance amending sections 1, 3, 4, 5 and 11 of General Ordinance #538, being an ordinance entitled "An ordinance prohibiting and regulating the erection of signs, sign boards or other structures to be used for advertising purposes" be amended to read as follows:

Section 2. That section 3 of General Ordinance #538 being an ordinance entitled "An ordinance prohibiting and regulating the erection of signs, sign boards or other structures to be used for advertising purposes," be amended to read as follows:

Section 3. The term "signs" shall apply to display boards or screen used as such having characters, letters or illustrations painted, enameled, written, cut or fastened thereon.

The term "banner sign" shall apply to all display signs painted, printed or written upon cloth or canvas either with or without frame.

The term "electric sign" shall apply to signs constructed entirely of metal or other approved non combustible material and shall have one opened socket for each square foot of sign surface and shall have at least 4 candle power illumination for each square foot of sign surface, except in raised letter type, electric signs shall be illuminated proportionate from 25 Watt lamps to every 10" "raised letter".

Section 4 This ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Jacob Hartman
J. B. Mills

Done at the Council Chamber in the City of Fort Wayne Indiana on the 12th day of May 1914

We hereby certify that the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 12th day of May 1914, by a majority vote of all the members elect, did pass the

ordinance hereunto attached, and known as
General Ordinance No. 653.

Wm A. Bayer
President

E V Borger
City Clerk.

Presented to the Mayor for approval on the
14th day of May 1914

E V Borger, City Clerk

Approved this 15th day of May 1914

Wm J. Hosey
Mayor.

General Ordinance No 654.

An ordinance changing the name of Court St. to Packard Avenue,

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that Court Street, from Hoagland Avenue to Piqua Road and the extension of Packard Avenue from Fairfield Avenue be called and known as Packard Avenue.

Section 2 That this ordinance be in full force and effect on and after its passage and approval by the mayor

J. B. Mills

Done at the Council Chamber in the City of Fort Wayne Indiana on the 12th day of May, 1914.

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 12th day of May 1914, by a majority vote of all the members elect, did pass the ordinance hereto attached, and known as General Ordinance No. 654.

Wm A. Bayer
President

E V Borger
City Clerk,

Presented to the Mayor for approval on the 14th day of May 1914,

E V Borger
City Clerk

Approved this 15th day of May 1914

Wm J. Hosey
Mayor.

General Ordinance No 655.

An Ordinance ratifying and approving a contract entered into on the 16th day of May 1914, between the City of Fort Wayne and Max Irmsher for construction of addition to Lighting Plant.

Whereas on the 16th day of May 1914 the City of Fort Wayne by and through its Board of Public Works entered into a contract with Max Irmsher for the building of an addition to the Electric Plant which contract is in the following words:-

Contract Made this 16th day of May, 1914 at the City of Fort Wayne State of Indiana and between the Board of Public Works of the City of Fort Wayne, hereinafter called the City ("The word "Board" refers to Board of Works and Max Irmsher, Fort Wayne of Indiana hereinafter called the Contractor.

Section 1. Contractors Undertakings. The Contractor shall do all the work and furnish all the labor, tools, machinery, materials and transportation, except as otherwise specified, required for performing and completing the work and construction set forth in the City plans and specifications hereinafter referred to, and which said work shall be performed and completed in the manner provided in and in full compliance with the plans and specifications for said work on file in the office of the Board of Public Works as well as in the manner provided in and in compliance with the proposals of the party of the second part in so far as they are not in conflict with this Contract or the provisions of said city plans and specifications, which said city plans and specifications are signed by the parties hereto for identifications and are made a part of this contract the same as if copied in full herein. In doing the stipulated work, the contractor shall adopt his own methods, ways and work and select the tools, machinery and labor therefor and shall not be subject to the City's Control or Orders, except as to the results to be obtained and as hereinafter provided for.

Section 2. All the work shall be prosecuted with diligence and shall be done in good, substantial and workmanlike manner. All the material shall be new and the best of their respective kinds, except as otherwise expressly allowed by the specifications.

Section 3. The contractor shall employ only competent men and, at the request of the Engineer of Board of Works, shall discharge any man on the work who, in the opinion of the Engineer or said Board, is incompetent, unfaithful or disorderly, and such man shall not be again employed.

Section 4. All work shall be done to the satisfaction of the Engineer and said Board. The amount, quality, acceptability, and fitness of the several kinds of work and materials furnished shall be determined by the Engineer and said Board, who shall have full power to reject or condemn materials furnished and work performed, which in their opinion, does not fully conform to the spirit and terms of this agreement.

Section 5. Work or materials rejected by the Engineer and said Board shall be immediately removed by the Contractor and replaced by other work and materials acceptable to the Engineer and Board.

Section 6. Except by written consent of the said Board, the Contractor shall not have, create, establish or allow any mortgage, mechanics or other lien on any of the tools, appliances, machinery, live stock or materials used or which may be used upon the work, or which are at any time upon the site thereof.

Section 7. Tools, etc, supplied by the City. The Contractor shall become immediately responsible for tools, machinery, equipment, appliances and materials and all other property furnished by the City which are on the ground at the time of the execution of this Contract, and he shall become responsible for all other tools or materials so furnished by the City immediately upon their arrival at the point to which they are to be delivered by the City hereunder; and the Contractor shall thereafter be solely responsible for all loss or damage, and demurrage or similar charges.

Section 8. All tools, machinery, appliances and equipment and unused material furnished by the City to the Contractor shall be protected and kept in good repair by the Contractor, and shall be returned by him to the City on completion or other termination of the work in as good order and condition as when received, except for ordinary wear and tear.

Section 9. Contractor's care of Work. — The contractor shall maintain, protect and care for all the work until its final acceptance by the City and shall at his own expense provide and do whatever may be necessary for such maintenance, protection and care, and shall repair or replace damaged parts of the work and damaged or lost materials to the satisfaction of the Engineer and said Board; and no approval of the work or payment or other act by the City or its Representatives shall release the Contractor from his obligation to make final delivery of the completed work in first-class, sound and perfect condition and free from all debts, liens, obligations and charges of every kind and nature.

Section 10. Contractor not to Assign or Sublet. Except the written consent of the said Board be first obtained, the Contractor shall not assign this Contract, by power of Attorney or otherwise, nor sublet the work, nor any part thereof, nor assign any of the moneys payable under this Contract; nor shall any assignment or subletting relieve the Contractor of any of his obligations hereunder.

Section 11. Payments By Contractor. The Contractor shall pay promptly all for all labor and materials and all liabilities incurred by him, and if and when required shall furnish the City with satisfactory evidence of such payment.

Section 12. Contractor to comply with Laws Ordinances etc. The Contractor shall comply with all building and sanitary laws and all State, County and Municipal laws, rules, Ordinances and regulations.

Section 13. Contractor to provide Roadways. The Contractor shall at his own expense, provide suitable bridges, crossings and roads for the accomodation of travel when the work herein interferes with any public highway or traveled road.

Section 14. Inspection. Representatives of the City may visit and inspect the work at all times during its progress, and the Contractor shall provide sufficient and safe facilities for such inspection.

Section 15. Refuse. The Contractor shall not permit the accumulation of refuse on the site of the work, or at any point contiguous thereto and shall remove the same whenever required by the Engineer or said Board, and on completion of the work shall leave the premises clean to the satisfaction of the Engineer and said Board.

Section 16. Sanitary Regulations. The Contractor shall not do or permit

any act or thing which may pollute the waters of any stream in the neighborhood of the work, he shall keep all buildings and premises in and about the work in a clean and sanitary condition at all times, and shall prevent any waste or unwholesome matter from draining or percolating into any such stream or gulch leading thereto. In case of any of the employes of the Contractor have or are exposed to any contagious disease, prompt and proper medical aid shall be employed, and the patient shall be isolated and all danger of communicating the disease or contaminating the waters of any stream or tributary shall be prevented, and all premises occupied or infected shall be thoroughly and repeatedly disinfected.

Section 17. Foremen on the Work. At all times when the work is in progress the contractor shall employ and keep on the work a foreman or headworkmen, and also a copy of the plans and specifications. Notice or directions given such foremen or headworkmen by or on behalf of the City or the Engineer shall have like effects as if given to the Contractor personally.

Section 18. Contractors Liabilities for personal injuries, etc. The Contractor shall indemnify and save harmless the City from any and all claims, demands, suits, actions proceedings, loss, costs and damages of every kind and description, including attorneys fees, which may be brought or made against the City on account of injury or damage to persons or property, received or sustained by any persons, firms, or corporations by reason of any acts or omissions of the Contractor or his agents or employes, or by reason of any explosives used on said work, or the character of or any defects in methods, materials, ways, work, machinery or tools, or the work itself, or any contingencies arising therefrom.

Section 19. Insurance. The Contractor shall procure and deliver to the City and maintain during the continuance of the work, fire and liability insurance policies in an amount providing an indemnity, and issued by an insurance Company or Companies approved in writing by the City, and insuring both the Contractor and the City.

Section 20. Patent Rights. All Royalties for any patented invention, article or arrangements that may be furnished by the Contractor and used or embraced in the work hereunder shall be paid solely by the Contractor, and the Contractor shall protect and save harmless the said City against any and all claims

sec 20 Cont. demands, proceedings Judgements, and costs, including attorneys fees, on account of any such royalties; and the contractor shall pay all Judgements against the City on account of any thereof before they become enforcible liens against the City's property. Should any suits for infringements of patents be brought against the City before the payments herein provided for, or any of them, are made, the Contractor shall give a bond in an amount with sureties satisfactory to the City, to indemnify the City against Judgements, costs and attorneys fees, before demanding any balance hereunder. Should any injunction be threatened or issued which would or might stop, hinder or delay the work, the contractor shall promptly secure dissolution thereof by giving bond or otherwise, or at the option of the City shall promptly cease the use of the patented article or arrangement complained of.

Section 21, Time for work. The contractor shall begin the work on or before the 18th day of May 1914, the rate of progress shall be such as, in the opinion of the Engineer or said City Board is necessary for completing it on or before the 1st day of August 1914, and the contractor shall finish and complete all the work to be done hereunder on or before the last named date.

Section 22, The time is the essence of this Contract.

Section 23, For each and every day, Sundays and Holidays excluded, that the work shall remain unfinished after said date, the sum of Twenty five Dollars ($25.00) per day shall be paid by the Contractor to the City and may be deducted by the City from any moneys due the Contractor, which sum is hereby agreed upon as liquidated damages for loss to the City on account of expense to the City due to the employment of Engineers, Inspectors and other employees after the expiration of the time for completion, and on account of the value of the operations of the work to be completed hereunder, and other work dependent thereon.

Section 24. Delays, Extension of Time. Should the whole or any part of the work be hindered, delayed or suspended by the Company or by act of God or Casualties, or by the abandonment of the work by the employees through no fault of the Contractor, or other thing, which the Engineer and said Board shall deem sufficient cause, the Contractor shall have a corresponding extension of time, to be determined by the Engineer and said Board, provided

the contractor shall give the City notice in writing of claim for such extension of time within seven days after any such reason therefor shall arise.

Section 25. Payments. For the work, labor, materials and other things done and furnished by the Contractor in place hereunder the City shall pay to the Contractor: $14,400.00

For the Building complete excluding the Crane

For extra excavation per Cubic Yard .15c

" " concrete in footings, foundations, per cu. yd. $7.00

" " Concrete in floors and roof per cu yd. .15

" " reinforcing steel in place per pound. .04

" " brick work in place per thousand $14.00

" " fabricated steel in place per pound .04

(I Beams, Channel Bars, Angle Bars, Etc,

Section 26 Payments thereof shall be made as follows: On or before the Fifth day of each month the Engineer shall make an estimate of the amount and cost at the price herein specified of the work done during the month proceeding, a copy of which, bearing the approval of the Engineer and said Board shall be forwarded to the Contractor; and on or before the tenth day of each month the City shall make a payment to the Contractor of 85% of such estimate.

Section 27. The final Estimate shall be made by the Engineer within 15 days after the completion of all ~~the~~ work, labor material and other things to be done or furnished by the Contractor hereunder, and shall not become due and payable to the Contractor until he has complied with all the provisions hereof and discharged all debts, liens, obligations, claims and charges against said work or him arising out of said work, and made proof thereof satisfactory to the Engineer and Board, if required, that there are no debts, liens, obligations, claims or charges unpaid arising out of said work or for which the City may become liable.

Section 28. The acceptance by the Contractor of the final payment on final estimate shall be conclusive evidence of his acceptance and approval of estimates, accounting, deductions, and full payment by the City for all work, labor, materials and services done or furnished hereunder, and of full satisfaction, discharge

release and waiver of all claims and demands of or on behalf of the Contractor against the City arising out of this Contract and the execution thereof.

Section 29. Extra work, when ordered by the Engineer or Board in writing to be done as extra work, shall be done by the Contractor, and failing such agreement at the actual cost of labor and materials, plus ten per cent., which shall cover supervision, use of tools, appliances and machinery, overhead office and general expenses and profit; and no claims for extra work shall be allowed unless so ordered prior to its commencement, and presented in writing on or before the tenth day of the month following that in which such work was done. Payment therefor shall be made by the City on the regular pay day following receipt by the City's or Engineer's Certificate therefor.

Section 30. Contractor's Books. The Engineer shall have access to the Contractor's books and accounts, if he shall deem it necessary to determine the City's rights or the Contractor's obligations hereunder, or to ascertain any facts relative to any claim against the Contractor or which may become a charge against the City or work.

Section 31. At Contractor's risk. The City does not guarantee the accuracy of plates or borings, nor the position of pipes or other underground objects. The Contractor shall take all risk and responsibility of the fitness or sufficiency of any methods, ways, works, appliances or kind the City may have adopted prior to the execution hereof preliminary to or in aid of the work covered by this contract, and shall inform himself by examination of the conditions of the site of the work.

Section 32. The contractor shall take all risks and responsibilities on account of quick-sands, springs, character and position of bed-rock and the like, and floods, frosts freezing, fires, all action of the elements, casualties, and other difficulties encountered.

Section 33. Time of Delivery by City. The City does not guarantee the time of delivery of tools, machinery, materials or other things, nor the continuity of electric service, but will use its best efforts to meet the needs of the Contractor in deliveries undertaken by it.

Section 34 Change in Plans, etc., by City. The City may make alterations in the line, grade, and minor details of plan, form, dimensions or materials for the work, either before or after the beginning of construction, providing such alterations shall not change the general character of the work as a whole. If such alterations increase the amount of work or materials, such increase shall be paid for according to the quantity of work or materials actually done or furnished, and at the prices and rates fixed herein for such work or materials, if so fixed; otherwise as extra work.

Section 35. Termination of Work by City. The City shall have the right at any time to terminate or suspend all or any part of the work under this contract or to decrease the amount thereof, and in such case the Contractor shall be paid for the work done and materials furnished at the rates of payment fixed hereunder, to be determined by the Engineer and said Board, or, in case of dispute, by arbitrators as hereinafter provided

Section 36. City may take over Work. If the work to be done shall be abandoned by the Contractor, or if this Contract be assigned or sub-let by him, or if he loses control of the work from any cause excepting the acts of God and the public enemy, or if at any time the Engineer shall certify in writing to the City that the Contractor refuses or neglects to provide sufficient and properly skilled or other labor, sufficient materials of proper quality, or fails in any respect to prosecute the work with diligence, or that the rate of progress from whatever cause is not such as to insure its completion within the time specified, or that the work or any part thereof is unnecessarily delayed, or that the Contractor is violating any of the conditions or covenants of this Contract in good faith, the City or not less than three days' written notice to the Contractor, and the surety on his bond, may require the Contractor to discontinue all work or any part thereof, as may be assigned by the City and thereupon the City may take and the Contractor shall deliver possession of the work, and all tools, machinery, teams, implements and machinery on the site thereof, or the part thereof as the City may require, and the City may thereupon complete said work or any part thereof by contract, or may take over the work or any part thereof and employ such labor and obtain such machinery, implements, teams and tools, and purchase such materials, as the Engineer may deem necessary to complete the work

or any part thereof, and in so doing the City may use such tools and machinery, implements, teams and materials as may be found on the site of the work. The cost of doing such work shall be charged to the Contractor, and any moneys that may then be due, or may at any time thereafter become due, to said contractor hereunder or any part thereof, shall apply by the City to the payment of such cost, so far as same shall suffice; and the remainder of the cost of so completing said work shall be paid by said contractor to the City on demand.

Section 37. The City shall not be held to obtain the lowest prices for the work of completing the Contract, or any part thereof, nor for insuring its proper completion, but all sums actually paid therefor shall be chargeable to the Contractor.

Section 38. Damages to Contractor. No damages, direct or consequential nor anticipated profits of the work not actually completed, shall be claimed by or allowed to the Contractor on account of any changes, alterations, or delays in, or suspension, discontinuance or termination of, or taking over or performing, any of the work hereunder by the City.

Section 39. Performance of City by Contractor's Obligations. On failure or refusal by the Contractor to pay any claim against him or the work or arising therefrom and which may become a charge against the City or its property, whether it shall arise or be presented or discovered before or after final payments to the Contractor hereunder, the City, on notice or knowledge thereof, shall withhold the amount thereof from any payments due or to become due to the Contractor hereunder, and on not less than three days notice in writing to the Contractor may pay or settle or compromise any such claim or to do and perform such obligations, and the Contractor shall pay to the City the actual cost thereof on demand, or the same may be deducted from any sums at any time due or to become due by the City to the Contractor.

Section 40 Other Contractors. Incase other contractors or the City are engaged upon or in connection with said work or any part thereof the Contractor shall allow them full access to their work and all proper means for performing the same in connection with his, and shall comply with all the directions of the Engineer with reference to their proper accomodations.

Section 41. Acceptance No Release. Any imperfect or unfaithful work which may be discovered before final acceptance of the work shall be corrected immediately by the Contractor and any unsatisfactory

materials shall be rejected, on the requirement of the Engineer or said Board notwithstanding that they may have been overlooked by the proper inspector. The inspection of the work shall not relieve the contractor of any of his obligations to perform sound work as herein prescribed.

Section 42 Failure or neglect on the part of the Engineer or any of his authorized agents to condemn or reject bad or inferior work or materials shall not be construed to imply an acceptance of such work or materials if it becomes evident at any time prior to final acceptance of the work; neither shall it be construed as barring the City at any subsequent time from the recovery of damages, or of such a sum of money as may be needed to build anew all portions of the work in which fraud was practised or improper materials used whenever found.

Section 43 No Waiver of Rights. Neither the inspection of the City, its Engineer of any of its employes, nor any order, measurement, or certificate by the Engineer, nor any order by the City for the payment of money, nor any payment for, nor acceptance of, the whole or any part of the work by the Engineer or the City nor any extension of time nor any position taken by the City, or its employes, shall operate as a waiver of any provision of the Contract, or of any power herein reserved to the City or any right to damages herein provided; nor shall any waiver of any breach of this Contract be held to be a waiver of any other or subsequent breach. All remedies provided in this contract shall be taken and construed as cumulative: that is, in addition to each and every other remedy herein provided; and the City shall have any and all equitable and legal remedies which it would in any case have.

Section 44. Interpretation; Decision by Engineer. The plans and Specifications are intended to be explanatory of each other. Should any discrepancy, errors or omissions in either appear, or further plans or specifications be required, or any misunderstanding arise or explanations of plans or specifications or of any portion of the Contract be required, the same shall be corrected, furnished or explained by the Engineer, and the effect thereof shall date from the written notice by the Engineer to the Contractor.

Section 45. The Engineer and said Board shall decide every question which may arise between the parties or with other contractors concerning the work, or in and about the execution of this Con-

tract or any of its terms, and their decision shall be final and binding upon both parties except as to such matters as it is agreed herein shall be submitted to arbitration.

Section 46. Definition: Engineer. The word "Engineer" used herein shall mean the consulting Engineer of the City. He may be represented on the work by assistants or inspectors appointed by him who, during any absence of his, shall have and exercise only such powers and authority as he shall delegate in writing. The word "Board" used herein means the Board of Public Works of the City of Fort Wayne.

Section 47. Contractors Bond. The Contractor shall deliver to the City within ten days after the execution hereof, a bond with surety or sureties acceptable to the City in the Sum of Seven Thousand Dollars conditioned upon the faithful performance by the Contractor of all the terms and conditions of this contract, including the payment to the City of all sums for which the Contractor may become liable to the City hereunder. No payment to the Contractor shall become due or payable hereunder until such bond has been executed and delivered, and accepted by the City.

Section 48. Notice to Contractor's Bondsmen. No notice need be given by the City to the surety on the Contractor's Bond of any act or thing hereunder except as herein specifically provided, and lack of such notice to such bondsmen shall be no defense to any action on the Contractor's Bond.

Section 49. This contract expresses all the agreements and understandings between the parties hereto concerning the subject matter, and supersedes all previous contracts, understandings or agreements, whether oral or written, relating hereto.

Section 50 This contract shall bind and insure to the benefit of the heirs, executors, administrators, successors and assigns of the parties hereto, but this provision shall not be taken to modify the restriction against assignment by the contractor hereinbefore contained

In Witness Whereof, the parties hereto have caused their names to be hereunto affixed by their proper officers and the individual parties have affixed their signatures hereto, the day and year first written above.

Mar Immeker
Frank E Singrey
Robert E Kelley
Henry Hilgemann

Section 1 Be it therefore ordained by the Common Council of the City of Fort Wayne that the Contract heretofore on the 16th day of May 1914 entered into by and between the City of Fort Wayne by and through the Board of Public Works and Wayne Irmaher for the construction of an addition to the Electric Light Plant as fully set forth in the preamble hereto be in all things ratified and approved.

Section 2. That this ordinance be in full force and effect on and after its passage and approval by the Mayor.

Wm A. Bayer

Done at the Council Chamber in the City of Fort Wayne, Indiana, this 9th day of June 1914.

We Hereby Certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting, held on the 9th day of June, 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No 655

Wm A Bayer
President

E W Boerger
City Clerk.

Presented to the Mayor for approval on the 11th day of June 1914.

E W Boerger
City Clerk.

Approved this 15th day of June 1914.

Wm J. Hosey
Mayor

General Ordinance No 656.

An ordinance ratifying and approving a contract entered into on the 9th day of June 1914, by and between the City of Fort Wayne, by and through its Board of Public Works and the Herman Dapp Construction Company for the construction of a retaining wall on Spy Run Avenue.

Whereas, on the 9th day of June, 1914, the City of Fort Wayne, by and through its Board of Public Works entered into a contract with the Herman Dapp Construction Company, for the construction by said company of a retaining wall on Spy Run Avenue, which contract is in the following words:

This agreement, made this 9th day of June 1914 by and between the City of Fort Wayne, by and through its Board of Public Works, party of the first part and the Herman Dapp Construction Company party of the second part, Witnesseth:

That in consideration of the mutual covenants herein contained, it is by the parties hereto agreed:

1. That the party of the second part agrees to construct for the party of the first part the Two Three hundred and seventy lineal feet (370) of the retaining wall on Spy Run Avenue, in the manner of the materials and as set forth in the plans and specifications on file in the office of the Board of Public Works of said City and signed by the parties hereto for identification, which said plans and specifications are made a part hereof the same as if fully copied herein.

2. That in consideration therefore the party of the first part agrees to pay to the party of the second part for said work the following sums of money:

Excavation for wall foundation per cubic yard	$2.10
Plain concrete for wall, " " "	6.10
Hardwood sheet piles, per thousand feet, Board measure	60.00

as follows:

Eighty per cent (80%) of the engineers monthly estimate of the value of material and labor at time of estimate and balance on final acceptance by the Board of Public Works.

It is understood that this contract is to be ratified and approved by the Common Council of said City and that it is executed with the understanding that the Board of County Commissioners of Allen County, Indiana, execute to the party of the second part a contract for the construction of the south one hundred and eighty feet (180) of said wall.

Witness our hands and seals this 9th day of June, 1914.

City of Fort Wayne, By
Frank C. Singsey
Robert E. Kelly
Henry Kilgemain
Board of Public Works

The Herman Papp Construction Company, By Herman H. Papp Pres.

Section 1 Therefore Be It Ordained by the Common Council of the City of Fort Wayne, that the contract heretofore entered into on the 9th day of June 1914 by and between the City of Fort Wayne, by and through its Board of Public Works, party of the first part and the Herman Papp Construction Company, party of the second part, for the construction by said Company of a retaining wall on Spy Run Avenue, as fully set forth in the preamble hereto be and the same is in all things approved and ratified. Frank J. Schlebecker

Done at the Council Chamber in the City of Fort Wayne this 23d June 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting held on the 23d day of June 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 656.

Wm A. Bayer Pres. G W Boerger City Clerk.

Presented to the Mayor for approval on the 26th day of June 1914

G W Boerger
City Clerk

Approved this 26th day of June 1914
Wm J. Hosey
Mayor

General Ordinance No 657.

An Ordinance extending the City Limits and annexing a certain territory to the City of Fort Wayne, Indiana, and making the same a part of the Tenth (10) Ward.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the territorial limits of the City of Fort Wayne Indiana, be and hereby extended as follows:-

Commencing at the intersection of the center line of Pontiac Street, with the Center line of Alexander Street, thence South on the center line of Alexander Street to its intersection with the present City limits line, thence East on the present City limits line to the center line of Abbott Street, thence North on the Center line of Abbott Street to the center line of Pontiac Strat, thence West on the center line of Pontiac Street to the place of beginning.

Section 2. This ordinance to be in full force and take effect from and after its passage, approved by the Mayor and Legal Publication.

V. J. Korte.

Done at the Council Chamber in the City of Fort Wayne, Indiana, this 14th day of July, 1914.

We hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting, held on the 14th day of July, 1914, by a majority vote of all the members elect did pass the ordinance hereunto attached, and known as General Ordinance No 657.

Wm C Bayer
President.

G W Boerger
City Clerk.

Presented to the Mayor for approval on the 17th day of July, 1914.

G W Boerger
City Clerk

Approved this 17th day July, 1914.

Wm J Hosey
Mayor

General Ordinance No 658.

An Ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne and E. D. Etnyre and Company, on the 26th day of May 1914.

Whereas, on the 26th day of May 1914, the City of Fort Wayne, by and through its Board of Public Works, entered into a contract with the E. D. Etnyre and Company, providing for the manufacture and delivery to said City of one motor truck power street flusher and road oiler, including self-filling equipment, which contract is as follows:-

This agreement, made this 26th day of May, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, party of the first part, and E. D. Etnyre and Company, party of the second part, Witnesseth:-

That in consideration of the payment by the party of the first part to the party of the second part, as hereinafter provided, the sum of forty-four hundred dollars ($4,400.00) the party of the second part hereby agrees to sell and deliver to the party of the first part one motor truck power street flusher and road oiler, including self filling equipment, according to specfications furnished by party of the second part attached hereto and made a part hereof, and according to advertisement for proposals, dated May 8th of the party of the first part, which advertisement is hereby made a part hereof and is attached hereto.

Party of the second part guarantees said flusher, oiler and all equipment to be of first class material and workmanship and agrees to replace, for a period of ninety (90) days, all defective workmanship of materials so as to make said flusher, oiler and equipment comply with the terms hereof.

Gearing to be red and tank green, with the words "Board of Public Works, Street Cleaning Department," printed on tank.

Party of the second part agrees to furnish cab top of standard size, material and workmanship.

Flush nozzle to be arranged in front of machine and one flush nozzle on right hand side in front of rear wheel.

Said flusher, oiler and equipment, complete, to be delivered to party of the first part, in the City of Fort

Wayne on or before the first day of July, 1914. Strikes, unavoidable accidents and unusual delays out of control of second party excepted, and at time of delivery, to furnish, without cost to City, a man to demonstrate said flusher and oiler, which is to comply with the requirements thereof and of said specifications, and to perform the work for which the same is intended. Said man so furnished by party of the second part to continue for three days, and longer if necessary, to instruct said employes in the use of said machine and within ten (10) days after successful demonstrating, party of first part to pay to party of the second part said sum of forty four hundred dollars ($4,400.00).

Witness our hands and seals the day and year first above written.

City of Fort Wayne, By
Frank E Singrey
Robert E Kelley
Henry Hilgeman
Its Board of Public Works.
E. D. Etnyre Company By
E. D. Etnyre.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that the contract heretofore entered into on the 26th day of May, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works and E. D. Etnyre and Company as fully set forth in the preamble hereto attached, be and the same is in all things ratified and approved.

Section 2. This ordinance to be in full force and take effect from and after its passage and approval by the Mayor.

C. O. Lepper

Done at the Council Chamber in the City of Fort Wayne, Indiana this 14th day of July 1914.

We hereby Certify, that the Common Council of the City of Fort Wayne, Indiana at a Regular Meeting held on the 14th day of July, 1914, by a majority vote of all Members elect, did pass the ordenance hereunto attached and known as General Ordinance No. 6558.

Wm A. Bayer, President
G M Boerger. City Clerk

Presented to the Mayor for approval on the 17th day of July 1914

G M Boerger. City Clerk.

Approved this 18th day of July, 1914.

Wm J Hosey,
Mayor

General Ordinance No 659.

An order giving the Controller the power to loan the Park Board, Money from the General Fund.

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana that the Controller is hereby authorized to loan the Park Board a sum of money not exceeding $12,000.00 which is to be refunded to the General Fund by the taxes which will be due the Park Board from the Fall payments of Taxes. This loan only to be for the period from July 1, 1914 to December 31, 1914.

Section 2 That this ordinance be in full force and effect on and after its passage and approval by the Mayor.

Wm A. Bayer

Done at the City Council Chamber in the City of Fort Wayne, Indiana this 28th day of July 1914.

We Hereby Certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 28th day of July 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as Special Ordinance No 659.

Wm A Bayer
President

E V Boerger
City Clerk.

Presented to the Mayor for approval on the 30th day of July 1914

E V Boerger
City Clerk

Approved this 7th day of August, 1914.

Wm J Hosey
Mayor

General Ordinance No 660

An Ordinance Regulating the Storing and Handling of Manure

Section 1. Be it Ordained by the Common Council of the City of Fort Wayne, that every person, firm, or corporation, owning or occupying any building, or part of building, within the Corporate Limits of the City of Fort Wayne, where one or more horses, mules, or cows, or similar animals are kept, shall maintain in connection therewith a bin, pit or other suitable receptacle for the reception of manure, and, pending the removal from the premises of the manure, from the animal or animals aforesaid, shall place such manure in said bin, pit or other suitable receptacle, and shall not allow the same to be over-filled or uncovered. The bin or pit or other suitable receptacle required by this ordinance shall be so constructed as to exclude rain water, and shall in all other respects be water tight except as it may be connected with a public sewer; and shall be provided with a suitable cover constructed so as to prevent the ingress and egress of flies.

Section 2. Every person, firm or corporation, having the use of any bin, pit or any other suitable receptacle for manure, and every person keeping manure, shall cause all such manure to be removed from the premises at least twice every week between June 1st and October 31st, inclusive, of each year, and at least once every week, between November 1st of each year and May 31st of the following year, both dates inclusive.

Section 3. No person who has removed manure from any bin, pit or other receptacle, or any place manure has been accumulated, shall deposit such manure in any place within the corporate limits of the City of Fort Wayne.

Section 4. Every person, firm or corporation, using within the corporate limits of the City of Fort Wayne any building or part of a building, as a stable for one or more horses, mules or cows, shall report that fact to the Department of Public Health in writing within 30 days after this ordinance takes effect, giving his, her or its name, and the location of such stable; and thereafter every person, firm or corporation occupying any building, or any portion of a building within the corporate limits of the City of Fort Wayne for the purpose aforesaid, shall report in like manner, his, her or its name and the location of said stable, within five days after the beginning of such occupancy of said building.

Section 5. Any person violating or failing to comply with the provisions of this ordinance shall be fined in any sum not exceeding One Hundred Dollars ($100.00.

Section 6. That this Ordinance be in full force and effect on and after its passage, approval by the Mayor and legal publication.

C. O. Lesper
Robt John

Done at the Council Chamber in the City of Fort Wayne, Indiana this 28th July 1914

We Hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Session, held on the 28th day of July 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No 660.

Wm A Bayer, President E M Boerger City Clerk

Presented to the Mayor for approval on the 30th day of July, 1914

E M Boerger City Clerk

Approved this 7th day of August, 1914

Wm J Hosey. Mayor

General Ordinance No 661.

An Ordinance authorizing the alienation of certain personal property.

Section I Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the Mayor be, and is hereby authorized to sell certain scrap brass and iron and other scrap metal now owned by the City under the Electric Light and Water Works Departments. Provided that such sale shall not be made, until said property has been appraised by appraisers appointed by the Judge of the Allen Circuit Court. Provided, however that such appointment may be made by said Judge in Chambers.

Section II That the City Attorney be and he is hereby authorized to petition the judge of the Allen Circuit Court for the appointment of three (3) appraisers to appraise the property referred to in Section I of this Ordinance

Section III That this Ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication

Frank J. Edelbecker.

Done at the Council Chamber in the City of Fort Wayne Indiana, this 28th day of July, 1914.

We, hereby Certify, That the Common Council of the City of Fort Wayne, Indiana at a Regular meeting, held on the 28th day of July, 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordenance No 661

Wm A Bayer
President.

G W Boerger
City Clerk

Presented to the Mayor for approval this 30th day of July, 1914.

G W Boerger
City Clerk

Approved this 7th day of August, 1914.

Wm J Hosey
Mayor

General Ordinance No 662

An Ordinance authorizing the Board of Public Health to employ one additional Sanitary Policeman and fixing the salaries of all Sanitary Police

Section I Be it Ordained by the Common Council of the City of Fort Wayne, Indiana, that the Department of Public Health be and the same is hereby authorized to employ one additional sanitary police officer upon the taking effect of this ordinance.

Section II That each Sanitary Police Officer under the control of the Department of Public Health receive a salary at the rate of Eight Hundred and Forty Dollars per annum ($840.00).

Section III That this Ordinance be in full force and take effect on and after its passage and approval by the Mayor and legal publication.

C. O. Lepper.

Done at the Council Chamber in the City of Fort Wayne, Indiana this 28th day of July, 1914.

We hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting, held on the 28th day of July 1914, by a majority of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No 662.

Wm A Bayer
President

E W Boerger
City Clerk

Presented to the Mayor for approval this 30th day of July 1914.

E W Boerger
City Clerk

Approved this 7th day of August 1914

Wm J Hosey
Mayor

General Ordinance No 663.

An ordinance amending Section 1. of General Ordinance #132, being an ordinance entitled "An ordinance prohibiting traction and other engines or boilers from being propelled over and along certain streets of the City of Fort Wayne and providing penalties for the violation thereof."

Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that Section 1. of General Ordinance #132, being an ordinance entitled "An ordinance prohibiting traction and other engines or boilers from being propelled over and along certain streets of the City of Fort Wayne and providing penalties for the violation thereof" be and the same is hereby amended to read as follows:

"Section 1. Be it ordained by the Common Council of the City of Fort Wayne, that it shall be unlawful for any person, firm or corporation to propel or move, or cause to be propelled or moved over and along any street or alley within the limits of said City, any traction or other engine and boiler unless the tires of the wheels thereon are smooth; Provided, that this Ordinance shall not be construed to prevent the use of steam rollers or other apparatus, employed under contract by the City of Fort Wayne, for the improvement or repair of any street or alley of said City, and, provided further that this ordinance shall not apply to or be held to limit, modify or prevent the use of steam fire engines or other apparatus employed by the City of Fort Wayne in connection with any department of public service."

Section 2. That this ordinance to be in full force and effect from and after its passage, legal publication and approval by the mayor.

J. B. Mills

Done at the Council Chamber of the City of Fort Wayne this 11th day of August 1914.

We hereby certify, that the Common Council of the City of Fort Wayne, Indiana, at a regular meeting held on the 11th day of August 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 663.

Wm A. Bayer President E. N. Berger City Clerk

Presented to the Mayor for approval on the 14th day of August 1914.

E. N. Berger City Clerk

approved this 20th of August 1914

Wm J. Tuley

Mayor.

General Ordinance No 664.

An Ordinance amending Section 2, Section 6, and repealing Section 5 of General Ordinance #626 being an Ordinance entitled "An Ordinance regulating the installation of service lines and meters for electric current," passed by the Common Council on November 11, 1913.

Section I. Be it ordained by the Common Council of the City of Fort Wayne, that Section 2 of General Ordinance #626 being an ordinance entitled "An Ordinance regulating the installation of service lines and meters for electric current," passed by the Common Council on November 11, 1913 be amended to read as follows: Section 2. In the future in the wiring of new buildings, rewiring of old buildings and in the installation of new wires in old buildings or additions thereto, all service wires supplying electric current within the limits of the City of Fort Wayne shall be enclosed in approved rigid iron conduit from the point of entrance of service wires to the service cabinet. Where wires leave the service cabinet at meter centers a meter loop not less than two (2) feet shall be provided.

If the electric meter is located on the outside of the building or under a protected roof or porch, approved riged iron conduit shall be run on the outside of the building from the point of attachment or connection of service wires to the meter centers; and where mete is located on inside of the building the conduit shall turn into building at a point not above the first floor of the consumer's premises.

At the entrance end of the service conduit there shall be provided a suitable conduit and at the service end the conduit shall be provided with a suitable cabinet, fusible main line switch."

Section II. That Section six (6) of General Ordinance #626 is hereinbefore fully referred to be amended to read as follows: Section 6. "There shall be installed at meter centers a suitable meter board for each separate meter which shall not be less than fourteen (14) inches long, ten (10) inches wide and seven eighths (7/8) of an inch thick, the long dimension to be placed vertically.

Section III That section five (5) of General Ordinance #626 as hereinbefore fully referred to and described, is hereby repealed.

Section IV That this ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

C. O. Lepper

Done at the Council Chamber of the City of Fort Wayne this 18th day of August 1914

OVER.

I, hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Session, held on the 11th day of August, 1914 by a majority vote of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No 664.

Wm A. Bayer
President.

G W Boerger
City Clerk.

Presented to the Mayor for approval on the 14th day of August 1914.

G W Boerger
City Clerk.

Approved this 20th day of August 1914.

Wm J Hosey
Mayor.

General Ordinance No 665.

An Ordinance regulating peddlers vendors and hawkers and requiring the use by them of scales on vehicles used for the sales of any commodity, and providing penalties for its violation.

Section I. Be it Ordained by the Common Council of the City of Fort Wayne, that all peddlers, vendors, and hawkers peddling, vending, or hawking goods, wares, provisions or merchandise over and upon the streets of said City shall have hung, at all times, on the end of the vehicle from which such goods, wares, provisions or merchandise are sold, a circular spring balance scale of not less capacity than thirty (30) pounds by one (1) ounce, and equipped with a galvanized iron scoop open at one end, which said scale shall bear the seal of the State Inspector of Weights and Measures.

Section II. That all peddlers, vendors, or hawkers selling any goods, wares, provisions or merchandise upon the streets of said City shall sell by weight whenever demanded by any purchaser, all commodities peddled or hawked by them, excepting liquids and commodities customarily sold by numerical count.

Section III. That any person, company, or corporation violating or failing to comply with the provisions of this ordinance shall be fined not less than five dollars ($5.00), nor more than $25.00 Twenty-Five Dollars, and on any second or subsequent conviction for the violation or failure to comply with any of the provisions hereof, the license of such peddler, vendor or hawker shall be by the Mayor of said City revoked.

Section IV. That this Ordinance be in full force and effect on and after its passage, approval by the Mayor and legal publication.

Done at the Council Chamber in the City of Fort Wayne Indiana this 11th day of August 1914.

We hereby certify, That the Common Council of the City of Fort Wayne Indiana, at a Regular Meeting, held on the 11th day of August 1914 by a majority vote of all the members elect, did pass the ordinance known as General Ordinance No 665.

Wm U. Bayer President E M Boerger City Clerk.

Presented to the Mayor for approval on the 14th day of August 1914.

E M Boerger
City Clerk

Approved ~~by~~ this 20th day of August, 1914

Wm J Bosey
Mayor

General Ordinance No 666.

Whereas, Henry W. Becker was appointed, on June 21, 1909 by the then Board of Public Works of the City of Fort Wayne as Clerk in the Fort Wayne Municipal Electric Light and Power Department, at a salary of sixteen dollars sixty-six and two-thirds cents ($16.66⅔) per month, with the understanding that the work to be performed by the said Becker to the said Electric Light Works was to be in addition to the work performed by him as Clerk to said Board of Public Works, and

Whereas, the said Henry Becker, in addition to his unusual heavy duties as clerk to said Board, did from the 21st day of June, 1909 to the first day of January, 1914, act as clerk in said Light and Power Department and did perform services that were reasonably worth sixteen dollars sixty-six and two-thirds cents ($16.66⅔) per month, and

Whereas, through some misunderstanding the said salary that said Board agreed to pay said Becker for said services from time to time was not paid, and said services were accepted and the said employment ratified by the different Boards during the term of the employment as hereinbefore set out, which salary now due said Becker amounts to nine hundred dollars ($900.00), and

Whereas, the present Board of Public Works of said City, recognizing the fact that the salary so fixed by the Board of Public Works on June 21, 1909 should have been paid to the said Henry W. Becker from time to time, did on the ___ day of July, 1914 adopt a resolution, which is set out in the minutes of its said meeting, wherein it was resolved that the said salary so fixed was fair and just and that the said sum of Nine Hundred Dollars ($900.00) should be paid to the said Henry W. Becker when and after the same was approved by an ordinance of the Common Council now therefore

Section I Be it Ordained by the Common Council of the City of Fort Wayne, that the Board of Public Works of said City operating the Municipal Electric Light and Power Works be and they are hereby empowered and authorized to pay to said Becker out of the funds of said Light and Power Department the sum of Nine Hundred Dollars ($900.00) immediately in payment for the services rendered by said Henry W. Becker, as Clerk in said Light and Power Department from June 21, 1909 to January 1, 1914 at the rate of sixteen dollars and sixty-six and two-thirds cents ($16.66⅔) per month.

Section II This Ordinance to be in full force and take effect from and after its passage and approval by the Mayor and Legal Publication.

Done at the Council Chamber in the City of Fort Wayne this 10th day of August, 1914.

Frank J. Schlebecker

We hereby Certify That the Common Council of the City of Fort Wayne, Indiana, at a regular meeting, held on the 11th day of August, 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No 666.

Wm A Bayer
President

E W Boerger
City Clerk

Presented to the Mayor for approval this 14th day of August, 1914.

E W Boerger
City Clerk.

Approved this 24th day of August, 1914.

Wm D Hozey
Mayor.

General Ordinance No 667.

An Ordinance fixing the tax levy for city purposes for the year 1915.

Section I. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that a levy of One Dollar and Sixteen Cents ($1.16) on Each One Hundred Dollars ($100.00) of assessed valuation of all property within the corporate limits of the City of Fort Wayne, Indiana be made for the year 1915. That the above levy be divided as follows:-

Appropriation Account	$ .855
Park Fund, General Expenses	.085
Park Fund Park Music	.005
Sinking Fund	.05
Track Elevation Fund	.10
Garbage Plant Fund	.03
Playground Fund.	.0125
Policemen's Pension Fund	.01
Firemen's Pension Fund	.01
Interest Fund	.0025
	$ 1.16

Also that there shall be collected from each male inhabitant liable according to law a poll tax of $2.00.

Section II. That all taxes shall be collected in semi annual installments.

Section III. This Ordinance shall be in full force and effect on and after its passage and approval by the Mayor.

Wm A Bayer

Done at the Council chamber in the City of Fort Wayne, Indiana, this 25th day of September, 1914.

We Hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Session, held on the 25th day of August, 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No 667.

Wm A Bayer
President.

G W Boerger
City Clerk

Presented to the Mayor for approval on the 28th day of August, 1914.

G W Boerger
City Clerk

Approved this 29th day of

General Ordinance No 668.

An Ordinance ratifying and approving a contract entered into by and between the City of Fort Wayne, Indiana, by and through its Board of Public Works, and Olds Coal Company, providing for the furnishing of a year's supply of coal for the City Crematory.

Contract and Bond.

This agreement made and entered into this 14th day of August, 1914, by and between the City of Fort Wayne, Indiana, by and through its Board of Public Works, party of the first part, and Olds Coal Company, doing business under the firm name of the Olds Coal Company, party of the second part, witnesseth:-

The party of the second part agrees to deliver to the party of the first part 1000 Tons or more of Pittsburg No 8. coal, mine run, to be delivered in approximate even quantities, monthly, for which the party of the first part agrees to pay to the party of the second part One dollar and seven Cents ($1.07) per ton F. O. B. mines.

Said City to buy from said Company all of the coal used by it at its crematory during said period of the time so long as the kind, quality and quantity is satisfactory to said Board of Public Works, and the same to be shipped and billed on flat bottom cars direct from the mines to said City at its crematory on the L. S. & M. S. unless otherwise directed by the Board; said City to pay all freight on the coal purchased by it, and it is understood and agreed that the freight shall not exceed One dollar and thirty-five Cents ($1.35) but if lower rates can be obtained by the party of the second part, then said City shall pay no more than the actual freight rates so obtained. If the rate is increased the City shall pay the same.

It is mutually agreed and understood between the parties hereto that payments by the first party shall be made to second party on or before the 15th day of every month, based upon invoice rates on all coal delivered as aforesaid during the month previous thereto. The strict performance of this contract by the party of the second part and prompt deliveries of coal herein on cars at said mines as aforesaid shall be subject to delays occassioned by strikes, accidents, and other unavoidable temporary casualties in the operation of said mines and want of car supply and failure of railway companies to deliver and place cars at the mines for loading, or other causes beyond control of the said party of the second part.

It is further agreed between the parties hereto that after the delivery of said coal on board of said cars by said party of the second part, said party, at the request of the first party and as the agent of the party of the first part, will use its best endeavors with the carriers to have said cars of

coal delivered as aforesaid. billed and sent forward promptly to destination.

The prices made in this contract are based upon the present mining rate and shall advance or decline during the period of this contract.

All freight rates over and above that mentioned in this contract shall be paid by the party of the second part.

This contract shall not be binding or take effect until the second party shall execute to the party of the first part a bond in the sum of One Thousand Dollars ($1000.00) with sufficient surety thereon, to be approved by the mayor and city controller of party of first part, and conditioned for the faithful performance by the party of the second part of all terms, conditions and agreements herein to be performed by it, and until this contract has been ratified and approved by the Common Council of said City.

Witness our hands and seals this 14th day of August 1914.

City of Fort Wayne, Indiana
By. Frank Singrey
Robert Kelley

Attest D. W Becker

Board of Public Works.
Olds Coal Company
By W E Olds, Treasurer

Section I. Be it Ordained by the Common Council of the City of Fort Wayne, Indiana, that the Contract entered into on the 14th day of August 1914 by and between the City of Fort Wayne, through its Board of Public Works, and Olds Coal Company, as more fully set out in the preamble hereto, be and the same is in all things ratified and approved.

Section II This ordinance to be in full force and effect on and after its passage, approval by the Mayor and Legal Publication.

Jacob Hartman.

Done at the Council Chamber of the City of Fort Wayne, Indiana this 8th day of September

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting held on the 8th day of September 1914 by a majority vote of all Members elect, did pass the Ordinance hereto attached and known as General Ordinance No 666.

Wm A Boyer President
G W Boerger City Clerk

Presented to the Mayor for Approval this 10th day of September 1914
G W Boerger City Clerk

Approved this 14th day of September 1914
W J Hosey
Mayor

General Ordinance No 669

An Ordinance authorizing the alienation of certain property and ordering an appraisement of same.

Section I Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the Mayor be and he is hereby authorized to sell a certain dwelling house, barn and other real fixtures located and situated on Lot No 1, Felts Amended Addition, formerly belonging to William and Martha Orr and condemned and appropriated by the City under Declaratory Resolution No 264, providing for the opening of Beaver Avenue from Broadway to Home Avenue in said City; that the Mayor be authorized to sign any and all necessary instruments to consumate such sale, providing such sale shall not be made until said property shall be appraised by the Appraisers appointed by the Judge of the Allen Circuit Court; that the money received from the sale of said property is to be placed in the Street Special Fund.

Section II That the City Attorney be and he is hereby authorized to petition the Judge of the Allen Circuit Court for the appointment of three (3) Appraisers to appraise the property referred to in Section One (1) of this Ordinance.

Section III This Ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

J. B. Mills

Done at the Council Chamber of the City of Fort Wayne, Indiana this 13th day of October, 1914.

We hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 13th day of October 1914, by a majority vote of all the Members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No 669.

William A Bayer
President

E M Boerger
City Clerk.

Presented to the Mayor for approval on the 15th day of October 1914

E M Boerger
City Clerk

Approved this 21st day of October, 1914
William J Hosey

General Ordinance No. 670.

An Ordinance concerning the removal of the habitation of Lanichies and other persons in the City of Fort Wayne, and providing penalties for the violation of said Ordinance

Section I. Be it ordained by the Common Council of the City of Fort Wayne, that hereafter all draymen and other persons who remove or assist in removing any family or person into any room or building in said City shall, on Monday morning of each week file with the Superintendent of Police of said City a statement containing every such transaction of previous week, giving the name of persons or family so removed, from where and to where removed, giving the street and number of the building from which and to which such removal takes place, and the date of such removal, which shall be entered upon cards provided for that purpose by the Superintendent of Police, and signed by the draymen or other person engaged in such removal

Section II. Any person failing or refusing to comply with the provision of this Ordinance, shall upon conviction thereof, be fined in any sum not less than five dollars nor more than ten dollars with cost of prosecution.

Section III. This Ordinance to be in full force and effect from and after its passage, approval by the Mayor and legal publication.

J. B. Wells.

Done at the Council Chamber in the City of Fort Wayne, Indiana on the 10th day of November, 1914.

We hereby certify that the Common Council of the City of Fort Wayne Indiana at a Regular Session, held on the 10th day of November, 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached and known as General Ordinance No 670.

Wm A Bayer
President

G W Boerger
City Clerk

Presented to the Mayor for approval on the 13th day of November, 1914.

G W Boerger
City Clerk

Approved this 23rd day of November, 1914.

Wm J Hosey
Mayor

General Ordinance No 671.

An Ordinance fixing the salary of the Superintendent of Streets.

Section I. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, That the Superintendent of Streets receive a salary at the rate of fifteen hundred dollars ($1500.00) per annum.

Section II. That this ordinance be in full force and take effect on and after January 1-1915, legal publication and approval by the Mayor.

Charles E. Welch.

Done at the Council Chamber in the City of Fort Wayne, Indiana on the 8th day of December 1914.

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting, held on the 8th day of December, 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No. 671.

E B Smith
Vice President.

G W Boerger
City Clerk

Presented to the Mayor for approval on the 14th day of December, 1914.

G W Boerger
City Clerk.

Approved this 16th day of December, 1914

Wm J Hosey
Mayor

General Ordinance No 672.

An Ordinance fixing the Salary of the Clerk of of the Health Department.

Section I. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the salary of the clerk of the Health Department be fixed at the sum of fifty-five dollars ($55.00) per month, and that the Department of Health be and the same is authorized to pay the same.

Section II. This ordinance shall repeal all parts of any Ordinances in conflict herewith.

Section III. That the ordinance be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

A. N. Keller

Done at the Council Chamber in the City of Fort Wayne, Indiana, this 8th day of December 1914.

A. N. Keller.

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular Meeting held on the 8th day of December, 1914, by a majority vote of all the members elect, did pass the Ordinance hereunto attached and known as General Ordinance No. 672.

E B Smith
Vice President.

G W Boerger
City Clerk

Presented to the Mayor for approval this 14th day of December 1914

G W Boerger
City Clerk

Approved this 16th day of December 1914

Wm J Hosey
Mayor

General Ordinance No. 673.

An Ordinance authorizing the sale of house and other buildings and property on the East Twenty (20) feet of lot number eleven (11) in Ewing's Sub-division.

Whereas the City of Fort Wayne, appropriated the East twenty feet (20) of lot number eleven (11) in Ewings Sub-division for the extending and widening of Sherman Street and upon which said Twenty (20) feet there are located a residence and other buildings and improvements which belong to said city by reason of said judgement and

Whereas the value of said buildings is greatly in excess of one hundred dollars ($100.00), now therefore.

Section I. Be it Ordained by the Common Council of the city of Fort Wayne, that said buildings be and the same are hereby ordered sold and the City Attorney be and he is hereby ordered and directed to cause proceedings to be instituted for the appraising of said property.

Section II. That this ordinance be in full force and take effect from and after its passage, approval by the Mayor and legal publication.

C. O. Lepper.

Done at the Council Chamber in the City of Fort Wayne this 22nd day of December 1914.

We hereby Certify, that the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 22nd day of December, 1914, by a majority vote of all the members elect did pass the ordinance hereunto attached and known as General Ordinance No. 673.

Wm A. Bayer
President

D. W. Boerger
city clerk.

Presented to the Mayor for approval on the 29th day of December, 1914.

D. W. Boerger
city clerk

Approved this 2nd day of January 1915

Wm J. Hosey
Mayor.

General Ordinance No. 674.

An ordinance approving a contract entered into by and between the City of Fort Wayne, Indiana by and through its Board of Public Works and the Walter Bledsoe and Company by an through its Secretary, on the 1st day of December 1914. relative to the purchase of part of the coal supply for the Fort Wayne Municipal Electric Light and Power Works during the year of 1915. Whereas, Heretofore on the 1st day of December 1914 the City of Fort Wayne entered into a contract with the Walter Bledsoe and Company, providing for the purchase of coal by said city, which contract is as follows

Contract.

This agreement, made and entered into by and between the City of Fort Wayne, Indiana, by and through its Board of Public Works, hereinafter called the "Consumer" and Walter Bledsoe and Company hereinafter called the "Company" Witnesseth, That

Whereas, it is desired by the parties hereto to enter into a contract of purchase and sale of coal as herein set forth;

Now Therefore, in consideration of the mutual covenants and agreements herein contained, the parties hereto do hereby agree as follows;

The Company agrees to sell to the Consumer, and the consumer hereby agrees to buy from the Company, coal for consumption during the term of this contract, for the Fort Wayne Electric Light and Power Works, located in the City of Fort Wayne, Indiana, the consumer agreeing to purchase not less than five thousand (5,000) tons and the company agreeing to furnish not more than seven thousand (7,000) tons; said coal to be delivered as ordered in equal weekly shipments estimated at two (2) cars per week; said delivery to continue until December 31, 1915, with the understanding that the city shall have the right to have said deliveries continue until April 1st, 1916 or until December 31st, 1916, provided that said city shall give to said company sixty (60) days notice before the termination of this contract, of its desire to so extend the same.

The company further agrees to furnish coal herein contracted for, in the grade and in such quantities and delivered to the consumer f.o.b their tracks, Fort Wayne, Indiana, at such times as ordered by the consumer from time to time during the term of this contract, of the kind of coal

described below,

The Kind of coal shall be 1¼ inch Run screenings, said coal to be mined from Geological vein Known as Harlan Straight Creek Seam. The coal originating on the L & N Railroad in Harlan County, Kentucky.

The consumer hereby agrees to pay the said company on the 10th day of the calendar month for all shipments made to the consumer during the previous month, a price of fifty-five cents (.55) per net ton, F.O.B. mines, to which shall be added one-dollar and sixty cents ($1.60), the present freight rate, subject to increase and decrease in freight rate as hereinafter stated. Said coal to be delivered by the company to the consumer on their tracks at Fort Wayne, Indiana. The coal heretofore described and to be furnished hereunder to be of the following analysis

Moisture	2%	
Ash	6%	(Specified Analysis)
B.T.U. (Per pound dry)	13800	

The company hereby agrees that for each unit of 200 BTU wherein the coal falls below the specified analysis, a reduction shall be made by the consumer at the rate of three (3) cents per ton, and for each unit of two (2) per cent in which the coal contains more ash than specified, a reduction shall be made at the rate of three (3) cents per ton

It is understood and agreed that all coal shipped on this contract shall be loaded in self-clearing hopper cars and the company hereby agrees to allow the consumer to make a reduction of ten cents per ton on any shipments made in other than hopper equipment.

It is agreed that when as a result of an act of Providence or of a strike or strikes at the mines or on the rail-road, it is impossible for the company to deliver coal hereunder, the obligations of delivery and acceptance of coal shall cease until such strikes are over or delivery of coal can again be made, provided the company notifies the consumer in writing of such probable inability to deliver coal as soon as the company first has Knowledge of such probable inability.

It is further agreed that when such strikes are over or delivery of coal can again be made, the rights and duties of the parties hereto shall be the same as before cessation of deliveries occurred.

It is further agreed that if during the term of this contract there be an increase or decrease in either the miners' wage scale at the mine or mines from which the contract coal is being

produced, or in the freight rate from the same mine or mines to the consumer's plant, the delivered value of the coal thereafter sold under this contract shall be correspondingly increased or decreased.

It is hereby understood and agreed that railroad weights shall govern all settlements made in accordance with the terms of this contract.

Should the company fail to deliver coal in accordance with the terms of this contract, the consumer may purchase on the open market such an amount or amounts of coal as the said company shall fail to deliver, in which event all cost hereunder of an equivalent amount of coal of corresponding grade, shall be borne and paid by said company.

The term of this contract shall be from January 1, 1915 to and including the 31st day of December, 1915, and said contract shall neither be effective nor binding upon the parties hereto, until the company shall execute to the consumer a bond to the amount of Three Thousand ($3000.00) dollars, said bond to have approval of the consumer for the proper and faithful performance of the terms, conditions and agreements of the contract.

The said company agrees to execute, within ten (10) days hereafter, a bond with a surety company as surety thereon, in the sum of Three Thousand dollars to be approved by the Board of Public Works of said city.

In witness Whereof, the parties hereto have hereunto set there hands and seals at Fort Wayne, Indiana, this 1st day of December, 1914.

City of Fort Wayne, Indiana, By
Frank E. Singrey
Robert E. Kelly,
Henry Hilgeman
Its Board of Public Works.

Attest
J. Wesely.

Walter Bledsoe and Company, by
Otto Gumbert Secy.

Section 1 Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the contract heretofore entered into on the 1st day of December 1914 by and between the city of Fort Wayne by and through its Board of Public Works and the Walter Bledsoe and Company, a corporation of Indianapolis, Indiana

as more fully set out in the preamble hereto, be and the same is in all things ratified and affirmed.

Section II This Ordinance to be in full force and to take effect after its passage by the Mayor and Legal Publication.

Frank J. Gehlhausen.

Done at the Council Chamber in the City of Fort Wayne this 22nd day of December, 1914.

We hereby Certify that the Common Council of the city of Fort Wayne, Indiana, at a Regular meeting, held on the 22nd day of December 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 674.

Wm A. Bayer
President.

H. W. Boerger
city clerk.

Presented to the Mayor for approval on the 29th day of December, 1914.

H W Boerger
city clerk.

Approved this 2nd day of January 1915,

Wm J. Hosey
Mayor

General Ordinance No. 675.

An Ordinance approving a contract entered into by and between the city of Fort Wayne, Indiana, by and through its board of Public Works and Lindley Schmid Company, by and through its secretary, on the 1st day of December, 1914 relative to the purchase of part of the coal supply for the Fort Wayne municipal electric light and power works during the year of 1915.

Whereas, Heretofore on the 1st day of December, 1914, the city of Fort Wayne entered into a contract with the Lindley, Schmid Company, providing for the purchase of coal by said city, which contract is as follows:

This agreement, made and entered into by and between the City of Fort Wayne, Indiana, by and through its Board of Public Works, hereinafter called the "Consumer" and Lindley Schmid and Company of Indianapolis, Indiana, hereinafter called the "Company", Witnesseth, That

Whereas, it is desired by the parties hereto to enter into a contract of purchase and sale of Coal as herein set forth:

Now, Therefore, in consideration of the mutual covenants and agreements herein contained, the parties hereto do hereby agree as follows:

The company hereby agrees to sell to the consumer and the consumer hereby agrees to buy from the Company, coal for consumption for the year 1915 at the Fort Wayne Municipal Electric Light and Power Works located in Fort Wayne, Indiana, the estimated quantity under contract of twelve thousand (12,000) ton, to be delivered as ordered in equal weekly shipments of approximately five (5) cars per week, said delivery to continue until December 31, 1915, with the understanding that the city shall have the right to have said deliveries continue until April 1, 1916 or until December 31, 1916, provided that said city shall give to said company sixty (60) days notice before the termination of this contract, of its desire to so extend the same.

The company further agrees to furnish coal herein contracted for, in the grade and in such quantities and delivered to the consumer f.o.b. their tracks, Fort Wayne, Indiana at such times as ordered by the consumer from time to time during the term of this contract, of the Kind of coal described below.

The Kind of coal shall be 1 1/4 inch bar screenings, said coal to be mined from Geological vein number five from the Bicknell Mine in Knox County, Indiana on the

Vandalia Railroad

The consumer hereby agrees to pay the said company on the 10th of the calendar month for all shipments made to the consumer during the previous month, a price of one dollar and eighty cents ($1.80) per net ton F.O.B. their tracks, Fort Wayne, Indiana for the Kind of coal as hereto-fore described and of an analysis equal to the following:

Moisture	10%	
Ash	11%	(Specified Analysis)
B.T.U. (Per Pound Dry)	12700	

This analysis, based on the price of one dollar and eighty cents ($1.80) per ton is equal to 123,234 net British Thermal Units for one cent which is the Contract Guarantee.

The company hereby agrees that for each unit of two hundred (200) BTU wherein the coal falls below the specified analysis, a reduction shall be made by the consumer at the rate of three (3) cents per ton, and for each unit of two (2) per cent in which the coal contains more ash than specified, a reduction shall be made at the rate of three (3) cents per ton.

It is understood and agreed that all coal shipped on this contract shall be loaded in self clearing hopper cars and the company hereby agrees to allow the consumer to make a reduction of ten cents per ton on any shipments made in other than hopper equipment.

It is agreed that when as a result of an act of Providence or of a strike or strikes at the mines or on the railroad, it is impossible for the company to deliver coal hereunder, the obligations of delivery and acceptance of coal shall cease until such strikes are over, or delivery of coal can again be made, provided the company notifies the consumer in writing of such probable inability to deliver coal as soon as the company first has Knowledge of such probable inability.

It is further agreed that when such strikes are over or delivery of coal can again be made, the rights and duties of the parties hereto shall be the same as before cessation of deliveries occurred.

It is further agreed that if during the term of this contract there be an increase or decrease in either the miners' wage scale at the mine or mines from which the contract coal is being produced, or in the freight rate from the same mine or

to the consumers plant, the delivered value of the coal thereafter sold under this contract shall be correspondingly increased or decreased.

It is hereby understood and agreed that railroad weights shall govern all settlements made in accordance with the terms of this contract.

Should the company fail to deliver coal in accordance with the terms of this contract, the consumer may purchase on the open market such an amount or amounts of coal as the said company shall fail to deliver, in which event all costs and expenses occasioned by such failure, in excess of the cost hereunder of an equivalent amount of coal of corresponding grade, shall be borne and paid by said company.

The term of this contract shall be from January 1, 1915. to and including the 31st day of December, 1915. and said contract shall neither be effective nor binding upon the parties hereto, until the company shall execute to the consumer, a bond to the amount of five thousand ($5000.00) dollars, said bond to have approval of the consumer, for the proper and faithful performance of the terms, conditions and agreements of the contract.

The said Company agrees to execute, within ten (10) days hereafter, a bond with a surety company as surety thereon, in the sum of Five thousand dollars ($5000.00) to be approved by the Board of Public Works of said city.

In Witness Whereof, the parties hereto have hereunto set their hands and seals at Fort Wayne, Indiana, this 1st day of December 1914.

City of Fort Wayne, By
Frank E. Singrey.
Robert E. Kelley.
Henry H. Hilgeman.
Its Board of Public Works
Lindley, Schmid and Co.,
By. D.R. Lindley
Its President

Attest
J Wessel Jr
Clerk.

Section I Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that the contract hereto fore entered into on the 1st day of December 1914. by and between the City of

Fort Wayne, by and through its Board of Public Works and the Lindley, Schmid and Company, a corporation of Indianapolis, Indiana, as more fully set out in the preamble hereto, be and the same is in all things ratified and approved.

Section II This Ordinance to be in full force and to take effect after its passage and approval by the Mayor and Legal Publication.

Frank J. Schlebecker.

Done at the Council Chamber in the City of Fort Wayne this 22nd day of December 1914.

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 22nd day of December 1914, by a majority vote of all the members elect, did pass the ordinance hereunto attached and known as General Ordinance No. 675.

Wm A. Bayer
President.

F. W. Boerger,
city clerk.

Presented to the Mayor for approval on the 29th day December, 1914

F W Boerger
city clerk.

Approved this 2nd day of January 1915,

Wm J. Hosey
Mayor

General Ordinance No 676

An Ordinance Regulating the Operation of Motor Vehicles.

Section I. Be it Ordained by the Common Council of the City of Fort Wayne, that no person company or corporation shall operate or cause, allow or permit to be operated, any motor vehicle upon any public highway in the city of Fort Wayne having lights there-on in excess of four (4) candle power, unless the same have attached thereto a suitable deflector or screen.

Section II. That It shall be unlawfull for any person, company or corporation to operate or cause, permit or allow to be operated upon any public highway in the city of Fort Wayne, any motor vehicle with out a muffler attached to the exhaust pipe of said motor vehicle.

Section III. It shall be unlawful for any person, company or corporation while operating a motor vehicle upon any of the public highways of the City of Fort Wayne, to open any cut out valve in the exhaust pipe of said motor vehicle.

Section IV Any person, firm or corporation violating any of the provisions of this ordinance shall be fined in any sum not less that Five dollars ($5.00) nor more than one hundred dollars ($100.00)

Section V. That this ordinance shall be in full force and take effect from and after its passage, approval by the mayor and legal publication.

Q. H. Keller.
Charles E. Welch

Done at the Council Chamber in the City of Fort Wayne this 12th day of January -1915.

We hereby certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 12th day of January, 1915, by a majority vote of all the members elect, did pass the Ordinance hereunto attached, and known as General Ordinance No. 676

Wm A. Bayer,
President

D. W. Boerger
city clerk.

Presented to the Mayor for approval on the 14th day of January 1915

D. W Boerger
city clerk.

Approved this 21st day of January, 1915

Wm J. Hosey
Mayor

General Ordinance No. 677.

An ordinance amending Section (1) One of an ordinance entitled "An Ordinance to amend section 23 of General Ordinance No. 43, entitled 'An Ordinance defining certain offenses.

Section I. Be it ordained by the Common Council of the city of Fort Wayne, Indiana, that section one (1) of General Ordinance No. 496 of the city of Fort Wayne, being an ordinance entitled "An Ordinance to amend section 23 of General Ordinance No. 43 entitled 'An Ordinance defining certain offenses", passed by the Common Council of said City on the 25th day of July, 1911, be amended to read as follows: Section 1. Be it ordained by the Common Council of the City of Fort Wayne, Indiana, that Section 23 of General Ordinance No. 143, entitled "An ordinance defining certain offenses," be amended to read as follows: Section 23. It shall be unlawful for any person to build or cause to be built, with in the limits of said city, any privy vaults, or to use for such purpose any vault unless the same is built of brick, stone or metallic substances, and made water tight and not less than four feet deep. And it shall be unlawful to construct or maintain any such privy vault or other vault use for that purpose with-in a distance less that fifty feet from any dwelling place. It shall be the duty of the Board of Public Health to report all cases where the said vaults are not built as herein provided to the Building Inspector who shall, after due notice to the owner of said vault, proceed to condemn any said vault not constructed as herein provided, and said Board of Health shall notify the owner of said vault to cause the same to be constructed as herein provided, or in case the same is within fifty (50) feet of any dwelling place to cause the same to be removed, as the case may be, within five (5) days from the service of such notice, and on failure of such owner to construct said vault as herein provided or to remove the same as the case may be, he shall be fined in any sum not exceeding Twenty-five dollars ($25.00) and each day's refusal to comply with said notice shall be considered a Separate offense.

Section II This Ordinance to be in full force and take effect from and after its passage, legal publication and approval by the Mayor

C. O. Lepper

Done at the Council Chamber in the City of Fort Wayne, this 12th day of January. 1915.

We hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 12th day of January, 1915. by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 677

Wm A. Bayer
President

J W Boerger
city clerk.

Presented to the Mayor for approval on the 14th day of January, 1915.

J W Boerger
city clerk.

Approved this 21st day of January, 1915.

Wm J. Hosey
Mayor.

General Ordinance No. 678.

An ordinance approving a contract entered into by and between the city of Fort Wayne, Indiana by and through its Board of Public Works and General Electric Company by and through its agent, on the 1st day of December, 1914. relative to the purchase of the Lamp Supply for the Fort Wayne Municipal Electric Light and Power Works during the year of 1915. Whereas, Heretofore on the 1st day of December 1914, the City of Fort Wayne entered into a contract with the General Electric Company, providing for the purchase of lamps by said city, which contract is as follows:

Contract for the Purchase of Incandescent Lamps.

Agreement, made this First day of December, 1914, between the General Electric Company, a New York corporation (hereinafter called the "Manufacturer") at its Edison Lamp Works, and Board of Public Works, of Fort Wayne, Indiana. (hereinafter called the "Purchaser";)

1. The purchaser desiring to purchase incandescent lamps for its own use, the manufacturer agrees to sell, and the purchaser agrees to take, within one (1) year from date hereof, and to pay for in accordance with the terms of payment hereinafter specified, a quantity of Edison Incandescent Lamps, (all of which are manufactured under Letters Patent of the United States) of classes and types stated in attached scedules, which shall in no event exceed the Purchaser's requirements of such lamps for its own use during the period of this contract.

2. The Purchaser estimates that its purchases will amount to not less than $5,000.00 dollars, net value, and the Manufacturer accepts the above estimate as a basis for billing and agrees to invoice lamps at the following discounts from the list prices given in the schedules hereto attached, and make part of this contract, which net invoice price in guaranteed to be at all times the lowest price made to Purchasers purchasing in like amounts.

Discounts.

Standard Package 31 % Broken Package 21 %

3. The Purchaser agrees to pay transportation charges in accordance with the Delivery Scedule hereto attached.

4. The Manufacturer agrees that should the Purchasers purchases during the contract period in accordance with contract terms, reach an amount entitling it to a lower price as determined by discounts from lists based on amounts purchased, given in attached schedules, the Manufacturer will credit the Purchasers account with an amount equal to the difference between the price at which the lamps have been invoiced and the price to which the Purchaser is entitled on the lamps ordered and paid for.

5. The Purchaser agrees that, should the purchases under this

under this contract and during the term there-of be less than the amount on which its discount is based, it will, within thirty (30) days after demand, pay an amount equal to the difference between the net billing price of the quantity of lamps actually purchased and the price to which it is entitled on such amount, as shown on attached schedules.

6. The Purchaser agrees, that it will pay all invoices for lamps not later than thirty days from the date of the invoice, and if payment of any invoice is made within ten (10) days from the date of same, two per cent. (2%) may be deducted from the net amount thereof.

7. The Manufacturer reserves the right immediately to cancel this if lamps sold hereunder are used on lighting circuits other than those supplied with current by the Purchaser exclusively or those circuits located in buildings or on property owned, occupied or leased by the Purchaser, or in case of the failure of the Purchaser to comply with any of its obligations under this contract.

8. This Agreement is hereby signed by the General Electric Company, the Manufacturer, by the Sales Manager of its Edison Lamp Works, or by his duly authorized representative located in the Sales Office of said works at Chicago, Ill.

Fred J. Benson,
Sales Manager — Edison Lamp Works.
Board of Public Works, Purchaser.
Frank R. Swigrey
President.

Section I. Be it Ordained by the Common Council of the City of Fort Wayne, Indiana, that the contract heretofore entered into on the 1st day of December 1914, by and between the City of Fort Wayne, by and through its Board of Public Works and the General Electric Company of N.Y. has more fully set out in the preamble hereto, be and the same is in all things ratified and approved.

Section II. This Ordinance to be in full force and to take effect after its passage and approval by the Mayor and legal Publication.

Eugene B. Bomith.

Done at the Council Chamber th the City of Fort Wayne, Indiana, this 26th, day of January 1915.

We Hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 26th. day of January, 1915, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 678.

Wm A. Bayer
President

D W Boerger
city clerk

Presented to the Mayor for approval on the 28th day of January, 1915.

D W Boerger
city clerk.

Approved this 30th day of January, 1915.

Wm J. Hosey
Mayor

General Ordinance No. 679.

An Ordinance ratifying and approving a contract entered into on the 14th day of December, 1914, by and between the City of Fort Wayne and the Wm Kaough Coal Company.

Whereas, heretofore on the 14th day of December, 1914, the City of Fort Wayne, by and through its Board of Public Works entered into a contract with the Wm Kaough Coal Company, providing for the purchase of its year's supply of coal to be used at its number two (2) Pumping station, which contract is in the following words:

This agreement, made and entred into this 14th day of December, 1914, by and between the City of Fort Wayne, by and through its Board of Public Works, party of the first part and the Wm Kaough Coal Company, party of the second part, Witnesseth:

That in consideration of the purchase by said city from the party of the second part of its year's supply of coal to be used at its No. 2 Pumping Station, from the 1st day of January, 1915, to the 31st day of December 1915, in the manner hereinafter provided, the party of the second part agrees to furnish to said city, during said period of time one thousand two hundred (1200) tons or more of Smithers Creek 3/4 lump Gas Coal at the price of one dollar and five cents ($1.05) per ton of two thousand (2000) pounds, F.O.B mines, all as shown by the bid of second party, which is filed in the office of the water works department of said city.

Said city to have the privilege of buying from said Company all of the coal used by it at its said No. 2 Pumping Station during said period of time, at the price named herein, so long as the kind, quality and quantity is satisfactory to said board of Public Works, and the same to be shipped and billed on flat bottom cars from the mines to said city, at its said pumping station, on the Lake Shore and Michigan Southern Railroad, said city to pay all freight on all coal so purchased.

It is mutually agreed between the parties hereto that payments by the first party shall be made to the second party on or before the 15th day of every month, based upon invoice weights on all coal delivered as aforesaid during the month previous thereto. The strict performance of this contract

by the party of the second part and the prompt deliveries of coal herein on cars at said mines as aforesaid shall be subject to delays occasioned by strikes, and want of car supply and failure of railway companies to deliver and place cars at the mines for loading.

It is further agreed between the parties hereto that after the delivery of said coal on board of said cars by said party of the second part, said party, at the request of the first party and as the agent of the party of the first part, will use its best endeavors with the carriers to have said cars of coal delivered as aforesaid, billed and sent forward promptly to destination.

This contract shall not be binding or take effect until the second party shall execute to the party of the first part a bond in the sum of one thousand dollars ($1000.00), with sufficient surety thereon to be approved by the mayor and city comptroller of party of the first part, and conditioned for the faithful performance by the party of the second part of all terms, conditions and agreements herein to be performed by it, and until this contract has been ratified and approved by the common Council of said city.

Witness our hands and seals this 14th day of December, 1914.

City of Fort Wayne, By.
Frank E. Singrey.
Robert E. Kelly.
Henry Hilgeman.
Its Board of Public Works.

Attest.
C. A. Bennet
Secretary.

Wm McKaough Coal Company, By.
Aug. Lassans, Pres't.

Section I. Be it Ordained by the Common Council of the city of Fort Wayne, Indiana, that the contract heretofore entered into on the 14th day of December, 1914, by and between the City of Fort Wayne, and the Wm McKaough Coal Company as fully set out in the preamble hereto, be and the same is in all things confirmed and approved.

Section II. This ordinance to be in full force and take effect from and after its passage and approval by the mayor and legal publication.

Jacob Agne.

Done at the Council Chamber, in the City of Fort Wayne, Indiana, this 26th day of January 1915.

We Hereby Certify, That the Common Council of the City of Fort Wayne, Indiana at a Regular meeting, held on the 26th day of January 1915, By a majority vote of all the members elect did Pass the ordinance hereunto attached and Known as General Ordinance No 679

Wm A. Bayer,
President.

G W Boerger
city clerk.

Presented to the Mayor for approval on the 28th day January, 1915.

G W Boerger
city clerk.

Approved this 30th day of January 1915.
Wm J. Hosey
Mayor.

General Ordinance No. 680.

An ordinance amending section one of an ordinance entitled "An ordinance amending sections two, eight, ten, twelve, thirteen, fourteen, and fifteen of an ordinance regulating the sale of meats and fish; prescribing the sanitary condition of meat shops, butchershops, slaughter houses and meat markets and the manner of handling meats and carcasses of animals intended for human consumption, providing for the licensing of such places, providing a penalty for its violation and repealing all ordinances in conflict therewith, as Amended November 26, 1907" being General Ordinance No. 361 and passed by the Common Council of said city on June 23, 1908.

Section I. Be it ordained by the Common Council of the City of Fort Wayne, that section one of said ordinance be and the same is hereby amended to read as follows:

"Section I. Be it ordained by the Common Council of the city of Fort Wayne that section two of said ordinance be and the same is hereby amended to read as follows:

Section 2. No person, firm or corporation shall conduct a slaughter house in the city of Fort Wayne or sell or offer for sale, dispose of, exchange, barter or give away, or with intent so to do, have in his or their possession, care, custody or control any flesh of any animal intended for human food without first obtaining a license so to do. Any person, firm, company or corporation desiring to obtain such license shall first file with the Board of Public Health a verified written application in such form as may be prescribed by such Board of Public Health, showing that such person, firm, company or corporation is prepared to conduct a slaughter house or to handle meats according to, and in the manner prescribed in this ordinance. If such application shall show that such applicant is prepared to conduct a slaughter house or to handle meats according to, and in the manner prescribed in, this ordinance, and if the place of business at which the applicant intends to conduct a slaughter house or handle meats is of the kind described in this ordinance, the Board of Public Health shall grant such application and it shall be the duty of the City Comptroller to issue a license upon the receipt of such application properly signed and approved by said Board of Public Health, and

upon the payment of the license fee in this section provided.
The following licenses shall be paid by the respective applicants:

For conducting a slaughter house a license fee of one hundred dollars ($100.00) per annum.

For selling meat at whole sale a license fee of twenty-five dollars ($25.00) per annum.

For selling meat at retail at each designated place or shop a license fee of five dollars ($5.00) per annum.

For conducting a fish market a license fee of five dollars ($5.00).

For selling meat from a wagon or other vehicle from each wagon or vehicle a license fee of five dollars ($5.00) per annum.

Provided, if a license shall be obtained to conduct a slaughter house the applicant shall have the power or authority to sell meat at wholesale with out paying the additional license as above required for selling meats at whole-sale.

All licenses shall be issued from the date of application for a period of one (1) year and no license shall be granted for a shorter period of time.

All licenses issued under the provisions of this ordinance shall be conditioned that the applicant or licensee shall comply with this ordinance and the amendments thereto now in force or to hereafter be enacted, and the mayor shall have, and is hereby given the power to revoke, in the manner provided by law, any license issued under this ordinance when such licensee shall wilfully violate any of the terms or conditions of his license or shall wilfully do, authorize, or permit to be done, any act in violation of the laws of the state or of this ordinance relating to the sale of meats and fish.

Any one violating or failing to comply with the provisions of this section shall be fined in any sum not exceeding one hundred dollars. ($100.00)

Section II That this ordinance be in full force and take effect on and after its passage, approval by the Mayor and legal publication.

Done at the Council Chamber in the City of Fort Wayne this 26th day of January 1915.

We Hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 26th, day of January, 1915. by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 680.

Wm C. Bayer
President.

F W Boerger
City clerk

Presented to the Mayor for approval on the 28th day of January, 1915.

F W Boerger
city Clerk.

Approved this 30th day of January 1915.

Wm J. Hosey
Mayor

General Ordinance #681

An ordinance approving Railroad Track Elevation Resolutions Nos. 15, 16, 17, 18, and 19 adopted by the Board of Public Works of the city of Fort Wayne, December 3rd - 1914, and which said resolutions numbered 16 and 17 were ratified and confirmed by said Board on December 29th, 1914, and said resolutions numbered 15, 18, and 19 were ratified and confirmed by said Board on the 8th day of January 1915.

Section I. Be it ordained by the Common Council of the city of Fort Wayne, that railroad Track Elevation Resolutions Nos. 16 and 17 adopted by the board of Public Works on the 3rd day of December 1914 and ratified and confirmed by said board on the 29th day of December 1914 and Railroad Track Elevation Resolutions nos. 15, 18, and 19 adopted by the Board of Public Works on the 3rd day of December 1914, and confirmed by said board on the 8th day of January 1915, be and the same are hereby in all things ratified confirmed and approved.

Section II. That this ordinance be in full force and effect on and after its passage and approval by the mayor

Wm A. Bayer
P. A. Ofenlock

Done at the Council Chamber in the City of Fort Wayne, Indiana, this 9th day of February 1915.

We hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 9th day of February, 1915, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and known as General Ordinance No. 681

Wm A. Bayer
President

J W Boerger
city clerk

Presented to the Mayor for approval on the 11th day of February 1915.

J S W Boergen
city clerk.

Approved this 16th day of February 1915.

Wm J. Hosey
Mayor

General Ordinance No. 682.

An Ordinance changing the name of Thomas Street to Bowser Ave.

Section I Be it Ordained by the Common Coencil of the City of Fort Wayne, That Thomas Street South from the Pennsylvania right-of-way to its southern terminus be hereafter Known as and called Bowser Avenue.

Section II. That this ordinance be in full force and effect from and after its passage and approval by the mayor.

H. J. Korte,

Done at the Council Chamber in the City of Fort Wayne, Indiana, this 9th day of February 1915.

We Hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting, held on the 9th day of February, 1915, by a majority vote of all the members elect, did pass the ordinance hereunto attached, and Known as General Ordinance No. 682.

Wm C. Bayer. D.W. Boerger

President. city Clerk.

Presented to the Mayor for approval on the 11th day of Feb-1915.

D. W. Boerger
city clerk.

Approved this 16th day of February, 1915.

Wm J. Hosey
Mayor

General Ordinance No. 683

An Ordinance ratifying and approving a contract entered into on the 21st day of January 1915, by and between the City of Fort Wayne, Indiana and the Fort Wayne Electric Works of General Electric Company of Fort Wayne, Indiana.

Whereas, On the 21st day of January 1915, the city of Fort Wayne, Indiana by and through its Board of Public Works entered into a contract with the Fort Wayne Electric Works of General Electric Company, which is in the following words:

Fort Wayne Electric Works of General Electric Company, Main Office, Fort Wayne, Ind.

Futher delivery Meter Contract.

This contract and agreement, executed in duplicate, made and entered into this 21st day of January, 1915, by and between the Fort Wayne Electric Works of General Electric Company, Fort Wayne, Indiana, party of the first part, and Board of Public Works of Fort Wayne, Indiana, party of the second part, their successors and assigns:—

Witnesseth:- That for and in consideration of one dollar and other valuable considerations, paid by said party of the first part to said party of the second part, the receipt of which is hereby acknowledged, the said party of the second part hereby agrees to purchase of the said party of the first part, all electric alternating current watthour meters required by the said party of the second part during a period of one year from the date of this contract, for use by them in the operation of the electric plants controlled by them and to pay for all meters purchased under this contract with in thirty (30) days from date of shipment thereof the price herein after set forth; and all meters to be used as above mentioned shall be of Type K alternating current watthour meters as manufactured by the said party of the first part at Fort Wayne, Indiana.

For and in consideration of the exclusive purchase of alternating current watthour meters, as hereinbefore mentioned, from the said party of the

first part, by the said party of the second part, the said party of the first part, hereby agrees that all meters purchased under this contract shall be free from all inherent electrical and mechanical defects, and to hold said party of the second part harmless and indemnified against all sums which the said party of the second part shall be adjudged to pay in any suit brought against them alleging infringement of patents by the use of the meters hereinbefore mentioned, provided that the party of the first part be given immediate written notice of suits and permission through their counsel to defend the same; and provided further that the said party of the second part is not in default in their payments.

The said party of the first part agrees to sell to the said party of the second part alternating current watthour meters as hereinbefore mentioned new and in good condition, delivered F. O. B. Fort Wayne, Indiana, consigned to the address of the said party of the second part at a discount of

60 per. cent from Schedule E.

60-5 per. cent from Schedule J.

Said schedule being attached hereto and made a part of this contract.

The party of the second part agrees that he is under no obligations inconsistent with the carrying out of the conditions of this agreement.

Fort Wayne Electric Works

A General Electric Company.

Accepted Fort Wayne Municipal Electric Light and Power Works.

By C. E Becker.

By Robert E. Kelly, Pres.

Board of Public Works

The above Contract and Agreement is hereby fully ratified and approved by us at Fort Wayne, Indiana, this 23rd day of January, 1915

Fort Wayne Electric Works.

A General Electric Company.

By. F. S. Hunting

Gen'l Mgr.

Section I. Be it ordained by the Common Council of the City of Fort Wayne, Indiana that the contract heretofore entered into on the 21st day of January 1915 by and between the city of Fort Wayne, by and through its Board of Public Works, and the Fort Wayne Electric Works of General Electric Company, as more fully set out in the preamble hereto, be and the same is in all things ratified and approved.

Section II. This Ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal publication.

Eugene B. Smith.

Done at the Council Chamber ~~this~~ in the city of Fort Wayne, Indiana, this 9th day of February 1915.

We hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 9th day of February, 1915 by a majority vote of all the members elect, did pass the ordinance hereunto attached and known as General Ordinance No. 688.

Wm A. Bayer
President.

J W Boerger
city clerk.

Presented to the Mayor for approval on the 11th day of February, 1915.

J. W. Boerger.
city clerk.

Approved this 16th day of February 1915.

Wm J. Hosey
Mayor

General Ordinance No. 684.

An Ordinance ratifying and approving a contract entered into on the 2nd day of January 1915, by and between the City of Fort Wayne, Indiana and the Fort Electric Works of General Electric Company of Fort Wayne, Indiana.

Whereas, On the 2nd day of January 1915, the City of Fort Wayne, Indiana, by and through its Board of Public Works entered into a contract with the Fort Wayne Electric Works of General Electric Company, which is in the following words:

Fort Wayne Electric Works.

of General Electric Company.

Main Office, Fort Wayne, Indiana.

Future delivery Transformer Contract.

This Contract and Agreement, executed in duplicate, made and entered into this 2nd day January, 1915, by and between the Fort Wayne Electric Works of General Electric Company, Fort Wayne, Indiana, party of the first part, and Board of Public Works, of Fort Wayne, Indiana, party of the second part, their successors and assigns:-

Witnesseth:- That for and in consideration of one dollar and other valuable considerations paid by said party of the first part to said party of the second part, the receipt of which is hereby acknowledged the said party of the second part hereby agrees to purchase of the said party of the first part, all multiple transformers required by the said party of the second part during the period of one year from the date of this contract, for use by them in the operation of the electric plants controlled by them all standard transformers to be rated 1100/2200 volts primary 110/220 volts secondary.

The party of the second part agrees to pay to the party of the first part for all transformers purchased under this contract with-in thirty (30) day from date of shipment thereof the price hereinafter set forth, and all transformers to be used as above mentioned shall be the Type A transformers as manufactured by the said party of the first part at Fort Wayne, Indiana.

For and in consideration of the purchase of transformers as hereinbefore mentioned from the said party of the first part, by the said party of the second part, the said party of the first part hereby agrees that all transformers purchased under this contract

shall be free from all inherent electrical and mechanical defects, and to hold said party of the second part harmless and indemnified against all sums which the said party of the second part shall be adjudged to pay in any suit brought against them alleging infringement of patents by the use of the trans-formers hereinbefore mentioned provided that the party of the first part be given immediate written notice of suits and permission through their counsel to defend same; and provided further that the said party of the second part is not in default in their payments.

Said party of the first part agrees to sell to the said party of the second part standard multiple transformers as hereinbefore mentioned, new and in good condition, delivered F. O. B. Fort Wayne, Indiana. consigned to the address of the said party of the second part, at a discount of:

50 -10-10-5 per cent. from Schedule A.

Said Transformer Schedules being attached hereto and made a part of this contract.

Should Transformer other than standard be required they will be furnished at prices comparable with prices on transformers as specified in the attached schedules.

The party of the second part agrees that he is under no obligations inconsistant with the carrying out of the conditions of this agreement.

This Contract is Not Binding Unless approved By the General Manager, Sales Manager, or Treasurer of the Party of the First part.

Fort Wayne Electric Works.
of General Electric Company
By C. E. Becker

Witness:
J Wesley Jr.

Accepted Ft. Wayne Municipal Elec. Light and Power Wks.
By Robert E. Kelly
Board of Public Works.

The Above Contract and Agreement is hereby ratified and approved by us at Fort Wayne, Indiana on the 22nd day of Jan. 1915.

Fort Wayne Electric Works.
of General Electric Company
By F. D. Hunting
Genl. Mgr

Section I. Be it ordained by the Common Council of the City of Fort Wayne, Indiana that the contract heretofore entered into on the 2nd day of January 1915 by and between the City of Fort Wayne, by and through its Board of Public Works, and the Fort Wayne Electric Works of General Electric Company, as more fully set out in the Preamble hereto, be and the same is in all things ratified and approved.

Section II. This Ordinance to be in full force and take effect from and after its passage and approval by the Mayor and legal Publication.

Eugene B. Smith.

Done at the Council Chamber in the City of Fort Wayne, Indiana, this 9th day February, 1915.

We Hereby Certify, That the Common Council of the City of Fort Wayne, Indiana, at a Regular meeting held on the 9th day of February, 1915. by a majority vote of all the members elect did pass the ordinance hereunto attached, and known as General Ordinance No. 684.

Wm A. Bayer
President

G. W. Boerger
City Clerk.

Presented to the Mayor for approval on the 11th day Feb. 1915.

G. W. Boerger

Approved this 16th day of February 1915

Wm J. Hosey
Mayor